Brimbank Planning Scheme

PLANNING SCHEME

Planning scheme last updated by VC282 on 08/09/2025

00 PURPOSE AND VISION

02/09/2025
VC283

This section sets out the purpose of this planning scheme, and the vision and strategic direction for Victoria and the municipality.

ACKNOWLEDGEMENT OF COUNTRY

The Victorian Government acknowledges Traditional Owners in Victoria as the custodians of Country. We acknowledge their extraordinary strength and resilience in the face of historical and ongoing social, economic and legal injustices, maintaining their connection to Country.

We pay our respects to Elders past and present, whose knowledge and wisdom have ensured the continuation of spiritual and cultural practices. We also acknowledge the diversity of First Peoples' communities in Victoria.

We acknowledge that the long-lasting, far-reaching and intergenerational consequences of colonisation and dispossession continue to exist today and continue to cause harm. Colonisation has left entrenched systemic and structural racism and suffering, including through the laws and policies of the Colony of Victoria, which specifically excluded First Peoples and their laws, lores, customs, languages and cultures. The Victorian Government has a responsibility to transform its systems and service delivery so First Peoples have decision-making power over matters that directly affect them.

To address this exclusion, the Victorian Government commits to ongoing engagement with Traditional Owners and First Peoples to restore and strengthen their rights in this planning scheme.

01 PURPOSES AND VISION FOR VICTORIA

02/09/2025
VC283

01.01 PURPOSES OF THIS PLANNING SCHEME

02/09/2025
VC283

- To provide a clear and consistent framework within which decisions about the use and development of land can be made.
- To express state, regional, local and community expectations for areas and land uses.
- To provide for the implementation of State, regional and local policies affecting land use and development.
- To support responses to climate change.

01.02 VISION FOR VICTORIA

02/09/2025
VC283

THE PEOPLE'S PANEL VISION FOR VICTORIA

By 2050 Victoria will be a vibrant, accessible and connected community, valued for its diverse cultures, sustainable environmental practices and respect for the First Peoples of Victoria.

Building a state which provides choices and opportunities for current and future generations of Victorians in quality housing, transport, employment, environment and connectivity, will require input from community, government, local businesses and industry alike.

We will create a society that caters to the unique needs of all Victorians, nurturing individual health through physical and cultural recreation.

02 MUNICIPAL PLANNING STRATEGY

27/06/2024
C225brim

02.01 CONTEXT

27/06/2024
C225brim

Brimbank is located between 11 and 23 kilometres northwest of the CBD and covers approximately 123 square kilometres. It is bound by the City of Hume to the north, the cities of Maribyrnong, Moonee Valley and Merri-bek to the east, the cities of Hobsons Bay and Wyndham to the south, and the City of Melton to the west.

Fifteen per cent of Brimbank is classified as open space, including parts of the Sunbury Green Wedge which occupies the northernmost portion of the municipality. The Maribyrnong River, Kororoit, Taylors, Jones, Jacksons, Steele and Stony Creeks traverse the municipality and contribute to the valued natural, volcanic plains environmental character. Key areas of environmental significance include Organ Pipes National Park, Mount Derrimut Grasslands, Taylors Creek Valley Conservation Area, Brimbank Park and Iramoo Wildflower Grassland Reserve.

There are two groups of Aboriginal people with cultural ties to Brimbank comprising the Wurundjeri and Bunurong Peoples. Within these there are two main language groups, the Woi-wurrung (Wurundjeri) and the Boonwurrung (Bunurong). Each group has their own history, culture and role in Aboriginal heritage. A significant part of the municipality is within the designated Registered Aboriginal Party area of the Wurundjeri Woi-wurrung Cultural Heritage Aboriginal Corporation, whilst land to the south is within the designated Registered Aboriginal Party area of the Bunurong Land Council Aboriginal Corporation.

Brimbank's estimated population of 197,000 people is projected to grow to more than 220,000 by 2036 (Victoria in Future, 2023).

The Sunshine National Employment and Innovation Cluster (NEIC) is forecast to receive the greatest increase in population. Within the NEIC there is a significant focus on growth, infrastructure investment and renewal. Population growth and change will place higher demands on social, environmental, transport and economic systems.

The Brimbank community is one of the most multicultural and socially diverse in Australia, with almost half of all residents born outside Australia, and more than half speaking a language other than English at home.

Brimbank is the second most disadvantaged municipality in metropolitan Melbourne according to the Australian Bureau of Statistics' Socio-Economic Index for Areas (SEIFA). Managing the social and economic impact of urban transformation on existing and future populations, including the provision of affordable housing will be important.

Brimbank’s economy comprises a diverse range of industrial activities including manufacturing, wholesale trade and transport which make up almost half of the local economy. Other activities, including healthcare, education, construction and retail trade, make up a quarter of the economy.

02.02 VISION

27/06/2024
C225brim

Brimbank City Council's vision is to provide a place that is vibrant, harmonious and welcoming: a great place to live, work and grow.

The following land use and development goals and objectives are intended to achieve this vision:

An inclusive community where:

- People are safe, healthy and well.
- People have opportunities to participate in community life.

A liveable community where:

- Public and open spaces are safe, clean and well-maintained.
- People can move around easily on foot, bike, car or public transport.
- People live sustainably by reducing their carbon footprint and becoming resilient to climate change.
- The natural environment supports thriving biodiversity that is protected.
- The urban environment supports a growing population in designated areas while respecting neighbourhood character and heritage.

A prosperous community where:

- The local economy is strong and provides opportunities for the community to thrive.
- Housing is of high quality, well located and relatively affordable.
- Brimbank is a leading destination for business, working, learning, recreation and living.

02.03 STRATEGIC DIRECTIONS

27/06/2024
C225brim

02.03-1 Settlement

27/06/2024
C225brim

Green wedge

The Brimbank portion of the Sunbury Green Wedge contains a number of environmental assets such as conservation reserves and areas used for recreation, horticulture, tourism and low density residential uses. It also contains heritage sites and significant landscapes. There is pressure to increase residential development and expand existing non-conforming uses within the area.

Maintaining the area's agricultural role is a key State Government objective for Sunbury Green Wedge. Over recent years production has been challenged by a number of factors including water supply, declining soil conditions and incompatible uses. Despite these challenges the fertile soils along the river flats and the area's proximity to urban populations and regional markets provide opportunity to maintain agricultural production in the area.

Strategic directions:

- Limit development within and immediately adjacent to the Sunbury Green Wedge.
- Protect local biodiversity values, cultural heritage and the scenic landscape.
- Maintain opportunities for extensive and intensive agriculture.
- Protect productive agricultural land from incompatible uses and development.
- Encourage productive, accessible agricultural and eco based tourism compatible with the green wedge.

Activity centres

Brimbank has one metropolitan activity centre, four major activity centres and a network of 47 other local and neighbourhood centres. Brimbank's metropolitan, major, local and neighbourhood activity centres are shown on the Strategic Framework Plans in Clause 02.04.

Sunshine Metropolitan Activity Centre is Brimbank's highest order activity centre. It is strategically positioned as an important centre for Melbourne's growing west and western Victoria, and a vibrant hub for the local community. Delivery of Melbourne Airport Rail (SRL Airport) and a new regional platform will support a new transport 'superhub' in and around Sunshine Railway Station, and improvements to Albion Railway Station as part of wider precinct planning will further enhance its role.

Sydenham Major Activity Centre is a regionally significant major activity centre with potential for a higher order classification due to its available vacant land and expected population growth from Brimbank and surrounding municipalities. This centre operates as a key transport and community hub with a mix of retail, bulky goods, entertainment, civic, and residential uses, including aged care. Arterial roads and the rail corridor are major physical barriers for pedestrians and cyclists.

St Albans Major Activity Centre is a location for significant expansion given its strategic location within the Sunshine National Employment and Innovation Cluster (NEIC), access to public transport, community facilities and Victoria University (St Albans campus).

Brimbank Central Major Activity Centre is a busy, standalone major activity centre with limited access to public transport. The centre contains a number of opportunities for future development and is adjacent to the Deer Park library, identified for expansion.

Deer Park Major Activity Centre is close to key development sites and Deer Park Railway Station which presents opportunities for renewal and growth, and integration of the fragmented commercial uses. Future use and development should respond to nearby major hazard facilities.

Keilor Downs Neighbourhood Activity Centre is a significant centre that services a large catchment area, established around the Keilor Shopping Centre that serves the general area of Keilor Downs, St Albans and parts of Keilor. The centre contains the Brimbank Aquatic and Wellness Centre that serves a regional recreational role. Moderate growth is expected in the form of variety and choice in housing types in the north and west.

Strategic directions:

- Support use and development that is consistent with the role and functions of the activity centre.
- Encourage a broad and diverse range of regional and sub-regional retail, entertainment, government, office, medical, community service, business and leisure uses in metropolitan and major activity centres.
- Support the development of an integrated transport superhub at Sunshine Railway Station in the Sunshine Metropolitan Activity Centre.
- Facilitate land use and development in the Sunshine Metropolitan Activity Centre that supports a safe centre that operates 24 hours a day.
- Encourage entertainment uses that support a night time economy in major activity centres.

02.03-2 Environmental and landscape values

27/06/2024
C225brim

Brimbank has a distinct landscape character formed by the Victorian Volcanic Plain Bioregion and contains areas of remnant grasslands, wetlands, woodlands, riparian terrain and escarpment shrubland vegetation that provides habitat for critically endangered species of National and State listed fauna and flora.

Key environmental and landscape values are shown on the map at Clause 02.04.

Brimbank’s waterways are important to the character of the municipality and function as habitat corridors, linear recreation parklands and stormwater drainage corridors. They include the Maribyrnong River, Kororoit, Taylors, Jones, Jacksons, Steele and Stony Creeks. Built form encroachment along Brimbank’s waterway escarpments and ridgelines needs to be managed.

Linear trails are encouraged along all of Brimbank’s waterway corridors. There is opportunity to extend unobstructed linear corridors and provide improvements and connections to parks and other destinations within and outside the municipality.

Strategic directions:

- Protect and enhance native vegetation and critical habitat within riparian environments.
- Support the provision of a network of habitat corridors for native flora and fauna.
- Support an open space corridor along the Maribyrnong River to protect its natural landscape character, indigenous values and endangered species habitat, and provide access to recreation opportunities.
- Ensure development along creek corridors, escarpments and ridgelines is sited and sensitively designed so it blends in with its natural landscape context.
- Protect and enhance the water quality of Brimbank's waterways, including the Maribyrnong River, Kororoit Creek, Taylors Creek, Jones Creek, Steele Creek and Stony Creek waterways.
- Encourage use and development that increases the extent and enhances the condition of natural habitat across the municipality.

02.03-3 Environmental risks and amenity

27/06/2024
C225brim

Climate change

Brimbank is particularly vulnerable to the impacts of climate change given the combined socio-economic, landscape and built environment characteristics. Brimbank City Council has declared a climate emergency and will seek to address the immediate challenge of climate change by becoming a low-carbon, resilient community.

Strategic directions:

- Encourage development that helps achieve Brimbank's zero net emissions by 2040 target.
- Support localised energy creation such as rooftop solar as part of new development and subdivision.
- Support development that incorporates environmentally sustainable design measures.
- Support the uptake of electric vehicles and associated infrastructure.
- Support integrated water management.
- Support urban greening and cooling.
- Reduce the urban heat island effect by increasing tree planting to assist in achieving a canopy cover of 30 per cent across the municipality.

Contaminated and potentially contaminated land and landfills

Contaminated and potentially contaminated land is an on-going issue in Brimbank resulting from current and historic land management practices and its industrial legacy. Contamination from on and off-site sources need to be addressed through sustainable land practices and environmental management, to protect the environment and human health.

Brimbank contains a number of known landfill sites. All except one are recognised as closed landfills and require sound onsite management and rehabilitation to mitigate impacts on surrounding areas.

Strategic directions:

- Mitigate the risk to the community and environment from landfill sites and land that is contaminated or potentially contaminated.
- Ensure risks associated with contaminated and potentially contaminated land are identified, investigated, and where necessary, remediated or managed prior to using or developing land.

Noise abatement

Part of the municipality is affected by the Melbourne Airport Environs Overlay (Schedules 1 and 2). Future expansion of Melbourne Airport is likely to change the extent of land that is impacted by aircraft noise.

Noise can impact sensitive uses such as residential and new mixed use developments adjoining freeways, arterial roads, train lines and loading areas in activity centres.

Strategic direction:

- Incorporate noise attenuation measures to protect residential amenity in developments under existing and known future flight paths where the development would be detrimentally affected by aircraft noise.

Non-residential use and development

A wide range of uses are compatible with residential land use. Uses can include medical centres, convenience stores, schools, child care centres and service stations, providing local access to services within residential areas and creating a reinforced sense of community. Non-residential uses in Brimbank need to be managed to ensure the amenity of the residential area is not negatively impacted upon.

Strategic directions:

- Ensure non-residential buildings in residential areas integrate with the streetscape in terms of design, form, massing and setbacks.
- Ensure the days and hours of operation, and location and access to car parking and bicycle facilities, protect the amenity of existing residential land use.

Land use compatibility

Industrial precincts in Brimbank facilitate a wide range of economic and social activities, however managing the relationship between industrial and non-industrial uses is a challenge. This issue is made particularly challenging as some of Brimbank's residential areas border established industrial precincts containing heavy industry. This has resulted in on and off-site amenity impacts from odour, dust, pollutants, noise emissions and contamination.

Strategic directions:

- Protect the ongoing operation of existing industrial uses.
- Minimise off-site amenity impacts from industrial uses on residential uses by encouraging separation distances between industrial use and development and residential use and development.
- Reduce the potential risk from industrial uses on new residential use and development by ensuring risk has been suitably addressed.
- Encourage design and construction techniques in new developments that will minimize off-site amenity impacts from industrial uses on residential uses.

Major hazard facilities

There are two major hazard facilities (MHFs) in Brimbank, which manufacture and supply LPG gas and chemical products. Both facilities are valued for their contribution to the State and local economy. High voltage power line easements and high pressure gas and aviation fuel pipelines also traverse the municipality. Land use and development should not undermine the continued operation and development of these facilities.

Strategic directions:

- Protect the ongoing operation of MHFs and pipelines.
- Discourage sensitive uses from locating within the threshold distance of an existing MHF.

02.03-4 Built environment and heritage

27/06/2024
C225brim

Built environment

Throughout the municipality the quality of the built environment, streetscapes and development along our river valleys and escarpments varies. Improving the built form and creating a sense of identity in the municipality by the community is a priority for Brimbank City Council.

Well-designed, sustainable development that contributes to the desired neighbourhood, industrial and commercial character is key to improving the community's sense of pride and will be encouraged.

A proliferation of excessive and poorly designed signage can detract from the appearance of an area, particularly along freeways, roads and major entrances.

Strategic directions:

- Encourage innovative built form, configurations and design in areas where a change in character is encouraged.
- Support development that incorporates durable and weather resistant building materials.
- Facilitate the delivery of attractive, safe, high amenity neighbourhoods that have a strong sense of identity.
- Enhance the appearance of industrial and employment areas through building form, innovative design treatments and landscaping.
- Ensure signage and associated structures do not detract from the natural or built environment and contribute to the improved appearance of the site and surrounds.

Heritage

A sense of Brimbank's history is reflected in the heritage places that were founded upon its early rural development, the later industrial development of Albion and Sunshine, and the municipality's planned suburbs and estates. The volcanic plains were one of the earliest areas of post-contact settlement in Victoria and from the early 1800s, they were transformed by large pastoral estates. Keilor is significant in part as a stopover on the way to the gold diggings. Heritage places dating back to the early 1900s are also located throughout the municipality. The recognition, retention, enhancement and preservation of these historic assets are a priority.

Brimbank also has rich Aboriginal cultural heritage with over 400 known places, objects and landscapes of cultural heritage significance. This includes a distinct natural landscape, including important remnant grasslands and wetlands, rock-faces, basalt escarpments and the incised valleys of the Maribyrnong River and Kororoit Creek.

Strategic direction:

- Manage development within the heritage overlay to ensure the conservation and protection of heritage places.

02.03-5 Housing

27/06/2024
C225brim

Residential development

As there are no greenfield development sites remaining in Brimbank, population growth will be accommodated through high and medium density infill development.

Brimbank encourages increased housing diversity, including a range of dwelling types to accommodate changing household demographics and an increasing population. The increased provision of affordable housing, including social housing, is encouraged.

Strategic directions:

- Encourage increased residential development in and around activity centres that are well serviced by public transport, services and community facilities.
- Encourage higher density development in substantial change areas as shown on the Housing map at Clause 02.04, comprising:
  - Sunshine Metropolitan Activity Centre.
  - Sydenham Major Activity Centre.
  - Deer Park Major Activity Centre, except for areas impacted by major hazard facilities.
  - Deer Park Railway Station, except for areas impacted by major hazard facilities.

  - St Albans Major Activity Centre.
  - Keilor Downs Neighbourhood Activity Centre.

- Encourage medium density development in incremental change areas as shown on the Housing map at Clause 02.04.

02.03-6 Economic development

27/06/2024
C225brim

Brimbank consistently experiences strong economic growth and investment in the commercial and industrial sectors.

Brimbank has the second largest gross supply of zoned industrial land in the western region, supporting many employment generating uses that contribute substantially to the local, regional and State economy.

Three types of land use precincts have been identified to preserve the supply of land and enhance opportunities for economic growth in strategic locations. The Economic development map at Clause 02.04 shows Brimbank's locally significant Employment, Industrial and Transitional precincts, activity centres, and other areas that support significant employment and education. These include the Western State Significant Industrial Precinct, the Sunshine National Employment and Innovation Cluster, the Sunshine Health, Wellbeing and Education Precinct, and various tertiary education precincts.

Strategic directions:

- Support the development of Employment, Industrial and Transitional Precincts as desirable locations for vibrant and diverse industries and world class businesses.
- Encourage development that enables Employment, Industrial and Transitional Precincts to be highly accessible and connected to public and active transport.

Industry

A number of key industry clusters have developed in sectors of the Brimbank economy. These clusters are important as collectively they provide opportunity for other businesses in the production chain.

The Western State Significant Industrial Precinct accommodates large scale national and international manufacturing, freight, resource recovery and recycling, warehousing, transport and logistics operations.

Transitional Precincts are currently zoned for industrial land uses but in the long-term may not be suitable as industrial or employment areas.

Strategic directions:

- Support the sustainable development of Industrial Precincts so they continue to be an important source of employment and economic opportunity for Brimbank and the western region.
- Retain and support the zoning of land that prioritises industrial land uses.
- Support the gradual transition of existing industrial zoned land identified in Transitional Precincts to higher order uses.

02.03-7 Transport

27/06/2024
C225brim

Brimbank is well-connected within the Victorian transport network, as shown in the Transport map at Clause 02.04. Multiple transport nodes provide connections to central Melbourne, rural Victoria, the Port of Melbourne and Melbourne Airport. Key freeways including the Calder, Tullamarine, West Gate and Hume Freeways also connect Brimbank to the Victorian transport network.

Brimbank is a key hub in Melbourne's west due to existing and planned transport investment including a new rail line for the Melbourne Airport Rail (SRL Airport), with a key interchange at Sunshine Railway Station.

The public transport network in Brimbank includes the 903 SmartBus, and the Sunbury and Melton railway lines. These are supported by the Geelong, Ballarat and Bendigo regional lines.

The Sunbury line connects the Sunshine Metropolitan Activity Centre to the St Albans and Sydenham Activity Centres.

Brimbank supports a variety of transport modes. However, private cars are relied on for access to employment, retail and recreation, and to maintain social connection. Past car parking management approaches have sought to satisfy demand by increasing supply. This approach can incentivise car use and conflict with sustainability aspirations seeking less traffic congestion and more walking, cycling and public transport use. To address this conflict, sustainable transport options will be prioritised. Existing pressure on the road network is expected to increase as the growth areas of Melton and Wyndham develop.

Strategic directions:

- Support the development of planned rail grade separations along the Melton and Sunbury line.
- Support improvements to the transport network that will increase connectivity, reduce congestion and encourage walking and cycling.
- Encourage the land footprint devoted to parking to reduce over time, as development increases and consolidation occurs.
- Encourage car parking in new development to be allocated and designed so that it does not incentivise car use and supports quality development and urban amenity.

Melbourne Airport

Strategic direction:

- Protect the operations of Melbourne Airport from development that could constrain the long-term functionality of the airport as a freight and passenger gateway for Melbourne.

02.03-8 Infrastructure

27/06/2024
C225brim

Community infrastructure

Brimbank City Council is committed to providing access to inclusive, well developed social and physical infrastructure. This will contribute to the health and wellbeing of the community and create opportunities to engage in community life.

Strategic direction:

- Provide, renew or adapt social and physical infrastructure to meet the changing needs of the community.

Open space

Open spaces make a significant contribution to the character of Brimbank's neighbourhoods and protect natural environments and cultural heritage.

The following three tier approach will guide the future development of Brimbank's open space network:

- Flagship Parks - serve a 3 kilometre walkable catchment, located near a landscape feature, have a sufficient size to accommodate a diverse range of facilities, are irrigated, and located on a principal trail network or main road. Flagship parks have the potential to provide café opportunities.

- Suburban Parks - serve a 1 kilometre walkable catchment, approximate size 0.6–1 hectare, irrigated.
- Neighbourhood Parks - 500 metre walkable catchment, approximate size 0.6-1 hectare.

Strategic directions:

- Ensure the use and development for Brimbank's open spaces is consistent with their categorisation.
- Develop and enhance the existing open space network to ensure all residents have equal access to open space within the municipality.
- Encourage the delivery of new open space through infill developments where there is insufficient provision of open space.

02.03-9 Gaming

27/06/2024
C225brim

Brimbank City Council is committed to minimising the impact of gambling on the most vulnerable members of the community.

Strategic direction:


- Direct electronic gaming machines away from locations where the net economic and social impact will be detrimental to the wellbeing of the community.

02.04 STRATEGIC FRAMEWORK PLANS


27/06/2024
C225brim

The plans contained in Clause 02.04 are to be read in conjunction with the strategic directions in Clause 02.03.


Context map




Housing map


HOUSING
To Bendigo
Rail improvements Sunbury to Cranbourne / Pakenham (including Metro Tunnel)
Melbourne Airport
PROPOSED-MELBOURNE AIRPORT RAIL
Calder Park
Taylors Lakes
Kings Road
Calder Freeway
Keilor North
Sydenham
Watergardens
SYDENHAM MAC
Melton Highway
Keilor
Keilor Downs
Keilor Park
Delahey
Keilor Plains
Taylors Road
ST ALBANS MAC
Kings Park
Station Road
Main Road W
Main Road E
St Albans
Sunshine Avenue
Kealba
Keilor East
Western Ring Road
Albanvale
St Albans Road
Victoria University St Albans Campus
Western Clinical School (Melbourne University & Victoria University)
Deer Park
BRIMBANK CENTRAL MAC
Ginifer
Cairnlea
Sunshine North
To Geelong/ Ballarat
REGIONAL RAIL LINK (Melton Line)
DEER PARK MAC
Ballarat Road
McIntyre Road
Victoria University Sunshine Campus
Albion
Ardeer
SUNSHINE MAC
Sunshine
Derrimut
Wright Street
To CBD
Western Freeway
Sunshine West
Somerville Road
Fairbairn Road
Brooklyn
Legend
Residential Strategic Investigation Areas
Incremental Change Area
Substantial Change Area
Metropolitan Activity Centre
Major Activity Centre
Neighbourhood Activity Centre
Education Precinct
Major Hazard Facilities (MHF)
Key environmental assets
Sunbury Green Wedge
Highways
Major Roads
Train line
Proposed Melbourne Airport Rail
Train Station
Key waterbodies
Non-conforming land use
Urban Growth Boundary
Municipal Boundary
Suburb Boundaries
0
1km
2km


Economic development map




Environmental and landscape values map




Transport map




Active transport map



Built environment and heritage map



Community infrastructure and open spaces map



10 PLANNING POLICY FRAMEWORK

31/07/2018
VC148

11 SETTLEMENT

02/09/2025
VC283

Planning is to anticipate and respond to the needs of existing and future communities through provision of zoned and serviced land for housing, employment, recreation and open space, commercial and community facilities and infrastructure.

Planning is to contribute towards:

- Housing for all Victorians.
- Accessible jobs and services.
- Great places, suburbs and towns.
- Sustainable environments.
- Self-determination and caring for Country.

Planning is to recognise the need for, and as far as practicable contribute towards:

- Health, wellbeing and safety.
- Diversity of choice.
- Adaptation in response to changing technology.
- Economic viability.
- A high standard of environmental sustainability, urban design and amenity.
- Climate change adaptation and mitigation.
- Prevention of land, water, air and noise pollution.
- Protecting, conserving and improving biodiversity, waterways and other natural resources.
- Accessibility.
- Land use and transport integration.
- Waste minimisation and resource recovery.

Planning is to prevent environmental, human health and amenity problems created by siting incompatible land uses close together.

Planning is to facilitate sustainable development that takes full advantage of existing settlement patterns and investment in transport, utility, social, community and commercial infrastructure and services.

11.01 VICTORIA

31/07/2018
VC148

11.01-1S Settlement

02/09/2025
VC283

Objective

To facilitate the sustainable growth and development of Victoria and deliver choice and opportunity for all Victorians through a network of settlements.

Strategies

Plan for the delivery of 2.24 million homes across Victoria by 2051.

Develop sustainable communities through a settlement framework that:

- Offers a range of housing choices.
- Provides convenient access to jobs, services, infrastructure and community facilities.
- Takes into account regional and municipal contexts and frameworks.

Focus investment and growth in:

- Melbourne Central City.
- Metropolitan Activity Centres and Suburban Rail Loop Precincts in Metropolitan Melbourne.
- Priority Precincts (including the Suburban Rail Loop East Precincts).
- Major regional cities of Ballarat, Bendigo and Geelong.
- Regional cities of Horsham, Latrobe City, Mildura, Shepparton, Wangaratta, Warrnambool and Wodonga.

Manage the expansion of settlements by:

- Creating and reinforcing settlement boundaries. Where no settlement boundary is identified, limit the expansion of a settlement to the extent of existing urban zoned land.
- Promoting and capitalising on opportunities for urban renewal and infill redevelopment.
- Limiting urban sprawl and directing growth into existing settlements.
- Ensuring land that may be required for future urban expansion is not compromised.

Provide for growth in population and development of facilities and services across a regional or sub-regional network in accordance with housing targets.

Plan for development and investment opportunities that make best use of existing and planned transport infrastructure.

Coordinate transport, communications and economic linkages between settlements through the identification of servicing priorities.

Strengthen transport links on national networks for the movement of commodities.

Deliver networks of high-quality integrated settlements, suburbs and towns that:

- Are great places with a strong identity and sense of place.
- Are inclusive, prosperous, liveable and sustainable.
- Comprise a form and density that supports healthy, active and sustainable transport.
- Are based around compact existing or planned activity centres to maximise accessibility to facilities and services.
- Concentrate retail, office-based employment, community facilities and services in central locations.

Facilitate environmentally resilient settlements by:

- Integrating the management of water resources into the urban environment in a way that supports water security, public health, environment and amenity outcomes.

- Minimising exposure to natural hazards.
- Contributing to net zero greenhouse gas emissions through renewable energy infrastructure and energy efficient urban layout and urban design.
- Supporting metropolitan and regional climate change adaption and mitigation measures.
- Supporting cooling and greening measures for urban areas.

Policy guidelines

Consider as relevant:


- Any settlement boundary identified in a document incorporated into this planning scheme.

Policy documents

Consider as relevant:

- *Plan for Victoria* (Department of Transport and Planning, 2025)
- *Victoria's housing Statement - The Decade Ahead 2024-2034* (Department of Premier and Cabinet, 2023)

Victoria Settlement Framework Plan



11.01-1R Settlement - Metropolitan Melbourne

02/09/2025
VC283

Strategies

Maintain a permanent urban growth boundary around Melbourne to create a more consolidated, sustainable city and protect the values of non-urban land.

Focus investment and growth in:

- Melbourne Central City.
- Employment and Innovation Areas.
- Metropolitan Activity Centres.
- Priority Precincts, including Suburban Rail Loop Precincts.
- Activity Centres - Housing Choice and Stations.
- State-Significant Industrial Precincts.
- Transport Gateways.
- Health and Education Precincts.

Facilitate substantial growth and change in employment, health and education precincts to help meet the needs of Melbourne's rapidly growing population.

Develop a series of Priority Precincts that provide for an expanded Melbourne central city to support jobs and housing choice across Metropolitan Melbourne.

Develop Employment and Innovation Areas centred around medical, research and tertiary institutions that foster the development of emerging industries.


Create mixed use neighbourhoods at varying densities, including through the development of urban-renewal precincts and Activity Centres - Housing Choice and Stations.

Develop Metropolitan Activity Centres as:

- Higher-order centres providing a diverse range of jobs, activities and housing for catchments well-served by public transport.
- Major locations for service delivery, including of government, health, justice and education services. It also provides many retail and commercial opportunities.

Support a network of activity centres of varying size, role and function.

Melbourne Settlement Framework Plan



11.01-1R Green wedges - Metropolitan Melbourne

31/07/2018
VC148

Objective

To protect the green wedges of Metropolitan Melbourne from inappropriate development.

Strategies

Promote and encourage the key features and related values of each green wedge area.

Support development in the green wedge that provides for environmental, economic and social benefits.

Consolidate new residential development in existing settlements and in locations where planned services are available and green wedge values are protected.

Plan and protect major state infrastructure and resource assets, such as airports and ports with their associated access corridors, water supply dams, water catchments and waste management and recycling facilities.

Protect important productive agricultural areas such as Werribee South, the Maribyrnong River flats, the Yarra Valley, Westernport and the Mornington Peninsula.

Support existing and potential agribusiness activities, forestry, food production and tourism.

Protect areas of environmental, landscape and scenic value such as biodiversity assets, national and state parks, Ramsar wetlands and coastal areas.

Protect significant resources of stone, sand and other mineral resources for extraction purposes.

Provide opportunities for renewable energy generation.

Policy documents

Consider as relevant:

- *Upper Yarra Valley and Dandenong Ranges Region - Regional Strategy Plan* (1996)

11.01-1L Sunbury green wedge

27/06/2024
C225brim

Policy application

This policy applies to the Brimbank portion of the wider Sunbury Green Wedge, which includes all land located outside the Urban Growth Boundary.

Objective

To protect the environmental, recreational, agricultural, and visual values of the area.

Strategies

Facilitate an open space recreation and habitat corridor along the green wedge portion of the Maribrynong River, including the provision of a continuous shared path.

Minimise visual impacts from development through the use of muted tones and non-reflective building materials, particularly along escarpments, ridgelines and areas clearly visible from roads.

Protect views and sightlines to highly visible landscapes within the Maribyrnong River Valley from visually dominant buildings and works, including signage.

Protect views and sightlines along the Maribrynong River escarpment, and to and from the city skyline.

Allow the expansion of existing non-rural uses only within existing site boundaries.

Encourage sustainable water use and management in order to provide sufficient supply for environmental flows as well as agricultural, recreation and residential uses.

Policy documents

Consider as relevant:

- *Brimbank Green Wedge Management Plan* (Brimbank City Council, 2010)

11.02 MANAGING GROWTH

31/07/2018
VC148

11.02-1S Development capacity

02/09/2025
VC283

Objective

To ensure sufficient development opportunities are available to meet the needs of current and future Victorians.

Strategies

Ensure that sufficient land is available to meet forecast demand and the needs of current and future Victorians for commercial, retail, recreational, institutional and other community needs.

Ensure that at least a 15 year supply of land and development capacity is available to meet housing targets.

Plan to accommodate housing targets and provide clear direction on the locations where growth should occur and ensure sufficient realisable capacity in planning schemes.

Ensure ongoing development opportunities and supporting infrastructure are available to support sustainable urban development.

Planning for urban growth should consider:

- Opportunities to consolidate, redevelop and intensify existing urban areas with good access to jobs and services.
- The liveability of neighbourhoods and delivery of quality urban landscapes.
- The limits of land capability and natural hazards and environmental quality.
- Service limitations and the costs of providing infrastructure.

Maintain access to productive natural resources and an adequate supply of well-located land for energy generation, infrastructure and industry.

Restrict rural residential development that would compromise future development at higher densities.

Policy guidelines

Consider as relevant:

- Victorian Government population projections and land supply estimates.

Policy documents

Consider as relevant:

- *Plan for Victoria* (Department of Transport and Planning, 2025)
- *Melbourne Industrial and Commercial Land Use Plan* (Department of Environment, Land, Water and Planning, 2020)
- *Industrial and Commercial Land Classifications* (Department of Transport and Planning, 2025)

11.02-2S Structure planning

02/09/2025
VC283

Objective

To facilitate the fair, orderly, economic and sustainable use and development of urban areas.

Strategies

Give clear direction on preferred locations for investment.

Ensure effective planning and management of the land use and development of an area through the preparation of relevant plans.

Undertake comprehensive planning for existing areas undergoing transition and new areas to support sustainable communities that offer high-quality, frequent and safe local and regional public transport and a range of local activities for living, working and recreation.

Undertake the preparation of a hierarchy of structure plans or precinct structure plans that:

- Address the strategic and physical context of the location, including increased physical risks associated with climate change.
- Provide the broad planning framework for an area as well as the more detailed planning requirements for neighbourhoods and precincts, where appropriate.
- Deliver sufficient development capacity for residential development to ensure housing targets can be met.
- Deliver sufficient development capacity for industrial and commercial development to ensure an appropriate supply of land to meet local demand.

Structure plans should:

- Protect and enhance areas of natural and cultural significance.
- Address environmental risk and amenity.
- Support the effective management of natural resources.
- Deliver a quality built environment.
- Support the delivery of a diverse range of lot sizes and housing typologies.
- Deliver housing and population densities that make local services and transport viable.
- Support economic development.
- Facilitate the development of walkable neighbourhoods.
- Facilitate the use of active and sustainable transport modes.
- Facilitate the logical and efficient provision of infrastructure.
- Facilitate the use of existing infrastructure and services.
- Encourage renewable energy generation, storage and distribution.
- Incorporate integrated water management and urban greening.

Policy document

Consider as relevant:

- *Precinct Structure Planning Guidelines: New Communities in Victoria* (Victorian Planning Authority, 2021).

11.02-3S Sequencing of development

02/09/2025
VC283

Objective

To manage the sequence of development in areas of growth so that services are available from early in the life of new communities.

Strategies

Define preferred development sequences in areas of growth to better coordinate infrastructure planning and funding.

Use staging plans to align the delivery of public infrastructure and services with housing and employment.

Ensure that new land is released in areas of growth in a timely fashion to facilitate coordinated and cost-efficient provision of local and regional infrastructure.

Require new development to make a financial contribution to the provision of infrastructure such as community facilities, public transport and roads.

Improve the coordination and timing of infrastructure and service delivery in areas of growth.

Support opportunities to co-locate facilities.

Ensure that planning for water supply, sewerage and drainage works receives high priority in early planning for areas of growth.

Policy documents

Consider as relevant:

- *North Growth Corridor Plan* (Victoria Planning Authority, 2012)
- *West Growth Corridor Plan* (Victoria Planning Authority, 2012)
- *Sunbury Growth Corridor Plan* (Victoria Planning Authority, 2012)
- *South East Growth Corridor Plan* (Victoria Planning Authority, 2012)
- *Precinct Structure Planning Guidelines: New Communities in Victoria* (Victorian Planning Authority, 2021)
- *Ministerial Direction No. 12 – Urban Growth Areas*

11.03 PLANNING FOR PLACES

31/07/2018
VC148

11.03-1S Activity centres and precincts

02/09/2025
VC283

Objective

To encourage the concentration of major retail, residential, commercial, administrative, entertainment and cultural developments into activity centres with good public transport services.

Strategies

Build up the central activity areas of Major regional cities, Metropolitan activity centres, Priority Precincts, Suburban Rail Loop Precincts and Activity Centres - Housing Choice and Stations as a focus for high-quality development, activity and living that:

- Are a focus for business, shopping, working, leisure and community facilities.
- Provide different types of housing, including forms of higher density housing.
- Are connected by transport.
- Maximise choices in services, employment and social interaction.

Undertake strategic planning for the use and development of land in and around Major regional cities, Metropolitan activity centres, Priority Precincts, Suburban Rail Loop Precincts and Activity Centres - Housing Choice and Stations and their residential catchments.

Encourage a diversity of housing types at higher densities in and around Major regional cities, Metropolitan activity centres, Priority Precincts, Suburban Rail Loop Precincts and Activity Centres - Housing Choice and Stations and their residential catchments.

Reduce the number of private motorised trips by concentrating activities that generate high numbers of (non-freight) trips in highly accessible activity centres.

Improve access by walking, cycling and public transport to services and facilities.

Support the continued growth and diversification of activity centres to give communities access to a wide range of goods and services, provide local employment and support local economies.

Improve the social, economic and environmental performance and amenity of activity centres.

Policy documents

Consider as relevant:

- *Urban Design Guidelines for Victoria* (Department of Environment, Land, Water and Planning, 2017)
- *Apartment Design Guidelines for Victoria* (Department of Environment, Land, Water and Planning, 2021)
- *Precinct Structure Planning Guidelines: New Communities in Victoria* (Victorian Planning Authority, 2021)

11.03-1R Activity centres and precincts - Metropolitan Melbourne

02/09/2025
VC283

Strategies

Support the development and growth of Metropolitan activity centres and Suburban Rail Loop Precincts by ensuring they:

- Are able to accommodate significant growth for a broad range of land uses.
- Are supported with appropriate infrastructure.
- Are hubs for public transport services.
- Offer good connectivity for a regional catchment.
- Provide high levels of amenity.

Plan the activity centres network to support thriving, productive and sustainable communities through:

- The delivery of new homes to meet housing target at appropriate Activity Centres - Housing Choice and Stations.
- Activity Centres – Housing Choice and Stations as a focus for facilities and services.
- Moderated housing growth at other designated activity centres (those not identified as Activity centres – Housing Choice and Stations or Metropolitan activity centres).

Support new activity centres within convenient walking distance of homes in the design of new subdivisions and in areas where services are not in walking distance.

Locate significant new education, justice, community, administrative and health facilities that attract users from large geographic areas in or on the edge of Metropolitan Activity Centres or activity centres with good public transport.

Locate new small scale education, health and community facilities that meet local needs in or around activity centres.

11.03-1L-01 Activity centres - Brimbank

27/06/2024
C225brim

All centres strategies

Encourage employment generating uses by supporting an increase in office uses and non-retail commercial uses.

Encourage retail and office uses at ground level with office, commercial and residential uses located above ground level.

Prioritise commercial use and development within activity centres while allowing for residential development where it complements commercial use and the character of the activity centre.

Encourage development that respects and enhances existing views, vistas and gateways, to and from activity centres.

Encourage provision of art in the design of built form and the public realm.

Encourage flexible and adaptable open space to enable multiple uses, including exhibitions and temporary markets.

Support the provision of integrated community facilities.

Enhance sustainable personal transport connections between the Principal Public Transport Network and surrounding activity centres.

Support new and improved visual and physical connections to landscape features, open space, community services and surrounding residential areas.

Encourage development to incorporate existing natural or cultural landscape features such as open space corridors, waterways and areas of significant landscape value.

Policy documents

Consider as relevant:

- *Brimbank Activity Centre Strategy* (Brimbank City Council, 2018)
- *Brimbank Economic Development Strategy 2016 - 2020* (Brimbank City Council, 2016)

11.03-1L-02 Metropolitan and major activity centres - Brimbank

27/06/2024
C225brim

Sunshine Metropolitan Activity Centre strategies

Encourage development that supports the creation of a gateway at the northern end of Hampshire Road.

Encourage night-time uses that can provide for improved safety and vitality.

St Albans Major Activity Centre strategy

Encourage night-time uses that can provide for improved safety and vitality.

Deer Park Major Activity Centre strategies

Encourage increased housing density outside the threshold area of major hazard facilities.

Improve physical integration and connections within the centre and to surrounding areas, particularly to Ballarat Road and Deer Park Station.

Facilitate re-development of the private car park to the south of the centre.

Sydenham Major Activity Centre strategies

Encourage night-time uses that can provide for improved safety and vitality.

Locate community services and facilities around Sydenham Library.

Support 24 hour pedestrian movement and access through enclosed retailing facilities and in larger development sites.

Encourage development that provides distinct built form edges with active frontages to roadways.

Provide for pedestrian and cycle access to link with the Melton Highway and Kings Road.

Encourage development that respects and enhances views along Taylors Creek.

Encourage development that supports the use of Taylors Creek as a habitat corridor and high amenity, open space corridor for pedestrian movement and access.

Brimbank Central Major Activity Centre strategy

Encourage new development to be sited and designed to integrate the centre with the Deer Park Library.

11.03-1L-03 Neighbourhood activity centres - Brimbank

27/06/2024
C225brim

General strategies

Encourage retail use and development including a small supermarket and specialty shops, commensurate with the scale of the centre.

Encourage dwellings above ground floor commercial uses.

Encourage medical services.

Support the development of 20 minute neighbourhoods through a focus on liveability and increased services to support living locally.

Keilor Village strategy

Encourage development that would establish a gateway at the western entrance to the Village, along the Old Calder Highway.

11.03-1L-04 Local activity centres - Brimbank

27/06/2024
C225brim

Strategies

Encourage convenience food and non-food retailing commensurate with the scale of the centre.

Encourage dwellings above ground floor commercial uses.

Discourage further expansion.

Support the provision of integrated community facilities such as neighbourhood houses and playgrounds.

11.03-2S Growth areas

02/09/2025
VC283

Objective

To locate urban growth close to transport corridors and services and provide efficient and effective infrastructure to create sustainability benefits while protecting primary production, major sources of raw materials and valued environmental areas.

Strategies

Concentrate urban expansion into growth areas that are served by high-capacity public transport.

Implement the strategic directions in the growth corridor plans.

Deliver residential densities in the growth areas of Melbourne and Major regional cities of an average of at least:

- 30 dwellings per net developable hectare in locations within walkable distance of existing and proposed activity centres, train stations, major transport routes and public open spaces.
- 20 dwellings per net developable hectare in other growth area locations.

Provide housing diversity and choice through a mix of housing types, particularly in areas suitable for higher residential densities.

Deliver accessible, integrated and adaptable community infrastructure, including a high-quality network of public open space with opportunities for passive and active recreation.

Plan for the timely and adequate provision of public transport and local and regional infrastructure and services, in line with a preferred sequence of land release.

Provide for significant amounts of local employment opportunities and in some areas, provide large scale industrial or other more regional employment generators.

Create a network of mixed-use activity centres that are high quality, well designed and create a sense of place.

Provide a diversity of housing type and distribution.

Retain unique characteristics of established areas impacted by growth.

Protect and manage natural resources and areas of heritage, cultural and environmental significance.

Create well planned, easy to maintain high amenity, environmentally resilient and safe public realms that contribute to a sense of place, support cooling and greening, reduce opportunities for crime, improve perceptions of safety and increase levels of community participation.

Develop and implement plans for growth areas that will:

- Include objectives for each growth area.
- Identify the long term pattern of urban growth.
- Identify the location of broad urban development types, for example activity centre, residential, employment, freight centres and mixed use employment.
- Identify the boundaries of individual communities, landscape values and, as appropriate, the need for discrete urban breaks and how land uses in these breaks will be managed.
- Identify transport networks and options for investigation, such as future railway lines and stations, freight activity centres, freeways and arterial roads.
- Identify the location of open space to be retained for recreation, and/or biodiversity protection and/or flood risk reduction purposes guided and directed by regional biodiversity conservation strategies.
- Show significant waterways as opportunities for creating linear trails, along with areas required to be retained for biodiversity protection and/or flood risk reduction purposes.
- Identify appropriate uses for constrained areas, including quarry buffers.

Develop precinct structure plans consistent with the *Precinct Structure Planning Guidelines: New Communities in Victoria* (Victorian Planning Authority, 2021) to:

- Establish a sense of place and community.
- Create greater housing choice, diversity and affordable places to live.
- Create highly accessible and vibrant activity centres.
- Provide for local employment and business activity.
- Provide better transport choices.
- Respond to climate change and increase environmental sustainability.

- Deliver accessible, integrated and adaptable community infrastructure.
- Deliver 30 per cent tree canopy cover within the public realm and in open spaces (excluding areas dedicated to biodiversity or native vegetation conservation).

Policy documents

Consider as relevant:

- *North Growth Corridor Plan* (Victorian Planning Authority, 2012)
- *West Growth Corridor Plan* (Victorian Planning Authority, 2012)
- *Sunbury Growth Corridor Plan* (Victorian Planning Authority, 2012)
- *South East Growth Corridor Plan* (Victorian Planning Authority, 2012)
- *Precinct Structure Planning Guidelines: New Communities in Victoria* (Victorian Planning Authority, 2021)
- *Ministerial Direction No. 12 – Urban Growth Areas*

11.03-3S Peri-urban areas

02/09/2025
VC283

Objective

To manage growth in peri-urban areas to protect and enhance their identified valued attributes.

Strategies

Identify and protect areas that are strategically important for the environment, biodiversity, landscape, open space, water, agriculture, energy, recreation, tourism, environment, cultural heritage, infrastructure, extractive and other natural resources.

Enhance the character, identity, attractiveness and amenity of peri-urban towns.

Prevent dispersed settlement and provide for non-urban breaks between urban areas.

Ensure development is linked to the timely and viable provision of physical and social infrastructure.

Improve connections to regional and metropolitan transport services.

11.03-4S Coastal settlement

02/09/2025
VC283

Objective

To plan for sustainable coastal development.

Strategies

Plan and manage coastal population growth and increased visitation so that impacts do not cause unsustainable use of coastal resources.

Support a network of diverse coastal settlements that provide for a broad range of housing types, economic opportunities and services.

Minimise linear urban sprawl along the coastal edge and ribbon development in rural landscapes.

Protect areas between settlements for non-urban use.

Limit development in identified coastal hazard areas, on ridgelines, primary coastal dune systems, shorelines of estuaries, wetlands and low-lying coastal areas, or where coastal processes may be detrimentally impacted.

Encourage the restructure of old and inappropriate subdivisions to reduce development impacts on the environment.

Ensure a sustainable water supply, stormwater management and sewerage treatment for all development.

Minimise the quantity and enhance the quality of stormwater discharge from new development into the ocean, bays and estuaries.

Prevent the development of new residential canal estates.

Policy documents

Consider as relevant:

- *Marine and Coastal Policy* (Department of Environment, Land, Water and Planning, 2020)
- *Marine and Coastal Strategy* (Department of Environment, Land, Water and Planning, 2022)
- *Siting and Design Guidelines for Structures on the Victorian Coast*(Department of Environment, Land, Water and Planning, 2020)

11.03-5S Distinctive areas and landscapes

30/04/2021
VC185

Objective

To recognise the importance of distinctive areas and landscapes to the people of Victoria and protect and enhance the valued attributes of identified or declared distinctive areas and landscapes.

Strategies

Recognise the unique features and special characteristics of these areas and landscapes.

Implement the strategic directions of approved Localised Planning Statements and Statements of Planning Policy.

Integrate policy development, implementation and decision-making for declared areas under Statements of Planning policy.

Recognise the important role these areas play in the state as tourist destinations.

Protect the identified key values and activities of these areas.

Enhance conservation of the environment, including the unique habitats, ecosystems and biodiversity of these areas.

Support use and development where it enhances the valued characteristics of these areas.

Avoid use and development that could undermine the long-term natural or non-urban use of land in these areas.

Protect areas that are important for food production.

Policy documents

Consider as relevant:

- *Bellarine Peninsula Localised Planning Statement* (Victorian Government, 2015)
- *Macedon Ranges Statement of Planning Policy* (Victorian Government, 2019)
- *Mornington Peninsula Localised Planning Statement* (Victorian Government, 2014)
- *Yarra Ranges Localised Planning Statement* (Victorian Government, 2017)

11.03-6S Regional and local places

31/07/2018
VC148

Objective

To facilitate integrated place-based planning.

Strategies

Integrate relevant planning considerations to provide specific direction for the planning of sites, places, neighbourhoods and towns.

Consider the distinctive characteristics and needs of regional and local places in planning for future land use and development.

12 ENVIRONMENTAL AND LANDSCAPE VALUES

10/06/2022
VC216

Planning should help to protect the health of ecological systems and the biodiversity they support (including ecosystems, habitats, species and genetic diversity) and conserve areas with identified environmental and landscape values.

Planning must implement environmental principles for ecologically sustainable development that have been established by international and national agreements. Foremost amongst the national agreements is the Intergovernmental Agreement on the Environment, which sets out key principles for environmental policy in Australia. Other agreements include the National Strategy for Ecologically Sustainable Development, National Greenhouse Strategy, the National Water Quality Management Strategy, Australia's Strategy for Nature 2019-2030, the National Forest Policy Statement and National Environment Protection Measures.

Planning should protect, restore and enhance sites and features of nature conservation, biodiversity, geological or landscape value.

12.01 BIODIVERSITY

31/07/2018
VC148

12.01-1S Protection of biodiversity

20/03/2023
VC229

Objective

To protect and enhance Victoria's biodiversity.

Strategies

Use biodiversity information to identify important areas of biodiversity, including key habitat for rare or threatened species and communities, and strategically valuable biodiversity sites.

Strategically plan for the protection and conservation of Victoria's important areas of biodiversity.

Ensure that decision making takes into account the impacts of land use and development on Victoria's biodiversity, including consideration of:

- Cumulative impacts.
- Fragmentation of habitat.
- The spread of pest plants, animals and pathogens into natural ecosystems.

Avoid impacts of land use and development on important areas of biodiversity.

Consider impacts of any change in land use or development that may affect the biodiversity value of national parks and conservation reserves or nationally and internationally significant sites; including wetlands and wetland wildlife habitat designated under the Convention on Wetlands of International Importance (the Ramsar Convention) and sites utilised by species listed under the Japan-Australia Migratory Birds Agreement (JAMBA), the China-Australia Migratory Birds Agreement (CAMBA), or the Republic of Korea-Australia Migratory Bird Agreement (ROKAMBA).

Assist in the identification, protection and management of important areas of biodiversity.

Assist in the establishment, protection and re-establishment of links between important areas of biodiversity, including through a network of green spaces and large-scale native vegetation corridor projects.

Support land use and development that contributes to protecting and enhancing habitat for indigenous plants and animals in urban areas.

Policy guidelines

Consider as relevant:

- State biodiversity information maintained by the Department of Energy, Environment and Climate Action.

Policy documents

Consider as relevant:

- *Any applicable biodiversity strategies, including the relevant Regional Catchment Strategy (prepared under Part 4 of the Catchment and Land Protection Act 1994)*
- *Biodiversity Conservation Strategy for Melbourne's Growth Corridors* (Department of Environment and Primary Industries, 2013)
- *Guidelines for the removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, 2017)
- *Protecting Victoria's Environment – Biodiversity 2037* (Department of Environment, Land, Water and Planning, 2017)
- *Victorian Waterway Management Strategy* (Department of Environment and Primary Industries, 2013)

12.01-1L Protection of biodiversity - Brimbank

27/06/2024
C225brim

Strategies

Increase connectivity between fragmented areas of biodiversity through the use of habitat corridors.

Support development that increases the diversity and sustainability of fauna habitat and remnant vegetation, including through adaptive management techniques.

Encourage the retention of native vegetation along railway corridors.

Avoid the degradation of critically endangered remnant grasslands and endangered vegetation communities.

Ensure development and any associated earth works do not change natural water flows or compromise the viability of nearby patches of native vegetation.

Ensure development adjoining native vegetation and habitat corridors along waterways is adequately fenced and set back to prevent weed invasion and disturbance to the site's land form and vegetation.

Encourage indigenous planting as part of development on land adjacent to and within habitat corridors.

Policy documents

Consider as relevant:

- *Brimbank Biodiversity Strategy 2012 - 2022* (Brimbank City Council, 2012)
- *Brimbank Habitat Connectivity Plan 2018 - 2023* (Brimbank City Council, 2018)

12.01-2S Native vegetation management

20/03/2023
VC229

Objective

To ensure that there is no net loss to biodiversity as a result of the removal, destruction or lopping of native vegetation.

Strategies

Ensure decisions that involve, or will lead to, the removal, destruction or lopping of native vegetation, apply the three-step approach in accordance with the *Guidelines for the removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, 2017):

- Avoid the removal, destruction or lopping of native vegetation.
- Minimise impacts from the removal, destruction or lopping of native vegetation that cannot be avoided.
- Provide an offset to compensate for the biodiversity impact from the removal, destruction or lopping of native vegetation.

Policy guidelines

Consider as relevant:

- State biodiversity information maintained by the Department of Energy, Environment and Climate Action.

Policy documents

Consider as relevant:

- *Guidelines for the removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, 2017)
- *Assessor's handbook – applications to remove, destroy or lop native vegetation* (Department of Environment, Land, Water and Planning, 2017)

12.02 MARINE AND COASTAL ENVIRONMENT

06/09/2021
VC171

12.02-1S Protection of the marine and coastal environment

20/03/2023
VC229

Objective

To protect and enhance the marine and coastal environment.

Strategies

Manage privately-owned foreshore consistently with the adjoining public land.

Protect coastal and foreshore environments and improve public access and recreation facilities around Port Phillip Bay and Western Port by focusing development in areas already developed or in areas that can tolerate more intensive use.

Enhance the ecological values of the ecosystems in the marine and coastal environment.

Protect and enhance the overall extent and condition of native habitats and species diversity distributions across public and private land in the marine and coastal environment.

Encourage revegetation of cleared land abutting coastal reserves.

Minimise direct, cumulative and synergistic effects on ecosystems and habitats.

Maintain the natural drainage patterns, water quality and biodiversity in and adjacent to coastal estuaries, wetlands and waterways.

Maintain and enhance water and soil quality by minimising disturbance of sediments.

Avoid disturbance of coastal acid sulfate soils.

Protect and enhance natural features, landscapes, seascapes and public visual corridors.

Plan for marine development and infrastructure to be sensitive to marine national parks and environmental assets.

Protect the heritage values, the aesthetic quality of locations, cultural links with maritime activities, sea country and sense of place.

Policy guidelines

Consider as relevant:

- Any applicable Regional and Strategic Partnership Product, environmental management plan or coastal and marine management plan approved under the *Marine and Coastal Act 2018* or *National Parks Act 1975*

Policy documents

Consider as relevant:

- *Coastal Spaces Landscape Assessment Study* (Department of Sustainability and Environment, 2006)
- *Marine and Coastal Policy* (Department of Environment, Land, Water and Planning, 2020)
- *Marine and Coastal Strategy* (Department of Environment, Land, Water and Planning, 2022)
- *Siting and Design Guidelines for Structures on the Victorian Coast* (Department of Environment, Land, Water and Planning, 2020)
- *Victorian Best Practice Guidelines for Assessing and Managing Coastal Acid Sulfate Soils* (Department of Environment, Land, Water and Planning, 2010)
- *Victorian Coastal Acid Sulfate Soils Strategy* (Department of Sustainability and Environment, 2009)

12.02-2S Marine and coastal Crown land

20/03/2023
VC229

Objective

To ensure the use and development of marine and coastal Crown land is ecologically sustainable, minimises impacts on cultural and environmental values, and improves public benefit for current and future generations.

Strategies

Design, locate and maintain buildings and structures to effectively manage:

- Any increase in exposure to coastal hazard risk, including rates of sea level rise, erosion, accretion or inundation.
- Exposure to public health and safety risks.
- Any detrimental impacts (in particular increased hazard risk) on neighbouring Crown or private land.
- Adverse effects on the environment and associated uses and values.
- Impact on marine and coastal functions and processes.

Ensure the siting and design of development on marine and coastal Crown land:

- Facilitates shared infrastructure and the use of land for more than one use.
- Uses materials and finishes that are sympathetic to the coastal environment.
- Is durable in the long term.
- Minimises the environmental footprint.

Ensures that use and development on or adjacent to marine and coastal Crown land:

- Maintains safe, equitable public access.
- Improves public benefit.
- Demonstrates need and has a coastal dependency.
- Minimises loss of public open space.

Policy guidelines

Consider as relevant:

- Any applicable Victorian Environmental Assessment Council recommendations
- The purpose for which land is reserved under the *Crown Land (Reserves) Act 1978*
- Any relevant environmental management plan or coastal and marine management plan approved under the *Marine and Coastal Act 2018* or *National Parks Act 1975*

Policy documents

Consider as relevant:

- *Marine and Coastal Policy* (Department of Environment, Land, Water and Planning, 2020)
- *Marine and Coastal Strategy* (Department of Environment, Land, Water and Planning, 2022)
- *Siting and Design Guidelines for Structures on the Victorian Coast* (Department of Environment, Land, Water and Planning, 2020)

12.03 WATER BODIES AND WETLANDS

31/07/2018
VC148

12.03-1S River and riparian corridors, waterways, lakes, wetlands and billabongs

16/12/2022
VC201

Objective

To protect and enhance waterway systems including river and riparian corridors, waterways, lakes, wetlands and billabongs.

Strategies

Protect the environmental, cultural, landscape values of all waterway systems as significant economic, environmental and cultural assets.

Conserve waterway systems and the landscapes and environmental values surrounding them by protecting ecological values, indigenous vegetation, terrestrial and aquatic habitats and encouraging biodiversity.

Sensitively design and site development to maintain and enhance the waterway system and the surrounding landscape setting, environmental assets, and ecological and hydrological systems.

Address the impacts of use and development on drought and flooding events at a catchment and site scale to protect the health and natural function of waterway systems and their surrounding landscape and environment.

Protect geomorphology, bank stability and flood management capacity to strengthen the environmental value and health of waterway systems by:

- Retaining, enhancing and re-establishing indigenous riparian vegetation along waterway systems, ensuring it responds to the bushfire risk of a location.
- Enhancing and re-establishing both terrestrial and aquatic habitats and their linkages along and surrounding waterway systems.
- Limiting earthworks in proximity to waterway systems to minimise alterations to geomorphology, natural drainage, natural flows and water quality.
- Facilitating the restoration of waterway systems through the removal of weeds, invasive species and pests.

Enhance a sense of place and landscape identity by:

- Conserving areas of identified Victorian Aboriginal cultural heritage significance relating to waterway systems.
- Retaining and re-establishing vegetation, including grasslands and canopy trees, surrounding waterway systems to enhance and connect to the landscape setting, ensuring it responds to the bushfire risk of a location.
- Protecting existing topographic features and maintaining a sense of naturalness through sensitive design and siting.

Retain and enhance the recreation and amenity values along waterway systems by:

- Planning for surrounding green spaces as recreation and tourism resources without adversely impacting environmental values and flood management capacity.
- Protecting and enhancing parklands for their economic, social and environmental values.
- Protecting and enhancing public access to waterway systems and surrounding parklands.
- Enhancing existing and providing new green links, pedestrian and cycle connections and open space.
- Discouraging privatisation of spaces that interface with or provide access to waterway systems.
- Avoiding overshadowing of waterway systems, their banks and adjacent public open space.
- Promoting safety by maximising visibility and passive surveillance and providing good connections and access.

Design and site development to maintain and enhance the natural environment of waterway systems by:

- Minimising the visual intrusion of development on the natural landscape views from major roads, bridge crossings, public open space, recreation trails and within waterway systems themselves.
- Ensuring development is visually subordinate to the local landscape setting, including through the use of vegetation to filter views of development.
- Ensuring development adjacent to waterways adopts high quality materials and respectful design and siting.
- Avoiding impeding the natural flow of waterways and future flood events.
- Directing growth to established settlements where water and wastewater can be managed.

Policy guidelines

Consider as relevant:

- Locating earthworks, including dams, a minimum of 30 metres from waterway systems.
- Locating development a minimum of 30 metres from the banks of waterway systems.
- The views of floodplain and waterway managers.
- Any regional catchment strategy and related plans approved under the Catchment and Land Protection Act 1994.

Policy documents

Consider as relevant:

- *Melbourne Water's Guidelines for Approval of Jetties* (Melbourne Water, 2011)
- *Healthy Waterways Strategy* (Melbourne Water, 2018)

12.03-1R Waterways of the West

16/12/2022
VC201

Objective

To maintain and enhance the natural landscape, biodiversity, cultural and social values, and the Traditional Owner living cultural heritage values of the waterways of Melbourne's west, including the Werribee River (Wirribi Yaluk), Maribyrnong River (Mirrangbamurn), Moonee Ponds Creek (Moonee Moonee), and associated tributaries and wetlands.

Strategies

Strengthen the natural environment and overall health of the waterways by protecting and enhancing both terrestrial and aquatic habitats and their linkages along the waterway corridors including:

- The Jacana Valley Parklands and the Trin Warren Tam-boore wetlands within the Moonee Ponds Creek.
- Newell's Paddock wetlands and Organ Pipes National Park within the Maribyrnong River corridor.
- Werribee Blue Box grassy woodlands, Cobbledicks Ford Reserve and Werribee Gorge State Park.
- The platypus and Growling Grass Frog habitats along the Werribee River corridor.
- Plains Grassland, Creekline Grassy Woodland and River Red Gum along the Little River.
- Smaller waterways such as Lollypop, Skeleton and Cherry creeks and Cunningham's and Edgar Road swamps.
- Coastal reserves and wetlands such as Cheetham Wetlands and Jawbone Coastal Reserve.

Ensure development protects and strengthens cultural heritage along waterways and at sensitive sites, including:

- Footscray Park and Brimbank Park.
- Stony Creek.
- Maribyrnong River valley from Braybrook to Maribyrnong.
- Moonee Ponds Creek Trail.
- Skeleton Waterholes Creek.
- Deep and Jacksons creeks and Emu Bottom Wetlands.
- Lower Werribee River

Promote a sense of place and landscape identity by:

- Enhancing a sense of remoteness that complements the waterway corridor and landscape setting, especially the sloping river valley landscape setting of the upper and middle reaches of the Maribyrnong River.
- Enhancing the landscape character along Stony, Laverton and Kororoit creeks.
- Retaining and re-establishing tree canopy and riparian vegetation cover along the waterways corridor including Werribee Blue Box and River Red Gum along the Werribee River.
- Maintaining and protecting the waterways' natural geomorphology and bank stability.
- Reducing the risk of erosion at key sites including the K Road Cliffs along Werribee River.
- Ensuring green linkages and public access to rivers and green spaces are protected and prioritised along the river corridors including the:
  - Werribee River Trail and Werribee Regional Parklands.

- Moonee Ponds Creek Trail.
- Steele Creek Trail.
- Maribyrnong River Trail, including around the former Department of Defence site.
- Stony Creek Trail.
- Kororoit Creek Trail.
- Footscray Wharf, Coode Island and the Port of Melbourne.

Policy documents

Consider as relevant:

- *Maribyrnong River Valley Design Guidelines* (Department of Planning and Community Development, 2010)

12.03-1L River corridors and waterways - Brimbank

27/06/2024
C225brim

General strategies

Encourage planting of local indigenous vegetation on land adjacent to river corridors and waterways.

Ensure development adjoining constructed waterways, including Stony Creek and Jones Creek, helps facilitate their natural re-instatement.

Ensure development does not result in fragmentation of waterway corridors.

Encourage the provision of linear trails along river corridors and waterways.

Encourage retention of native vegetation and habitat values along waterways and associated open space corridors.

Maribyrnong River Valley and Kororoit Creek strategies

Design development to respond to the landscape qualities along and adjacent to escarpments, ridgelines and waterways through building materials of muted colours and use of local landscape materials such as natural rocks, timber and native plantings.

Ensure any fencing abutting escarpments and ridgelines is visually transparent.

Ensure buildings, particularly their height and materials, complement the natural environment of the Maribyrnong River valley and the Kororoit Creek waterway.

Set back development along escarpment and ridgelines to accommodate landscaping that minimises the visual impacts of development.

Encourage development or subdivision along escarpment and ridgelines to front onto open space along the riparian corridor, and allow for habitat connectivity.

Discourage the construction of impervious areas adjacent to escarpment and ridgelines.

Design development to respond to the natural topography of the land and minimise cut and fill.

Position building mass away from any boundary abutting an escarpment or ridgeline.

Policy documents

Consider as relevant:

- *Kororoit Creek Regional Strategy 2005 - 2030* (Department of Sustainability, 2006)
- *Brimbank Green Wedge Management Plan* (Brimbank City Council, 2010)
- *Brimbank Habitat Connectivity Plan 2018 - 2023* (Brimbank City Council, 2018)

12.04 ALPINE AREAS

31/07/2018
VC148

12.04-1S Sustainable development in alpine areas

20/03/2023
VC229

Objective

To facilitate sustainable use and development of Alpine areas for year-round use and activity.

Strategies

Protect and manage significant environmental features and ecosystems, taking into account the sensitive and fragile nature of the alpine environment.

Ensure that the use and development of land is managed to minimise the disturbance of indigenous flora and fauna and sensitive landscapes.

Ensure that there is a mixture of use and development to cater for users of alpine areas in all seasons.

Recognise the distinct environments, infrastructure needs and capabilities to support different activities of each alpine resort and other alpine areas.

Provide for the development of consolidated alpine villages, including a diverse range of employment, social and economic opportunities.

Promote development for active recreation solely at Falls Creek, Lake Mountain, Mt Buffalo, Mt Baw Baw, Mt Buller and Mt Hotham.

Promote intensive residential and commercial development at Falls Creek, Mt Baw Baw, Mt Buller and Mt Hotham.

Maintain Mt Stirling as an all-season nature based tourist, recreational and educational resource.

Ensure that the sustainable long term planning and management of Victoria's six alpine resorts is consistent with the strategic directions contained in the *Alpine Resorts Strategic Plan 2020-2025 Responding to a Changing Climate* (Victorian Government, Alpine Resorts Co-ordinating Council, 2019).

Develop, monitor and regularly review the Alpine Resort Environmental Management Plans and Comprehensive Development Plans for each alpine resort, recognising their unique characteristics, constraints and opportunities.

Encourage best practice in design that responds to the alpine character of the area.

Ensure heritage places are protected and conserved, including Aboriginal cultural heritage and post contact heritage places.

Ensure that increases in skier, pedestrian and vehicular activity in the resorts do not compromise public safety or the accessibility and capacity of ski fields, services, commercial activity and development of trailheads.

Implement approved plans, manage development and work with Alpine Resort Management Boards to effectively operate alpine resorts and protect alpine resources.

Ensure that the use and development of land responds to potential environmental risks and contributes to maintaining or improving the environmental quality of alpine environments.

Policy guidelines

Consider as relevant:

- Any applicable approved Victorian Environmental Assessment Council recommendations.
- Any approved management plan or guideline endorsed by the Minister for Environment or Minister for Water.

Policy documents

Consider as relevant:

- *Alpine Resorts Strategic Plan 2020-2025 Responding to a Changing Climate* (Victorian Government, Alpine Resorts Co-ordinating Council, 2019)
- The Memorandum of Understanding in relation to the Co-operative Management of the Australian Alps National Parks, agreed to by the member states and territories of Victoria, Australian Capital Territory and New South Wales

12.05 SIGNIFICANT ENVIRONMENTS AND LANDSCAPES

31/07/2018
VC148

12.05-1S Environmentally sensitive areas

31/07/2018
VC148

Objective

To protect and conserve environmentally sensitive areas.

Strategies

Protect environmentally sensitive areas with significant recreational value from development that would diminish their environmental conservation or recreational values. These areas include the Dandenong and Macedon Ranges, the Upper Yarra Valley, Western Port and Port Phillip Bay and their foreshores, the Mornington Peninsula, the Yarra and Maribyrnong Rivers and the Merri Creek, the Grampians, the Gippsland Lakes and its foreshore, the coastal areas and their foreshores, Alpine areas and nominated urban conservation areas, historic buildings and precincts.

12.05-2S Landscapes

31/07/2018
VC148

Objective

To protect and enhance significant landscapes and open spaces that contribute to character, identity and sustainable environments.

Strategies

Ensure significant landscape areas such as forests, the bays and coastlines are protected.

Ensure development does not detract from the natural qualities of significant landscape areas.

Improve the landscape qualities, open space linkages and environmental performance in significant landscapes and open spaces, including green wedges, conservation areas and non-urban areas.

Recognise the natural landscape for its aesthetic value and as a fully functioning system.

Ensure important natural features are protected and enhanced.

12.06 SUSTAINABLE ENVIRONMENT

02/09/2025
VC283

12.06-1S Urban forests

02/09/2025
VC283

Objective

To protect and enhance tree canopy in urban areas.

Strategies

Contribute to achieving an overall 30 per cent tree canopy target for urban areas by:

- Encouraging the retention of existing canopy trees.
- Promoting the planting of new canopy trees:
  - Within the public realm and open space (excluding areas dedicated to biodiversity or native vegetation conservation).
  - On private land.

Ensuring that canopy tree species are appropriate for the locality, available space, growing conditions and future climate conditions.

Policy documents

Consider as relevant:

- *Trees for Cooler and Greener Streetscapes Planning and Design Guidelines* (Department of Environment, Land, Water and Planning, 2019)

13 ENVIRONMENTAL RISKS AND AMENITY

01/07/2021
VC203

Planning should strengthen the resilience and safety of communities by adopting a best practice environmental management and risk management approach.

Planning should identify, prevent and minimise the risk of harm to the environment, human health, and amenity through:

- Land use and development compatibility.
- Effective controls to prevent or mitigate significant impacts.

Planning should identify and manage the potential for the environment and environmental changes to impact on the economic, environmental or social wellbeing of society.

Planning should ensure development and risk mitigation does not detrimentally interfere with important natural processes.

Planning should prepare for and respond to the impacts of climate change.

13.01 CLIMATE CHANGE IMPACTS

31/07/2018
VC148

13.01-1S Natural hazards and climate change

05/09/2025
VC268

Objective

To minimise the impacts of natural hazards and adapt to the impacts of climate change through risk-based planning.

Strategies

Respond to the risks associated with climate change in planning and management decision making processes.

Identify at risk areas using the best available data and climate change science.

Integrate strategic land use planning with emergency management decision making.

Direct population growth and development to low risk locations.

Develop adaptation response strategies for existing settlements in risk areas to accommodate change over time.

Ensure planning controls allow for risk mitigation and climate change adaptation strategies to be implemented.

Site and design development to minimise risk to life, health, property, the natural environment and community infrastructure from natural hazards.

Policy guidelines

Consider as relevant:

- Climate change data and information maintained by the Department of Energy, Environment and Climate Action.
- Adaptation action plans prepared under Division 2 of Part 5 of the *Climate Action Act 2017*.

Policy documents

Consider as relevant:

- Climate science report prepared under Part 6 of the *Climate Action Act 2017*

13.01-2S Coastal inundation and erosion

05/09/2025
VC268

Objective

To plan for and manage coastal hazard risk and climate change impacts.

Strategies

Plan for sea level rise of not less than 0.8 metres by 2100 and allow for the combined effects of tides, storm surges, coastal processes and local conditions such as topography and geology when assessing risks and coastal impacts associated with climate change.

Ensure that land subject to hazards is identified and appropriately managed to ensure that future use and development is not at risk.

Avoid use and development in areas vulnerable to coastal inundation and erosion.

Respond to marine and coastal processes in the context of the coastal compartment type.

Assess the effectiveness, costs, benefits, impacts (direct, cumulative and synergistic) and path dependency of available adaptation options in the following order:

1. non-intervention
2. avoid
3. nature-based methods
4. accommodate
5. retreat
6. protect

Ensure that development or protective works that seek to respond to coastal hazard risks avoid detrimental impacts on coastal processes.

Policy guidelines

Consider as relevant:

- Any applicable Victorian Environmental Assessment Council recommendations.
- Any applicable Regional and Strategic Partnership Product, environmental management plan or coastal and marine management plan approved under the *Marine and Coastal Act 2018* or *National Parks Act 1975*.
- Any coastal erosion advice required under section 75 of the *Marine and Coastal Act 2018*.
- Local coastal hazard assessments and localised projections.

Policy documents

Consider as relevant:

- Any applicable adaptation action plan prepared under the *Climate Action Act 2017*
- *Guidelines for Coastal Catchment Management Authorities: Assessing Development in relation to Sea Level Rise* (June, 2012)
- *Marine and Coastal Policy* (Department of Environment, Land, Water and Planning, 2020)
- *Marine and Coastal Strategy* (Department of Environment, Land, Water and Planning, 2022)
- *Planning for Sea Level Rise Guidelines, Port Phillip and Westernport Region* (Melbourne Water, 2017)
- *Siting and Design Guidelines for Structures on the Victorian Coast* (Department of Environment, Land, Water and Planning, 2020)
- *The Victorian Coastal Hazard Guide* (Department of Sustainability and Environment, 2012)

13.01-3S Urban heat

02/09/2025
VC283

Objectives

To reduce urban heat and minimise impacts of urban heat on human health and wellbeing.

Strategies

Support development that contributes to cooler urban environments.

Support cooling design responses in urban areas through the:

- Planting and maintenance of canopy trees and other vegetation.
- Use of integrated water management.
- Provision of shading of pedestrian walkways.
- Use of permeable surfaces and low heat absorbing surface materials, such as green roofs and walls.

Encourage use of alternative water resources such as recycled water, stormwater and rainwater to support canopy tree and vegetation growth.

Policy documents

Consider as relevant:

- *Trees for Cooler and Greener Streetscapes Planning and Design Guidelines* (Department of Environment, Land, Water and Planning, 2019)

13.02 BUSHFIRE

31/07/2018
VC148

13.02-1S Bushfire planning

20/03/2023
VC229

Policy application

This policy must be applied to all planning and decision making under the *Planning and Environment Act 1987* relating to land that is:

- Within a designated bushfire prone area;
- Subject to a Bushfire Management Overlay; or
- Proposed to be used or developed in a way that may create a bushfire hazard.

Objective

To strengthen the resilience of settlements and communities to bushfire through risk-based planning that prioritises the protection of human life.

Strategies

Protection of human life

Give priority to the protection of human life by:

- Prioritising the protection of human life over all other policy considerations.
- Directing population growth and development to low risk locations and ensuring the availability of, and safe access to, areas where human life can be better protected from the effects of bushfire.
- Reducing the vulnerability of communities to bushfire through the consideration of bushfire risk in decision making at all stages of the planning process.

Bushfire hazard identification and assessment

Identify bushfire hazard and undertake appropriate risk assessment by:

- Applying the best available science to identify vegetation, topographic and climatic conditions that create a bushfire hazard.
- Considering the best available information about bushfire hazard including the map of designated bushfire prone areas prepared under the *Building Act 1993* or regulations made under that Act.
- Applying the Bushfire Management Overlay to areas where the extent of vegetation can create an extreme bushfire hazard.
- Considering and assessing the bushfire hazard on the basis of:
  - Landscape conditions - meaning conditions in the landscape within 20 kilometres (and potentially up to 75 kilometres) of a site;
  - Local conditions - meaning conditions in the area within approximately 1 kilometre of a site;
  - Neighbourhood conditions - meaning conditions in the area within 400 metres of a site; and
  - The site for the development.
- Consulting with emergency management agencies and the relevant fire authority early in the process to receive their recommendations and implement appropriate bushfire protection measures.
- Ensuring that strategic planning documents, planning scheme amendments, planning permit applications and development plan approvals properly assess bushfire risk and include appropriate bushfire protection measures.
- Not approving development where a landowner or proponent has not satisfactorily demonstrated that the relevant policies have been addressed, performance measures satisfied or bushfire protection measures can be adequately implemented.

Settlement planning

Plan to strengthen the resilience of settlements and communities and prioritise protection of human life by:

- Directing population growth and development to low risk locations, being those locations assessed as having a radiant heat flux of less than 12.5 kilowatts/square metre under *AS 3959-2018 Construction of Buildings in Bushfire-prone Areas* (Standards Australia, 2018).
- Ensuring the availability of, and safe access to, areas assessed as a BAL-LOW rating under *AS 3959-2018 Construction of Buildings in Bushfire-prone Areas* (Standards Australia, 2018) where human life can be better protected from the effects of bushfire.
- Ensuring the bushfire risk to existing and future residents, property and community infrastructure will not increase as a result of future land use and development.
- Achieving no net increase in risk to existing and future residents, property and community infrastructure, through the implementation of bushfire protection measures and where possible reducing bushfire risk overall.
- Assessing and addressing the bushfire hazard posed to the settlement and the likely bushfire behaviour it will produce at a landscape, settlement, local, neighbourhood and site scale, including the potential for neighbourhood-scale destruction.
- Assessing alternative low risk locations for settlement growth on a regional, municipal, settlement, local and neighbourhood basis.
- Not approving any strategic planning document, local planning policy, or planning scheme amendment that will result in the introduction or intensification of development in an area that has, or will on completion have, more than a BAL-12.5 rating under *AS 3959-2018 Construction of Buildings in Bushfire-prone Areas* (Standards Australia, 2018).

Areas of biodiversity conservation value

Ensure settlement growth and development approvals can implement bushfire protection measures without unacceptable biodiversity impacts by discouraging settlement growth and development in bushfire affected areas that are important areas of biodiversity.

Use and development control in a Bushfire Prone Area

In a bushfire prone area designated in accordance with regulations made under the *Building Act 1993,* bushfire risk should be considered when assessing planning applications for the following uses and development:

- Subdivisions of more than 10 lots.
- Accommodation.
- Child care centre.
- Education centre.
- Emergency services facility.
- Hospital.
- Indoor recreation facility.
- Major sports and recreation facility.
- Place of assembly.
- Any application for development that will result in people congregating in large numbers.

When assessing a planning permit application for the above uses and development:

- Consider the risk of bushfire to people, property and community infrastructure.

- Require the implementation of appropriate bushfire protection measures to address the identified bushfire risk.
- Ensure new development can implement bushfire protection measures without unacceptable biodiversity impacts.

Policy guidelines

Consider as relevant:

- Any applicable approved state, regional and municipal fire prevention plan.

Policy documents

Consider as relevant:

- *AS 3959-2018 Construction of Buildings in Bushfire-prone Areas* (Standards Australia, 2018)
- *Building in bushfire-prone areas - CSIRO & Standards Australia* (SAA HB36-1993, 1993)
- Any bushfire prone area map prepared under the *Building Act 1993* or regulations made under that Act

13.03 FLOODPLAINS

31/07/2018
VC148

13.03-1S Floodplain management

20/03/2023
VC229

Objective

To assist the protection of:

- Life, property and community infrastructure from flood hazard, including coastal inundation, riverine and overland flows.
- The natural flood carrying capacity of rivers, streams and floodways.
- The flood storage function of floodplains and waterways.
- Floodplain areas of environmental significance or of importance to river, wetland or coastal health.

Strategies

Identify land affected by flooding, including land inundated by the 1 in 100 year flood event (1 per cent Annual Exceedance Probability) or as determined by the floodplain management authority in planning schemes.

Avoid intensifying the impact of flooding through inappropriately located use and development.

Plan for the cumulative impacts of use and development on flood behaviour.

Locate emergency and community facilities (including hospitals, ambulance stations, police stations, fire stations, residential aged care facilities, communication facilities, transport facilities, community shelters, child care centres and schools) outside the 1 in 100 year (1 per cent Annual Exceedance Probability) floodplain and, where possible, at levels above the height of the probable maximum flood.

Locate use and development that involve the storage or disposal of environmentally hazardous industrial and agricultural chemicals or wastes and other dangerous goods (including intensive animal industries and sewage treatment plants) outside floodplains unless site design and management is such that potential contact between such substances and floodwaters is prevented, without affecting the flood carrying and flood storage functions of the floodplain.

Ensure land use on floodplains minimises the risk of waterway contamination occurring during floods and floodplains are able to function as temporary storage to moderate peak flows and minimise downstream impacts.

Policy guidelines

Consider as relevant:

- Regional catchment strategies and special area plans approved by the Minister for Environment or Minister for Water.
- Any floodplain management manual or guideline of policy and practice, or catchment management, river health, wetland or floodplain management strategy adopted by the relevant responsible floodplain management authority.
- Any best practice environmental management guidelines for stormwater adopted by the Environment Protection Authority.

Policy documents

Consider as relevant:

- *Victorian Floodplain Management Strategy* (Department of Environment, Land, Water and Planning, 2016)

13.04 SOIL DEGRADATION

31/07/2018
VC148

13.04-1S Contaminated and potentially contaminated land

04/05/2022
VC210

Objective

To ensure that contaminated and potentially contaminated land is used and developed safely.

Strategies

Ensure contaminated or potentially contaminated land is or will be suitable for the proposed use, prior to the commencement of any use or development.

Protect a sensitive use (residential use, childcare centre, kindergarten, pre-school centre, primary school, even if ancillary to another use), children's playground or secondary school from the effects of contamination.

Facilitate the remediation of contaminated land to make the land suitable for future intended use or development.

Policy guideline

Consider as relevant the potential for contamination to impact the proposed use or development through an assessment that is proportionate to the risk, including:

- An assessment in accordance with the *National Environment Protection (Assessment of Site Contamination) Measure* (National Environment Protection Council, 1999)
- A preliminary risk screen assessment or environmental audit under Part 8.3 of the *Environment Protection Act 2017*.

Policy documents

Consider as relevant:

- *Ministerial Direction No. 1 - Potentially Contaminated Land*
- *National Environment Protection (Assessment of Site Contamination) Measure* (National Environment Protection Council, 1999)

13.04-2S Erosion and landslip

31/07/2018
VC148

Objective

To protect areas prone to erosion, landslip or other land degradation processes.

Strategies

Identify areas subject to erosion or instability in planning schemes and when considering the use and development of land.

Prevent inappropriate development in unstable areas or areas prone to erosion.

Promote vegetation retention, planting and rehabilitation in areas prone to erosion and land instability.

Policy guidelines

Consider as relevant:

- Any applicable regional catchment strategy.
- Any special area plan approved under the *Catchment and Land Protection Act 1994*.

13.04-3S Salinity

31/07/2018
VC148

Objective

To minimise the impact of salinity and rising water tables on land uses, buildings and infrastructure in rural and urban areas and areas of environmental significance and reduce salt load in rivers.

Strategies

Identify areas subject to salinity in the preparation of planning schemes and land use planning decisions.

Promote vegetation retention and replanting in aquifer recharge areas contributing to groundwater salinity problems.

Prevent inappropriate development in areas affected by groundwater salinity.

Policy guidelines

Consider as relevant:

- Any applicable regional catchment strategy and any associated implementation plan or strategy (particularly salinity management plans and regional vegetation plans).
- Any special area plan approved under the *Catchment and Land Protection Act 1994*.

Policy documents

Consider as relevant:

- *Salinity Information Kit: Volume 1 - A Local Government Planning Guide for Dryland Salinity* (Department of Conservation and Natural Resources, 1995)

13.05 NOISE

31/07/2018
VC148

13.05-1S Noise management

10/06/2022
VC216

Objective

To assist the management of noise effects on sensitive land uses.

Strategy

Ensure that development is not prejudiced and community amenity and human health is not adversely impacted by noise emissions.

Minimise the impact on human health from noise exposure to occupants of sensitive land uses (residential use, child care centre, school, education centre, residential aged care centre or hospital) near the transport system and other noise emission sources through suitable building siting and design (including orientation and internal layout), urban design and land use separation techniques as appropriate to the land use functions and character of the area.

Policy guidelines

Consider as relevant:

- The noise requirements in accordance with the Environment Protection Regulations under the *Environment Protection Act 2017*.

Policy documents

Consider as relevant:

- *Environment Protection Regulations under the Environment Protection Act 2017*
- *Noise Limit and Assessment Protocol for the Control of Noise from Commercial, Industrial and Trade Premises and Entertainment Venues* (Publication 1826, Environment Protection Authority, May 2021)
- *Environment Reference Standard* (Gazette No. S 245, 26 May 2021)
- *Passenger Rail Infrastructure Noise Policy* (Victorian Government, 2013)
- *VicTrack Rail Development Interface Guidelines* (VicTrack, 2019)

13.05-1L Noise abatement - Brimbank

27/06/2024
C225brim

Strategies

Ensure residential development in the following locations incorporates appropriate noise attenuation to protect the amenity of residents:

- Adjacent to Calder Park Raceway.
- Close to loading areas within activity centres.

Encourage appropriate noise attenuation along the extent of the proposed railway line for the Melbourne Airport Rail Link.

13.06 AIR QUALITY

31/07/2018
VC148

13.06-1S Air quality management

14/01/2025
VC237

Objective

To assist the protection and improvement of air quality.

Strategies

Ensure that land use planning and transport infrastructure provision contribute to improved air quality by:

- Integrating transport and land use planning to improve transport accessibility and connections.
- Locating key developments that generate high volumes of trips in the Central City, Metropolitan Activity Centres and Major Activity Centres.
- Providing infrastructure for walking, cycling and public transport.

Ensure, wherever possible, that there is suitable separation between land uses that pose a human health risk or reduce amenity due to air pollutants, and sensitive land uses (residential use, child care centre, school, education centre, residential aged care centre or hospital).

Minimise air pollutant exposure to occupants of sensitive land uses near the transport system through suitable siting, layout and design responses.

Policy documents

Consider as relevant:

- *Separation Distance Guideline* (Environment Protection Authority, August 2024)
- *Landfill Buffer Guideline* (Environment Protection Authority, August 2024)
- *Environment Reference Standard* (Gazette No. S 245, 26 May 2021)

13.07 AMENITY, HUMAN HEALTH AND SAFETY

26/05/2020
VC175

13.07-1S Land use compatibility

14/01/2025
VC237

Objective

To protect community amenity, human health and safety while facilitating appropriate commercial, industrial, infrastructure or other uses with potential adverse off-site impacts.

Strategies

- Ensure that use or development of land is compatible with adjoining and nearby land uses
- Avoid locating incompatible uses in areas that may be impacted by adverse off-site impacts from commercial, industrial and other uses.
- Avoid or otherwise minimise adverse off-site impacts from commercial, industrial and other uses through land use separation, siting, building design and operational measures.
- Protect commercial, industrial and other employment generating uses from encroachment by use or development that would compromise the ability of those uses to function safely and effectively.

Policy documents

Consider as relevant:

- *Separation Distance Guideline* (Environment Protection Authority, August 2024)
- *Landfill Buffer Guideline* (Environment Protection Authority, August 2024)

13.07-1L Non-residential use and development

27/06/2024
C225brim

Policy application

This policy applies to non-residential use and development within residential zones.

Strategies

Avoid or otherwise minimise adverse offsite impacts of non-residential use and development within residential zones.

Provide landscaping opportunities to accommodate canopy trees, screen tree planting and mature vegetation within front and rear setbacks that will provide a visual buffer between non-residential development and surrounding residential properties.

Encourage non-residential uses to locate on sites that:

- Are close to non-residential zones, commercial uses or retail activities.
- Provide convenient access to public transport.
- Have frontage to a main road.

13.07-2S Major hazard facilities

26/10/2018
VC152

Objective

To minimise the potential for human and property exposure to risk from incidents that may occur at a major hazard facility and to ensure the ongoing viability of major hazard facilities.

Strategies

Ensure major hazard facilities are sited, designed and operated to minimise risk to surrounding communities and the environment.

Consider the risks associated with increasing the intensity of use and development within the threshold distance of an existing major hazard facility.

Apply appropriate threshold distances from sensitive land uses for new major hazard facilities and between major hazard facilities.

Protect registered or licenced major hazard facilities as defined under Regulation 5 of the Occupational Health and Safety Regulations 2017 from encroachment of sensitive land uses.

13.07-3S Live music

01/07/2025
VC286

Objective

To encourage, create and protect opportunities for the enjoyment of live music.

Strategies

Identify areas where live music venues are encouraged or where there are clusters of live music venues.

Implement measures to ensure live music venues can co-exist with nearby residential and other noise sensitive land uses.

Policy guidelines

Consider as relevant:

- The social, economic and cultural benefits to the community of:
  - Retaining an existing live music venue.
  - The development of new live music entertainment venues.
  - Clustering live music venues.

14 NATURAL RESOURCE MANAGEMENT

31/07/2018
VC148

Planning is to assist in the conservation and wise use of natural resources including energy, water, land, stone and minerals to support both environmental quality and sustainable development.

Planning should ensure agricultural land is managed sustainably, while acknowledging the economic importance of agricultural production.

14.01 AGRICULTURE

31/07/2018
VC148

14.01-1S Protection of agricultural land

20/03/2023
VC229

Objective

To protect the state's agricultural base by preserving productive farmland.

Strategies

Identify areas of productive agricultural land, including land for primary production and intensive agriculture.

Consider state, regional and local, issues and characteristics when assessing agricultural quality and productivity.

Avoid permanent removal of productive agricultural land from the state's agricultural base without consideration of the economic importance of the land for the agricultural production and processing sectors.

Protect productive farmland that is of strategic significance in the local or regional context.

Protect productive agricultural land from unplanned loss due to permanent changes in land use.

Prevent inappropriately dispersed urban activities in rural areas.

Protect strategically important agricultural and primary production land from incompatible uses.

Limit new housing development in rural areas by:

- Directing housing growth into existing settlements.
- Discouraging development of isolated small lots in the rural zones from use for dwellings or other incompatible uses.
- Encouraging consolidation of existing isolated small lots in rural zones.

Identify areas of productive agricultural land by consulting with the Department of Energy, Environment and Climate Action and using available information.

In considering a proposal to use, subdivide or develop agricultural land, consider the:

- Desirability and impacts of removing the land from primary production, given its agricultural productivity.
- Impacts on the continuation of primary production on adjacent land, with particular regard to land values and the viability of infrastructure for such production.
- Compatibility between the proposed or likely development and the existing use of the surrounding land.
- The potential impacts of land use and development on the spread of plant and animal pests from areas of known infestation into agricultural areas.
- Land capability.

Avoid the subdivision of productive agricultural land from diminishing the long-term productive capacity of the land.

Give priority to the re-structure of inappropriate subdivisions where they exist on productive agricultural land.

Balance the potential off-site effects of a use or development proposal (such as degradation of soil or water quality and land salinisation) against the benefits of the proposal.

14.01-1R Protection of agricultural land - Metropolitan Melbourne

31/07/2018
VC148

Strategy

Protect agricultural land in Metropolitan Melbourne's green wedges and peri-urban areas to avoid the permanent loss of agricultural land in those locations.

14.01-2S Sustainable agricultural land use

21/09/2018
VC150

Objective

To encourage sustainable agricultural land use.

Strategies

Ensure agricultural and productive rural land use activities are managed to maintain the long-term sustainable use and management of existing natural resources.

Support the development of innovative and sustainable approaches to agricultural and associated rural land use practices.

Support adaptation of the agricultural sector to respond to the potential risks arising from climate change.

Encourage diversification and value-adding of agriculture through effective agricultural production and processing, rural industry and farm-related retailing.

Assist genuine farming enterprises to embrace opportunities and adjust flexibly to market changes.

Support agricultural investment through the protection and enhancement of appropriate infrastructure.

Facilitate ongoing productivity and investment in high value agriculture.

Facilitate the establishment and expansion of cattle feedlots, pig farms, poultry farms and other intensive animal industries in a manner consistent with orderly and proper planning and protection of the environment.

Ensure that the use and development of land for animal keeping or training is appropriately located and does not detrimentally impact the environment, the operation of surrounding land uses and the amenity of the surrounding area.

Policy documents

Consider as relevant:

- *Victorian Code for Cattle Feedlots* (Department of Agriculture, Energy and Minerals, 1995)
- *Victorian Code for Broiler Farms* (Department of Primary Industries, 2009, plus 2018 amendments)
- *Apiary Code of Practice* (Department of Planning and Community Development, 2011)
- *Planning Guidelines for Land Based Aquaculture in Victoria* (Department of Primary Industries, No. 21, 2005)
- *Victorian Low Density Mobile Outdoor Poultry Farm Planning Permit Guidelines* (Department of Economic Development, Jobs, Transport and Resources, June 2018)
- *Victorian Low Density Mobile Outdoor Pig Farm Planning Permit Guidelines* (Department of Economic Development, Jobs, Transport and Resources, June 2018)

14.01-3S Forestry and timber production

20/03/2023
VC229

Objective

To facilitate the establishment, management and harvesting of plantations and the harvesting of timber from native forests.

Strategies

Identify areas that may be suitably used and developed for plantation timber production.

Promote the establishment of softwood and hardwood plantations on predominantly cleared land, as well as other areas that are subject to or contributing to land and water degradation.

Ensure protection of water quality and soil.

Ensure timber production in native forests is conducted in a sustainable manner.

Conduct timber production (except agroforestry, windbreaks and commercial plantations of 5 hectares or less) in accordance with the *Code of Practice for Timber Production 2014 (as amended 2022)* (Department of Environment, Land, Water and Planning, 2022).

Ensure Victoria's greenhouse sinks are protected and enhanced by controlling land clearing, containing the growth of urban areas and supporting revegetation programs.

Policy documents

Consider as relevant:

- *Code of Practice for Timber Production 2014 (as amended 2022)* (Department of Environment, Land, Water and Planning, 2022)

14.02 WATER

31/07/2018
VC148

14.02-1S Catchment planning and management

22/11/2024
VC263

Objective

To assist the protection and restoration of catchments, waterways, estuaries, bays, water bodies, groundwater, and the marine environment.

Strategies

Ensure the continued availability of clean, high-quality drinking water by protecting water catchments and water supply facilities.

Consider the impacts of catchment management on downstream water quality and freshwater, coastal and marine environments.

Retain natural drainage corridors with vegetated buffer zones at least 30 metres wide along each side of a waterway to:

- Maintain the natural drainage function, stream habitat and wildlife corridors and landscape values,
- Minimise erosion of stream banks and verges, and
- Reduce polluted surface runoff from adjacent land uses.

Undertake measures to minimise the quantity and retard the flow of stormwater from developed areas.

Require appropriate measures to filter sediment and wastes from stormwater prior to its discharge into waterways, including the preservation of floodplain or other land for wetlands and retention basins.

Ensure that development at or near waterways provide for the protection and enhancement of the environmental qualities of waterways and their instream uses.

Ensure land use and development minimises nutrient contributions to water bodies and the potential for the development of algal blooms.

Require appropriate measures to restrict sediment discharges from construction sites.

Ensure planning is coordinated with the activities of catchment management authorities.

Ensure that water quality infrastructure is designed to minimise risk of harm to surface waters and groundwater.

Policy guidelines

Consider as relevant:

- Any regional catchment strategy and related plans approved under the *Catchment and Land Protection Act 1994*.
- Any applicable implementation strategy approved by a catchment management authority or waterway management authority.
- Any special area or management plan under the *Heritage Rivers Act 1992*.
- Any action statement or management plan prepared under the *Flora and Fauna Guarantee Act 1988*.

Policy documents

Consider as relevant:

- *Murray River Regional Environmental Plan No 2 (REP2) of New South Wales*
- *Marine and Coastal Policy* (Department of Environment, Land, Water and Planning, 2020)

- *Planning Permit Applications in Special Water Supply Catchment Areas* (Department of Energy, Environment and Climate Action, 2024)
- *Urban Stormwater - Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999)

14.02-2S Water quality

22/11/2024
VC263

Objective

To protect water quality.

Strategies

Protect reservoirs, water mains and local storage facilities from potential contamination.

Ensure that land use activities potentially discharging contaminated runoff or wastes to waterways are sited and managed to minimise such discharges and to protect the quality of surface water and groundwater resources, rivers, streams, wetlands, estuaries and marine environments.

Discourage incompatible land use activities in areas subject to flooding, severe soil degradation, groundwater salinity or geotechnical hazards where the land cannot be sustainably managed to ensure minimum impact on downstream water quality or flow volumes.

Prevent the establishment of incompatible land uses in aquifer recharge or saline discharge areas and in potable water catchments.

Ensure that the siting, design, operation and rehabilitation of landfills avoids impacts on groundwater and surface water.

Avoid detrimental impacts on groundwater resources and minimise risk of harm to human health and the environment from proposed land use or development.

Policy documents

Consider as relevant:

- *Civil Construction, Building and Demolition Guide* (Publication 1834, Environment Protection Authority, November 2020)
- *Environment Reference Standard* (Gazette No. S 245, 26 May 2021)
- *Planning Permit Applications in Special Water Supply Catchment Areas* (Department of Energy, Environment and Climate Action, 2024)

14.02-3S Protection of declared irrigation districts

28/10/2022
VC224

Objective

To plan and manage for sustainable change within irrigation districts declared under Part 6A of the *Water Act 1989*.

Strategies

Identify and plan for the future needs of communities to adapt and adjust to strategic land use change within an irrigation district.

Ensure the future viability of an irrigation district by preventing non-agricultural use of land in a declared irrigation district where the land is serviced, or was serviced as at 17 September 2019, by rural water corporation irrigation infrastructure, unless the rural water corporation infrastructure has been, or is planned to be, decommissioned.

Ensure non-agricultural land use does not undermine the integrity of irrigation infrastructure and complements existing and future agricultural production.

Ensure land use change within an irrigation district does not negate the potential opportunities for a rural water corporation to make adjustments to the footprint of an irrigation district that are identified under an approved plan or strategy.

Ensure land use change does not limit the ability of future investment in irrigation infrastructure that achieves the intended benefits of minimising water loss, and improved irrigation service efficiency to the farm gate and overall agricultural production.

Policy documents

Consider as relevant:

- *Water for Victoria* (Department of Environment, Land, Water and Planning, 2016)
- *Gippsland Region Sustainable Water Strategy* (Department of Sustainability and Environment, 2011)
- *Western Region Sustainable Water Strategy* (Department of Sustainability and Environment, 2011)
- *Northern Region Sustainable Water Strategy* (Department of Sustainability and Environment, 2009)
- *Central Region Sustainable Water Strategy* (Department of Sustainability and Environment, 2006)
- *Victorian Government White Paper, Securing Our Water Future Together – Our Water, Our Future* (Department of Sustainability and Environment, 2004)

14.03 EARTH AND ENERGY RESOURCES

31/07/2018
VC148

14.03-1S Resource exploration and extraction

19/08/2021
VC196

Objective

To encourage exploration and extraction of natural resources in accordance with acceptable environmental standards.

Strategies

Provide for the long-term protection of natural resources in Victoria.

Protect the opportunity for exploration and extraction of natural resources where this is consistent with overall planning considerations and acceptable environmental practice.

Recognise the possible need to provide infrastructure, including transport networks, for the exploration and extraction of natural resources.

Ensure planning schemes do not impose conditions on the use or development of land that are inconsistent with the *Mineral Resources (Sustainable Development) Act 1990,* the *Greenhouse Gas Geological Sequestration Act 2008,* the *Geothermal Energy Resources Act 2005,* or the *Petroleum Act 1998*.

Develop and maintain buffers around mining and extractive industry activities.

Ensure planning permit applications clearly define buffer areas appropriate to the nature of the proposed extractive uses, which are to be owned or controlled by the proponent of an extractive industry.

Determine buffer areas between extractive activities and sensitive land uses on the following considerations:

- Appropriate limits on effects can be met at the sensitive locations using practical and available technology.
- Whether a change of land use in the vicinity of the extractive industry is proposed.
- Use of land within the buffer areas is not limited by adverse effects created by the extractive activities.
- Performance standards identified under the relevant legislation.
- Types of activities within land zoned for public use.

Identify and protect extractive industry resources within Strategic Extractive Resource Areas, based on their current or potential contribution to state supply, access to supporting transport networks and proximity to demand markets.

Facilitate the use and development of Strategic Extractive Resource Areas for extractive industries and other compatible land uses.

Protect the brown coal resource in Central Gippsland by ensuring that:

- Changes in use and development of land overlying coal resources, as generally defined in *Framework for the Future* (Minister for Industry, Technology and Resources and Minister for Planning and Environment, 1987) and the *Land Over Coal and Buffer Area Study* (Ministry for Planning and Environment, 1988), do not compromise the winning or processing of coal.
- Coal-related development is adequately separated from residential or other sensitive uses and main transport corridors by buffer areas to minimise adverse effects such as noise, dust, fire, earth subsidence and visual intrusion.
- Use and development within the buffer areas are compatible with use and development adjacent to these areas.
- Ensure that the use and development of land for extractive industry responds to potential environmental risks and maintains or improves the quality of the air, land, acoustic and water environments.

Policy documents

Consider as relevant:

- *Mineral Resources (Sustainable Development) Act 1990*
- *Greenhouse Gas Geological Sequestration Act 2008*
- *Geothermal Energy Resources Act 2005*
- *Petroleum Act 1998*
- *Melbourne Supply Area - Extractive Industry Interest Areas Review* (Geological Survey of Victoria Technical Record, 2003/2)
- *Ballarat Supply Area - Extractive Industry Interest Areas* (Geological Survey of Victoria Technical Record, 1997/3)
- *Bendigo Supply Area - Extractive Industry Interest Areas* (Geological Survey of Victoria Technical Record, 1998/6)
- *Geelong Supply Area - Extractive Industry Interest Areas* (Geological Survey of Victoria Technical Record, 1999/2)
- *La Trobe Supply Area - Extractive Industry Interest Areas* (Geological Survey of Victoria Technical Record, 1999/4)
- *Strategic Extractive Resource Areas Pilot Project Report* (Victorian Government, 2020)

15 BUILT ENVIRONMENT AND HERITAGE

02/09/2025
VC283

Planning is to recognise the role of urban design, building design, heritage and energy and resource efficiency in delivering liveable and sustainable cities, towns and neighbourhoods.

Planning should ensure all land use and development appropriately responds to its surrounding landscape and character, valued built form and cultural context.

Planning should protect places and sites with significant heritage, architectural, aesthetic, natural, scientific and cultural value.

Planning should incorporate measures to protect culturally significant heritage places in locations exposed to climate related hazards.

Planning must support the establishment and maintenance of communities by delivering functional, accessible, safe and diverse physical and social environments, through the appropriate location of use and development and through high quality buildings and urban design.

Planning should promote excellence in the built environment and create places that:

- Are enjoyable, engaging, and comfortable to be in.
- Support human health and community wellbeing.
- Accommodate people of all abilities, ages and cultures.
- Contribute positively to local character and sense of place.
- Reflect the particular characteristics and cultural identity of the community.
- Celebrate, acknowledge and protect cultural heritage.
- Enhance the function, amenity and safety of the public realm.

Planning should promote development that is environmentally sustainable and minimise detrimental impacts on the built and natural environment.

Planning should facilitate development that:

- Is adapted and resilient to climate related hazards.
- Supports the transition to net zero greenhouse gas emissions.
- Minimises waste generation and supports resource recovery.
- Conserves potable water.
- Supports the use of, and access to, low emission forms of transport.
- Protects and enhances natural values.
- Minimises off-site detrimental impacts on people and the environment.

15.01 BUILT ENVIRONMENT

31/07/2018
VC148

15.01-1S Urban design

02/09/2025
VC283

Objective

To create urban environments that are safe, healthy, functional and enjoyable and that contribute to a sense of place and cultural identity.

Strategies

Require development to respond to its context in terms of character, cultural identity and heritage, natural features, surrounding landscape and climate.

Ensure development contributes to community and cultural life by improving the quality of living and working environments, facilitating accessibility and providing for inclusiveness.

Ensure the interface between the private and public realm protects and enhances personal safety.

Ensure development supports public realm amenity and safe access to walking and cycling environments and public transport.

Ensure that the design and location of publicly accessible private spaces, including car parking areas, forecourts and walkways, is of a high standard, creates a safe environment for users and enables easy and efficient use.

Ensure that development provides landscaping that supports the amenity, attractiveness and safety of the public realm.

Ensure that development, including signs, minimises detrimental impacts on amenity, on the natural and built environment and on the safety and efficiency of roads.

Promote good urban design along and abutting transport corridors.

Policy documents

Consider as relevant:

- *Urban Design Guidelines for Victoria* (Department of Environment, Land, Water and Planning, 2017)

15.01-1R Urban design - Metropolitan Melbourne

31/07/2018
VC148

Objective

To create a distinctive and liveable city with quality design and amenity.

Strategies

Support the creation of well-designed places that are memorable, distinctive and liveable.

Integrate place making practices into road space management.

Strengthen Melbourne's network of boulevards.

Create new boulevards in urban-growth areas and selected existing road corridors across Melbourne.

Provide spaces and facilities that encourage and support the growth and development of Melbourne's cultural precincts and creative industries.

15.01-1L Urban design - Brimbank

27/06/2024
C225brim

Strategies

Encourage low-level planting adjacent to windows, fencing and pathways to define private and public land.

Encourage landscaping design that complements the landscape treatments of adjoining public spaces.

Encourage landscaping that enhances pedestrian safety, provides clear sight lines and does not create concealed spaces.

Ensure outdoor spaces are designed to be safe, accessible and adaptable so that they can be used by different age groups and for different purposes.

Encourage lighting along pedestrian pathways.

Avoid zero street setbacks in residential areas that directly adjoin activity centres.

Design residential areas that directly adjoin activity centres to ensure a gradual transition between the centre and residential areas.

Discourage signs that would contribute to, or result in, a proliferation or repetition of similar signs.

Ensure signage in commercial areas does not protrude over building lines or above the rooflines of buildings.

Discourage promotional signage on or adjacent to major arterial roads, freeways and gateways.

Policy guidelines

Consider as relevant:

- Using indigenous, drought tolerant species in landscaped areas.
- Avoiding the use of species identified as environmental weeds.

15.01-2S Building design

01/01/2024
VC250

Objective

To achieve building design and siting outcomes that contribute positively to the local context, enhance the public realm and support environmentally sustainable development.

Strategies

Ensure a comprehensive site analysis forms the starting point of the design process and provides the basis for the consideration of height, scale, massing and energy performance of new development.

Ensure development responds and contributes to the strategic and cultural context of its location.

Minimise the detrimental impact of development on neighbouring properties, the public realm and the natural environment.

Improve the energy performance of buildings through siting and design measures that encourage:

- Passive design responses that minimise the need for heating, cooling and lighting.
- On-site renewable energy generation and storage technology.
- Use of low embodied energy materials.

Restrict the provision of reticulated natural gas in new dwelling development.

Ensure the layout and design of development supports resource recovery, including separation, storage and collection of waste, mixed recycling, glass, organics and e-waste.

Encourage use of recycled and reusable materials in building construction and undertake adaptive reuse of buildings, where practical.

Encourage water efficiency and the use of rainwater, stormwater and recycled water.

Minimise stormwater discharge through site layout and landscaping measures that support on-site infiltration and stormwater reuse.

Ensure the form, scale, and appearance of development enhances the function and amenity of the public realm.

Ensure buildings and their interface with the public realm support personal safety, perceptions of safety and property security.

Ensure development is designed to protect and enhance valued landmarks, views and vistas.

Ensure development considers and responds to transport movement networks and provides safe access and egress for pedestrians, cyclists and vehicles.

Encourage development to retain existing vegetation.

Ensure development provides landscaping that responds to its site context, enhances the built form, creates safe and attractive spaces and supports cooling and greening of urban areas.

Policy documents

Consider as relevant:

- *Urban Design Guidelines for Victoria* (Department of Environment, Land, Water and Planning, 2017)
- *Apartment Design Guidelines for Victoria* (Department of Environment, Land, Water and Planning, 2021)
- *Waste Management and Recycling in Multi-unit Developments* (Sustainability Victoria, 2019)

15.01-2L-01 Building design - Brimbank

27/06/2024
C225brim

Commercial strategies

Avoid blank walls and the use of reflective glazing at ground level.

Design shopfront canopies to provide weather protection, be lightweight and not detract from the appearance of the building.

Ensure pedestrian entries are clearly visible from the street, provide weather protection, are well-lit and directly face the street or adjoining public space.

Ensure shopfronts are designed to facilitate passive surveillance, including by incorporating clear windows.

Avoid solid roller shutters on shopfronts.

Encourage commercial development to incorporate underground power and solar street lighting, where possible.

Locate loading facilities away from public spaces, streets and residential areas, and screen them from the public realm.

Residential strategies

Incorporate external services and equipment such as storage, plumbing, heating, ventilation and lift over-runs into the building design and conceal them from public view.

Encourage unobtrusive waste collection and storage areas that are screened from the street and accessible by waste collection vehicles.

Encourage covered car parking spaces to be located behind the front facade of dwellings.

Provide for landscaping opportunities within front and side setbacks and between dwellings in new developments.

Industrial strategies

Encourage transparent fencing that integrates with the building and maintains adequate security.

Avoid the use of barbed wire fencing.

Locate loading facilities away from public spaces, streets and residential areas, and screen them from the public realm.

Articulate exposed side and rear walls of buildings to provide visual interest.

15.01-2L-02 Environmentally sustainable development

27/06/2024
C225brim

Policy application

This policy applies to residential and non-residential development, excluding subdivision, in accordance with the thresholds detailed in this policy.

Objective

To achieve best practice in environmentally sustainable development from the design stage through to construction and operation.

Strategies

Facilitate development that minimises environmental impacts.

Encourage environmentally sustainable development that:

- Is consistent with the type and scale of the development.

- Responds to site opportunities and constraints.
- Adopts best practice through a combination of methods, processes and locally available technology that demonstrably minimise environmental impacts.

Energy performance

Reduce both energy use and energy peak demand through design measures such as:

- Building orientation.
- Shading to glazed surfaces.
- Optimising glazing to exposed surfaces.
- Inclusion of or space allocation for renewable technologies.

Integrated water management

Reduce total operating potable water use through appropriate design measures such as water efficient fixtures, appliances, equipment, irrigation and landscaping.

Encourage the appropriate use of alternative water sources (including greywater, rainwater and stormwater).

Incorporate best practice water sensitive urban design to improve the quality of stormwater runoff and reduce impacts on water systems and water bodies.

Indoor environment quality

Achieve a healthy indoor environment quality, including thermal comfort and access to fresh air and daylight, by prioritising passive design over mechanical heating, ventilation, cooling and lighting.

Reduce indoor air pollutants by encouraging use of low-toxicity materials.

Minimise noise levels and noise transfer within and between buildings and associated external areas.

Transport

Design development to promote the use of walking, cycling and public transport, in that order; and minimise car dependency.

Promote the use of low emissions vehicle technologies and supporting infrastructure.

Waste management

Promote waste avoidance, reuse and recycling during the design, construction and operation stages of development.

Encourage use of durable and reuseable building materials.

Ensure sufficient space is allocated for future change in waste management needs, including (where possible) composting and green waste facilities.

Urban ecology

Protect and enhance biodiversity by incorporating natural habitats and planting indigenous vegetation.

Reduce urban heat island effects through building design, landscape design, water sensitive urban design and the retention and provision of canopy and significant trees.

Encourage the provision of space for productive gardens, particularly in larger residential developments.

Policy guidelines

Consider as relevant:

Residential

A Sustainable Design Assessment (including an assessment using BESS, STORM or other methods) for:

- 2 - 9 dwellings.
- A building used for accommodation other than dwellings with a gross floor area between 50 square metres and 2000 square metres.

A Sustainability Management Plan including an assessment using BESS/Green star, STORM/MUSIC or other methods) and a Green Travel Plan for:

- 10 or more dwellings.
- A building used for accommodation other than dwellings with a gross floor area of more than 2000 square metres.

Non-residential

A Sustainable Design Assessment (including an assessment using BESS and STORM/MUSIC or other methods) for:

- A non-residential building with a gross floor area of 50 square metres to 2000 square metres.

A Sustainability Management Plan (including an assessment using BESS/Green star, STORM/MUSIC or other methods) and a Green Travel Plan for:

- A non-residential building with a gross floor area of more than 2000 square metres.

Mixed use

Applicable assessments for the residential and non-residential components of the development.

Consider as relevant the following tools to support a Sustainable Design Assessment or Sustainability Management Plan:

- *Sustainable Design Assessment in the Planning Process* (IMAP, 2015)
- *Built Environment Sustainability Scorecard 'BESS'* (Council Alliance for a Sustainable Built Environment 'CASBE', 2015)
- *Green Star* (Green Building Council of Australia)
- *Model for Urban Stormwater Improvement Conceptualisation 'MUSIC'* (Melbourne Water)
- *Nationwide House Energy Rating Scheme 'NatHERS'* (Department of Climate Change and Energy Efficiency)
- *Stormwater Treatment Objective - Relative Measure 'STORM'* (Melbourne Water)
- *Urban Stormwater Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999)
- *Waste Management and Recycling in Multi-Unit Developments - Better Practice Guide* (Sustainability Victoria, 2019)

Commencement

This policy does not apply to applications received by the responsible authority before 18/10/2018.

Expiry

This policy will expire when it is superseded by a comparable provision of the Victorian Planning Provisions.

15.01-3S Subdivision design

01/01/2024
VC250

Objective

To ensure the design of subdivisions achieves attractive, safe, accessible, diverse and sustainable neighbourhoods.

Strategies

In the development of new residential areas and in the redevelopment of existing areas, subdivision should be designed to create liveable and sustainable communities by:

- Creating compact neighbourhoods that have walkable distances between activities.
- Developing activity centres in appropriate locations with a mix of uses and services and access to public transport.
- Creating neighbourhood centres that include services to meet day to day needs.
- Creating urban places with a strong sense of place that are functional, safe and attractive.
- Providing a range of lot sizes to suit a variety of dwelling and household types to meet the needs and aspirations of different groups of people.
- Creating landscaped streets and a network of open spaces to meet a variety of needs with links to regional parks where possible.
- Protecting and enhancing habitat for native flora and fauna, and providing opportunities for people to experience nature in urban areas.
- Facilitating an urban structure where neighbourhoods are clustered to support larger activity centres served by high quality public transport.
- Reduce car dependency by allowing for:
  - Convenient and safe public transport.
  - Safe and attractive spaces and networks for walking and cycling.
  - Subdivision layouts that allow easy movement within and between neighbourhoods.
  - A convenient and safe road network.
- Minimising exposure of sensitive uses to air and noise pollution from the transport system.
- Being accessible to people with disabilities.
- Creating an urban structure that:
  - Responds to climate related hazards.
  - Incorporates integrated water management, including sustainable irrigation of open space.
  - Minimises peak demand on the electricity network.
  - Supports energy efficiency and solar energy generation through urban layout and lot orientation.
  - Supports waste minimisation and increased resource recovery.
- Providing utilities and services that support the uptake of renewable energy technologies, such as microgrids and energy storage systems, including batteries.
- Providing all-electric lots.

Policy documents

Consider as relevant:

- *Urban Design Guidelines for Victoria* (Department of Environment, Land, Water and Planning, 2017)

15.01-3L Subdivision design - Brimbank

27/06/2024
C225brim

General strategies

Encourage all subdivisions to incorporate underground power and solar street lighting.

Ensure that the dimensions of streets in new subdivisions can accommodate waste collection and emergency vehicles.

Residential subdivision strategies

Provide multiple active transport connections through new subdivisions.

Facilitate passive surveillance to enhance the safety of active transport routes.

Encourage an interconnected street layout that avoids the creation of new cul-de-sacs and no-through roads.

Industrial subdivision strategies

Discourage small lot subdivisions within industrial areas (Industrial Precincts, Employment Precincts and Transitional Precincts) shown on the Economic development map at Clause 02.04.

Encourage new subdivisions in industrial areas to incorporate areas of public open space.

Policy document

Consider as relevant:

- *Brimbank Industrial Land Strategy 2018 – 2030* (Brimbank City Council, 2018)

15.01-4S Healthy neighbourhoods

02/09/2025
VC283

Objective

To achieve neighbourhoods that foster healthy and active living and community wellbeing.

Strategies

Design neighbourhoods that foster community interaction and make it easy for people of all ages and abilities to live healthy lifestyles and engage in regular physical activity by providing:

- Connected, safe, pleasant and attractive walking and cycling networks that enable and promote walking and cycling as a part of daily life.
- Streets with direct, safe and convenient access to destinations.
- Conveniently located public spaces for active recreation and leisure.
- Accessibly located public transport stops.
- Amenities and protection to support physical activity in all weather conditions.

Create 20 minute neighbourhoods, that give people the ability to meet most of their everyday needs within a 20 minute walk, cycle or local public transport trip from their home.

Policy documents

Consider as relevant:

- *Urban Design Guidelines for Victoria* (Department of Environment, Land, Water and Planning, 2017)

15.01-5S Neighbourhood character

09/10/2020
VC169

Objective

To recognise, support and protect neighbourhood character, cultural identity, and sense of place.

Strategies

Support development that respects the existing neighbourhood character or contributes to a preferred neighbourhood character.

Ensure the preferred neighbourhood character is consistent with medium and higher density housing outcomes in areas identified for increased housing.

Ensure development responds to its context and reinforces a sense of place and the valued features and characteristics of the local environment and place by respecting the:

- Pattern of local urban structure and subdivision.
- Underlying natural landscape character and significant vegetation.
- Neighbourhood character values and built form that reflect community identity.

15.01-5L Neighbourhood character - Brimbank

27/06/2024
C225brim

Policy application

This policy applies to development in the Neighbourhood Residential Zone and General Residential Zone.

Strategies

Orient development to address the street frontage.

Preserve or enhance the landscape character by:

- Ensuring access ways are located to minimise any impact on street trees.
- Ensuring driveways and hard stand areas do not dominate the frontage of dwellings.
- Encouraging the retention and planting of canopy trees, especially within front setbacks.

Ensure secluded private open space is located behind the front façade of dwellings.

Policy guideline

Consider as relevant:

- Providing no more than one vehicle crossover per site frontage.

Policy document

Consider as relevant:

- *Brimbank Housing Strategy, 'Home and Housed'* (Brimbank City Council, 2014)

15.01-6S Design for rural areas

31/07/2018
VC148

Objective

To ensure development respects valued areas of rural character.

Strategies

Ensure that the siting, scale and appearance of development protects and enhances rural character.

Protect the visual amenity of valued rural landscapes and character areas along township approaches and sensitive tourist routes by ensuring new development is sympathetically located.

Site and design development to minimise visual impacts on surrounding natural scenery and landscape features including ridgelines, hill tops, waterways, lakes and wetlands.

15.02 [NO CONTENT]

10/06/2022
VC216

15.02-1S [NO CONTENT]

10/06/2022
VC216

15.03 HERITAGE

31/07/2018
VC148

15.03-1S Heritage conservation

02/09/2025
VC283

Objective

To ensure the conservation of places of heritage significance.

Strategies

Identify, assess and document places of natural and cultural heritage significance as a basis for their inclusion in the planning scheme.

Provide for the protection of natural heritage sites and man-made resources.

Provide for the conservation and enhancement of those places that are of aesthetic, archaeological, architectural, cultural, scientific or social significance.

Encourage appropriate development that respects places with identified heritage values.

Retain those elements that contribute to the importance of the heritage place.

Encourage the conservation and restoration of contributory elements of a heritage place.

Ensure an appropriate setting and context for heritage places is maintained or enhanced.

Support adaptive reuse of heritage buildings where their use has become redundant.

Consider whether it is appropriate to require the restoration or reconstruction of a heritage building in a Heritage Overlay that has been unlawfully or unintentionally demolished in order to retain or interpret the cultural heritage significance of the building, streetscape or area.

Policy guidelines

Consider as relevant:

- The findings and recommendations of the Victorian Heritage Council.

Policy documents

- The Burra Charter: The Australia ICOMOS Charter for Places of Cultural Significance (Australia ICOMOS Incorporated, 2013).

15.03-1L Heritage conservation - Brimbank

27/06/2024
C225brim

Policy application

This policy applies to all land affected by the Heritage Overlay.

Demolition strategies

Avoid the demolition of individually significant or contributory heritage places unless:

- The structural condition of the building is such that it cannot feasibly be repaired or adapted for reuse.
- The replacement building or works positively supports the ongoing heritage significance of the heritage place.

Ensure a visual record of heritage buildings that are approved for demolition is provided prior to demolition commencing.

Discourage the demolition of original chimneys.

Demolition policy guideline

Consider as relevant:

- Any application for new development to replace a heritage building that is proposed to be demolished.

Subdivision strategies

Ensure that subdivision layout maintains the original setting of the heritage place, including the retention of any original garden areas and other features where these contribute to the significance of the heritage place.

Ensure that subdivision of a heritage place will support development that is sympathetic to the scale, bulk and setbacks of surrounding heritage places.

Development strategies

Disregard the impact of non-contributory buildings and works when determining the appropriate siting, massing and scale of extension and upper storey additions to existing heritage buildings and the construction of new buildings.

Contributory buildings

Ensure that alterations and additions to contributory buildings:

- Maintain the building's architectural integrity and character.
- Do not obscure, alter or remove original features and details that contribute to the significance of the heritage place.
- Are distinguishable from the original building.
- Avoid reproduction or "mock" heritage design.
- Are sympathetic to the heritage place in terms of scale, bulk and setbacks.
- Do not introduce new building elements that are visible from the street, such as dormer windows, porticos and verandahs that detract from the significance of the heritage place.
- Do not obscure views of the principal façade(s) of surrounding heritage buildings.

Ensure that upper level additions to contributory buildings:

- Are located to the rear of the building and retain the building's original roof form.

- Are designed to minimise their visual impact.
- Do not detract from the visual dominance of the original building.

Discourage the installation of new window or door openings in the principal façade(s) of buildings.

Encourage new window and door openings that are visible to the public to be proportionally related to those of the heritage place.

Discourage the installation of external shading devices such as shutters and awnings over windows that are visible to the public.

Discourage the replacement of original timber window frames with an alternative material such as aluminium or plastic.

Encourage the accurate reconstruction of contributory features where there is evidence that they have previously been removed.

Non-contributory buildings

Locate upper level additions to the rear of non-contributory buildings and design them to be visually recessive and integrate with the heritage character and rhythm of the streetscape.

New buildings

Ensure that new buildings located to the rear of an existing contributory or non-contributory building:

- Incorporate rear setbacks to allow for landscaping and open space, for both the existing and proposed buildings.
- Reflect the scale, form, setting and side setbacks of the contributory building at the frontage of the site.

Ensure that new buildings located at the frontage of a site:

- Respect the scale, form, siting, setting and front and side setbacks of nearby contributory buildings.
- Employ a street setback that is at least the average distance of the front setbacks of existing heritage buildings on the abutting allotments.
- Adopt a contemporary, contextual design response.
- Avoid use of reproduction or ‘mock’ heritage design.
- Do not obscure views of the principal façade(s) and significant features of surrounding heritage buildings.
- Incorporate doors and windows that are proportionally related to those of surrounding heritage buildings.
- Incorporate eaves height, roof form and overall building height that relate to the surrounding heritage buildings.
- Articulate visible wall elevations and include window and doors, where appropriate, that complement any existing buildings on site.
- Limit areas of paving that are visible from the public realm, to reduce the impact of the development on the streetscape.

Industrial Heritage Buildings

Encourage the adaptive reuse of industrial heritage buildings for non-industrial uses when it can be demonstrated they won’t negatively impact on the on-going operation of existing industrial uses.

Support the removal or demolition of industrial heritage fabric to facilitate the continued operation of historically significant uses.

Car parking

Ensure car parking facilities do not dominate heritage places.

Locate car parking facilities to the side or rear of buildings.

Design car parking structures to be freestanding so they do not form part of the main façade of any building.

Ensure garages are set back behind the rear wall of the building, preferably at the rear of the site.

Ensure new crossovers and driveways do not exceed a single car width, are located to the side or rear of the site and do not allow for the parking of vehicles in front of buildings.

Ensure new crossovers and driveways are constructed using materials that reflect the character of the heritage place.

Materials, colours and finishes

Discourage the painting or rendering of unpainted surfaces.

Encourage the use of materials and colours that will enhance the significance of the heritage place.

Services and equipment

Conceal external services and equipment such as air-conditioners, hot water units, solar panels and satellite dishes from the street.

Fences

Retain original front fences, where possible.

Ensure front fences do not obscure views of a heritage place.

Ensure front fences are consistent in height, style and materials with the architectural period of the heritage place.

Signs

Ensure signs:

- Do not obscure any architectural elements that contribute to the significance of the heritage place.
- Are not internally illuminated, except where located under a verandah on an existing commercial premises.
- Are located flush to the building parapet and not at right angles to the building façade.

Landscaping

Discourage the removal of trees where the schedule to the Heritage Overlay identifies that tree controls apply, unless the trees:

- Cannot be maintained in a reasonably safe and healthy manner.
- Are causing significant structural damage to a heritage building that cannot be rectified.

Development policy guidelines

Consider as relevant:

- Providing no more than one vehicle crossover per allotment.
- Encouraging carports to be set back at least 500 millimetres behind the principal façade of a building.

Policy documents

Consider as relevant:

- *Brimbank City Council Post-Contact Cultural Heritage Study, Version 2* (Gary Vines, Olwen Ford, Graeme Butler & Francine Gilfedder, 2014)
- *Brimbank Heritage Design Guidelines, Parts 1 – 9* (Brimbank City Council, 2009)

15.03-2S Aboriginal cultural heritage

31/07/2018
VC148

Objective

To ensure the protection and conservation of places of Aboriginal cultural heritage significance.

Strategies

Identify, assess and document places of Aboriginal cultural heritage significance, in consultation with relevant Registered Aboriginal Parties, as a basis for their inclusion in the planning scheme.

Provide for the protection and conservation of pre-contact and post-contact Aboriginal cultural heritage places.

Ensure that permit approvals align with the recommendations of any relevant Cultural Heritage Management Plan approved under the *Aboriginal Heritage Act 2006.*

Policy guidelines

Consider as relevant:

- The findings and recommendations of the Aboriginal Heritage Council.
- The findings and recommendations of the Victorian Heritage Council for post-contact Aboriginal heritage places.

Policy documents

Consider as relevant:

- *Aboriginal Heritage Act 2006*

16 HOUSING

31/07/2018
VC148

Planning should provide for housing diversity, and ensure the efficient provision of supporting infrastructure.

Planning should ensure the long term sustainability of new housing, including access to services, walkability to activity centres, public transport, schools and open space.

Planning for housing should include the provision of land for affordable housing.

16.01 RESIDENTIAL DEVELOPMENT

31/07/2018
VC148

16.01-1S Housing supply

02/09/2025
VC283

Objective

To facilitate well-located, integrated and diverse housing that meets community needs.

Strategies

Plan to accommodate housing targets specified in this clause by ensuring zones and overlays deliver sufficient realisable development capacity.

Ensure that an appropriate quantity, quality and type of housing is provided, including aged care facilities and other housing suitable for older people, supported accommodation for people with disability, rooming houses, student accommodation and social housing.

Increase the proportion of housing in urban areas with good access to opportunities and servi (including under-utilised urban land) and reduce the share of new dwellings in greenfield, fringe and dispersed development areas.

Encourage higher density housing development on sites that are well located in relation to jobs, services and public transport.

Identify opportunities for increased residential densities to help consolidate urban areas.

Facilitate diverse housing that offers choice and meets changing household needs by widening housing diversity through a mix of housing types.

Encourage the development of well-designed housing that:

- Provides a high level of internal and external amenity.
- Incorporates universal design and adaptable internal dwelling design.

Support opportunities for a range of income groups to choose housing in well-serviced locations.

Plan for growth areas to provide for a mix of housing types through a variety of lot sizes, including higher housing densities in and around activity centres.

Policy documents

Consider as relevant:

- *Homes for Victorians - Affordability, Access and Choice* (Victorian Government, 2017)
- *Apartment Design Guidelines for Victoria* (Department of Environment, Land, Water and Planning, 2021)

Table 1 - Metropolitan Melbourne Housing Targets

	Housing Target	Greenfield Area Target	Established Area Target
Growth Municipalities			
Mitchell	66,000	56,000	10,000
Cardinia	30,000	21,000	9,000
Casey	87,000	58,500	28,500
Hume	79,000	53,500	25,500
Melton	109,000	104,000	5,000
Whittlesea	72,000	43,000	29,000

Wyndham	99,000	74,000	25,000
Inner Melbourne			
Melbourne	119,500	-	119,500
Port Phillip	55,000	-	55,000
Stonnington	50,000	-	50,000
Yarra	44,000	-	44,000
Middle Melbourne			
Banyule	45,500	-	45,500
Bayside	30,000	-	30,000
Boroondara	65,500	-	65,500
Darebin	69,000	-	69,000
Glen Eira	63,500	-	63,500
Hobsons Bay	22,500	-	22,500
Kingston	51,500	-	51,500
Manningham	28,500	-	28,500
Maribyrnong	48,000	-	48,000
Merri-bek	69,000	-	69,000
Monash	69,500	-	69,500
Moonee Valley	47,500	-	47,500
Whitehorse	76,500	-	76,500
Outer Melbourne			
Brimbank	59,500	-	59,500
Frankston	33,000	-	33,000
Greater Dandenong	52,500	-	52,500
Knox	43,000	-	43,000
Maroondah	39,500	-	39,500
Mornington Peninsula	24,000	-	24,000
Nillumbik	6,500	-	6,500
Yarra Ranges	25,000	-	25,000

Table 2 - Regional Victoria Housing Targets

	Housing Target	Greenfield Area Target	Established Area Target
Barwon			
Colac Otway	3,700	-	3,700
Greater Geelong	128,600	51,100	77,500
Queenscliffe	400	-	400
Surf Coast	8,000	-	8,000
Central Highlands			
Ararat	1,000	-	1,000
Ballarat	46,900	18,900	28,000
Golden Plains	12,500	-	12,500
Hepburn	3,150	-	3,150
Moorabool	20,000	-	20,000
Pyrenees	1,300	-	1,300
Gippsland			
Bass Coast	19,250	-	19,250
Baw Baw	25,700	-	25,700
East Gippsland	11,000	-	11,000
Latrobe	13,000	-	13,000
South Gippsland	8,000	-	8,000
Wellington	8,000	-	8,000
Goulburn			
Greater Shepparton	15,250	-	15,250
Mitchell	66,000	56,000	10,000
Moria	4,500	-	4,500
Murrindindi	3,350	-	3,350
Strathbogie	2,400	-	2,400
Great South Coast			
Corangamite	1,400	-	1,400
Glenelg	1,400	-	1,400
Moyne	2,900	-	2,900

Southern Grampians	1,250	-	1,250
Warrnambool	7,200	-	7,200
Loddon Campaspe			
Campaspe	4,500	-	4,500
Central Goldfields	1,700	-	1,700
Greater Bendigo	37,000	11,000	26,000
Loddon	550	-	550
Macedon Ranges	13,200	-	13,200
Mount Alexander	4,500	-	4,500
Mallee			
Buloke	150	-	150
Gannawarra	850	-	850
Mildura	8,500	-	8,500
Swan Hill	2,100	-	2,100
Ovens Murray			
Alpine	1,250	-	1,250
Benalla	1,700	-	1,700
Indigo	3,100	-	3,100
Mansfield	3,900	-	3,900
Towong	550	-	550
Wangaratta	6,000	-	6,000
Wodonga	15,200	-	15,200
Wimmera Southern Mallee			
Hindmarsh	250	-	250
Horsham	3,300	-	3,300
Northern Grampians	750	-	750
West Wimmera	200	-	200
Yarriambiack	300	-	300

16.01-1R Housing supply - Metropolitan Melbourne

02/09/2025
VC283

Strategies

Create development opportunities to meet housing targets population growth and create a sustainable city by developing housing and mixed use development opportunities in locations that are:

- In and around the Central City.
- Metropolitan activity centres and their residential catchments.
- Priority Precincts, including Suburban Rail Loop East Precincts.
- Activity centres - Housing Choice and Stations.
- Areas for residential growth.
- Areas for greyfield renewal, particularly through opportunities for land consolidation.
- Established areas close to existing services, jobs and public transport.
- Neighbourhood activity centres - especially those with good public transport connections.
- Areas near existing and proposed railway stations that can support transit-oriented development.

Identify areas that offer opportunities for more medium and high density housing near employment and transport in Metropolitan Melbourne.

Provide certainty about the scale of growth by prescribing appropriate height and site coverage provisions for different areas.

Allow for a range of minimal, incremental and high change residential areas that balance the need to protect valued areas with the need to ensure choice and growth in housing.

Create mixed use neighbourhoods at varying densities that offer more choice in housing.

16.01-1L Housing supply - Brimbank

27/06/2024
C225brim

Strategies

Increase the amount of housing and a mix of dwelling types in and around the Sunshine Metropolitan Activity Centre, St Albans Major Activity Centre, Sydenham Major Activity Centre, Deer Park Major Activity Centre and Keilor Downs Activity Centre where there is good access to services, facilities and transport.

Support residential development within heritage precincts provided that development is located to the rear of existing dwellings.

Encourage student accommodation to locate within walking distance of tertiary institutions including Victoria University campuses at Sunshine and St Albans and University of Melbourne.

Policy guideline

Consider as relevant:

- Encouraging a mix of dwelling configurations and bedroom numbers in developments of three or more dwellings.

Policy documents

Consider as relevant:

- *Brimbank Housing Strategy, 'Home and Housed'* (Brimbank City Council, 2014)
- *Brimbank Activity Centre Strategy* (Brimbank City Council, 2018)

16.01-2S Housing affordability

02/09/2025
VC283

Objective

To deliver affordable housing in areas with good access to opportunities and services.

Strategies

Improve housing affordability by:

- Ensuring housing supply continues to be sufficient to meet demand.
- Increasing choice in housing type, tenure and cost to meet the needs of households as they move through life cycle changes and to support diverse communities.
- Promoting good housing and urban design to minimise negative environmental impacts and keep costs down for residents and the wider community.
- Encouraging a significant proportion of new development to be affordable for households on very low to moderate incomes.

Increase the supply of well-located affordable housing by:

- Facilitating a mix of private, affordable and social housing in suburbs, growth areas, activity centres and urban renewal precincts.
- Ensuring the redevelopment and renewal of public housing stock better meets community needs.

Facilitate the delivery of social housing by identifying surplus government land suitable for housing.

Policy documents

Consider as relevant:

- *Homes for Victorians - Affordability, Access and Choice* (Victorian Government, 2017)

16.01-2L Housing affordability - Brimbank

27/06/2024
C225brim

Strategies

Encourage the provision of affordable housing in large scale residential developments.

Encourage affordable housing to be provided in partnership with registered community housing agencies.

16.01-3S Rural residential development

09/10/2020
VC169

Objective

To identify land suitable for rural residential development.

Strategies

Manage development in rural areas to protect agriculture and avoid inappropriate rural residential development.

Encourage the consolidation of new housing in existing settlements where investment in physical and community infrastructure and services has already been made.

Demonstrate need and identify locations for rural residential development through a housing and settlement strategy.

Ensure planning for rural residential development avoids or significantly reduces adverse economic, social and environmental impacts by:

- Maintaining the long-term sustainable use and management of existing natural resource attributes in activities including agricultural production, water, mineral and energy resources.
- Protecting existing landscape values and environmental qualities such as water quality, native vegetation, biodiversity and habitat.
- Minimising or avoiding property servicing costs carried by local and state governments.
- Maintaining an adequate buffer distance between rural residential development and animal production.

Ensure land is not zoned for rural residential development if it will encroach on high quality productive agricultural land or adversely impact on waterways or other natural resources.

Discourage development of small lots in rural zones for residential use or other incompatible uses.

Encourage consolidation of existing isolated small lots in rural zones.

Ensure land is only zoned for rural residential development where it:

- Is located close to existing towns and urban centres, but not in areas that will be required for fully serviced urban development.
- Can be supplied with electricity, water and good quality road access.

16.01-4S Community care accommodation

04/11/2022
VC226

Objective

To facilitate the establishment of community care accommodation and support their location being kept confidential.

Strategies

Planning schemes should not require a planning permit for or prohibit the use of land in a residential area for community care accommodation provided no more than 20 clients are accommodated and the use is funded by, or carried out by or on behalf of, a government department or public authority, including a public authority established for a public purpose under a Commonwealth Act.

Facilitate the confidential establishment of community care accommodation through appropriate permit, notice and review exemptions.

16.01-5S Residential aged care facilities

09/10/2020
VC169

Objective

To facilitate the development of well-designed and appropriately located residential aged care facilities.

Strategies

Recognise that residential aged care facilities contribute to housing diversity and choice, and are an appropriate use in a residential area.

Recognise that residential aged care facilities are different to dwellings in their purpose and function, and will have a different built form (including height, scale and mass).

Ensure local housing strategies, precinct structure plans and activity centre structure plans provide for residential aged care facilities.

Ensure that residential aged care facilities are located in residential areas, activity centres and urban renewal precincts, close to services and public transport.

Encourage planning for housing that:

- Delivers an adequate supply of land or redevelopment opportunities for residential aged care facilities.
- Enables older people to live in appropriate housing in their local community.

Provide for a mix of housing for older people with appropriate access to care and support services.

Ensure that proposals to establish residential aged care facilities early in the life of a growth area are in locations that will have early access to services and public transport.

Ensure that residential aged care facilities are designed to respond to the site and its context.

Promote a high standard of urban design and architecture in residential aged care facilities.

Policy guidelines

Consider as relevant:

- The Commonwealth Government's Responsible ratios for the provision of aged care places under the *Aged Care Act 1997*.

16.01-5L Residential aged care facilities - Brimbank

27/06/2024
C225brim

Strategy

Ensure that the design of residential aged care facilities:

- Provides open space.
- Maximises security and amenity for residents.
- Provides safe and convenient pedestrian and vehicle access.

Policy documents

Consider as relevant:

- *Brimbank Age Friendly City Plan 2018 - 2022* (Brimbank City Council, 2018)
- *Brimbank Housing Strategy, 'Home and Housed'* (Brimbank City Council, 2014)

17 ECONOMIC DEVELOPMENT

31/07/2018
VC148

Planning is to provide for a strong and innovative economy, where all sectors are critical to economic prosperity.

Planning is to contribute to the economic wellbeing of the state and foster economic growth by providing land, facilitating decisions and resolving land use conflicts, so that each region may build on its strengths and achieve its economic potential.

17.01 EMPLOYMENT

31/07/2018
VC148

17.01-1S Diversified economy

31/07/2018
VC148

Objective

To strengthen and diversify the economy.

Strategies

Protect and strengthen existing and planned employment areas and plan for new employment areas.

Facilitate regional, cross-border and inter-regional relationships to harness emerging economic opportunities.

Facilitate growth in a range of employment sectors, including health, education, retail, tourism, knowledge industries and professional and technical services based on the emerging and existing strengths of each region.

Improve access to jobs closer to where people live.

Support rural economies to grow and diversify.

17.01-1R Diversified economy - Metropolitan Melbourne

02/09/2025
VC283

Strategies

Support the Central City to become Australia's largest commercial and residential centre by 2050, by planning for office, retail, residential, education, health, entertainment and cultural activity spaces.

Plan for the redevelopment of Priority Precincts and Urban-Renewal Precincts in and around the Central City to deliver high-quality, distinct and diverse neighbourhoods offering a mix of uses.

Provide a mix of uses within Suburban Rail Loop Precincts and prioritise higher density development.

Avoid development in Suburban Rail Loop Precincts that would impede opportunities for significant future growth.

Facilitate the development of Employment and Innovation Areas by ensuring they:

- Have a high level of amenity to attract businesses and workers.
- Are supported by good public transport services and integrated walking and cycling paths.
- Maximise investment opportunities for the location of knowledge intensive firms and jobs.

Support the employment and servicing role of Health and Education Precincts by:

- Focussing on improving access, particularly public transport access.
- Encouraging co-location of facilities to better utilise existing infrastructure.
- Supporting and facilitating growth of associated businesses and industries.
- Reinforcing their specialised economic functions while also providing opportunities for ancillary retail, commercial, accommodation and supporting services.

Support diverse employment generating uses, including offices, innovation and creative industries in identified areas within regionally significant industrial precincts, where compatible with adjacent uses and well connected to transport networks.

Consider how land use change proposals can respond to local and regional employment demand or identify how it can be accommodated elsewhere.

Plan for industrial land in suitable locations to support employment and investment opportunities.

Facilitate investment in Melbourne's outer areas to increase local access to employment.

17.01-1L Diversified economy - Brimbank

27/06/2024
C225brim

Strategy

Support the redevelopment of the Western Highway and McIntyre Road Employment Precincts as locations for industry, research and development, and business services.

17.01-2S Innovation and research

04/10/2018
VC149

Objective

To create opportunities for innovation and the knowledge economy within existing and emerging industries, research and education.

Strategies

Encourage the expansion and development of logistics and communications infrastructure.

Support the development of business clusters.

Support the development of enterprise precincts that build the critical mass of employment in an area, leverage the area's public and private sector economic competitive strengths and assets, and cater to a diversity of employment types and scales.

Promote an accessible, well-connected, high-amenity and collaborative physical environment that is conducive to innovation and to creative activities.

Encourage the provision of infrastructure that helps people to be innovative and creative, learn new skills and start new businesses in locations identified to accommodate employment and economic growth.

Support well-located, appropriate and low-cost premises for not-for-profit or start-up enterprises.

Improve access to community-based information and training through further developing libraries as community learning centres.

17.01-2L Innovation and research - Brimbank

27/06/2024
C225brim

Strategy

Support the provision of community services, tertiary education, health-related training, healthcare, retail and professional services in the Sunshine National Employment and Innovation Cluster (NEIC).

Policy document

Consider as relevant:

- *Brimbank Activity Centre Strategy* (Brimbank City Council, 2018)

17.02 COMMERCIAL

31/07/2018
VC148

17.02-1S Business

15/03/2024
VC256

Objective

To encourage development that meets the community's needs for retail, entertainment, office and other commercial services.

Strategies

Plan for an adequate supply of commercial land in appropriate locations.

Ensure commercial facilities are aggregated and provide net community benefit in relation to their viability, accessibility and efficient use of infrastructure.

Locate commercial facilities in existing or planned activity centres.

Provide new convenience shopping facilities to provide for the needs of the local population in new residential areas and within, or immediately adjacent to, existing commercial centres.

Provide small scale shopping opportunities that meet the needs of local residents and workers in convenient locations.

Provide outlets of trade-related goods or services directly serving or ancillary to industry that have adequate on-site car parking.

Locate cinema based entertainment facilities within or on the periphery of existing or planned activity centres.

Apply a five year time limit for commencement to any planning permit for a shopping centre or shopping centre expansion of more than 1000 square metres leasable floor area.

Regulate the use and development of land for a sex services premises in commercial and mixed use areas in the same way as for other types of shop.

Ensure that planning for the use and development of land for a sex services premises and home based business is consistent with decriminalisation of sex work and provides for the reduction of discrimination against, and harm to, sex workers.

17.02-2S Out-of-centre development

31/07/2018
VC148

Objective

To manage out-of-centre development.

Strategies

Discourage proposals for expansion of single use retail, commercial and recreational facilities outside activity centres.

Give preference to locations in or on the border of an activity centre for expansion of single use retail, commercial and recreational facilities.

Discourage large sports and entertainment facilities of metropolitan, state or national significance in out-of-centre locations unless they are on the Principal Public Transport Network and in locations that are highly accessible to their catchment of users.

Ensure that out-of-centre proposals are only considered where the proposed use or development is of net benefit to the community in the region served by the proposal or provides small scale shopping opportunities that meet the needs of local residents and workers in convenient locations.

17.03 INDUSTRY

31/07/2018
VC148

17.03-1S Industrial land supply

14/01/2025
VC237

Objective

To ensure availability of land for industry.

Strategies

Provide an adequate supply of industrial land in appropriate locations including sufficient stocks of large sites for strategic investment.

Identify land for industrial development in urban growth areas where:

- Good access for employees, freight and road transport is available.
- Appropriate buffer areas can be provided between the proposed industrial land and nearby sensitive land uses.

Protect and carefully plan existing industrial areas to, where possible, facilitate further industrial development.

Preserve locally significant industrial land for industrial or employment generating uses, unless long-term demand for these uses can be demonstrably met elsewhere.

Avoid non-industrial land uses that will prejudice the availability of land in identified industrial areas for future industrial use.

Policy documents

Consider as relevant:

- *Separation Distance Guideline* (Environment Protection Authority, August 2024)
- *Landfill Buffer Guideline* (Environment Protection Authority, August 2024)

17.03-1L Industrial land supply - Brimbank

27/06/2024
C225brim

Strategies

Encourage coordinated and integrated, rather than ad-hoc development of large sites or Transitional Precincts.

Discourage retailing and non-industrial uses within industrial areas unless they are:

- Manufacturing sales, ancillary retail or uses that provide a service to employees.
- Designed and sited to reinforce the primacy of industrial uses.

Discourage sensitive uses such as fitness centres, play centres and sports facilities within the Industrial 2 Zone.

Support office uses where they are associated with the industry carried out on site.

Policy documents

Consider as relevant:

- *Brimbank Industrial Land Use Strategy 2018 - 2030* (Brimbank City Council, 2018)

17.03-2S Sustainable industry

14/01/2025
VC237

Objective

To facilitate the sustainable operation of industry.

Strategies

Ensure that industrial activities requiring substantial threshold distances are located in the core of industrial areas.

Encourage activities with minimal threshold requirements to locate towards the perimeter of the industrial area.

Minimise inter-industry conflict and encourage like industries to locate within the same area.

Protect industrial activity in industrial zones from the encroachment of commercial, residential and other sensitive uses that would adversely affect industry viability.

Encourage industrial uses that meet appropriate standards of safety and amenity to locate within activity centres.

Support the retention of small-scale industries servicing established urban areas through appropriate zoning.

Provide adequate separation and buffer areas between sensitive uses and offensive or dangerous industries and quarries to ensure that residents are not affected by adverse environmental effects, nuisance or exposure to hazards.

Encourage manufacturing and storage industries that generate significant volumes of freight to locate close to air, rail and road freight terminals.

Policy documents

Consider as relevant:

- *Separation Distance Guideline* (Environment Protection Authority, August 2024)
- *Landfill Buffer Guideline* (Environment Protection Authority, August 2024)

17.03-3S Significant industrial land

02/09/2025
VC283

Objective

To protect significant industrial land.

Strategies

Protect state significant industrial precincts from incompatible land uses to allow for future growth. State significant industrial precincts include but are not limited to:

- Southern Industrial Precinct - Dandenong South.
- Northern Industrial Precinct - Campbellfield, Somerton and Thomastown.
- Western Industrial Precinct - Laverton North and Derrimut.
- Officer / Pakenham Industrial Precinct.
- Port of Hastings Industrial Precinct.

Ensure sufficient availability of strategically located land for major industrial development, particularly for industries and storage facilities that require significant threshold distances from sensitive or incompatible uses.

Protect heavy industrial areas from inappropriate development and maintain adequate buffer distances from sensitive or incompatible uses.

Policy documents

Consider as relevant:

- *Melbourne Industrial and Commercial Land Use Plan* (Department of Environment, Land, Water and Planning, 2020)
- *Industrial and Commercial Land Classifications* (Department of Transport and Planning, 2025)

17.03-3R Regionally significant industrial land - Metropolitan Melbourne

02/09/2025
VC283

Strategies

Protect industrial land of regional significance and facilitate continual growth in freight, logistics and manufacturing investment.

Support the transition from manufacturing land uses to other employment uses in strategically identified areas well connected to transport networks, especially in Suburban Rail Loop Precincts.

17.03-3R Regionally significant industrial land - Metropolitan Melbourne - Western Metro Region

03/03/2023
VC215

Strategy

Protect industrial land in Toolern, Plumpton and South of Werribee, and industrial land adjacent to major transport gateways by:

- Prioritising the retention of industrial uses on existing unfragmented industrial zoned land.
- Supporting other employment uses where compatible with or supportive of adjacent industrial uses, in areas well connected to transport networks.

17.03-3L Industrial land and precincts - Brimbank

27/06/2024
C225brim

Western State Significant Industrial Precinct strategies

Retain and support the zoning of land that prioritises industrial land uses.

Support the retention and creation of large industrial lots to maintain land supply for large scale operations.

Derrimut Industrial Precinct strategies

Support the development of the precinct as a key hub for logistics.

Encourage use and development that supports food manufacturing, metal manufacturing, transport and warehousing.

North Sunshine Industrial Precinct strategy

Support the development of the precinct as a location for small-scale manufacturing, furniture manufacturing, trade supplies, artisan and craft production and start-up businesses.

Sunshine Industrial Precinct strategies

Encourage complementary non-industrial uses to locate along Sunshine Road and adjacent to existing sensitive uses.

Facilitate active transport connections within the transmission line easement.

Sunshine West Industrial Precinct strategies

Encourage use and development that supports transport and warehousing.

Facilitate improved access to the Kororoit Creek trail and Buckingham Reserve.

Facilitate active transport connections within the transmission line easement.

Brooklyn Industrial Precinct strategies

Support innovative, emerging and environmentally sustainable industries.

Enhance the image of the precinct through urban design and landscaping improvements.

Encourage buildings that are of a contemporary architectural style.

Support the upgrading of physical infrastructure in the precinct, particularly roads and drainage.

Encourage use and development that supports food manufacturing and materials recycling.

Support the delivery of an accessible open space network along Kororoit Creek to service the precinct.

Manage the environmental impacts of land contamination, stormwater quality, drainage and environmental degradation from the precinct.

Support the coordinated and staged re-development of larger lots within the precinct.

Support light industry, warehousing, small factory and other supporting commercial uses, where these do not compromise industrial uses.

Encourage industrial use and development to be designed and sited to internalise operations.

Encourage development that utilises innovative engineering and technology solutions to reduce amenity impacts, including odour and noise emissions.

Orica Industrial Precinct strategies

Encourage use and development that supports chemical production.

Ensure development of the precinct and reuse of heritage places does not undermine the continued operation of existing major hazard facilities.

Calder Park Industrial Precinct strategy

Support the development of the precinct as an industrial area for warehousing and logistics.

Tullamarine Industrial Precinct strategy

Encourage use and development that supports food manufacturing, metal manufacturing, transport and warehousing.

Policy documents

Consider as relevant:

- *Brooklyn Evolution* (Brimbank City Council, 2016)
- *Brimbank Industrial Land Use Strategy 2018 – 2030* (Brimbank City Council, 2018)

17.04 TOURISM

31/07/2018
VC148

17.04-1S Facilitating tourism

31/07/2018
VC148

Objective

To encourage tourism development to maximise the economic, social and cultural benefits of developing the state as a competitive domestic and international tourist destination.

Strategies

Encourage the development of a range of well-designed and sited tourist facilities, including integrated resorts, accommodation, host farm, bed and breakfast and retail opportunities.

Seek to ensure that tourism facilities have access to suitable transport.

Promote tourism facilities that preserve, are compatible with and build on the assets and qualities of surrounding activities and attractions.

Create innovative tourism experiences.

Encourage investment that meets demand and supports growth in tourism.

Policy guidelines

Consider as relevant:

- Any applicable regional tourism development strategy.

Policy documents

Consider as relevant:

- *Tourism Investment Guidelines – Your Guide to Tourism Investment in Victoria* (Tourism Victoria, 2008)

17.04-1R Tourism in Metropolitan Melbourne

31/07/2018
VC148

Objective

To maintain and develop Metropolitan Melbourne as a desirable tourist destination.

Strategies

Maintain Metropolitan Melbourne's position as a global, national and local destination in its own right and as a gateway to regional Victoria by:

- Developing city precincts and promenades.
- Revitalising the retail core of the Central City.
- Supporting artistic and cultural life.
- Improving public facilities, amenities and access.
- Maintaining city safety.
- Providing information and leisure services.
- Improving transport infrastructure.

17.04-2S Coastal and maritime tourism and recreation

20/03/2023
VC229

Objective

To encourage a diverse range of strategically located and well-designed coastal and maritime tourism and recreational opportunities that strengthen people's connection with the marine and coastal environment.

Strategies

Support safe and sustainable recreation and tourism development including ecotourism, tourism and major maritime events that:

- Responds to identified demand.
- Minimises impact on environmental and cultural values.
- Minimises impact on other users.
- Minimises direct and cumulative impacts.
- Maintains public safety.
- Responds to the carrying capacity of the site.
- Minimises exposure to coastal hazard risks and risks posed by climate change.

Ensure a diverse range of accommodation options and coastal experiences are provided for and maintained.

Ensure sites and facilities are accessible to all.

Ensure tourism development, within non-urban areas, demonstrates a tourist accommodation need and supports a nature-based approach.

Ensure development is of an appropriate scale, use and intensity relative to its location and minimises impacts on the surrounding natural, visual, environmental and coastal character.

Develop a network of maritime precincts around Port Phillip and Western Port that serve both local communities and visitors.

Maintain and expand boating and recreational infrastructure around the bays in maritime precincts at Frankston, Geelong, Hastings, Hobsons Bay, Mordialloc, Mornington, Patterson River, Portarlington, Queenscliff, St Kilda, Stony Point/Cowes and Wyndham.

Support a sustainable network of facilities for recreational boating and water-based activities that respond to:

- Identified demand.
- Use and safety considerations.
- The carrying capacity of the location.
- Coastal processes.
- Environmental values.

Strategically plan and operate ports to complement each other in the context of the broader economy, transport networks and the maritime and coastal environments within which they are regulated.

Provide public access to recreational facilities and activities on land and water.

Policy guidelines

Consider as relevant:

- *Coastal Spaces Landscape Assessment Study* (Department of Sustainability and Environment, 2006)

- *Gippsland Boating Coastal Action Plan 2013 - Gippsland Coastal Board*
- *Recreational Boating Facilities Framework July 2014 - Central Coastal Board*
- *Western Boating Coastal Action Plan 2010 - Western Coastal Board*

Policy documents

Consider as relevant:

- *Marine and Coastal Policy* (Department of Environment, Land, Water and Planning, 2020)
- *Marine and Coastal Strategy* (Department of Environment, Land, Water and Planning, 2022)
- *Siting and Design Guidelines on the Victorian Coast* (Department of Environment, Land, Water and Planning, 2020)

18 TRANSPORT

09/12/2021
VC204

Planning should ensure a safe, integrated and sustainable transport system that:

- Provides access to social and economic opportunities to support individual and community wellbeing.
- Facilitates economic prosperity.
- Actively contributes to environmental sustainability.
- Facilitates network-wide efficient, coordinated and reliable movements of people and goods.
- Supports health and wellbeing.

18.01 LAND USE AND TRANSPORT

09/12/2021
VC204

18.01-1S Land use and transport integration

02/09/2025
VC283

Objective

To facilitate access to social, cultural and economic opportunities by effectively integrating land use and transport.

Strategies

Plan and develop a transport system that facilitates:

- Social and economic inclusion for all people and builds community wellbeing.
- The best use of existing social and economic infrastructure.
- A reduction in the distances people have to travel to access jobs and services.
- Better access to, and greater mobility within, local communities.
- Network-wide efficiency and coordinated operation.

Plan land use and development to:

- Protect existing transport infrastructure from encroachment or detriment that would impact on the current or future function of the asset.
- Protect transport infrastructure that is in delivery from encroachment or detriment that would impact on the construction or future function of the asset.
- Protect planned transport infrastructure from encroachment or detriment that would impact deliverability or future operation.
- Protect identified potential transport infrastructure from being precluded by land use and development.

Plan land use and development to allow for the ongoing improvement and development of the State Transport System in the short and long term.

Plan movement networks and adjoining land uses to minimise disruption to residential communities and their amenity.

Plan the timely delivery of transport infrastructure and services to support changing land use and associated transport demands.

Plan improvements to public transport, walking and cycling networks to coordinate with the ongoing development and redevelopment of urban areas.

Plan the use of land adjacent to the transport system having regard to the current and future development and operation of the transport system.

Reserve land for strategic transport infrastructure to ensure the transport system can be developed efficiently to meet changing transport demands.

Support urban development that makes jobs and services more accessible:

- In accordance with forecast demand.
- By taking advantage of all available modes of transport.

Protect existing and facilitate new walking and cycling access to public transport.

Locate major government and private sector investments in Major regional cities, Regional Cities and Regional service centres on major transport corridors to maximise the access and mobility of communities.

Design neighbourhoods to:

- Better support active living.
- Increase the share of trips made using sustainable transport modes.

- Respond to the safety needs of all users.

Design the transport system and adjacent areas to achieve visual outcomes that are responsible to local context with particular reference to:

- Landscaping.
- The placement of signs.
- Providing buffer zones and resting places.

Policy documents

Consider as relevant:

- *Movement and Place in Victoria* (Department of Transport, February 2019)
- *Delivering the Goods, Creating Victorian Jobs: Victorian Freight Plan* (Department of Economic Development, Jobs, Transport and Resources, July 2018)

18.01-2S Transport system

02/09/2025
VC283

Objective

To facilitate the efficient, coordinated and reliable movement of people and goods by developing an integrated and efficient transport system.

Strategies

Plan and develop a transport system integrated across all movement networks that:

- Facilitates the efficient, coordinated and reliable movement of people and goods at all times.
- Optimises transport system capacity.
- Improves connectivity and facilitates the growth and development of regional Victoria.
- Improves connectivity between Victoria's Major regional cities, Regional cities, Regional service centres and metropolitan Melbourne.
- Ensures sufficient capacity for the movement of passengers into and out of Victoria at Principal Transport Gateways.
- Improves how goods are moved to local, interstate and overseas markets.
- Maximises access to residential areas, employment, markets, services and recreation.
- Improves local transport options to support 20-minute neighbourhoods in Melbourne's suburbs and Victoria's regional cities and towns.
- Is legible and enables easy access and movement between modes.

Plan movement networks that share the same space to do so in a way that balances the needs of the different users of the transport system.

Plan and develop the State Transport System comprising the:

- Principal Bicycle Network: Existing and future high quality cycling routes that provide access to major destinations and facilitate cycling for transport, sport, recreation and fitness.
- Principal Public Transport Network: Existing and future high quality public transport routes in the Melbourne metropolitan area.
- Regional Rail Network: Existing and future passenger rail routes in regional Victoria.
- Principal Road Network: Declared arterial roads and freeways under the *Road Management Act 2004*.
- Principal Freight Network: Existing and future corridors and precincts where the movement of high volumes of freight are concentrated or of strategic value.
- Principal Transport Gateways: Existing and future ports, airports and interstate terminals that serve as key locations for moving passengers and freight into, out of and around Victoria.

Facilitate delivery of:


- Declared major transport projects and their ancillary projects that are of economic, social or environmental significance to the State of Victoria.
- Transport projects that improve the State Transport System.

Policy documents

Consider as relevant:

- *Movement and Place in Victoria* (Department of Transport, February 2019)

State Transport System – Metropolitan Melbourne Plan



State Transport System – Regional Victoria Plan



© The State of Victoria Department of Environment, Land, Water and Planning 2021 The State of Victoria does not warrant the accuracy or completeness of information in this publication and any person using or relying upon such information does so on the basis that the State of Victoria shall bear no responsibility or liability whatsoever for any errors, faults, defects or omissions in the information.

18.01-3S Sustainable and safe transport

09/12/2021
VC204

Objective

To facilitate an environmentally sustainable transport system that is safe and supports health and wellbeing.

Strategies

Plan and develop the transport system to:

- Maximise the efficient use of resources including infrastructure, land, services and energy.
- Prepare for and adapt to climate change impacts.
- Prioritise the use of sustainable personal transport.
- Protect, conserve and improve the natural environment by supporting forms of transport, energy use and transport technologies that have the least environmental impact.
- Avoid, minimise and offset harm to the environment by:
  - Protecting biodiversity.
  - Reducing transport-related greenhouse gas emissions.

Plan the transport system to be safe by:

- Developing safe transport infrastructure.
- Optimising accessibility, emergency access, service and amenity.
- Separating pedestrians, bicycles and motor vehicles, where practicable.
- Reducing the need for cyclists to mix with other road users.
- Supporting road users to make safe choices through design and wayfinding techniques.
- Prioritising transport safety when designing high-speed roads and intersections.

Support forms of transport and energy use that have the greatest benefit for, and least negative impact on, health and wellbeing.

Design the transport system to be accessible to all users.

Design new suburbs to respond to the safety, health and wellbeing needs of all road users.

Design development to promote walking, cycling and the use of public transport, in that order, and minimise car dependency.

Policy documents

Consider as relevant:

- *Victorian Road Safety Strategy 2021-2030* (Department of Transport, 2021)

18.01-3R Sustainable and safe transport - Metropolitan Melbourne

09/12/2021
VC204

Strategies

Improve local travel options for walking and cycling to support 20 minute neighbourhoods.

18.02 MOVEMENT NETWORKS

31/07/2018
VC148

18.02-1S Walking

09/12/2021
VC204

Objective

To facilitate an efficient and safe walking network and increase the proportion of trips made by walking.

Strategies

Plan and develop walking networks to:

- Provide pedestrian routes that are safe, direct and comfortable to use.
- Enable walking as a part of everyday life.
- Enable people to meet more of their needs locally and rely less on their cars.
- Be accessible to vehicles that use footpaths, including wheelchairs, prams and scooters.
- Accommodate emerging forms of low-emission, low-speed personal transport.

Develop principal pedestrian networks for local areas that link with the transport system.

Provide walking infrastructure in all major transport projects.

Design walking routes to be comfortable by providing shelter from the sun through canopy trees, verandahs and other structures.

Design direct, comfortable and connected walking infrastructure to and between key destinations including activity centres, public transport interchanges, employment areas, urban renewal precincts and major attractions.

Policy documents

Consider as relevant:

- *Guidelines for developing Principal Pedestrian Networks* (Department of Economic Development, Jobs, Transport and Resources, 2015)

18.02-2S Cycling

02/09/2025
VC283

Objective

To facilitate an efficient and safe bicycle network and increase the proportion of trips made by cycling.

Strategies

Plan and develop cycling networks to:

- Provide routes that are safe, comfortable, low-stress and well connected.
- Enable cycling as a part of everyday life.
- Enable people to meet more of their needs locally by cycling and to rely less on their cars.
- Accommodate emerging forms of low emission, low and moderate speed personal transport.

Protect and develop the Principal Bicycle Network to provide high-quality cycling routes that are direct and connected, to and between key destinations including activity centres, public transport interchanges, employment areas, urban renewal precincts and major attractions.

Develop Strategic Cycling Corridors by:

- Integrating them with stations and major interchanges on the public transport network that serve places of state significance.
- Integrating them with the central city, Employment and Innovation Areas, major activity centres and other destinations of metropolitan or state significance.
- Facilitating safer, lower stress and more direct journeys using a combination of cycleways, cycle paths and shared streets.
- Providing the most direct route practical.
- Designing transport corridors to prioritise cycling links and cyclists.

Protect Strategic Cycling Corridors from encroachment by development and incompatible interface treatments such as cross overs.

Support increased cycling by providing:

- Cycling routes and cycling infrastructure early in new developments and in in all major transport projects.
- Cycle parking and related end of trip facilities to meet demand at education, recreation, transport, shopping, commercial, public transport interchanges and community facilities, significant trip generating developments and other major attractions.
- Facilities for cyclists, particularly storage, at public transport interchanges and rail stations.
- Vegetation to shade cycling routes.

Policy documents

Consider as relevant:

- *Principal Bicycle Network* (VicRoads, 2012)
- *Strategic Cycling Corridors* (Department of Transport, 2021)
- *Victorian Cycling Strategy 2018-28* (Transport for Victoria)

18.02-3S Public transport

09/12/2021
VC204

Objective

To facilitate an efficient and safe public transport network and increase the proportion of trips made by public transport.

Strategies

Plan and develop public transport to:

- Connect activity centres, job-rich areas and outer suburban areas.
- Enable people to not have to rely on cars for personal transport.
- Integrate bus and tram networks and stops and public transport interchanges in new development areas, including key urban renewal precincts and outer-suburban areas.
- Integrate with land use and development in outer suburban and growth areas.

Protect and develop the Principal Public Transport Network and Regional Rail Network to facilitate:

- High quality public transport services that support increased diversity and density of development, particularly at interchanges, activity centres and where Principal Public Transport Network routes intersect.
- Modern commuter-style public transport services that link Melbourne with the regional growth areas of Geelong, Bendigo, Ballarat, Seymour and Traralgon.
- Service improvements to other regional and rural areas.
- A metro-style rail system that provides a very high frequency of service in the Melbourne metropolitan area.
- A new high quality orbital rail (Suburban Rail Loop) through Melbourne's middle suburbs.
- A balance between the rail usage needs of public transport and freight.

Facilitate public transport infrastructure in all major transport projects.

Allocate adequate land and infrastructure to support public transport provision in activity centres, transport interchanges and major commercial, retail and community facilities.

Locate higher density and increased development on or close to the Principal Public Transport Network in a way that does not compromise the efficiency of the Principal Public Transport Network.

Support development that facilitates the delivery and operation of public transport services.

Policy documents

Consider as relevant:

- *Principal Public Transport Network* (State Government of Victoria, 2017)
- *VicTrack Rail Development Interface Guidelines* (VicTrack, 2019)
- *Public Transport Guidelines for Land Use Development* (Department of Transport, 2008)

18.02-3R Principal Public Transport Network

09/12/2021
VC204

Strategies

Facilitate high-quality public transport access to job-rich areas.

Maximise the use of existing infrastructure and increase the diversity and density of development along the Principal Public Transport Network, particularly at interchanges, activity centres and where principal public transport routes intersect.

Identify and plan for new Principal Public Transport Network routes.

Support the Principal Public Transport Network with a comprehensive network of local public transport.

Plan for local bus services to provide for connections to the Principal Public Transport Network.

Improve the operation of the Principal Public Transport Network by providing for:

- A metro-style rail system.
- Extended tram lines and the establishment of a light rail system.
- Road space management measures including transit lanes, clearways, stops and interchanges.

18.02-4S Roads

02/09/2025
VC283

Objective

To facilitate an efficient and safe road network that integrates all movement networks and makes best use of existing infrastructure.

Strategies

Plan and develop the road network to:

- Ensure people are safe on and around roads.
- Improve people's perceptions of safety on and around roads.
- Improve road connections for all road users.
- Facilitate the use of public transport, cycling and walking.
- Integrate new and emerging technologies into road design, including the increasing connectivity and automation of vehicles.
- Accommodate the expansion of the High Productivity Freight Vehicle Network, and oversize and overmass vehicles.

Protect and develop the Principal Road Network to:

- Provide high mobility for through traffic and the efficient movement of freight by facilitating adequate movement capacity and speeds.
- Improve cross-town arterial links in outer suburbs and growth areas, including circumferential and radial movement to facilitate access to jobs and services.
- Limit access points to high-volume, high-speed roads by utilising urban design techniques such as service roads and internal connector roads.
- Improve high-capacity on-road public transport.

Develop declared freeways to:

- Link Melbourne with major regional cities, major interstate locations and other key locations important to the economy along major national and state transport corridors.
- Connect and provide access to Principal Transport Gateways and freight-generating areas.
- Improve connections to Employment and Innovation Areas.
- Connect dispersed major residential areas with key destinations and lower density employment areas.
- Avoid private access, except for service centres.

Provide for grade separation at railway crossings, except with the approval of the Minister for Transport and Infrastructure.

Improve Melbourne's distinctive, established boulevards by developing a connected, contemporary network of boulevards within the urban growth boundary.

Design road space to complement land use and meet business and community needs through the provision of wider footpaths, bicycle lanes, transit lanes (for buses and commercial passenger vehicles) and freight routes, in line with the designated role of the road.

Design roads to facilitate the safe movement of people and goods while providing places for people to interact and gather in high pedestrian areas like activity centres, around schools and around community facilities.

Plan an adequate supply of car parking that is designed and located to:

- Protect the role and function of nearby roads.

- Enable the efficient movement and delivery of goods.
- Facilitate the use of public transport.
- Maintain journey times and the reliability of the on-road public transport network.
- Protect residential areas from the effects of road congestion created by on-street parking.
- Enable easy and efficient use.
- Achieve a high standard of urban design.
- Protect the amenity of the locality, including the amenity of pedestrians and other road users.
- Create a safe environment, particularly at night.

Allocate land for car parking considering:

- The existing and potential modes of access including public transport.
- The demand for off-street car parking.
- Road capacity.
- The potential for demand-management of car parking.

Consolidate car parking facilities to improve efficiency.

Design public car parks to incorporate electric charging facilities to support the use of low-emission vehicles.

Policy documents

Consider as relevant:

- *Victorian Road Safety Strategy 2021-2030* (Department of Transport, 2021)
- *Movement and Place in Victoria* (Department of Transport, February 2019)

18.02-5S Freight

09/12/2021
VC204

Objective

To facilitate an efficient, coordinated, safe and sustainable freight and logistics system that enhances Victoria's economic prosperity and liveability.

Strategies

Plan and develop Victoria's freight and logistics system to:

- Support the movement of freight within Victoria's freight and logistics system.
- Improve freight efficiency and capacity.
- Manage negative impacts of freight generating activities on urban amenity, the development of urban areas, and on the efficient operation of movement networks.
- Prioritise new technologies that enhance road and rail safety, optimise the metropolitan road network, better manage congestion and reduce supply chain costs.
- Accommodate High Productivity Freight Vehicles, and oversize and overmass vehicles.
- Increase the capacity of the rail network to carry larger volumes of freight.

Protect and develop the Principal Freight Network, including freight movement corridors and freight places, and Principal Transport Gateways, by:

- Facilitating the movement of high volumes of freight and freight of strategic value.
- Linking areas of production and manufacturing to national and international gateways and export markets.
- Increasing the capacity of Principal Transport Gateways and supporting their use and development as important locations for employment and economic activity.
- Designing the Principal Freight Network to adapt to commodity, market and operating changes.
- Managing encroachment from incompatible land use and development that would undermine its ability to operate.

Support the development of freight and logistics precincts in strategic locations within and adjacent to Principal Transport Gateways and along the Principal Freight Network movement corridors by:


- Allocating land for complementary uses and employment-generating activities, such as distribution and warehousing.
- Reserving and appropriately zoning land for interstate freight terminals to support development that allows for the direct and immediate delivery of goods to market.
- Allocating land to allow high-volume freight customers to locate adjacent to interstate freight terminals, including the Western Interstate Freight Terminal and the Beveridge Interstate Freight Terminal.

Policy documents

Consider as relevant:

- *Principal Freight Network* (Department of Transport, 2021)
- *Principal Transport Gateways* (Department of Transport, 2021)
- *Delivering the Goods, Creating Victorian Jobs: Victorian Freight Plan* (Department of Economic Development, Jobs, Transport and Resources, July 2018)

Principal Transport Gateways



18.02-5R Freight links - Metropolitan Melbourne

09/12/2021
VC204

Strategy

Ensure suitable sites are provided for intermodal freight terminals at key locations around Metropolitan Melbourne, particularly for the Beveridge Interstate Freight Terminal and the Western Interstate Freight Terminal.

18.02-6S Ports

09/12/2021
VC204

Planning for ports objective

To support the effective and competitive operation of Victoria's commercial trading ports at local, national and international levels, and to facilitate their ongoing sustainable operation and development.

Planning for ports strategies

Provide for the ongoing development of ports at Melbourne, Geelong, Hastings and Portland in accordance with approved Port Development Strategies.

Identify and protect key transport corridors linking ports to the broader transport network.

Manage any impacts of a commercial trading port and any related industrial development on nearby sensitive uses to minimise the impact of vibration, light spill, noise and air emissions from port activities.

Planning for port environs objective

To plan for and manage land near commercial trading ports so that development and use are compatible with port operations and provide reasonable amenity expectations.

Planning for port environs strategies

Protect commercial trading ports from encroachment of sensitive and incompatible land uses in the port environs.

Plan for and manage land in the port environs to accommodate uses that depend upon, or gain significant economic advantage from, proximity to the port's operations.

Ensure that industrially zoned land within the environs of a commercial trading port is maintained and continues to support the role of the port as a critical freight and logistics precinct.

Identify and protect key transport corridors linking ports to the broader transport network.

Ensure any new use or development within the environs of a commercial trading port does not prejudice the efficient and curfew-free operations of the port.

Ensure that the use and intensity of development does not expose people to unacceptable health or safety risks and consequences associated with an existing major hazard facility.

Ensure that any use or development within port environs:

- Is consistent with policies for the protection of the environment.
- Takes into account planning for the port.

Policy documents

Consider as relevant:

- *Statement of Planning Policy No 1 - Western Port* (1970-varied 1976)
- *2018 Port Development Strategy* (Port of Hastings Development Authority, December 2018)
- *Port of Geelong Port Development Strategy 2018* (Victorian Regional Channels Authority, 2018)
- *2050 Port Development Strategy, 2020 edition* (Port of Melbourne, 2020)
- *Port of Portland – Port Development Strategy* (Port of Portland, 2019)

18.02-7S Airports and airfields

18/05/2022
VC218

Objective

To strengthen the role of Victoria's airports and airfields within the state's economic and transport infrastructure, guide their siting and expansion, and safeguard their ongoing, safe and efficient operation.

Strategies

Protect airports and airfields from incompatible land use and development.

Prevent land use or development that poses risks to the safety or efficiency of an airport or airfield, including any of the following risks:

- Building-generated windshear and turbulence.
- Increased risk of wildlife strike.
- Pilot distraction from lighting.
- Intrusion into protected airspace.
- Interference with communication, navigation and surveillance facilities.
- Increased risk to public safety at the end of runways.

Minimise the detrimental effects of aircraft noise when planning for areas around airports and airfields.

Limit the intensification of noise-sensitive land uses, and avoid zoning or overlay changes that allow noise-sensitive land use and development, where ultimate capacity or long-range noise modelling indicates an area is within a 20 Australian Noise Exposure Forecast (ANEF) contour or higher.

Avoid zoning or overlay changes that allow noise-sensitive land uses outside the Urban Growth Boundary, and encourage measures to reduce the impact of aircraft noise in planning for areas within the Urban Growth Boundary, where ultimate capacity or long-range noise modelling indicates an area is within 'number above' contours (N Contours) representing:

- 20 or more daily events greater than 70 dB(A).
- 50 or more daily events of greater than 65 dB(A).
- 100 or more daily events greater than 60 dB(A).
- 6 events or more between the hours of 11pm to 6am greater than 60 dB(A).

Ensure land use and development at airports and airfields contributes to the aviation needs of the state and the efficient and functional operation of the airport or airfield.

Ensure land use and development at airports complements the role of the airport including as listed below:

- Melbourne Airport – major domestic and international airport with no curfew, 24-hour access, freight capability and an adjoining employment precinct.
- Avalon Airport – domestic and international airport with no curfew, 24-hour access, freight capability and an adjoining employment precinct.
- Essendon Fields Airport – a general aviation airport that is an important regional and state aviation asset with specialised functions, including executive charter, emergency aviation services, freight, logistics and an adjoining employment precinct.

- Moorabbin Airport – a general aviation airport that is an important regional and state aviation asset supporting the state's aviation industry and access to regional Victoria.
- Point Cook Airfield – an operating airport complementary to Moorabbin Airport.

Plan for areas around airports and airfields so that land use or development does not prejudice future airport or airfield operations or expansions in accordance with an approved strategy or master plan for that airport or airfield.

Preserve long-term options for a new general aviation airport south-east of metropolitan Melbourne by ensuring urban land use and development does not infringe on possible sites, buffer zones or flight paths.

Avoid the location of new airports and airfields in areas that have greater long-term value to the community for other purposes.

Ensure that in the planning of airports and airfields, land use decisions are integrated, appropriate land use buffers are in place and provision is made for associated businesses that service airports.

Plan the location of airports and airfields, nearby existing and potential development, and the land-based transport system required to serve them, as an integrated operation.

Plan the visual amenity and impact of any land use or development on the approaches to an airport or airfield to be consistent with the status of the airport or airfield.

Policy documents

Consider as relevant:

- *National Airports Safeguarding Framework* (as agreed by Commonwealth, State and Territory Ministers at the meeting of the Standing Council on Transport and Infrastructure on 18 May 2012)
- *Avalon Airport Master Plan* (Avalon Airport Australia Pty Ltd, 2015)
- *Avalon Airport Strategy* (Department of Business and Employment/Aerospace Technologies of Australia, 1993) and its associated Aircraft Noise Exposure Concepts
- *Melbourne Airport Strategy* (Government of Victoria/Federal Airports Corporation, approved 1990) and its associated *Final Environmental Impact Statement*

18.02-7R Melbourne Airport

20/03/2023
VC229

Strategies

Protect the curfew-free status of Melbourne Airport and ensure any new use or development does not prejudice its operation or optimum usage.

Policy documents

Consider as relevant:

- *Melbourne Airport Master Plan 2022* (Australia Pacific Airports (Melbourne) Pty Ltd)
- *Melbourne Airport Strategy* (Government of Victoria/Federal Airports Corporation, approved 1990) and its associated *Final Environmental Impact Statement*

19 INFRASTRUCTURE

10/06/2022
VC216

Planning for development of social and physical infrastructure should enable it to be provided in a way that is efficient, equitable, accessible and timely.

Planning is to recognise social needs by providing land for a range of accessible community resources, such as education, cultural, health and community support (mental health, aged care, disability, youth and family services) facilities.

Planning should ensure that the growth and redevelopment of settlements is planned in a manner that allows for the logical and efficient provision and maintenance of infrastructure, including the setting aside of land for the construction of future transport routes.

Planning should facilitate efficient use of existing infrastructure and human services. Providers of infrastructure, whether public or private bodies, are to be guided by planning policies and should assist strategic land use planning.

Planning should minimise the impact of use and development on the operation of major infrastructure of national, state and regional significance, including communication networks and energy generation and distribution systems.

Infrastructure planning should avoid, minimise and offset environmental impacts, and incorporate resilience to natural hazards, including future climate change risks.

Planning authorities should consider the use of development and infrastructure contributions in the funding of infrastructure.

19.01 ENERGY

31/07/2018
VC148

19.01-1S Energy supply

05/09/2025
VC268

Objective

To facilitate appropriate development of energy supply infrastructure.

Strategies

Support the development of energy generation, storage, transmission, and distribution infrastructure to transition to a low-carbon economy.

Develop appropriate infrastructure to meet community demand for energy services.

Ensure energy generation, storage, transmission and distribution infrastructure and projects are resilient to the impacts of climate change.

Facilitate the production and distribution of zero emission gases and fuels.

Support energy infrastructure projects in locations that minimise land use conflicts, including in any renewable energy zones declared under section 63 of the *National Electricity (Victoria) Act 2005*.

Support energy infrastructure projects in locations that take advantage of existing and planned resources and infrastructure networks.

Facilitate energy infrastructure projects that help diversify local economies and improve sustainability and social outcomes.

Facilitate renewable energy generation and storage to meet on-site energy needs.

Policy guidelines

Consider as relevant:

- The long-term emissions reduction target specified in section 6 of Part 2 of the *Climate Action Act 2017*.
- Interim emissions reduction targets determined under Division 2 of Part 2 of the *Climate Action Act 2017*.
- Adaptation action plans prepared under Division 2 of Part 5 of the *Climate Action Act 2017*.

Policy documents

Consider as relevant:

- *2025 Victorian Transmission Plan* (VicGrid, 2025)

19.01-2S Renewable energy

05/09/2025
VC268

Objective

To support the provision and use of renewable energy in a manner that ensures appropriate siting and design considerations are met.

Strategies

Facilitate renewable energy development in appropriate locations, including in any renewable energy zones declared under section 63 of the *National Electricity (Victoria) Act 2005*.

Protect renewable energy infrastructure against competing and incompatible uses.

Set aside suitable land for future renewable energy infrastructure.

Consider the economic, social and environmental benefits to the broader community of renewable energy generation while also considering the need to minimise the effects of a proposal on the local community and environment.

Support wind energy facilities in locations with consistently strong winds over the year.

Policy documents

Consider as relevant:

- *Policy and Planning Guidelines for Development of Wind Energy Facilities in Victoria* (Department of Environment, Land, Water and Planning, November 2021)
- *Solar Energy Facilities Design and Development Guideline* (Department of Environment, Land, Water and Planning, October 2022)
- *Victoria's Climate Change Strategy* (Department of Environment, Land, Water and Planning, May 2021)
- *Community Engagement and Benefit Sharing in Renewable Energy Development in Victoria* (Department of Environment, Land, Water and Planning, July 2021)
- *2025 Victorian Transmission Plan* (VicGrid, 2025)

19.01-2R Renewable energy - Metropolitan Melbourne

31/07/2018
VC148

Strategy

Facilitate the uptake of renewable energy technologies on a site-by-site and neighbourhood level during the master planning of new communities and in green wedge and peri-urban areas.

19.01-3S Pipeline infrastructure

31/07/2018
VC148

Objective

To ensure that gas, oil and other substances are safely delivered to users and to and from port terminals at minimal risk to people, other critical infrastructure and the environment.

Strategies

Plan for the development of pipeline infrastructure subject to the *Pipelines Act 2005*.

Recognise existing transmission-pressure gas pipelines in planning schemes and protect from further encroachment by residential development or other sensitive land uses, unless suitable additional protection of pipelines is provided.

Plan new pipelines along routes with adequate buffers to residences, zoned residential land and other sensitive land uses and with minimal impacts on waterways, wetlands, flora and fauna, erosion prone areas and other environmentally sensitive sites.

Provide for environmental management during construction and on-going operation of pipeline easements.

19.02 COMMUNITY INFRASTRUCTURE

31/07/2018
VC148

19.02-1S Health facilities

31/07/2018
VC148

Objective

To assist the integration of health facilities with local and regional communities.

Strategies

Facilitate the location of health and health-related facilities (including acute health, aged care, disability services and community care facilities) taking into account demographic trends, the existing and future demand requirements and the integration of services into communities.

Plan public and private developments together, where possible, including some degree of flexibility in use.

Locate hospitals and other large health facilities in designated health precincts and areas highly accessible to public and private transport.

Provide adequate car parking for staff and visitors of health facilities.

19.02-1R Health precincts - Metropolitan Melbourne

31/07/2018
VC148

Strategies

Facilitate health and community wellbeing precincts through the co-location of:

- Hospitals, allied health services and not-for-profit health providers at the regional level.
- General practitioners, community health facilities, allied health services and not-for-profit health providers at the neighbourhood level.

Create health precincts in new suburbs in or close to town centres.

Ensure health precincts are well serviced by community services.

19.02-1L Health facilities - Brimbank

27/06/2024
C225brim

Strategies

Encourage health facilities to co-locate with new multipurpose community hubs.

Design health facilities to cater for people of all abilities.

Policy document

Consider as relevant:

- *Community Services and Infrastructure Plan 2018 - 2038* (Brimbank City Council, 2018)

19.02-2S Education facilities

29/09/2022
VC222

Objective

To assist the integration of education and early childhood facilities with local and regional communities.

Strategies

Consider demographic trends, existing and future demand requirements and the integration of facilities into communities in planning for the location of education and early childhood facilities.

Locate childcare, kindergarten and primary school facilities to maximise access by public transport and safe walking and cycling routes.

Ensure childcare, kindergarten and primary school and secondary school facilities provide safe vehicular drop-off zones.

Facilitate the establishment and expansion of primary and secondary education facilities to meet the existing and future education needs of communities.

Recognise that primary and secondary education facilities are different to dwellings in their purpose and function and can have different built form (including height, scale and mass).

Locate secondary school and tertiary education facilities in designated education precincts and areas that are highly accessible to public transport.

Locate tertiary education facilities within or adjacent to activity centres.

Ensure streets and accessways adjoining education and early childhood facilities are designed to encourage safe bicycle and pedestrian access.

Consider the existing and future transport network and transport connectivity.

Develop libraries as community based learning centres.

Co-locate a kindergarten facility with all new Victorian Government primary schools.

19.02-2R Education precincts - Metropolitan Melbourne

31/07/2018
VC148

Strategy

Ensure education precincts are well serviced by community services.

19.02-2L Education facilities - Brimbank

27/06/2024
C225brim

Strategies

Encourage flexible, multi-purpose and adaptable education and early childhood facilities that can support a variety of community uses.

Locate education and early childhood facilities within or adjacent to activity centres.

Policy document

Consider as relevant:

- *Community Services and Infrastructure Plan 2018 - 2038* (Brimbank City Council, 2018)

19.02-3S Cultural facilities

31/07/2018
VC148

Objective

To develop a strong cultural environment and increase access to arts, recreation and other cultural facilities.

Strategies

Encourage a wider range of arts, cultural and entertainment facilities including cinemas, restaurants, nightclubs and live theatres in the Central City and at Metropolitan Activity Centres.

Reinforce the existing major precincts for arts, sports and major events of state wide appeal.

Establish new facilities at locations well served by public transport.

19.02-3R Cultural facilities - Metropolitan Melbourne

31/07/2018
VC148

Strategies

Maintain and strengthen Melbourne's distinctiveness as a leading cultural and sporting city with world-class facilities.

19.02-3L Cultural facilities - Brimbank

27/06/2024
C225brim

Strategy

Encourage cultural facilities to be designed for people of all abilities.

Policy document

Consider as relevant:

- *Community Services and Infrastructure Plan 2018 - 2038* (Brimbank City Council, 2018)

19.02-4S Social and cultural infrastructure

31/07/2018
VC148

Objective

To provide fairer distribution of and access to, social and cultural infrastructure.

Strategies

Identify and address gaps and deficiencies in social and cultural infrastructure, including additional regionally significant cultural and sporting facilities.

Encourage the location of social and cultural infrastructure in activity centres.

Ensure social infrastructure is designed to be accessible.

Ensure social infrastructure in growth areas, is delivered early in the development process and in the right locations.

Plan and design community places and buildings so they can adapt as the population changes and different patterns of work and social life emerge.

Support innovative ways to maintain equitable service delivery to settlements that have limited or no capacity for further growth, or that experience population decline.

Identify and protect land for cemeteries and crematoria.

19.02-4L Social and cultural infrastructure - Brimbank

27/06/2024
C225brim

Strategy

Encourage integrated, multi-purpose community facilities that are located close to public transport, community hubs, shopping centres and public open space.

Policy document

Consider as relevant:

- *Community Services and Infrastructure Plan 2018 - 2038* (Brimbank City Council, 2018)

19.02-5S Emergency services

31/07/2018
VC148

Objective

To ensure suitable locations for police, fire, ambulance and other emergency services.

Strategies

Ensure police, fire, ambulance and other emergency services are provided for in or near activity centres.

Locate emergency services together in newly developing areas.

19.02-6S Open space

31/07/2018
VC148

Objective

To establish, manage and improve a diverse and integrated network of public open space that meets the needs of the community.

Strategies

Plan for regional and local open space networks for both recreation and conservation of natural and cultural environments.

Ensure that open space networks:

- Are linked, including through the provision of walking and cycling trails.
- Are integrated with open space from abutting subdivisions.
- Incorporate, where possible, links between major parks and activity areas, along waterways and natural drainage corridors, connecting places of natural and cultural interest.
- Maintain public accessibility on public land immediately adjoining waterways and coasts.

Create opportunities to enhance open space networks within and between settlements.

Ensure that land is set aside and developed in residential areas for local recreational use and to create pedestrian and bicycle links to commercial and community facilities.

Ensure that land use and development adjoining regional open space networks, national parks and conservation reserves complements the open space in terms of visual and noise impacts, preservation of vegetation and treatment of waste water to reduce turbidity and pollution.

Improve the quality and distribution of open space and ensure long-term protection.

Protect large regional parks and significant conservation areas.

Ensure land identified as critical to the completion of open space links is transferred for open space purposes.

Ensure that where there is a reduction of open space due to a change in land use or occupation, additional or replacement parkland of equal or greater size and quality is provided.

Ensure that urban open space provides for nature conservation, recreation and play, formal and informal sport, social interaction, opportunities to connect with nature and peace and solitude.

Accommodate community sports facilities in a way that is not detrimental to other park activities.

Ensure open space provision is fair and equitable with the aim of providing access that meets the needs of all members of the community, regardless of age, gender, ability or a person's location.

Develop open space to maintain wildlife corridors and greenhouse sinks.

Provide new parkland in growth areas and in areas that have an undersupply of parkland.

Encourage the preparation of management plans or explicit statements of management objectives for urban parks.

Ensure exclusive occupation of parkland by community organisations is restricted to activities consistent with management objectives of the park to maximise broad community access to open space.

Ensure the provision of buildings and infrastructure is consistent with the management objectives of the park.

Ensure public access is not prevented by developments along stream banks and foreshores.

Ensure public land immediately adjoining waterways and coastlines remains in public ownership.

Plan open space areas for multiple uses, such as community gardens, sports and recreation, active transport routes, wildlife corridors and flood storage basins.

19.02-6R Open space - Metropolitan Melbourne

14/04/2025
VC281

Objective

To strengthen the integrated metropolitan open space network.

Strategies

Develop a network of local open spaces that are accessible and of high-quality and include opportunities for new local open spaces through planning for urban redevelopment projects.

Ensure major open space corridors are protected and enhanced.

Develop open space networks in growth areas and in the surrounding region of Metropolitan Melbourne, where existing open space is limited and demand is growing, including:

- Cardinia Creek Parklands.
- Cranbourne Regional Park.
- Kororoit Creek Corridor.
- Quarry Hills Regional Park.
- Chain of Parks - Sandbelt.
- Sunbury Regional Park - Jacksons Creek Valley.
- Toolern Creek Regional Park.
- Werribee Township Regional Park.

Create continuous open space links and trails along the:

- Frankston parklands (linking existing parks from Carrum to Mornington).
- Maribyrnong River parklands.
- Merri Creek parklands (extending to Craigieburn).
- Western Coastal parklands (linking Point Gellibrand, Point Cook and Werribee).
- Birrarung (Yarra River) parklands (extending from Warrandyte to the Port Phillip Bay).

Provide long term planning protection to meet demand for future open space along the Plenty Gorge parklands, Yarra Valley parklands, Cardinia Creek parklands, Heatherton/Dingley 'Sandbelt' parklands and Dandenong Valley parklands.

Protect the metropolitan water's edge parklands from intrusion and encroachment of development that impacts on open space and their natural landscape setting.

Continue development of the Birrarung (Yarra River) Inner City reach, identified in clause 12.03-1R Map 1, as a focus for sport, entertainment and leisure.

Support establishing community gardens and productive streetscapes.

Policy documents

Consider as relevant:

- *Open Space for Everyone: Open Space Strategy for Metropolitan Melbourne 2021* (Department of Environment, Land, Water and Planning, 2021)
- *Maribyrnong River – Vision for Recreational and Tourism Development* (Melbourne Parks and Waterways, 1996)
- *Maribyrnong River Valley Design Guidelines* (Department of Planning and Community Development, 2010)

19.02-6L Open space - Brimbank

27/06/2024
C225brim

Strategies

Ensure open space areas are safe and attractive places.

Design public open space areas to accommodate cyclists and pedestrians.

Ensure lighting is provided to all paths, amenities and playground facilities in flagship and suburban parks where sporting facilities provide lighting at night.

Ensure lighting is provided in parks used as pedestrian links to community facilities, public transport or activity centres.

Orient development adjoining open spaces towards the open space to provide opportunities for passive surveillance.

Increase the amount of public open space in and adjacent to industrial and employment areas.

Ensure that new public open space in and adjacent to industrial and employment areas is located and designed to be easily accessible for workers and visitors.

Facilitate the extension of the open space corridor along:

- The Maribyrnong River from Brimbank Park to Organ Pipes National Park.
- The length of Kororoit Creek.
- The length of Taylors Creek.
- The Federation Trail.

Policy documents

Consider as relevant:

- *Creating Better Parks Policy & Plan* (Brimbank City Council, 2016)
- *Brimbank Cycling and Walking Strategy* (Brimbank City Council, 2016)
- *Brimbank Industrial Land Use Strategy 2018 – 2030* (Brimbank City Council, 2018)

19.03 DEVELOPMENT INFRASTRUCTURE

31/07/2018
VC148

19.03-1S Development and infrastructure contributions plans

24/01/2020
VC160

Objective

To facilitate the timely provision of planned infrastructure to communities through the preparation and implementation of development contributions plans and infrastructure contributions plans.

Strategies

Prepare development contributions plans and infrastructure contributions plans, under the *Planning and Environment Act 1987*, to manage contributions towards infrastructure.

Collect development contributions on the basis of approved development and infrastructure contributions plans.

Require annual reporting by collecting and development agencies to monitor the collection and expenditure of levies and the delivery of infrastructure.

Policy documents

Consider as relevant:

- *Development Contributions Guidelines* (Department of Sustainability and Environment, 2003 -as amended 2007)
- *Infrastructure Contributions Plan Guidelines* (Department of Environment, Land, Water and Planning, November 2019)
- *Ministerial Direction on the Preparation and Content of Development Contribution Plans and Reporting Requirements for Development Contributions Plans*
- *Ministerial Direction on the Preparation and Content of Infrastructure Contribution Plans and Reporting Requirements for Infrastructure Contributions Plans*

19.03-2S Infrastructure design and provision

09/10/2020
VC169

Objective

To provide timely, efficient and cost-effective development infrastructure that meets the needs of the community.

Strategies

Provide an integrated approach to the planning and engineering design of new subdivision and development.

Integrate developments with infrastructure and services, whether they are in existing suburbs, growth areas or regional towns.

19.03-3S Integrated water management

22/11/2024
VC263

Objective

To sustainably manage water supply and demand, water resources, wastewater, drainage and stormwater through an integrated water management approach.

Strategies

Plan and coordinate integrated water management, bringing together stormwater, wastewater, drainage, water supply, water treatment and re-use, to:

- Take into account the catchment context.
- Protect downstream environments, waterways and bays.
- Manage and use potable water efficiently.
- Reduce pressure on Victoria's drinking water supplies.
- Minimise drainage, water or wastewater infrastructure and operational costs.
- Minimise flood risks.
- Provide urban environments that are more resilient to the effects of climate change.

Integrate water into the landscape to facilitate cooling, local habitat improvements and provision of attractive and enjoyable spaces for community use.

Facilitate use of alternative water sources such as rainwater, stormwater, recycled water and run-off from irrigated farmland.

Ensure that development protects and improves the health of water bodies including creeks, rivers, wetlands, estuaries and bays by:

- Minimising stormwater quality and quantity related impacts.
- Filtering sediment and waste from stormwater prior to discharge from a site.
- Managing industrial and commercial toxicants in an appropriate way.
- Requiring appropriate measures to mitigate litter, sediment and other discharges from construction sites.

Manage stormwater quality and quantity through a mix of on-site measures and developer contributions at a scale that will provide greatest net community benefit.

Provide for sewerage at the time of subdivision or ensure lots created by the subdivision are capable of adequately treating and retaining all domestic wastewater within the boundaries of each lot.

Ensure land is set aside for water management infrastructure at the subdivision design stage.

Minimise the potential impacts of water, sewerage and drainage assets on the environment.

Protect significant water, sewerage and drainage assets from encroaching sensitive and incompatible uses.

Protect areas with potential to recycle water for forestry, agriculture or other uses that can use treated effluent of an appropriate quality.

Ensure that the use and development of land identifies and appropriately responds to potential environmental risks, and contributes to maintaining or improving the environmental quality of water and groundwater.

Policy guidelines

Consider as relevant:

- Any applicable Sustainable Water Strategy endorsed under Division 1B of Part 3 of the *Water Act 1989*.

Policy documents

Consider as relevant:

- *Water for Victoria - Water Plan* (Victorian Government, 2016)
- *Environment Reference Standard* (Gazette No. S 245, 26 May 2021)
- *Urban Stormwater - Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999)
- *Planning Permit Applications in Special Water Supply Catchment Areas* (Department of Energy, Environment and Climate Action, 2024)
- *Victorian guideline for water recycling* (Publication 1910, Environment Protection Authority, March 2021)
- *Technical information for the Victorian guideline for water recycling* (Publication 1911, Environment Protection Authority, March 2021)

19.03-3L Integrated water management - Brimbank

27/06/2024
C225brim

Strategies

Encourage the use of on-site stormwater detention systems to manage peak stormwater flows.

Ensure development does not impede floodwater flows and temporary flood storage.

Ensure development maximises permeable surfaces and minimises hard surface or paved areas, to increase water infiltration and reduce stormwater runoff.

Support the installation of stormwater treatment and harvesting systems in and along the municipality's waterways.

Policy document

Consider as relevant:

- *Brimbank Sustainable Water Management Strategy 2013 - 2023* (Brimbank City Council, 2018)

19.03-4S Telecommunications

04/11/2022
VC226

Objective

To facilitate the orderly development, extension and maintenance of telecommunications infrastructure.

Strategies

Facilitate the upgrading and maintenance of telecommunications facilities.

Ensure that modern telecommunications facilities are widely accessible and that the telecommunications needs of business, domestic, entertainment and community services are met.

Encourage the continued deployment of telecommunications facilities that are easily accessible by:

- Increasing and improving access for all sectors of the community to the telecommunications network.
- Supporting access to transport and other public corridors for the deployment of telecommunications networks in order to encourage infrastructure investment and reduce investor risk.

Ensure a balance between the provision of telecommunications facilities and the need to protect the environment from adverse impacts arising from telecommunications infrastructure.

Co-locate telecommunications facilities wherever practical.

Planning should have regard to national implications of a telecommunications network and the need for consistency in infrastructure design and placement.

19.03-4R Telecommunications - Metropolitan Melbourne

26/10/2018
VC154

Strategy

Support the provision of high-quality telecommunications infrastructure in Melbourne's employment, urban renewal and growth areas through early planning for fibre-ready facilities and wireless infrastructure.

19.03-5S Waste and resource recovery

02/09/2025
VC283

Objective

To reduce waste and maximise resource recovery to reduce reliance on landfills and minimise environmental, amenity and public health impacts.

Strategies

Ensure future waste and resource recovery infrastructure needs are identified and planned for to safely and sustainably manage all waste streams and maximise opportunities for resource recovery.

Ensure the long-term viability of waste and resource recovery infrastructure is secured through the use of defined buffer areas that protect against encroachment from incompatible land uses.

Ensure waste and resource recovery facilities are sited, designed, built and operated so as to minimise impacts on surrounding communities and the environment.

Enable waste and resource recovery facilities to be located in proximity to other related facilities and to materials' end-market destinations, to reduce the impacts of waste transportation and improve the economic viability of resource recovery.

Site, design, manage and rehabilitate waste disposal facilities to prevent or minimise contamination of groundwater and surface waters, litter, odour, dust and noise.

Integrate waste and resource recovery infrastructure planning with land use and transport planning.

Encourage technologies that increase recovery and treatment of resources to produce high value, marketable end products.

Encourage development that facilitates sustainable waste and resource recovery, including facilities for Victoria’s container deposit scheme.

Policy documents

Consider as relevant:

- *Victorian Recycling Infrastructure Plan* (Department of Energy, Environment and Climate Action, October 2024)
- *Management and Storage of Combustible Recyclable and Waste Materials - Guideline* (Publication 1667, Environment Protection Authority, October 2018)
- *Best Practice Environmental Management Guideline (Siting, Design, Operation and Rehabilitation of Landfills)* (Environment Protection Authority, 2015)
- *Designing, Constructing and Operating Composting Facilities* (Publication 1588, Environment Protection Authority, June 2015)
- *Separation Distance Guideline* (Environment Protection Authority, August 2024)
- *Landfill Buffer Guideline* (Environment Protection Authority, August 2024)
- *Waste Management and Recycling in Multi-unit Developments. Better Practice Guide* (Sustainability Victoria, 2019)
- *Recycling Victoria a New Economy* (DELWP, February 2020*)*

30 ZONES

19/01/2006
VC37

This section sets out the zones which apply in this scheme.

31 [NO CONTENT]

31/07/2018
VC148

32 RESIDENTIAL ZONES

19/01/2006
VC37

32.04 MIXED USE ZONE

31/07/2018
VC148

Shown on the planning scheme map as **MUZ** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide for a range of residential, commercial, industrial and other uses which complement the mixed-use function of the locality.

To provide for housing at higher densities.

To encourage development that responds to the existing or preferred neighbourhood character of the area.

To facilitate the use, development and redevelopment of land in accordance with the objectives specified in a schedule to this zone.

32.04-1 Objectives

15/07/2013
VC100

A schedule to this zone may contain objectives to be achieved for the area.

32.04-2 Table of uses

14/01/2025
VC237

Section 1 – Permit not required

Use	Condition
Art gallery	
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Bed and breakfast	No more than 10 persons may be accommodated away from their normal place of residence. At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence.
Community care accommodation	Must meet the requirements of Clause 52.22-2.
Domestic animal husbandry (other than Domestic animal boarding)	Must be no more than 2 animals.
Dwelling (other than Bed and breakfast)	
Food and drink premises	The leasable floor area must not exceed 150 square metres.
Home based business	
Informal outdoor recreation	
Medical centre	The gross floor area must not exceed 250 square metres.
Museum	
Office (other than Medical centre)	The leasable floor area must not exceed 250 square metres.

Use	Condition
Place of worship	The gross floor area of all buildings must not exceed 250 square metres.
Racing dog husbandry	Must be no more than 2 animals.
Railway	
Residential aged care facility	
Rooming house	Must meet the requirements of Clause 52.23-2.
Shop (other than Adult sex product shop)	The leasable floor area must not exceed 150 square metres.
Small second dwelling	Must be no more than one dwelling existing on the lot. Must be the only small second dwelling on the lot. Reticulated natural gas must not be supplied to the building, or part of a building, used for the small second dwelling.
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Accommodation (other than Community care accommodation, Dwelling, Residential aged care facility, Rooming house and Small second dwelling)	
Agriculture (other than Animal production, Apiculture, Domestic animal husbandry and Racing dog husbandry)	
Container deposit scheme centre	
Domestic animal boarding	
Domestic animal husbandry (other than Domestic animal boarding) – if the Section 1 condition is not met	Must be no more than 5 animals.
Grazing animal production	
Industry (other than Materials recycling and Transfer station)	Must not be a purpose listed in the table to Clause 53.10.
Leisure and recreation (other than Informal outdoor recreation)	
Place of assembly (other than Art gallery, Carnival, Circus, Museum and Place of worship)	
Retail premises (other than Food and drink premises and Shop)	
Utility installation (other than Minor utility installation and Telecommunications facility)	Must not be a purpose listed in the table to Clause 53.10.

Use	Condition
Warehouse	Must not be a purpose listed in the table to Clause 53.10.
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Adult sex product shop
Animal production (other than Grazing animal production)
Extractive industry
Materials recycling
Small second dwelling – if the Section 1 condition is not met
Transfer station (other than Automated collection point and Container deposit scheme centre)

32.04-3 Use for industry, service station and warehouse

31/07/2018
VC148

Amenity of the neighbourhood

The use of land for an industry, service station or warehouse must not adversely affect the amenity of the neighbourhood, including through:

- The transport of materials or goods to or from the land.
- The appearance of any stored materials or goods.
- Traffic generated by the use.
- Emissions from the land.

32.04-4 Subdivision

14/12/2023
VC253

Permit requirement

A permit is required to subdivide land.

An application to subdivide land, other than an application to subdivide land into lots each containing an existing dwelling or car parking space, must meet the requirements of Clause 56 and:

- Must meet all of the objectives included in the clauses specified in the following table.
- Should meet all of the standards included in the clauses specified in the following table.

Class of subdivision	Objectives and standards to be met
60 or more lots	All except Clause 56.03-5.
16 – 59 lots	All except Clauses 56.03-1 to 56.03-3, 56.03-5, 56.06-1 and 56.06-3.
3 – 15 lots	All except Clauses 56.02-1, 56.03-1 to 56.03-4, 56.05-2, 56.06-1, 56.06-3 and 56.06-6.

Class of subdivision	Objectives and standards to be met
2 lots	Clauses 56.03-5, 56.04-2, 56.04-3, 56.04-5, 56.06-8 to 56.09-2.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

32.04-5 Construction and extension of one dwelling on a lot

08/09/2025
VC282

Permit requirement

A permit is required to construct or extend one dwelling on a lot of less than 300 square metres.

A development must meet the requirements of Clause 54.

No permit required

No permit is required to:

- Construct or carry out works normal to a dwelling.

- Construct or extend an out-building (other than a garage or carport) on a lot provided the gross floor area of the out-building does not exceed 10 square metres and the maximum building height is not more than 3 metres above ground level.
- Make structural changes to a dwelling provided the size of the dwelling is not increased or the number of dwellings is not increased.

VicSmart applications

Subject to clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct or extend a dwelling on a lot less than 300 square metres if the development meets the following standards of Clause 54: - clause 54.02-1 Street setback. - clause 54.02-2 Building height. - clause 54.02-3 Side and rear setbacks. - clause 54.02-4 Walls on boundaries. - clause 54.02-5 Site coverage. - clause 54.02-6 Tree canopy. - clause 54.02-7 Front fences. - clause 54.04-1 Daylight to existing windows. - clause 54.04-2 Existing north-facing windows. - clause 54.04-3 Overshadowing secluded open space. - clause 54.04-4 Overlooking. - clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	Clause 54

Transitional provisions

Clauses 32.04-5, 54 and 59.14 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.04-6 Construction and extension of a small second dwelling on a lot

08/09/2025
VC282

Permit requirement

A permit is required to construct or extend a small second dwelling on a lot less than 300 square metres.

A development must meet the requirements of Clause 54.

VicSmart applications

Subject to clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct or extend a small second dwelling on a lot less than 300 square metres if the development meets the following standards of Clause 54: ▪ clause 54.02-1 Street setback ▪ clause 54.02-2 Building height ▪ clause 54.02-3 Side and rear setbacks ▪ clause 54.02-4 Walls on boundaries ▪ clause 54.02-5 Site coverage ▪ clause 54.02-6 Tree canopy ▪ clause 54.02-8 Building setback for small second dwellings ▪ clause 54.03-5 Safety and accessibility for small second dwellings ▪ clause 54.04-1 Daylight to existing windows ▪ clause 54.04-2 Existing north-facing windows ▪ clause 54.04-3 Overshadowing secluded open space ▪ clause 54.04-4 Overlooking ▪ clause 54.05-2 Overshadowing domestic solar energy systems If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	Clause 54

Transitional provisions

Clauses 32.04-6, 54 and 59.14 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.04-7 Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

31/03/2025
VC267

Permit requirement

A permit is required to:

- Construct a dwelling if there is at least one dwelling existing on the lot.
- Construct two or more dwellings on a lot.
- Extend a dwelling if there are two or more dwellings on the lot.
- Construct or extend a dwelling if it is on common property.
- Construct or extend a residential building.

A permit is required to construct or extend a front fence within 3 metres of a street if:

- The fence is associated with 2 or more dwellings on a lot or a residential building, and
- The fence exceeds the maximum height specified in Clause 55.02-8.

A development must meet the requirements of Clause 55. This does not apply to a development of four or more storeys, excluding a basement.

A development of four storeys, excluding a basement, must meet the requirements of Clause 57.

An apartment development of five or more storeys, excluding a basement, must meet the requirements of Clause 58.

Transitional provisions

Clause 55 of this scheme, as in force immediately before the approval date of Amendment VC136, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 58 does not apply to:

- An application for a planning permit lodged before the approval date of Amendment VC136.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before the approval date of Amendment VC136.

Clauses 55 and 58 of this scheme, as in force immediately before the approval date of Amendment VC174, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 55 of this planning scheme, as in force immediately before the approval date of Amendment VC267, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct or extend a front fence within 3 metres of a street if the fence is associated with 2 or more dwellings on a lot or a residential building.	Clause 59.03

32.04-8 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

A schedule to this zone may specify the requirements of:

- Standards A2-1, A2-5, A2-7 and A3-2 of Clause 54 of this scheme.
- Standards B2-1, B2-5, B2-8 and B3-5 of Clause 55 of this scheme.

If a requirement is not specified in a schedule to this zone, the requirement set out in the relevant standard of Clause 54 or Clause 55 applies.

32.04-9 Residential aged care facility

14/12/2023
VC253

Permit requirements

A permit is required to construct a building or construct or carry out works for a residential aged care facility.

A development must meet the requirements of Clause 53.17 - Residential aged care facility.

32.04-10 Buildings and works associated with a Section 2 use

08/09/2025
VC282

A permit is required to construct a building or construct or carry out works for a use in Section 2 of Clause 32.04-2.

VicSmart applications

Subject to clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct a building or construct or carry out works where: ▪ The building or works are not associated with a dwelling, primary school or secondary school and have an estimated cost of up to $100,000; or ▪ The building or works are associated with a primary school or secondary school and have an estimated cost of up to $500,000; and ▪ The requirements in the following standards of Clause 54 are met, where the land adjoins land in a residential zone used for residential purposes: – clause 54.02-3 Side and rear setbacks. – clause 54.02-4 Walls on boundaries. – clause 54.04-1 Daylight to existing windows. – clause 54.04-2 Existing north-facing windows. – clause 54.04-3 Overshadowing secluded open space. – clause 54.04-4 Overlooking. – clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	Clause 59.04

Transitional provisions

Clauses 32.04-10, 54 and 59.04 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.04-11 Buildings on lots that abut another residential zone

02/04/2025
VC276

Any buildings or works constructed on a lot that abuts land which is in a General Residential Zone, Neighbourhood Residential Zone, Residential Growth Zone, or Township Zone must meet the requirements of Clauses 55.02-3, 55.02-4, 55.04-1, 55.04-3, 55.04-4 and 55.05-2 along that boundary.

This does not apply to a building or works for a residential aged care facility.

32.04-12 Maximum building height requirement

14/12/2023
VC253

A building must not be constructed that exceeds the maximum building height specified in a schedule to this zone.

A building may exceed the maximum building height specified in a schedule to this zone if:

- It replaces an immediately pre-existing building and the new building does not exceed the building height of the pre-existing building.
- There are existing buildings on both abutting allotments that face the same street and the new building does not exceed the building height of the lower of the existing buildings on the abutting allotments.
- It is on a corner lot abutted by lots with existing buildings and the new building does not exceed the building height of the lower of the existing buildings on the abutting allotments.
- It is constructed pursuant to a valid building permit that was in effect prior to the introduction of this provision.
- It is a residential aged care facility and the maximum building height in the schedule to the zone is less than 16 metres.

An extension to an existing building may exceed the maximum building height specified in a schedule to this zone if it does not exceed the building height of the existing building.

A building may exceed the maximum building height by up to 1 metre if the slope of the natural ground level, measured at any cross section of the site of the building wider than 8 metres, is greater than 2.5 degrees.

The maximum building height requirement in this zone or a schedule to this zone applies whether or not a planning permit is required for the construction of a building.

Building height if land is subject to inundation

If the land is in a Special Building Overlay, Land Subject to Inundation Overlay or is land liable to inundation the maximum building height specified in the zone or schedule to the zone is the vertical distance from the minimum floor level determined by the relevant drainage authority or floodplain management authority to the roof or parapet at any point.

32.04-13 Application requirements

14/01/2025
VC237

General

Any application requirements specified in a schedule to this zone.

Use for industry and warehouse

Unless the circumstances do not require, an application to use land for an industry or warehouse must be accompanied by the following information:

- The purpose of the use and the types of activities to be carried out.
- The type and quantity of materials and goods to be stored, processed or produced.

- Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority.
- Whether a notification under the Occupational Health and Safety Regulations 2017 is required, a licence under the *Dangerous Goods Act 1985* is required, or a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022 is exceeded.
- How land not required for immediate use is to be maintained.
- The likely effects, if any, on the neighbourhood, including noise levels, traffic, air-borne emissions, emissions to land and water, light spill, glare, solar access and hours of operation (including the hours of delivery and dispatch of materials and goods).

Buildings and works associated with a Section 2 use

An application to construct a building or construct or carry out works must be accompanied by the following information, as appropriate:

- A site analysis and descriptive statement explaining how the proposal responds to the site and its context.
- Plans drawn to scale and dimensioned which show:
  - The layout of proposed buildings and works.
  - An elevation of the building design and height.
  - Setbacks to property boundaries.
  - All proposed access and pedestrian areas.
  - All proposed driveway, car parking and loading areas.
  - Existing vegetation and proposed landscape areas.
  - The location of easements and services.

32.04-14 Exemption from notice and review

08/09/2025
VC282

Subdivision

An application for subdivision is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Construction and extension of one dwelling on a lot

An application under clause 32.04-5 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-6, 54.02-7, 54.04 and 54.05-2 are met.

Construction and extension of a small second dwelling on a lot

An application under clause 32.04-6 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-6, 54.02-8, 54.03-5, 54.04 and 54.05-2 are met.

Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

An application under clause 32.04-7 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clause 55.02, 55.04-1, 55.04-2, 55.04-3, 55.04-4 and 55.05-2 are met.

Other applications

A schedule to this zone may specify that an application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

32.04-15 Decision guidelines

31/03/2025
VC267

General

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The objectives set out in a schedule to this zone.
- Any other decision guidelines specified in a schedule to this zone.
- The impact of overshadowing on existing rooftop solar energy systems on dwellings on adjoining lots in a Housing Choice and Transport Zone, Mixed Use Zone or Residential Growth Zone.

Use for industry, service station and warehouse

- The effect that existing uses on adjoining or nearby land may have on the proposed use.
- The design of buildings, including provision for solar access.
- The availability and provision of utility services.
- The effect of traffic to be generated by the use.
- The interim use of those parts of the land not required for the proposed use.
- Whether the use is compatible with adjoining and nearby land uses.
- For non-residential uses, the proposed hours of operation, noise and any other likely off-site amenity impacts.

Subdivision

- The pattern of subdivision and its effect on the spacing of buildings.
- For subdivision of land for residential development, the objectives and standards of Clause 56.

Construction and extension of one dwelling on a lot and a small second dwelling

- The applicable objectives, standards and decision guidelines of Clause 54.

Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

- For two or more dwellings on a lot, dwellings on common property and residential buildings of three storeys or less, excluding a basement, the objectives, standards and decision guidelines of Clause 55.
- For two or more dwellings on a lot, dwellings on common property and residential buildings of four storeys, excluding a basement, the objectives, standards and decision guidelines of Clause 57.
- For an apartment development of five or more storeys, excluding a basement, the objectives, standards and decisions guidelines of Clause 58.

32.04-16 Signs

14/12/2023
VC253

Sign requirements are at Clause 52.05. This zone is in Category 3 unless a schedule to this zone specifies a different category.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 32.04 MIXED USE ZONE

Shown on the planning scheme map as **MUZ**.

BRIMBANK MIXED USE AREAS

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Clause 54 and Clause 55 requirements

08/09/2025
VC282

	Standard	Requirement
Minimum street setback	A2-1	None specified
	B2-1	None specified
Site coverage	A2-5	None specified
	B2-5	None specified
Private open space	A3-2	None specified
	B3-5	None specified
Front fence height	A2-7 and B2-8	None specified

3.0 Maximum building height requirement

08/07/2021
C211brim

None specified.

4.0 Exemption from notice and review

08/07/2021
C211brim

None specified.

5.0 Application requirements

08/07/2021
C211brim

None specified.

6.0 Decision guidelines

08/07/2021
C211brim

None specified.

7.0 Signs

08/07/2021
C211brim

None specified.

32.07 RESIDENTIAL GROWTH ZONE

31/07/2018
VC148

Shown on the planning scheme map as **RGZ** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide housing at increased densities in buildings up to and including four storey buildings.

To encourage a diversity of housing types in locations offering good access to services and transport including activity centres and town centres.

To encourage a scale of development that provides a transition between areas of more intensive use and development and other residential areas.

To ensure residential development achieves design objectives specified in a schedule to this zone.

To allow educational, recreational, religious, community and a limited range of other non-residential uses to serve local community needs in appropriate locations.

32.07-1 Design objectives

27/03/2017
VC110

A schedule to this zone must contain the design objectives to be achieved for the area.

32.07-2 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Bed and breakfast	No more than 10 persons may be accommodated away from their normal place of residence. At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence.
Community care accommodation	Must meet the requirements of Clause 52.22-2.
Domestic animal husbandry (other than Domestic animal boarding)	Must be no more than 2 animals.
Dwelling (other than Bed and breakfast)	
Home based business	
Informal outdoor recreation	
Medical centre	The gross floor area of all buildings must not exceed 250 square metres.
Place of worship	The gross floor area of all buildings must not exceed 250 square metres. The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.

Use	Condition
Racing dog husbandry	Must be no more than 2 animals.
Railway	
Residential aged care facility	
Rooming house	Must meet the requirements of Clause 52.23-2.
Small second dwelling	Must be no more than one dwelling existing on the lot. Must be the only small second dwelling on the lot. Reticulated natural gas must not be supplied to the building, or part of a building, used for the small second dwelling.
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 – Permit required

Use	Condition
Accommodation (other than Community care accommodation, Dwelling, Residential aged care facility, Rooming house and Small second dwelling)	
Agriculture (other than Animal production, Animal training, Apiculture, Domestic animal husbandry, Horse husbandry and Racing dog husbandry)	
Car park	Must be used in conjunction with another use in Section 1 or 2.
Car wash	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Convenience restaurant	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Convenience shop	
Domestic animal husbandry (other than Domestic animal boarding) – if the Section 1 condition is not met	Must be no more than 5 animals.
Food and drink premises (other than Convenience restaurant and Take away food premises)	
Grazing animal production	
Leisure and recreation (other than Informal outdoor recreation and Motor racing track)	
Market	

Use	Condition
Office (other than Medical centre)	The land must be located within 100 metres of a commercial zone. The land must have the same street frontage as the land in the commercial zone. The leasable floor area must not exceed 250 square metres.
Place of assembly (other than Amusement parlour, Carnival, Cinema based entertainment facility, Circus, Nightclub and Place of worship)	
Plant nursery	
Retail premises (other than Food and drink premises, Market, Plant nursery and Shop)	The use must be associated with a use or development to which clause 53.23 (Significant residential development with affordable housing) applies.
Service station	The site must either: ▪ Adjoin a commercial zone or industrial zone. ▪ Adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3. The site must not exceed either: ▪ 3000 square metres. ▪ 3600 square metres if it adjoins on two boundaries a road in a Transport Zone 2 or a Transport Zone 3.
Shop (other than Adult sex product shop, Bottle shop and Convenience shop)	The land must be located within 100 metres of a commercial zone or Mixed Use Zone. The land must have the same street frontage as the land in the commercial zone or Mixed Use Zone.
Store	Must be in a building, not a dwelling, and used to store equipment, goods, or motor vehicles used in conjunction with the occupation of a resident of a dwelling on the lot.
Take away food premises	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Utility installation (other than Minor utility installation and Telecommunications facility)	
Any other use not in Section 1 or 3	

Section 3 – Prohibited

Use
Adult sex product shop

Use
Amusement parlour
Animal production (other than Grazing animal production)
Animal training
Bottle shop
Cinema based entertainment facility
Domestic animal boarding
Extractive industry
Horse husbandry
Industry (other than Automated collection point and Car wash)
Motor racing track
Nightclub
Saleyard
Small second dwelling – if the Section 1 condition is not met
Transport terminal
Warehouse (other than Store)

32.07-3 Subdivision

14/12/2023
VC253

Permit requirement

A permit is required to subdivide land.

An application to subdivide land, other than an application to subdivide land into lots each containing an existing dwelling or car parking space, must meet the requirements of Clause 56 and:

- Must meet all of the objectives included in the clauses specified in the following table.
- Should meet all of the standards included in the clauses specified in the following table.

Class of subdivision	Objectives and standards to be met
60 or more lots	All except Clause 56.03-5.
16 – 59 lots	All except Clauses 56.03-1 to 56.03-3, 56.03-5, 56.06-1 and 56.06-3.
3 – 15 lots	All except Clauses 56.02-1, 56.03-1 to 56.03-4, 56.05-2, 56.06-1, 56.06-3 and 56.06-6.
2 lots	Clauses 56.03-5, 56.04-2, 56.04-3, 56.04-5, 56.06-8 to 56.09-2.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

32.07-4 Construction and extension of one dwelling on a lot

08/09/2025
VC282

Permit requirement

A permit is required to construct or extend one dwelling on a lot less than 300 square metres.

A development must meet the requirements of Clause 54.

No permit required

No permit is required to:

- Construct or carry out works normal to a dwelling.
- Construct or extend an out-building (other than a garage or carport) on a lot provided the gross floor area of the out-building does not exceed 10 square metres and the maximum building height is not more than 3 metres above ground level.
- Make structural changes to a dwelling provided the size of the dwelling is not increased or the number of dwellings is not increased.

VicSmart applications

Subject to clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct or extend a dwelling on a lot less than 300 square metres if the development meets the following standards of Clause 54: ▪ clause 54.02-1 Street setback. ▪ clause 54.02-2 Building height. ▪ clause 54.02-3 Side and rear setbacks. ▪ clause 54.02-4 Walls on boundaries. ▪ clause 54.02-5 Site coverage ▪ clause 54.02-6 Tree canopy. ▪ clause 54.02-7 Front fences. ▪ clause 54.04-1 Daylight to existing windows. ▪ clause 54.04-2 Existing north-facing windows. ▪ clause 54.04-3 Overshadowing secluded open space. ▪ clause 54.04-4 Overlooking. ▪ clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	Clause 54

Transitional provisions

Clauses 32.07-4, 54 and 59.14 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.07-5 Construction and extension of a small second dwelling on a lot

08/09/2025
VC282

Permit requirement

A permit is required to construct or extend a small second dwelling on a lot of less than 300 square metres.

A development must meet the requirements of Clause 54.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct or extend a small second dwelling on a lot less than 300 square metres if the development meets the following standards of Clause 54: ▪ clause 54.02-1 Street setback. ▪ clause 54.02-2 Building height.	Clause 54

Class of application	Provision
▪ clause 54.02-3 Side and rear setbacks. ▪ clause 54.02-4 Walls on boundaries. ▪ clause 54.02-5 Site coverage. ▪ clause 54.02-6 Tree canopy. ▪ clause 54.02-8 Building setback for small second dwellings. ▪ clause 54.03-5 Safety and accessibility for small second dwellings. ▪ clause 54.04-1 Daylight to existing windows. ▪ clause 54.04-2 Existing north-facing windows. ▪ clause 54.04-3 Overshadowing secluded open space. ▪ clause 54.04-4 Overlooking. ▪ clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	

Transitional provisions

Clauses 32.07-5, 54 and 59.14 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.07-6 Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

31/03/2025
VC267

Permit requirement

A permit is required to:

- Construct a dwelling if there is at least one dwelling existing on the lot.
- Construct two or more dwellings on a lot.
- Extend a dwelling if there are two or more dwellings on the lot.
- Construct or extend a dwelling if it is on common property.
- Construct or extend a residential building.

A permit is required to construct or extend a front fence within 3 metres of a street if:

- The fence is associated with 2 or more dwellings on a lot or a residential building, and
- The fence exceeds the maximum height specified in Clause 55.02-8.

A development must meet the requirements of Clause 55. This does not apply to a development of four or more storeys, excluding a basement.

A development of four storeys, excluding a basement, must meet the requirements of Clause 57.

An apartment development of five or more storeys, excluding a basement, must meet the requirements of Clause 58.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct or extend a front fence within 3 metres of a street if the fence is associated with 2 or more dwellings on a lot or a residential building.	Clause 59.03

Transitional provisions

Clause 55 of this scheme, as in force immediately before the approval date of Amendment VC136, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 58 does not apply to:

- An application for a planning permit lodged before the approval date of Amendment VC136.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before the approval date of Amendment VC136.

Clauses 55 and 58 of this scheme, as in force immediately before the approval date of Amendment VC174, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 55 of this planning scheme, as in force immediately before the approval date of Amendment VC267, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.07-7 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

A schedule to this zone may specify the requirements of:

- Standards A2-1, A2-5, A2-7 and A3-2 of Clause 54 of this scheme.
- Standards B2-1, B2-5, B2-8 and B3-5 of Clause 55 of this scheme.

If a requirement is not specified in a schedule to this zone, the requirement set out in the relevant standard of Clause 54 or Clause 55 applies.

32.07-8 Residential aged care facility

14/12/2023
VC253

Permit requirements

A permit is required to construct a building or construct or carry out works for a residential aged care facility.

A development must meet the requirements of Clause 53.17 - Residential aged care facility.

32.07-9 Buildings and works associated with a Section 2 use

08/09/2025
VC282

A permit is required to construct a building or construct or carry out works for a use in Section 2 of Clause 32.07-2.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct a building or construct or carry out works where: ▪ The building or works are not associated with a dwelling, primary school or secondary school and have an estimated cost of up to $100,000; or ▪ The building or works are associated with a primary school or secondary school and have an estimated cost of up to $500,000; and ▪ The requirements in the following standards of Clause 54 are met, where the land adjoins land in a residential zone used for residential purposes: – clause 54.02-3 Side and rear setbacks. – clause 54.02-4 Walls on boundaries. – clause 54.04-1 Daylight to existing windows. – clause 54.04-2 Existing north-facing windows. – clause 54.04-3 Overshadowing secluded open space. – clause 54.04-4 Overlooking. – clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	Clause 59.04

Transitional provisions

Clauses 32.07-9, 54 and 59.04 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.07-10 Maximum building height requirement for a dwelling, small second dwelling or residential building

08/09/2025
VC282

A building must not be constructed for use as a dwelling, small second dwelling or a residential building that exceeds the maximum building height specified in a schedule to this zone.

If no maximum building height is specified in a schedule to this zone, the building height should not exceed 13.5 metres.

This building height requirement replaces the maximum building height specified in clauses 54.02-2, 55.02-2 and 57.02-2.

A building may exceed the maximum building height specified in a schedule to this zone if:

- It replaces an immediately pre-existing building and the new building does not exceed the building height of the pre-existing building.
- There are existing buildings on both abutting allotments that face the same street and the new building does not exceed the building height of the lower of the existing buildings on the abutting allotments.
- It is on a corner lot abutted by lots with existing buildings and the new building does not exceed the building height of the lower of the existing buildings on the abutting allotments.
- It is constructed pursuant to a valid building permit that was in effect prior to the introduction of this provision.

An extension to an existing building may exceed the maximum building height specified in a schedule to this zone if it does not exceed the building height of the existing building.

A building may exceed the maximum building height by up to 1 metre if the slope of the natural ground level, measured at any cross section of the site of the building wider than 8 metres, is greater than 2.5 degrees.

The maximum building height requirement in this zone or a schedule to this zone applies whether or not a planning permit is required for the construction of a building.

Building height if land is subject to inundation

If the land is in a Special Building Overlay, Land Subject to Inundation Overlay or is land liable to inundation the maximum building height specified in the zone or schedule to the zone is the vertical distance from the minimum floor level determined by the relevant drainage authority or floodplain management authority to the roof or parapet at any point.

32.07-11 Buildings on lots that abut another residential zone

08/09/2025
VC282

Any buildings or works constructed on a lot that abuts land which is in a General Residential Zone, Neighbourhood Residential Zone, or Township Zone must meet the requirements of Clauses 55.02-3, 55.02-4, 55.04-1, 55.04-3, 55.04-4 and 55.05-2 along that boundary.

32.07-12 Application requirements

08/09/2025
VC282

An application must be accompanied by the following information, as appropriate:

- For a development of one dwelling on a lot or a small second dwelling on a lot, the site description and design response as required in Clause 54.
- For a development of two or more dwellings on a lot, dwellings on common property and residential buildings of three storeys or less, excluding a basement, the site description and design response as required in Clause 55.
- For a development of two or more dwellings on a lot, dwellings on common property and residential buildings of four storeys, excluding a basement, the site description and design response as required in Clause 57.
- For an apartment development of five or more storeys, an urban context report and design response as required in clause 58.01.
- For an application for subdivision, a site and context description and design response as required in Clause 56.
- Plans drawn to scale and dimensioned which show:
  - Site shape, size, dimensions and orientation.
  - The siting and use of existing and proposed buildings.
  - Adjacent buildings and uses.

  - The building form and scale.
  - Setbacks to property boundaries.

- The likely effects, if any, on adjoining land, including noise levels, traffic, the hours of delivery and despatch of good and materials, hours of operation and light spill, solar access and glare.
- Any other application requirements specified in a schedule to this zone.

If in the opinion of the responsible authority an application requirement is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

32.07-13 Exemption from notice and review

08/09/2025
VC282

Subdivision

An application to subdivide land is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Construction and extension of one dwelling on a lot

An application under clause 32.07-4 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-6, 54.02-7, 54.04 and 54.05-2 are met.

Construction and extension of a small second dwelling on a lot

An application under clause 32.07-5 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-6, 54.02-8, 54.03-5, 54.04 and 54.05-2 are met.

Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

An application under clause 32.07-6 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 55.02, 55.04-1, 55.04-2, 55.04-3, 55.04-4 and 55.05-2 are met.

32.07-14 Decision guidelines

31/03/2025
VC267

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General

- The Municipal Planning Strategy and the Planning Policy Framework.
- The purpose of this zone.
- The objectives set out in a schedule to this zone.
- Any other decision guidelines specified in a schedule to this zone.
- The impact of overshadowing on existing rooftop solar energy systems on dwellings on adjoining lots in a Housing Choice and Transport Zone, Mixed Use Zone or Residential Growth Zone.

Subdivision

- The pattern of subdivision and its effect on the spacing of buildings.
- For subdivision of land for residential development, the objectives and standards of Clause 56.

Dwellings, small second dwellings and residential buildings

- For the construction of one dwelling on a lot, whether the development is an under-utilisation of the lot.
- For the construction and extension of one dwelling on a lot and a small second dwelling, the applicable objectives, standards and decision guidelines of Clause 54.
- For the construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings of three storeys or less, excluding a basement, the objectives, standards and decision guidelines of Clause 55.
- For the construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings of four storeys, excluding a basement, the objectives, standards and decision guidelines of Clause 57.
- For the construction and extension of an apartment development of five or more storeys, excluding a basement, the objectives, standards and decisions guidelines of Clause 58.

Non-residential use and development

- Whether the use or development is compatible with residential use.
- Whether the use generally serves local community needs.
- The scale and intensity of the use and development.
- The design, height, setback and appearance of the proposed buildings and works.
- The proposed landscaping.
- The provision of car and bicycle parking and associated accessways.
- Any proposed loading and refuse collection facilities.
- The safety, efficiency and amenity effects of traffic to be generated by the proposal.

32.07-15 Signs

14/12/2023
VC253

Sign requirements are at Clause 52.05. This zone is in Category 3.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 32.07 RESIDENTIAL GROWTH ZONE

Shown on the planning scheme map as **RGZ1**.

SUBSTANTIAL CHANGE AREAS

1.0 Design objectives

08/07/2021
C211brim

None specified.

2.0 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

	Standard	Requirement
Minimum street setback	A2-1	Ground level and level 1 are set back the same distance as the lesser front wall setback of the adjoining lots. Side street setbacks requirements specified in the table to Standard A2-1 continues to apply.
	B2-1	Ground level and level 1 are set back the same distance as the lesser front wall setback of the adjoining lots. Side street setback requirements specified in the table to Standard B2-1 continue to apply.
Site coverage	A2-5	None specified
	B2-5	None specified
Private open space	A3-2	An area of 15 sqm of secluded private open space at ground level. All other requirements in Standard A3-2 apply, including alternate private open space provisions.
	B3-5	An area of 15 sqm of secluded private open space at ground level. All other requirements in Standard B3-5 apply, including alternate private open space provisions.
Front fence height	A2-7 and B2-8	None specified

3.0 Maximum building height requirement for a dwelling, small second dwelling or residential building

26/04/2024
VC252

None specified.

4.0 Application requirements

08/07/2021
C211brim

The following application requirements apply to an application for a permit under Clause 32.07, in addition to those specified in Clause 32.07 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A neighbourhood and site description (NSD) plan which must show:
  - At least three sites or buildings on both sides of the proposed development, opposite and to the rear of the proposed development.
  - The built form, scale and character of the area, including front fencing (i.e. height of buildings, front and side setbacks, location and width of vehicle and pedestrian crossovers, vegetation, land topography).

- Architectural and roof styles.
- A streetscape elevation showing the proposed development in the context of three adjoining dwellings or buildings on each side.

- A Design Response Plan which must demonstrate:
  - How the proposed development responds to the characteristics identified in the neighbourhood and site description plan and contributes to a preferred denser character.
  - Plans showing bin enclosures integrated into the design of the development.
  - Demonstrate that on site water storage and detention has been considered in the design.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 32.07, in addition to those specified in Clause 32.07 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Opportunities to maximise development through consolidation of lots.
- Whether the development provides for an appropriate built form, scale and height transition to an adjoining Neighbourhood Residential Zone, General Residential Zone or commercial zoning.
- The extent to which landscaping softens the appearance of the proposed development and assists in the transition to existing development.
- The layout and appearance of areas set aside for car parking, access and egress, loading and the location of any proposed off street car parking.
- Whether garages and carports visually dominate the proposed development.
- Whether a variation to the requirements of Clause 2.0 would result in a loss of on or off-site amenity.
- The use of architectural features and building design, rather than screens, as a mechanism to protect privacy for adjoining residents.
- The concealment of ancillary services from the front, side and rear boundary views.

32.08 GENERAL RESIDENTIAL ZONE

31/03/2025
VC267

Shown on the planning scheme map as **GRZ**, **R1Z**, **R2Z** or **R3Z** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To encourage development that is responsive to the neighbourhood character of the area.

To encourage a diversity of housing types and housing growth particularly in locations offering good access to services and transport.

To allow educational, recreational, religious, community and a limited range of other non-residential uses to serve local community needs in appropriate locations.

32.08-1 Neighbourhood character objectives

27/03/2017
VC110

A schedule to this zone may contain neighbourhood character objectives to be achieved for the area.

32.08-2 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Bed and breakfast	No more than 10 persons may be accommodated away from their normal place of residence. At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence.
Community care accommodation	Must meet the requirements of Clause 52.22-2.
Domestic animal husbandry (other than Domestic animal boarding)	Must be no more than 2 animals.
Dwelling (other than Bed and breakfast)	
Home based business	
Informal outdoor recreation	
Medical centre	The gross floor area of all buildings must not exceed 250 square metres. Must not require a permit under Clause 52.06-3. The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Place of worship	The gross floor area of all buildings must not exceed 250 square metres.

Use	Condition
	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Racing dog husbandry	Must be no more than 2 animals.
Railway	
Residential aged care facility	
Rooming house	Must meet the requirements of Clause 52.23-2.
Small second dwelling	Must be no more than one dwelling existing on the lot. Must be the only small second dwelling on the lot. Reticulated natural gas must not be supplied to the building, or part of a building, used for the small second dwelling.
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Accommodation (other than Community care accommodation, Dwelling, Residential aged care facility, Rooming house and Small second dwelling)	
Agriculture (other than Animal production, Animal training, Apiculture, Domestic animal husbandry, Horse husbandry and Racing dog husbandry)	
Car park	Must be used in conjunction with another use in Section 1 or 2.
Car wash	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Convenience restaurant	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Convenience shop	
Domestic animal husbandry (other than Domestic animal boarding) – if the Section 1 condition is not met	Must be no more than 5 animals.
Food and drink premises (other than Convenience restaurant and Take away food premises)	
Grazing animal production	
Leisure and recreation (other than Informal outdoor recreation and Motor racing track)	
Market	

Use	Condition
Office (other than Medical centre)	The use must be associated with a use or development to which clause 53.23 (Significant residential development with affordable housing) applies.
Place of assembly (other than Amusement parlour, Carnival, Cinema based entertainment facility, Circus, Nightclub and Place of worship)	
Plant nursery	
Retail premises (other than Convenience shop, Food and drink premises, Market and Plant nursery)	The use must be associated with a use or development to which clause 53.23 (Significant residential development with affordable housing) applies.
Service station	The site must either: ▪ Adjoin a commercial zone or industrial zone. ▪ Adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3. The site must not exceed either: ▪ 3000 square metres. ▪ 3600 square metres if it adjoins on two boundaries a road in a Transport Zone 2 or a Transport Zone 3.
Store	Must be in a building, not a dwelling, and used to store equipment, goods, or motor vehicles used in conjunction with the occupation of a resident of a dwelling on the lot.
Take away food premises	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Utility installation (other than Minor utility installation and Telecommunications facility)	
Any other use not in Section 1 or 3	

Section 3 – Prohibited

Use
Amusement parlour
Animal production (other than Grazing animal production)
Animal training
Cinema based entertainment facility
Domestic animal boarding
Extractive industry

Use
Horse husbandry
Industry (other than Automated collection point and Car wash)
Motor racing track
Nightclub
Saleyard
Small second dwelling – if the Section 1 condition is not met
Transport terminal
Warehouse (other than Store)

32.08-3 Subdivision

14/12/2023
VC253

Permit requirement

A permit is required to subdivide land.

An application to subdivide land that would create a vacant lot less than 400 square metres capable of development for a dwelling or residential building, must ensure that each vacant lot created less than 400 square metres contains at least 25 percent as garden area. This does not apply to a lot created by an application to subdivide land where that lot is created in accordance with:

- An approved precinct structure plan or an equivalent strategic plan;
- An incorporated plan or approved development plan; or
- A permit for development.

An application to subdivide land, other than an application to subdivide land into lots each containing an existing dwelling or car parking space, must meet the requirements of Clause 56 and:

- Must meet all of the objectives included in the clauses specified in the following table.
- Should meet all of the standards included in the clauses specified in the following table.

Class of subdivision	Objectives and standards to be met
60 or more lots	All except Clause 56.03-5.
16 – 59 lots	All except Clauses 56.03-1 to 56.03-3, 56.03-5, 56.06-1 and 56.06-3.
3 – 15 lots	All except Clauses 56.02-1, 56.03-1 to 56.03-4, 56.05-2, 56.06-1, 56.06-3 and 56.06-6.
2 lots	Clauses 56.03-5, 56.04-2, 56.04-3, 56.04-5, 56.06-8 to 56.09-2.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

32.08-4 Construction or extension of a dwelling, small second dwelling or residential building

14/12/2023
VC253

Minimum garden area requirement

An application to construct or extend a dwelling, small second dwelling or residential building on a lot must provide a minimum garden area as set out in the following table:

Lot size	Minimum percentage of a lot set aside as garden area
400 - 500 sqm	25%
Above 500 - 650 sqm	30%
Above 650 sqm	35%

This does not apply to:

- An application to construct or extend a dwelling, small second dwelling or residential building if specified in a schedule to this zone as exempt from the minimum garden area requirement;
- An application to construct or extend a dwelling, small second dwelling or residential building on a lot if:

- The lot is designated as a medium density housing site in an approved precinct structure plan or an approved equivalent strategic plan;
- The lot is designated as a medium density housing site in an incorporated plan or approved development plan; or

- An application to alter or extend an existing building that did not comply with the minimum garden area requirement of Clause 32.08-4 on the approval date of Amendment VC110.

32.08-5 Construction and extension of one dwelling on a lot

08/09/2025
VC282

Permit requirement

A permit is required to construct or extend one dwelling on a lot less than 300 square metres.

A permit is required to construct or extend a front fence within 3 metres of a street if the fence is associated with one dwelling on a lot less than 300 square metres and the fence exceeds the maximum height specified in clause 54.02-7.

A development must meet the requirements of Clause 54.

No permit required

No permit is required to:

- Construct or carry out works normal to a dwelling.
- Construct or extend an out-building (other than a garage or carport) on a lot provided the gross floor area of the out-building does not exceed 10 square metres and the maximum building height is not more than 3 metres above ground level.
- Make structural changes to a dwelling provided the size of the dwelling is not increased or the number of dwellings is not increased.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct or extend a dwelling on a lot less than 300 square metres if the development meets the following standards of Clause 54: ▪ clause 54.02-1 Street setback. ▪ clause 54.02-2 Building height. ▪ clause 54.02-3 Side and rear setbacks. ▪ clause 54.02-4 Walls on boundaries. ▪ clause 54.02-5 Site coverage ▪ clause 54.02-6 Tree canopy. ▪ clause 54.02-7 Front fences. ▪ clause 54.04-1 Daylight to existing windows. ▪ clause 54.04-2 Existing north-facing windows. ▪ clause 54.04-3 Overshadowing secluded open space.	Clause 54

Class of application	Provision
▪ clause 54.04-4 Overlooking. ▪ clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	
Construct or extend a front fence within 3 metres of a street if the fence is associated with one dwelling on a lot less than 300 square metres.	Clause 59.03

Transitional provisions

Clauses 32.08-5, 54 and 59.14 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.08-6 Construction and extension of a small second dwelling on a lot

08/09/2025
VC282

Permit requirement

A permit is required to construct or extend a small second dwelling on a lot of less than 300 square metres.

A development must meet the requirements of Clause 54.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct or extend a small second dwelling on a lot less than 300 square metres if the development meets the following standards of Clause 54: ▪ clause 54.02-1 Street setback. ▪ clause 54.02-2 Building height. ▪ clause 54.02-3 Side and rear setbacks. ▪ clause 54.02-4 Walls on boundaries. ▪ clause 54.02-5 Site coverage. ▪ clause 54.02-6 Tree canopy. ▪ clause 54.02-8 Building setback for small second dwellings. ▪ clause 54.03-5 Safety and accessibility for small second dwellings. ▪ clause 54.04-1 Daylight to existing windows. ▪ clause 54.04-2 Existing north-facing windows. ▪ clause 54.04-3 Overshadowing secluded open space.	Clause 54

Class of application	Provision
▪ clause 54.04-4 Overlooking. ▪ clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	

Transitional provisions

Clauses 32.08-6, 54 and 59.14 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.08-7 Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

31/03/2025
VC267

Permit requirement

A permit is required to:

- Construct a dwelling if there is at least one dwelling existing on the lot.
- Construct two or more dwellings on a lot.
- Extend a dwelling if there are two or more dwellings on the lot.
- Construct or extend a dwelling if it is on common property.
- Construct or extend a residential building.

A permit is required to construct or extend a front fence within 3 metres of a street if:

- The fence is associated with 2 or more dwellings on a lot or a residential building, and
- The fence exceeds the maximum height specified in Clause 55.02-8.

A development must meet the requirements of Clause 55. This does not apply to a development of four or more storeys, excluding a basement.

A development of four storeys, excluding a basement, must meet the requirements of Clause 57.

An apartment development of five or more storeys, excluding a basement, must meet the requirements of Clause 58.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct or extend a front fence within 3 metres of a street if the fence is associated with 2 or more dwellings on a lot or a residential building.	Clause 59.03

Transitional provisions

Clause 55 of this scheme, as in force immediately before the approval date of Amendment VC136, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 58 does not apply to:

- An application for a planning permit lodged before the approval date of Amendment VC136.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before the approval date of Amendment VC136.

Clauses 55 and 58 of this scheme, as in force immediately before the approval date of Amendment VC174, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 55 of this planning scheme, as in force immediately before the approval date of Amendment VC267, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.08-8 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

A schedule to this zone may specify the requirements of:

- Standards A2-1, A2-5, A2-7 and A3-2 of Clause 54 of this scheme.
- Standards B2-1, B2-5, B2-8 and B3-5 of Clause 55 of this scheme.

If a requirement is not specified in a schedule to this zone, the requirement set out in the relevant standard of Clause 54 or Clause 55 applies.

32.08-9 Residential aged care facility

14/12/2023
VC253

Permit requirements

A permit is required to construct a building or construct or carry out works for a residential aged care facility.

A development must meet the requirements of Clause 53.17 - Residential aged care facility.

32.08-10 Buildings and works associated with a Section 2 use

08/09/2025
VC282

A permit is required to construct a building or construct or carry out works for a use in Section 2 of Clause 32.08-2.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct a building or construct or carry out works where: ▪ The building or works are not associated with a dwelling, primary school or secondary school and have an estimated cost of up to $100,000; or ▪ The building or works are associated with a primary school or secondary school and have an estimated cost of up to $500,000; and ▪ The requirements in the following standards of Clause 54 are met, where the land adjoins land in a residential zone used for residential purposes: – clause 54.02-3 Side and rear setbacks. – clause 54.02-4 Walls on boundaries. – clause 54.04-1 Daylight to existing windows. – clause 54.04-2 Existing north-facing windows. – clause 54.04-3 Overshadowing secluded open space. – clause 54.04-4 Overlooking. – clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	Clause 59.04

Transitional provisions

Clauses 32.08-10, 54 and 59.04 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.08-11 Maximum building height requirement for a dwelling, small second dwelling or residential building

14/12/2023
VC253

A building must not be constructed for use as a dwelling, small second dwelling or a residential building that:

- exceeds the maximum building height specified in a schedule to this zone; or
- contains more than the maximum number of storeys specified in a schedule to this zone.

If no maximum building height or maximum number of storeys is specified in a schedule to this zone:

- the building height must not exceed 11 metres; and
- the building must contain no more than 3 storeys at any point.

A building may exceed the applicable maximum building height or contain more than the applicable maximum number of storeys if:

- It replaces an immediately pre-existing building and the new building does not exceed the building height or contain a greater number of storeys than the pre-existing building.
- There are existing buildings on both abutting allotments that face the same street and the new building does not exceed the building height or contain a greater number of storeys than the lower of the existing buildings on the abutting allotments.

- It is on a corner lot abutted by lots with existing buildings and the new building does not exceed the building height or contain a greater number of storeys than the lower of the existing buildings on the abutting allotments.
- It is constructed pursuant to a valid building permit that was in effect prior to the introduction of this provision.

An extension to an existing building may exceed the applicable maximum building height or contain more than the applicable maximum number of storeys if it does not exceed the building height of the existing building or contain a greater number of storeys than the existing building.

A building may exceed the maximum building height by up to 1 metre if the slope of the natural ground level, measured at any cross section of the site of the building wider than 8 metres, is greater than 2.5 degrees.

A basement is not a storey for the purposes of calculating the number of storeys contained in a building.

The maximum building height and maximum number of storeys requirements in this zone or a schedule to this zone apply whether or not a planning permit is required for the construction of a building.

Building height if land is subject to inundation

If the land is in a Special Building Overlay, Land Subject to Inundation Overlay or is land liable to inundation the maximum building height specified in the zone or schedule to the zone is the vertical distance from the minimum floor level determined by the relevant drainage authority or floodplain management authority to the roof or parapet at any point.

32.08-12 Application requirements

08/09/2025
VC282

An application must be accompanied by the following information, as appropriate:

- For a development of one dwelling on a lot or a small second dwelling on a lot, the site description and design response as required in Clause 54.
- For a development of two or more dwellings on a lot, dwellings on common property and residential buildings of three storeys or less, excluding a basement, the site description and design response as required in Clause 55.
- For a development of two or more dwellings on a lot, dwellings on common property and residential buildings of four storeys, excluding a basement, the site description and design response as required in Clause 57.
- For an apartment development of five or more storeys, an urban context report and design response as required in Clause 58.01.
- For an application for subdivision, a site and context description and design response as required in Clause 56.
- Plans drawn to scale and dimensioned which show:
  - Site shape, size, dimensions and orientation.
  - The siting and use of existing and proposed buildings.
  - Adjacent buildings and uses.
  - The building form and scale.
  - Setbacks to property boundaries.

- The likely effects, if any, on adjoining land, including noise levels, traffic, the hours of delivery and despatch of good and materials, hours of operation and light spill, solar access and glare.
- Any other application requirements specified in a schedule to this zone.

If in the opinion of the responsible authority an application requirement is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

32.08-13 Exemption from notice and review

08/09/2025
VC282

Subdivision

An application to subdivide land into lots each containing an existing dwelling or car parking space is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Construction and extension of one dwelling on a lot

An application under clause 32.08-5 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-6, 54.02-7, 54.04 and 54.05-2 are met.

Construction and extension of a small second dwelling on a lot

An application under clause 32.08-6 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-6, 54.02-8, 54.03-5, 54.04 and 54.05-2 are met.

Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

An application under clause 32.08-7 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clause 55.02, 55.04-1, 55.04-2, 55.04-3, 55.04-4 and 55.05-2 are met.

32.08-14 Decision guidelines

31/03/2025
VC267

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General

- The Municipal Planning Strategy and the Planning Policy Framework.
- The purpose of this zone.
- The objectives set out in a schedule to this zone.
- Any other decision guidelines specified in a schedule to this zone.
- The impact of overshadowing on existing rooftop solar energy systems on dwellings on adjoining lots in a General Residential Zone, Housing Choice and Transport Zone, Mixed Use Zone, Neighbourhood Residential Zone, Residential Growth Zone or Township Zone.

Subdivision

- The pattern of subdivision and its effect on the spacing of buildings.
- For subdivision of land for residential development, the objectives and standards of Clause 56.

Dwellings, small second dwellings and residential buildings

- For the construction and extension of one dwelling on a lot and a small second dwelling, the applicable objectives, standards and decision guidelines of Clause 54.

- For the construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings of three storeys or less, excluding a basement, the objectives, standards and decision guidelines of Clause 55.
- For the construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings of four storeys, excluding a basement, the objectives, standards and decision guidelines of Clause 57.
- For the construction and extension of an apartment development of five or more storeys, excluding a basement, the objectives, standards and decisions guidelines of Clause 58.

Non-residential use and development

- Whether the use or development is compatible with residential use.
- Whether the use generally serves local community needs.
- The scale and intensity of the use and development.
- The design, height, setback and appearance of the proposed buildings and works.
- The proposed landscaping.
- The provision of car and bicycle parking and associated accessways.
- Any proposed loading and refuse collection facilities.
- The safety, efficiency and amenity effects of traffic to be generated by the proposal.

32.08-15 Signs

14/12/2023
VC253

Sign requirements are at Clause 52.05. This zone is in Category 3.

32.08-16 Transitional provisions

14/12/2023
VC253

The minimum garden area requirements of Clause 32.08-4 and the maximum building height and number of storeys requirements of Clause 32.08-9 introduced by Amendment VC110 do not apply to:

- A planning permit application for the construction or extension of a dwelling or residential building lodged before the approval date of Amendment VC110.
- Where a planning permit is not required for the construction or extension of a dwelling or residential building:
  - A building permit issued for the construction or extension of a dwelling or residential building before the approval date of Amendment VC110.
  - A building surveyor has been appointed to issue a building permit for the construction or extension of a dwelling or residential building before the approval date of Amendment VC110. A building permit must be issued within 12 months of the approval date of Amendment VC110.
  - A building surveyor is satisfied, and certifies in writing, that substantial progress was made on the design of the construction or extension of a dwelling or residential building before the approval date of Amendment VC110. A building permit must be issued within 12 months of the approval date of Amendment VC110.

The minimum garden area requirement of Clause 32.08-3 introduced by Amendment VC110 does not apply to a planning permit application to subdivide land for a dwelling or a residential building lodged before the approval date of Amendment VC110.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 32.08 GENERAL RESIDENTIAL ZONE

Shown on the planning scheme map as **GRZ1**.

INCREMENTAL CHANGE AREAS

1.0 Neighbourhood character objectives

08/07/2021
C211brim

None specified.

2.0 Construction or extension of a dwelling, small second dwelling or residential building - minimum garden area requirement

26/04/2024
VC252

Is the construction or extension of a dwelling, small second dwelling or residential building exempt from the minimum garden area requirement?
No

3.0 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

	Standard	Requirement
Minimum street setback	A2-1	None specified
	B2-1	None specified
Site coverage	A2-5	None specified
	B2-5	None specified
Private open space	A3-2	None specified
	B3-5	None specified
Front fence height	A2-7 and B2-8	None specified

4.0 Maximum building height requirement for a dwelling, small second dwelling or residential building

26/04/2024
VC252

None specified.

5.0 Application requirements

26/04/2024
VC252

The following application requirements apply to an application for a permit under Clause 32.08, in addition to those specified in Clause 32.08 and elsewhere in the scheme and must accompany an application, s appropriate, to the satisfaction of the responsible authority:

- The neighbourhood and site description plan (NSD) which must show:
  - At least three sites or buildings on both sides of the proposed development, opposite and to the rear of the proposed development.
  - The built form, scale and character of the area, including front fencing (i.e. height of buildings, front and side setbacks, location and width of vehicle and pedestrian crossovers, vegetation, land topography).
  - Location of open space (i.e. degree of openness at the rear of lots).
  - Architectural and roof styles.
  - A streetscape elevation showing the proposed development in the context of three adjoining dwellings or buildings on each side.
- A Design Response plan which must demonstrate:

  - How the proposed development responds to the characteristics identified in the neighbourhood and site description plan and should include a written evaluation of how the features of the neighbourhood identified in the neighbourhood and site description plan influence the design.

- Demonstrate that on site water storage and detention has been considered in the design, where necessary.

6.0 Decision guidelines

26/04/2024
VC252

The following decision guidelines apply to an application for a permit under Clause 32.08, in addition to those specified in Clause 32.08 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the development provides for an appropriate transition in built form, scale and height to the adjoining Neighbourhood Residential Zone or Residential Growth Zone.
- The extent to which the proposed building or works assists in respecting and enhancing the character of the area.
- The extent to which the proposed buildings or works retain existing canopy trees and create new opportunities for landscaping and adequate space for canopy tree planting.
- The extent to which the proposed built form reflects prevailing side setbacks, where applicable.
- The layout and appearance of areas set aside for car parking, access and egress and the location of any proposed off-street car parking.
- Whether garages and carports are located behind the façade of the proposed development.
- Whether a variation to the requirements of part 3.0 would result in a loss of on or off-site amenity.

16/01/2020
C215brim

SCHEDULE 2 TO CLAUSE 32.08 GENERAL RESIDENTIAL ZONE

Shown on the planning scheme map as **GRZ2**.

CAIRNLEA MIXED USE PRECINCT

1.0 Neighbourhood character objectives

16/01/2020
C215brim

None specified

2.0 Construction or extension of a dwelling, small second dwelling or residential building - minimum garden area requirement

26/04/2024
VC252

Is the construction or extension of a dwelling, small second dwelling or residential building exempt from the minimum garden area requirement?
Yes

3.0 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

	Standard	Requirement
Minimum street setback	A2-1	None specified
	B2-1	None specified
Site coverage	A2-5	None specified
	B2-5	None specified
Private open space	A3-2	None specified
	B3-5	None specified
Front fence height	A2-7 and B2-8	None specified

4.0 Maximum building height requirement for a dwelling, small second dwelling or residential building

26/04/2024
VC252

A building used as a dwelling, small second dwelling or a residential building must not exceed a height of 13.5 metres and 4 storeys.

5.0 Application requirements

26/04/2024
VC252

None specified

6.0 Decision guidelines

26/04/2024
VC252

None specified

32.09 NEIGHBOURHOOD RESIDENTIAL ZONE

31/03/2025
VC267

Shown on the planning scheme map as **NRZ** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To recognise areas of predominantly single and double storey residential development.

To manage and ensure that development is responsive to the identified neighbourhood character, heritage, environmental or landscape characteristics.

To allow educational, recreational, religious, community and a limited range of other non-residential uses to serve local community needs in appropriate locations.

32.09-1 Neighbourhood character objectives

27/03/2017
VC110

A schedule to this zone must contain the neighbourhood, heritage, environment or landscape character objectives to be achieved for the area.

32.09-2 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Bed and breakfast	No more than 10 persons may be accommodated away from their normal place of residence. At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence.
Community care accommodation	Must meet the requirements of Clause 52.22-2.
Domestic animal husbandry (other than Domestic animal boarding)	Must be no more than 2 animals.
Dwelling (other than Bed and breakfast)	
Home based business	
Informal outdoor recreation	
Medical centre	The gross floor area of all buildings must not exceed 250 square metres. Must be located in an existing building. The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3. Must not require a permit under Clause 52.06-3.
Place of worship	The gross floor area of all buildings must not exceed 250 square metres.

Use	Condition
	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3. Must not require a permit under Clause 52.06-3.
Racing dog husbandry	Must be no more than 2 animals.
Railway	
Residential aged care facility	
Rooming house	Must meet the requirements of Clause 52.23-2.
Small second dwelling	Must be no more than one dwelling existing on the lot. Must be the only small second dwelling on the lot. Reticulated natural gas must not be supplied to the building, or part of a building, used for the small second dwelling.
Tramway	
Any use listed in clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Accommodation (other than Community care accommodation, Dwelling, Residential aged care facility, Rooming house and Small second dwelling)	
Agriculture (other than Animal production, Animal training, Apiculture, Domestic animal husbandry, Horse husbandry and Racing dog husbandry)	
Car park	Must be used in conjunction with another use in Section 1 or 2.
Car wash	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Convenience restaurant	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Convenience shop	The leasable floor area must not exceed 80 square metres.
Domestic animal husbandry (other than Domestic animal boarding) – if the Section 1 condition is not met	Must be no more than 5 animals.
Food and drink premises (other than Convenience restaurant and Take away food premises)	
Grazing animal production	

Use	Condition
Leisure and recreation (other than Informal outdoor recreation and Motor racing track)	
Market	
Office (other than Medical centre)	The use must be associated with a use or development to which clause 53.23 (Significant residential development with affordable housing) applies.
Place of assembly (other than Amusement parlour, Carnival, Cinema based entertainment facility, Circus, Nightclub and Place of worship)	
Plant nursery	
Retail premises (other than Convenience shop, Food and drink premises, Market and Plant nursery)	The use must be associated with a use or development to which clause 53.23 (Significant residential development with affordable housing) applies.
Service station	The site must either: ▪ Adjoin a commercial zone or industrial zone. ▪ Adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3. The site must not exceed either: ▪ 3000 square metres. ▪ 3600 square metres if it adjoins on two boundaries a road in a Transport Zone 2 or a Transport Zone 3.
Store	Must be in a building, not a dwelling, and used to store equipment, goods, or motor vehicles used in conjunction with the occupation of a resident of a dwelling on the lot.
Take away food premises	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Utility installation (other than Minor utility installation and Telecommunications facility)	
Any other use not in Section 1 or 3	

Section 3 – Prohibited

Use
Amusement parlour
Animal production (other than Grazing animal production)
Animal training

Use
Cinema based entertainment facility
Domestic animal boarding
Extractive industry
Horse husbandry
Industry (other than Automated collection point and Car wash)
Motor racing track
Nightclub
Saleyard
Small second dwelling - if the Section 1 condition is not met
Transport terminal
Warehouse (other than Store)

32.09-3 Subdivision

14/12/2023
VC253

Permit requirement

A permit is required to subdivide land.

An application to subdivide land that would create a vacant lot less than 400 square metres capable of development for a dwelling or residential building, must ensure that each vacant lot created less than 400 square metres contains at least 25 percent as garden area. This does not apply to a lot created by an application to subdivide land where that lot is created in accordance with:

- An approved precinct structure plan or an equivalent strategic plan;
- An incorporated plan or approved development plan; or
- A permit for development.

A schedule to this zone may specify a minimum lot size to subdivide land. Each lot must be at least the area specified for the land, except where an application to subdivide land is made to create lots each containing an existing dwelling or car parking space, where an application for the existing dwelling or car parking space was made or approved before the approval date of the planning scheme amendment that introduced this clause 32.09 into the planning scheme.

An application to subdivide land, other than an application to subdivide land into lots each containing an existing dwelling or car parking space, must meet the requirements of Clause 56 and:

- Must meet all of the objectives included in the clauses specified in the following table.
- Should meet all of the standards included in the clauses specified in the following table.

Class of subdivision	Objectives and standards to be met
60 or more lots	All except Clause 56.03-5.
16 – 59 lots	All except Clauses 56.03-1 to 56.03-3, 56.03-5, 56.06-1 and 56.06-3.
3 – 15 lots	All except Clauses 56.02-1, 56.03-1 to 56.03-4, 56.05-2, 56.06-1, 56.06-3 and 56.06-6.

Class of subdivision	Objectives and standards to be met
2 lots	Clauses 56.03-5, 56.04-2, 56.04-3, 56.04-5, 56.06-8 to 56.09-2.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

32.09-4 Construction or extension of a dwelling, small second dwelling or residential building

14/12/2023
VC253

Minimum garden area requirement

An application to construct or extend a dwelling, small second dwelling or residential building on a lot must provide a minimum garden area as set out in the following table:

Lot size	Minimum percentage of a lot set aside as garden area
400 - 500 sqm	25%
Above 500 - 650 sqm	30%
Above 650 sqm	35%

This does not apply to:

- An application to construct or extend a dwelling, small second dwelling or residential building on a lot if:
  - The lot is designated as a medium density housing site in an approved precinct structure plan or an approved equivalent strategic plan;
  - The lot is designated as a medium density housing site in an incorporated plan or approved development plan; or
- An application to alter or extend an existing building that did not comply with the minimum garden area requirement of Clause 32.09-4 on the approval date of Amendment VC110.

32.09-5 Construction and extension of one dwelling on a lot

08/09/2025
VC282

Permit requirement

A permit is required to construct or extend one dwelling on a lot less than 300 square metres.

A permit is required to construct or extend a front fence within 3 metres of a street if the fence is associated with one dwelling on a lot less than 300 square metres and the fence exceeds the maximum height specified in clause 54.02-7.

A development must meet the requirements of Clause 54.

No permit required

No permit is required to:

- Construct or carry out works normal to a dwelling.
- Construct or extend an out-building (other than a garage or carport) on a lot provided the gross floor area of the out-building does not exceed 10 square metres and the maximum building height is not more than 3 metres above ground level.
- Make structural changes to a dwelling provided the size of the dwelling is not increased or the number of dwellings is not increased.

VicSmart applications

Subject to clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct or extend a dwelling on a lot less than 300 square metres if the development meets the following standards of Clause 54: ▪ clause 54.02-1 Street setback. ▪ clause 54.02-2 Building height. ▪ clause 54.02-3 Side and rear setbacks. ▪ clause 54.02-4 Walls on boundaries. ▪ clause 54.02-5 Site coverage ▪ clause 54.02-6 Tree canopy. ▪ clause 54.02-7 Front fences. ▪ clause 54.04-1 Daylight to existing windows. ▪ clause 54.04-2 Existing north-facing windows.	Clause 54

Class of application	Provision
▪ clause 54.04-3 Overshadowing secluded open space. ▪ clause 54.04-4 Overlooking. ▪ clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	
Construct or extend a front fence within 3 metres of a street if the fence is associated with one dwelling on a lot less than 300 square metres.	Clause 59.03

Transitional provisions

Clauses 32.09-5, 54 and 59.14 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.09-6 Construction and extension of a small second dwelling on a lot

08/09/2025
VC282

Permit requirement

A permit is required to construct or extend a small second dwelling on a lot of less than 300 square metres.

A development must meet the requirements of Clause 54.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct or extend a small second dwelling on a lot less than 300 square metres if the development meets the following standards of Clause 54: ▪ clause 54.02-1 Street setback. ▪ clause 54.02-2 Building height. ▪ clause 54.02-3 Side and rear setbacks. ▪ clause 54.02-4 Walls on boundaries. ▪ clause 54.02-5 Site coverage. ▪ clause 54.02-6 Tree canopy. ▪ clause 54.02-8 Building setback for small second dwellings. ▪ clause 54.03-5 Safety and accessibility for small second dwellings. ▪ clause 54.04-1 Daylight to existing windows. ▪ clause 54.04-2 Existing north-facing windows. ▪ clause 54.04-3 Overshadowing secluded open space.	Clause 54

Class of application	Provision
▪ clause 54.04-4 Overlooking. ▪ clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	

Transitional provisions

Clauses 32.09-6, 54 and 59.14 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.09-7 Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

31/03/2025
VC267

Permit requirement

A permit is required to:

- Construct a dwelling if there is at least one dwelling existing on the lot.
- Construct two or more dwellings on a lot.
- Extend a dwelling if there are two or more dwellings on the lot.
- Construct or extend a dwelling if it is on common property.
- Construct or extend a residential building.

A permit is required to construct or extend a front fence within 3 metres of a street if:

- The fence is associated with 2 or more dwellings on a lot or a residential building, and
- The fence exceeds the maximum height specified in Clause 55.02-8.

A development must meet the requirements of Clause 55. This does not apply to a development of four or more storeys, excluding a basement.

A development of four storeys, excluding a basement, must meet the requirements of Clause 57.

An apartment development of five or more storeys, excluding a basement, must meet the requirements of Clause 58.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct or extend a front fence within 3 metres of a street if the fence is associated with 2 or more dwellings on a lot or a residential building.	Clause 59.03

Transitional provisions

Clause 55 of this scheme, as in force immediately before the approval date of Amendment VC136, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 55 of this scheme, as in force immediately before the approval date of Amendment VC174, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 55 of this planning scheme, as in force immediately before the approval date of Amendment VC267, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.09-8 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

A schedule to this zone may specify the requirements of:

- Standards A2-1, A2-5, A2-7 and A3-2 of Clause 54 of this scheme.
- Standards B2-1, B2-5, B2-8 and B3-5 of Clause 55 of this scheme.

If a requirement is not specified in a schedule to this zone, the requirement set out in the relevant standard of Clause 54 or Clause 55 applies.

32.09-9 Residential aged care facility

15/03/2024
VC256

Permit requirements

A permit is required to construct a building or construct or carry out works for a residential aged care facility.

A development must meet the requirements of Clause 53.17 - Residential aged care facility.

32.09-10 Buildings and works associated with a Section 2 use

08/09/2025
VC282

A permit is required to construct a building or construct or carry out works for a use in Section 2 of clause 32.09-2.

VicSmart applications

Subject to clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Provision
Construct a building or construct or carry out works where: ▪ The building or works are not associated with a dwelling, primary school or secondary school and have an estimated cost of up to $100,000; or	Clause 59.04

Class of application	Provision
▪ The building or works are associated with a primary school or secondary school and have an estimated cost of up to $500,000; and ▪ The requirements in the following standards of Clause 54 are met, where the land adjoins land in a residential zone used for residential purposes: – clause 54.02-3 Side and rear setbacks. – clause 54.02-4 Walls on boundaries. – clause 54.04-1 Daylight to existing windows. – clause 54.04-2 Existing north-facing windows. – clause 54.04-3 Overshadowing secluded open space. – clause 54.04-4 Overlooking. – clause 54.05-2 Overshadowing domestic solar energy systems. If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard, the requirement in the schedule to the zone applies and must be met.	

Transitional provisions

Clauses 32.09-10, 54 and 59.04 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

32.09-11 Maximum building height requirement for a dwelling, small second dwelling or residential building

14/12/2023
VC253

A building must not be constructed for use as a dwelling, small second dwelling or a residential building that:

- exceeds the maximum building height specified in a schedule to this zone; or
- contains more than the maximum number of storeys specified in a schedule to this zone.

If no maximum building height or maximum number of storeys is specified in a schedule to this zone:

- the building height must not exceed 9 metres; and
- the building must contain no more than 2 storeys at any point.

A building may exceed the applicable maximum building height or contain more than the applicable maximum number of storeys if:

- It replaces an immediately pre-existing building and the new building does not exceed the building height or contain a greater number of storeys than the pre-existing building.
- There are existing buildings on both abutting allotments that face the same street and the new building does not exceed the building height or contain a greater number of storeys than the lower of the existing buildings on the abutting allotments.

- It is on a corner lot abutted by lots with existing buildings and the new building does not exceed the building height or contain a greater number of storeys than the lower of the existing buildings on the abutting allotments.
- It is constructed pursuant to a valid building permit that was in effect prior to the introduction of this provision.

An extension to an existing building may exceed the applicable maximum building height or contain more than the applicable maximum number of storeys if it does not exceed the building height of the existing building or contain a greater number of storeys than the existing building.

A building may exceed the maximum building height by up to 1 metre if the slope of the natural ground level, measured at any cross section of the site of the building wider than 8 metres, is greater than 2.5 degrees.

A basement is not a storey for the purposes of calculating the number of storeys contained in a building.

The maximum building height and maximum number of storeys requirements in this zone or a schedule to this zone apply whether or not a planning permit is required for the construction of a building.

Building height if land is subject to inundation

If the land is in a Special Building Overlay, Land Subject to Inundation Overlay or is land liable to inundation the maximum building height specified in the zone or schedule to the zone is the vertical distance from the minimum floor level determined by the relevant drainage authority or floodplain management authority to the roof or parapet at any point.

32.09-12 Application requirements

08/09/2025
VC282

An application must be accompanied by the following information, as appropriate:

- For a development of one dwelling on a lot or a small second dwelling on a lot, the site description and design response as required in Clause 54.
- For a development of two or more dwellings on a lot, dwellings on common property and residential buildings of three storeys or less, excluding a basement, the site description and design response as required in Clause 55.
- For a development of two or more dwellings on a lot, dwellings on common property and residential buildings of four storeys, excluding a basement, the site description and design response as required in Clause 57.
- For an apartment development of five or more storeys, an urban context report and design response as required in clause 58.01.
- For an application for subdivision, a site and context description and design response as required in Clause 56.
- Plans drawn to scale and dimensioned which show:
  - Site shape, size, dimensions and orientation.
  - The siting and use of existing and proposed buildings.
  - Adjacent buildings and uses, including siting and dimensioned setbacks.
  - The building form and scale.
  - Setbacks to property boundaries.

- The likely effects, if any, on adjoining land, including noise levels, traffic, the hours of delivery and despatch of good and materials, hours of operation and light spill, solar access and glare.
- Any other application requirements specified in a schedule to this zone.

If in the opinion of the responsible authority an application requirement is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

32.09-13 Exemption from notice and review

08/09/2025
VC282

Subdivision

An application to subdivide land into lots each containing an existing dwelling or car parking space is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Construction and extension of one dwelling on a lot

An application under clause 32.09-5 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-6, 54.02-7, 54.04 and 54.05-2 are met.

Construction and extension of a small second dwelling on a lot

An application under clause 32.09-6 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-6, 54.02-8, 54.03-5, 54.04 and 54.05-2 are met.

Construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings

An application under clause 32.09-7 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if all the applicable standards under clauses 55.02, 55.04-1, 55.04-2, 55.04-3, 55.04-4 and 55.05-2 are met.

32.09-14 Decision guidelines

31/03/2025
VC267

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General

- The Municipal Planning Strategy and the Planning Policy Framework.
- The purpose of this zone.
- The objectives set out in the schedule to this zone.
- Any other decision guidelines specified in a schedule to this zone.
- The impact of overshadowing on existing rooftop solar energy systems on dwellings on adjoining lots in a General Residential Zone, Housing Choice and Transport Zone, Mixed Use Zone, Neighbourhood Residential Zone, Residential Growth Zone or Township Zone.

Subdivision

- The pattern of subdivision and its effect on the spacing of buildings.
- For subdivision of land for residential development, the objectives and standards of Clause 56.

Dwellings, small second dwellings and residential buildings

- For the construction and extension of one dwelling on a lot and a small second dwelling, the applicable objectives, standards and decision guidelines of Clause 54.

- For the construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings of three storeys or less, excluding a basement, the objectives, standards and decision guidelines of Clause 55.
- For the construction and extension of two or more dwellings on a lot, dwellings on common property and residential buildings of four storeys, excluding a basement, the objectives, standards and decision guidelines of Clause 57.
- For the construction and extension of an apartment development of five or more storeys, excluding a basement, the objectives, standards and decisions guidelines of Clause 58.

Non-residential use and development

In the local neighbourhood context:

- Whether the use or development is compatible with residential use.
- Whether the use generally serves local community needs.
- The scale and intensity of the use and development.
- The design, height, setback and appearance of the proposed buildings and works.
- The proposed landscaping.
- The provision of car and bicycle parking and associated accessways.
- Any proposed loading and refuse collection facilities.
- The safety, efficiency and amenity effects of traffic to be generated by the proposal.

32.09-15 Signs

14/12/2023
VC253

Sign requirements are at Clause 52.05. This zone is in Category 3.

32.09-16 Transitional provisions

14/12/2023
VC253

The minimum garden area requirements of Clause 32.09-4 and the maximum building height and number of storeys requirements of Clause 32.09-9 introduced by Amendment VC110 do not apply to:

- A planning permit application for the construction or extension of a dwelling or residential building lodged before the approval date of Amendment VC110.
- Where a planning permit is not required for the construction or extension of a dwelling or residential building:
  - A building permit issued for the construction or extension of a dwelling or residential building before the approval date of Amendment VC110.
  - A building surveyor has been appointed to issue a building permit for the construction or extension of a dwelling or residential building before the approval date of Amendment VC110. A building permit must be issued within 12 months of the approval date of Amendment VC110.
  - A building surveyor is satisfied, and certifies in writing, that substantial progress was made on the design of the construction or extension of a dwelling or residential building before the approval date of Amendment VC110. A building permit must be issued within 12 months of the approval date of Amendment VC110.

The minimum garden area requirement of Clause 32.09-3 introduced by Amendment VC110 does not apply to a planning permit application to subdivide land for a dwelling or a residential building lodged before the approval date of Amendment VC110.

03/03/2016
C166

SCHEDULE 1 TO CLAUSE 32.09 NEIGHBOURHOOD RESIDENTIAL ZONE

Shown on the planning scheme map as **NRZ1**.

LIMITED CHANGE AREAS (1)

1.0 Neighbourhood character objectives

08/07/2021
C211brim

None specified

2.0 Minimum subdivision area

08/07/2021
C211brim

None specified.

3.0 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

	Standard	Requirement
Minimum street setback	A2-1	None specified
	B2-1	None specified
Site coverage	A2-5	None specified
	B2-5	None specified
Private open space	A3-2	None specified
	B3-5	None specified
Front fence height	A2-7 and B2-8	None specified

4.0 Maximum building height requirement for a dwelling, small second dwelling or residential building

26/04/2024
VC252

None specified

5.0 Application requirements

26/04/2024
VC252

The following application requirements apply to an application for a permit under Clause 32.09, in addition to those specified in Clause 32.09 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A neighbourhood and site description plan (NSD) which must show:
  - At least three sites or buildings on both sides of the proposed development, opposite and to the rear of the proposed development.
  - The built form, scale and character of the area, including front fencing (i.e. height of buildings, front and side setbacks, location and width of vehicle and pedestrian crossovers, vegetation and land topography).
  - Location of open space (i.e. degree of openness at the rear of lots).
  - Architectural and roof styles.
  - A streetscape elevation showing the proposed development in the context of three adjoining dwellings or buildings.
- A Design Response plan which must demonstrate:

  - How the proposed development responds to the characteristics identified in the neighbourhood and site description (NSD) plan and should include a written evaluation of how the features of the neighbourhood identified in the NSD influence the design.

- Demonstrate that on site water storage and detention has been considered in the design, where necessary.

6.0 Decision guidelines

26/04/2024
VC252

The following decision guidelines apply to an application for a permit under Clause 32.09, in addition to those specified in Clause 32.09 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The extent to which the proposed building or works respects and enhances the character of the area.
- The extent to which the proposed buildings or works retain existing canopy trees and create opportunities for landscaping and adequate space for canopy tree planting.
- The layout and appearance of areas set aside for car parking, access and egress and the location of any proposed off street car parking.
- Whether garages and carports are located behind the façade of the proposed development.
- The extent to which the proposed built form respects prevailing side setbacks, where applicable.
- Whether a variation to the requirements of part 3.0 would result in a loss of on or off-site amenity.

03/03/2016
C166

SCHEDULE 2 TO CLAUSE 32.09 NEIGHBOURHOOD RESIDENTIAL ZONE

Shown on the planning scheme map as **NRZ2**.

LIMITED CHANGE AREAS (2)

1.0 Neighbourhood character objectives

08/07/2021
C211brim

None specified

2.0 Minimum subdivision area

08/07/2021
C211brim

None specified.

3.0 Requirements of Clause 54 and Clause 55

08/09/2025
VC282

	Standard	Requirement
Minimum street setback	A2-1	None specified
	B2-1	None specified
Site coverage	A2-5	None specified
	B2-5	None specified
Private open space	A3-2	None specified
	B3-5	None specified
Front fence height	A2-7 and B2-8	None specified

4.0 Maximum building height requirement for a dwelling, small second dwelling or residential building

26/04/2024
VC252

The maximum height of a building used for the purpose of a dwelling, small second dwelling or residential building must not exceed 12 metres.

5.0 Application requirements

26/04/2024
VC252

The following application requirements apply to an application for a permit under Clause 32.09, in addition to those specified in Clause 32.09 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A neighbourhood and site description plan (NSD) which must show, as appropriate:
  - The built form, scale and character of the area, including front fencing (i.e. height of buildings, front and side setbacks, location and width of vehicle and pedestrian crossovers, vegetation, land topography etc).
  - Location of open space (i.e. degree of openness at the rear of lots).
  - Architectural and roof styles.
  - At least three sites or buildings on both sides of the proposed development, opposite and to the rear of the proposed development.
  - A streetscape elevation showing the proposed development in the context of three adjoining dwellings or buildings on each side.
- A Design Response plan which must demonstrate, as appropriate:

  - How the proposed development responds to the characteristics identified in the neighbourhood and site description (NSD) plan and should include a written evaluation of how the features of the neighbourhood identified in the NSD influence the design.

- Demonstrate that on site water storage and detention has been considered in the design, where necessary.

6.0 Decision guidelines

26/04/2024
VC252

The following decision guidelines apply to an application for a permit under Clause 32.09, in addition to those specified in Clause 32.09 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The extent to which the proposed building or works respects and enhances the character of the area.
- The extent to which the proposed buildings or works retain existing canopy trees and create new opportunities for landscaping and adequate space for canopy tree planting.
- The layout and appearance of areas set aside for car parking, access and egress, loading and the location of any proposed off street car parking.
- Whether garages and carports are located behind the façade of the proposed development.
- The extent to which the proposed built form respects prevailing side setbacks, where applicable.
- Whether a variation to the requirements of part 3.0 would result in an unacceptable loss of on or off-site amenity.

33 INDUSTRIAL ZONES

19/01/2006
VC37

33.01 INDUSTRIAL 1 ZONE

31/07/2018
VC148

Shown on the planning scheme map as **IN1Z**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide for manufacturing industry, the storage and distribution of goods and associated uses in a manner which does not affect the safety and amenity of local communities.

33.01-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Convenience shop	
Crop raising	
Grazing animal production	
Home based business	
Industry (other than Materials recycling and Transfer station)	Must not be a purpose listed in the table to Clause 53.10 with no threshold distance specified. The land must be at least the following distances from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution: ▪ The threshold distance, for a purpose listed in the table to Clause 53.10. ▪ 30 metres, for a purpose not listed in the table to Clause 53.10. Must not: ▪ Exceed a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022. ▪ Require a notification under the Occupational Health and Safety Regulations 2017. ▪ Require a licence under the Dangerous Goods (Explosives) Regulations 2011. ▪ Require a licence under the Dangerous Goods (HCDG) Regulations 2016. Must not adversely affect the amenity of the neighbourhood, including through the: ▪ Transport of materials, goods or commodities to or from the land. ▪ Appearance of any stored goods or materials. ▪ Emission of noise, artificial light, vibration, odour, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.

Use	Condition
Informal outdoor recreation	
Mail centre	
Railway	
Service station	The land must be at least 30 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution. Must not adversely affect the amenity of the neighbourhood, including through the: ▪ Transport of materials, goods or commodities to or from the land. ▪ Appearance of any stored goods or materials. Emission of noise, artificial light, vibration, odour, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.
Shipping container storage	Must not be a purpose listed in the table to Clause 53.10 with no threshold distance specified. The land must be at least the following distances from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution: ▪ The threshold distance, for a purpose listed in the table to Clause 53.10. ▪ 100 metres, for a purpose not listed in the table to Clause 53.10. Must not: ▪ Exceed a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022. ▪ Require a notification under the Occupational Health and Safety Regulations 2017. ▪ Require a licence under the Dangerous Goods (Explosives) Regulations 2011. ▪ Require a licence under the Dangerous Goods (HCDG) Regulations 2016. The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3. Shipping containers must be setback at least 9 metres from a road in a Transport Zone 2 or a Transport Zone 3. The height of shipping container stacks must not exceed 6 containers or 16 metres, whichever is the lesser. Must not adversely affect the amenity of the neighbourhood, including through the: ▪ Transport of materials, goods or commodities to or from the land. ▪ Appearance of any stored goods or materials. ▪ Emission of noise, artificial light, vibration, odour, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.

Use	Condition
Take away food premises	
Tramway	
Warehouse (other than Mail centre and Shipping container storage)	Must not be a purpose listed in the table to Clause 53.10 with no threshold distance specified. The land must be at least the following distances from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution: ▪ The threshold distance, for a purpose listed in the table to Clause 53.10. ▪ 30 metres, for a purpose not listed in the table to Clause 53.10. Must not: ▪ Exceed a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022. ▪ Require a notification under the Occupational Health and Safety Regulations 2017. ▪ Require a licence under the Dangerous Goods (Explosives) Regulations 2011. ▪ Require a licence under Dangerous Goods (HCDG) Regulations 2016. Must not adversely affect the amenity of the neighbourhood, including through the: ▪ Transport of materials, goods or commodities to or from the land. ▪ Appearance of any stored goods or materials. ▪ Emission of noise, artificial light, vibration, odour, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Adult sex product shop	Must be at least 200 metres (measured by the shortest route reasonably accessible on foot) from a residential zone or land used for a hospital, primary school or secondary school or land in a Public Acquisition Overlay to be acquired for a hospital, primary school or secondary school.
Agriculture (other than Apiculture, Crop raising, Grazing animal production, Intensive animal production, Pig farm and Poultry farm)	
Caretaker's house	
Container deposit scheme centre	

Use	Condition
Education centre	Must not be a primary or secondary school.
Leisure and recreation (other than Informal outdoor recreation)	
Materials recycling	The land must be at least 30 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone or land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution.
Office	The leasable floor area must not exceed the amount specified in the schedule to this zone.
Place of assembly (other than Carnival, Cinema based entertainment facility and Circus)	
Restricted retail premises	
Retail premises (other than Shop and Take away food premises)	
Sex services premises	
Transfer station (other than Automated collection point and Container deposit scheme centre)	The land must be at least 30 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone or land used for a hospital, an education centre a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution.
Utility installation (other than Minor utility installation and Telecommunications facility).	Any gas holder, or sewerage or refuse treatment or disposal works, must be at least 30 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution.
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Accommodation (other than Caretaker's house)
Cinema based entertainment facility
Hospital
Intensive animal production

Use
Pig farm
Poultry farm
Shop (other than Adult sex product shop, Convenience shop, Restricted retail premises and Sex services premises)

33.01-2 Use of land

14/01/2025
VC237

Application requirements

An application to use land for an industry or warehouse must be accompanied by the following information, as appropriate:

- The purpose of the use and the types of processes to be utilised.
- The type and quantity of goods to be stored, processed or produced.
- How land not required for immediate use is to be maintained.
- Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority.
- Whether a notification under the Occupational Health and Safety Regulations 2017 is required, a licence under the *Dangerous Goods Act 1985* is required, or a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022 is exceeded.
- The likely effects, if any, on the neighbourhood, including:
  - Noise levels.
  - Air-borne emissions.
  - Emissions to land or water.
  - Traffic, including the hours of delivery and despatch.
  - Light spill or glare.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The effect that the use may have on nearby existing or proposed residential areas or other uses which are sensitive to industrial off-site effects, having regard to any comments or directions of the referral authorities.
- The effect that nearby industries may have on the proposed use.
- The drainage of the land.
- The availability of and connection to services.
- The effect of traffic to be generated on roads.
- The interim use of those parts of the land not required for the proposed use.

33.01-3 Subdivision

31/07/2018
VC148

Permit requirement

A permit is required to subdivide land.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

Exemption from notice and review

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to land within 30 metres of land (not a road) which is in a residential zone or land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a hospital or an education centre.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any natural or cultural values on or near the land.
- Streetscape character.
- Landscape treatment.

- Interface with non-industrial areas.

33.01-4 Buildings and works

15/03/2024
VC256

Permit requirement

A permit is required to construct a building or construct or carry out works.

This does not apply to:

- A building or works which rearrange, alter or renew plant if the area or height of the plant is not increased.
- A building or works which are used for crop raising or informal outdoor recreation.
- A rainwater tank with a capacity of more than 10,000 litres if the following requirements are met:
  - The rainwater tank is not located within the building's setback from a street (other than a lane).
  - The rainwater tank is no higher than the existing building on the site.
  - The rainwater tank is not located in an area that is provided for car parking, loading, unloading or accessway.
- A building or works which are used for grazing animal production, except for permanent or fixed feeding infrastructure for seasonal or supplementary feeding constructed within 100 metres of:
  - A waterway, wetland or designated flood plain.
  - A dwelling not in the same ownership.
  - A residential or urban growth zone.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $1,000,000 where the land is not: ▪ Within 30 metres of land (not a road) which is in a residential zone. ▪ Used for a purpose listed in the table to Clause 53.10. ▪ Used for an Adult sex product shop.	Clause 59.04

Application requirements

An application to construct a building or construct or carry out works must be accompanied by the following information, as appropriate:

- A plan drawn to scale which shows:
  - The boundaries and dimensions of the site.
  - Adjoining roads.
  - Relevant ground levels.

  - The layout of existing and proposed buildings and works.
  - Driveways and vehicle parking and loading areas.
  - Proposed landscape areas.
  - External storage and waste treatment areas.
- Elevation drawings to scale which show the colour and materials of all buildings and works.
- Construction details of all drainage works, driveways and vehicle parking and loading areas.
- A landscape layout which includes the description of vegetation to be planted, the surfaces to be constructed, a site works specification and the method of preparing, draining, watering and maintaining the landscape area.

Exemption from notice and review

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to an application for a building or works within 30 metres of land (not a road) which is in a residential zone or land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a hospital or an education centre.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any natural or cultural values on or near the land.
- Streetscape character.
- Built form.
- Landscape treatment.
- Interface with non-industrial areas.
- Parking and site access.
- Loading and service areas.
- Outdoor storage.
- Lighting.
- Stormwater discharge.

Maintenance

All buildings and works must be maintained in good order and appearance to the satisfaction of the responsible authority.

33.01-5 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 2.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 33.01 INDUSTRIAL 1 ZONE

1.0 Maximum leasable floor area requirements

08/07/2021
C211brim

Land	Maximum leasable floor area for Office (square metres)
None specified	None specified

33.02 INDUSTRIAL 2 ZONE

31/07/2018
VC148

Shown on the planning scheme map as **IN2Z**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide for manufacturing industry, the storage and distribution of goods and associated facilities in a manner which does not affect the safety and amenity of local communities.

To promote manufacturing industries and storage facilities that require a substantial threshold distance within the core of the zone.

To keep the core of the zone free of uses which are suitable for location elsewhere so as to be available for manufacturing industries and storage facilities that require a substantial threshold distance as the need for these arises.

33.02-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Crop raising	
Grazing animal production	
Home based business	
Informal outdoor recreation	
Railway	
Service station	
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Adult sex product shop	Must be at least 200 metres (measured by the shortest route reasonably accessible on foot) from a residential zone or land used for a hospital, primary school or secondary school or land in a Public Acquisition Overlay to be acquired for a hospital, primary school or secondary school.

Use	Condition
Agriculture (other than Apiculture, Crop raising, Grazing animal production, Intensive animal production, Pig farm and Poultry farm)	
Caretaker's house	
Convenience shop	
Education centre	Must not be a primary or secondary school.
Equestrian supplies	
Industry (other than Automated collection point)	
Leisure and recreation (other than Informal outdoor recreation)	
Office	The leasable floor area must not exceed the amount specified in the schedule to this zone.
Party supplies	
Retail premises (other than Shop)	
Sex services premises	
Utility installation (other than Minor utility installation and Telecommunications facility)	
Warehouse	
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Accommodation (other than Caretaker's house)
Display home centre
Hospital
Intensive animal production
Pig farm
Place of assembly (other than Carnival or Circus)
Poultry farm
Shop (other than Adult sex product shop, Convenience shop, Equestrian supplies, Party supplies and Sex services premises)
Veterinary centre

33.02-2 Use of land

14/01/2025
VC237

Application requirements

An application to use land for an industry or warehouse must be accompanied by the following information, as appropriate:

- The suitability of the industry or warehouse being located in the core of the zone, where the land is more than 1500 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone and land used for a hospital, an education centre or corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or corrective institution and the industry or warehouse is a purpose which is listed in the table to Clause 53.10 as requiring a threshold distance of less than 1500 metres, or is not listed in the table.
- The purpose of the use and the types of processes to be utilised.
- The type and quantity of goods to be stored, processed or produced.
- How land not required for immediate use is to be maintained.
- Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority,
- Whether a notification under the Occupational Health and Safety Regulations 2017 is required, a licence under the *Dangerous Goods Act 1985* is required, or a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022 is exceeded.
- The likely effects, if any, on the neighbourhood, including:
  - Noise levels.
  - Air-borne emissions.
  - Emissions to land or water.
  - Traffic, including the hours of delivery and dispatch.
  - Light spill or glare.

Exemption from notice and review

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

This exemption does not apply to land within 30 metres from land (not a road) which is a residential zone, Capital City Zone or Docklands Zone, land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a hospital or an education centre.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The suitability of the industry or warehouse being located in the core of the zone, where the land is more than 1500 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution and the industry or warehouse is a purpose which is listed in the table to Clause 53.10 as requiring a threshold distance of less than 1500 metres, or is not listed in the table.

- The effect that the use may have on nearby existing or proposed residential areas or other uses which are sensitive to industrial off-site effects, having regard to any comments or directions of the referral authorities.
- The effect that nearby industries may have on the proposed use.
- The drainage of the land.
- The availability of and connection to services.
- The effect of traffic to be generated on roads.
- The interim use of those parts of the land not required for the proposed use.

33.02-3 Subdivision

31/07/2018
VC148

Permit requirement

A permit is required to subdivide land.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

Exemption from notice and review

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to land within 30 metres from land (not a road) which is in a residential zone or land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a hospital or an education centre.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any natural or cultural values on or near the land.
- Streetscape character.
- Landscape treatment.
- Interface with non-industrial areas.
- The suitability of the proposed lots for the types of industries and warehouses shown in the table to Clause 53.10.

33.02-4 Buildings and works

15/03/2024
VC256

Permit requirement

A permit is required to construct a building or construct or carry out works.

This does not apply to:

- A building or works which rearrange, alter or renew plant if the area or height of the plant is not increased.
- A building or works which are used for crop raising or informal outdoor recreation.
- A rainwater tank with a capacity of more than 10,000 litres if the following requirements are met:
  - The rainwater tank is not located within the building's setback from a street (other than a lane).
  - The rainwater tank is no higher than the existing building on the site.
  - The rainwater tank is not located in an area that is provided for car parking, loading, unloading or accessway.
- A building or works which are used for grazing animal production, except for permanent or fixed feeding infrastructure for seasonal or supplementary feeding constructed within 100 metres of:
  - A waterway, wetland or designated flood plain.
  - A dwelling not in the same ownership.
  - A residential or urban growth zone.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $1,000,000 where the land is not: ▪ Within 30 metres of land (not a road) which is in a residential zone. ▪ Used for a purpose listed in the table to Clause 53.10. ▪ Used for an Adult sex product shop.	Clause 59.04

Application requirements

An application to construct a building or construct or carry out works must be accompanied by the following information, as appropriate:

- A plan drawn to scale which shows:
  - The boundaries and dimensions of the site.
  - Adjoining roads.
  - Relevant ground levels.
  - The layout of existing and proposed buildings and works.
  - Driveways and vehicle parking and loading areas.
  - Proposed landscape areas.
  - External storage and waste treatment areas.
- Elevation drawings to scale which show the colour and materials of all buildings and works.
- Construction details of all drainage works, driveways and vehicle parking and loading areas.
- A landscape layout which includes the description of vegetation to be planted, the surfaces to be constructed, a site works specification and the method of preparing, draining, watering and maintaining the landscape area.

Exemption from notice and review

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to an application for a building or works within 30 metres of land (not a road) which is in a residential zone or land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a hospital or an education centre.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The suitability of the proposed buildings or works for the types of industries and warehouses shown in the table to Clause 53.10.
- Any natural or cultural values on or near the land.
- Streetscape character.
- Built form.
- Landscape treatment.

- Interface with non-industrial areas.
- Parking and site access.
- Loading and service areas.
- Outdoor Storage.
- Lighting.
- Stormwater discharge.

Maintenance

All buildings and works must be maintained in good order and appearance to the satisfaction of the responsible authority.

33.02-5 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 2.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 33.02 INDUSTRIAL 2 ZONE

1.0 Maximum leasable floor area requirements

08/07/2021
C211brim

Land	Maximum leasable floor area for Office (square metres)
None specified	None specified

33.03 INDUSTRIAL 3 ZONE

31/07/2018
VC148

Shown on the planning scheme map as **IN3Z**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide for industries and associated uses in specific areas where special consideration of the nature and impacts of industrial uses is required or to avoid inter-industry conflict.

To provide a buffer between the Industrial 1 Zone or Industrial 2 Zone and local communities, which allows for industries and associated uses compatible with the nearby community.

To allow limited retail opportunities including convenience shops, small scale supermarkets and associated shops in appropriate locations.

To ensure that uses do not affect the safety and amenity of adjacent, more sensitive land uses.

33.03-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Convenience shop	
Crop raising	
Grazing animal production	
Home based business	
Informal outdoor recreation	
Mail centre	
Railway	
Service industry	Must not be a purpose listed in the table to Clause 53.10 with no threshold distance specified. The land must be at least the following distances from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution: ▪ The threshold distance, for a purpose listed in the table to Clause 53.10. ▪ 30 metres, for a purpose not listed in the table to Clause 53.10. Must not: ▪ Exceed a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022.

Use	Condition
	▪ Require a notification under the Occupational Health and Safety Regulations 2017. ▪ Require a licence under the Dangerous Goods (Explosives) Regulations 2011. ▪ Require a licence under Dangerous Goods (HCDG) Regulations 2016.
Service station	The land must be at least 30 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution.
Shop (other than Adult sex product shop, Convenience shop, Restricted retail premises and Supermarket)	Must adjoin, or be on the same lot as, a supermarket when the use commences. The combined leasable floor area for all shops adjoining or on the same lot as the supermarket must not exceed 500 square metres. The site must adjoin, or be within 30 metres of, a road in a Transport Zone 2 or a Transport Zone 3.
Supermarket	The leasable floor area must not exceed 1800 square metres. The site must adjoin, or be within 30 metres of, a road in a Transport Zone 2 or a Transport Zone 3. Must be on land within an urban growth boundary and in metropolitan Melbourne.
Take away food premises	
Tramway	
Warehouse (other than Fuel depot, Mail centre or Shipping container storage)	Must not be a purpose listed in the table to Clause 53.10 with no threshold distance specified. The land must be at least the following distances from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution: ▪ The threshold distance, for a purpose listed in the table to Clause 53.10. ▪ 30 metres, for a purpose not listed in the table to Clause 53.10. Must not: ▪ Exceed a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022. ▪ Require a notification under the Occupational Health and Safety Regulations 2017. ▪ Require a licence under the Dangerous Goods (Explosives) Regulations 2011. ▪ Require a licence under the Dangerous Goods (HCDG) Regulations 2016.

Use	Condition
	Must not adversely affect the amenity of the neighbourhood, including through the: ▪ Transport of materials, goods or commodities to or from the land. ▪ Appearance of any stored goods or materials. ▪ Emission of noise, artificial light, vibration, odour, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Adult sex product shop	Must be at least 200 metres (measured by the shortest route reasonably accessible on foot) from a residential zone or land used for a hospital, primary school or secondary school or land in a Public Acquisition Overlay to be acquired for a hospital, primary school or secondary school.
Agriculture (other than Apiculture, Crop raising, Grazing animal production, Intensive animal production, Pig farm and Poultry farm)	
Caretaker's house	
Education centre	Must not be a primary or secondary school.
Industry (other than Automated collection point and Service industry)	
Leisure and recreation (other than Informal outdoor recreation, Major sports and recreation facility, and Motor racing track)	
Office	The leasable floor area must not exceed the amount specified in the schedule to this zone.
Place of assembly (other than Carnival, Cinema based entertainment facility and Circus)	
Restricted retail premises	
Retail premises (other than Shop and Take away food premises)	
Sex services premises - if the Section 1 conditions for a shop are not met	

Use	Condition
Utility installation (other than Minor utility installation and Telecommunications facility)	
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Accommodation (other than Caretaker's house)
Cinema based entertainment facility
Hospital
Intensive animal production
Major sports and recreation facility
Motor racing track
Pig farm
Poultry farm
Shop (other than Adult sex product shop, Convenience shop, Restricted retail premises, Sex services premises and Supermarket) – if the Section 1 conditions are not met
Supermarket – if the section 1 conditions are not met

33.03-2 Use of land

14/01/2025
VC237

Amenity of the neighbourhood

A use must not adversely affect the amenity of the neighbourhood, including through the:

- Transport of materials, goods or commodities to or from the land.
- Appearance of any stored goods or materials.
- Emission of noise, artificial light, vibration, odour, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.

Application requirements

An application to use land for an industry or warehouse must be accompanied by the following information, as appropriate:

- The purpose of the use and the types of processes to be utilised.
- The type and quantity of goods to be stored, processed or produced.
- How land not required for immediate use is to be maintained.
- Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority.

- Whether a notification under the Occupational Health and Safety Regulations 2017 is required, a licence under the *Dangerous Goods Act 1985* is required, or a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022 is exceeded.
- The likely effects, if any, on the neighbourhood, including:
  - Noise levels.
  - Air-borne emissions.
  - Emissions to land or water.
  - Traffic, including the hours of delivery and despatch.
  - Light spill or glare.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The effect that the use may have on nearby existing or proposed residential areas or other uses which are sensitive to industrial off-site effects, having regard to any comments or directions of the referral authorities.
- The effect that nearby industries may have on the proposed use.
- The drainage of the land.
- The availability of and connection to services.
- The effect of traffic to be generated on roads.
- The interim use of those parts of the land not required for the proposed use.
- The effect on nearby industries.

33.03-3 Subdivision

31/07/2018
VC148

Permit requirement

A permit is required to subdivide land.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme.	Clause 59.02

Class of application	Information requirements and decision guidelines
▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

Exemption from notice and review

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to land within 30 metres from land (not a road) which is in a residential zone or land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a hospital or an education centre.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any natural or cultural values on or near the land.
- Streetscape character.
- Landscape treatment.
- Interface with non-industrial areas.

33.03-4 Buildings and works

01/12/2023
VC217

Permit requirement

A permit is required to construct a building or construct or carry out works.

This does not apply to:

- A building or works which rearrange, alter or renew plant if the area or height of the plant is not increased.
- A building or works which are used for crop raising or informal outdoor recreation.
- A rainwater tank with a capacity of more than 10,000 litres if the following requirements are met:
  - The rainwater tank is not located within the building's setback from a street (other than a lane).

  - The rainwater tank is no higher than the existing building on the site.
  - The rainwater tank is not located in an area that is provided for car parking, loading, unloading or accessway.
- A building or works which are used for grazing animal production, except for permanent or fixed feeding infrastructure for seasonal or supplementary feeding constructed within 100 metres of:
  - A waterway, wetland or designated flood plain.
  - A dwelling not in the same ownership.
  - A residential or urban growth zone.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $1,000,000 where the land is not: ▪ Within 30 metres of land (not a road) which is in a residential zone. ▪ Used for a purpose listed in the table to Clause 53.10. ▪ Used for an Adult sex product shop.	Clause 59.04

Application requirements

An application to construct a building or construct or carry out works must be accompanied by the following information, as appropriate:

- A plan drawn to scale which shows:
  - The boundaries and dimensions of the site.
  - Adjoining roads.
  - Relevant ground levels.
  - The layout of existing and proposed buildings and works.
  - Driveways and vehicle parking and loading areas.
  - Proposed landscape areas.
  - External storage and waste treatment areas.
  - Mechanisms to mitigate noise, odour and other adverse amenity impacts of, and on, nearby industries.
- Elevation drawings to scale which show the colour and materials of all buildings and works.
- Construction details of all drainage works, driveways and vehicle parking and loading areas.
- A landscape layout which includes the description of vegetation to be planted, the surfaces to be constructed, a site works specification and the method of preparing, draining, watering and maintaining the landscape area.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any natural or cultural values on or near the land.
- Streetscape character.
- Built form.
- Landscape treatment.
- Interface with non-industrial areas.
- Parking and site access.
- Loading and service areas.
- Outdoor storage.
- Lighting.
- Stormwater discharge.
- The effect on nearby industries.
- The effect of nearby industries.

Maintenance

All buildings and works must be maintained in good order and appearance to the satisfaction of the responsible authority.

33.03-5 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 2.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 33.03 INDUSTRIAL 3 ZONE

1.0 Maximum leasable floor area requirements

08/07/2021
C211brim

Land	Maximum leasable floor area for Office (square metres)
None specified	None specified

34 COMMERCIAL ZONES

15/07/2013
VC100

34.01 COMMERCIAL 1 ZONE

31/07/2018
VC148

Shown on the planning scheme map as **B1Z**, **B2Z**, **B5Z** or **C1Z**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To create vibrant mixed use commercial centres for retail, office, business, entertainment and community uses.

To provide for residential uses at densities complementary to the role and scale of the commercial centre.

Operation

A schedule may apply under this zone to a planning scheme outside of metropolitan Melbourne. That schedule may:

- specify the maximum leasable floor area for office
- specify the maximum leasable floor area for shop (other than restricted retail premises).

34.01-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Accommodation (other than Community care accommodation, Corrective institution, Rooming house and Small second dwelling)	Any frontage at ground floor level must not exceed 2 metres (other than a bed and breakfast and caretaker's house).
Art and craft centre	
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Child care centre	Any frontage at ground floor level must not exceed 2 metres and access must not be shared with a dwelling (other than a caretaker's house).
Cinema	
Cinema based entertainment facility	
Community care accommodation	Any frontage at ground floor level must not exceed 2 metres. Must meet the requirements of Clause 52.22-2.
Education centre (other than Child care centre)	
Exhibition centre	
Home based business	
Informal outdoor recreation	

Use	Condition
Office	The leasable floor area for all offices must not exceed any amount specified in the schedule to this zone.
Place of worship	The gross floor area of all buildings must not exceed 250 square metres.
Railway	
Retail premises (other than Shop)	
Rooming house	Any frontage at ground floor level must not exceed 2 metres. Must meet the requirements of Clause 52.23-2.
Shop (other than Adult sex product shop)	The leasable floor area for all shops must not exceed any amount specified in the schedule to this zone.
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Adult sex product shop	Must be at least 200 metres (measured by the shortest route reasonably accessible on foot) from a residential zone or, land used for a hospital, primary school or secondary school or land in a Public Acquisition Overlay to be acquired for a hospital, primary school or secondary school.
Agriculture (other than Animal production and Apiculture)	
Container deposit scheme centre	
Grazing animal production	
Industry (other than Automated collection point and Container deposit scheme centre)	Must not be a purpose listed in the table to Clause 53.10.
Leisure and recreation facility (other than Informal outdoor recreation, Major sports and recreation facility and Motor racing track)	
Place of assembly (other than Carnival, Cinema, Cinema based entertainment facility, Circus, Exhibition centre and Place of worship)	
Utility installation (other than Minor utility installation and Telecommunications facility)	Must not be a purpose listed in the table to Clause 53.10.
Warehouse	Must not be a purpose listed in the table to Clause 53.10.

Use	Condition
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Animal production (other than Grazing animal production)
Corrective institution
Major sports and recreation facility
Motor racing track
Small second dwelling

34.01-2 Use of land

15/07/2013
VC100

A use must not detrimentally affect the amenity of the neighbourhood, including through the:

- Transport of materials, goods or commodities to or from the land.
- Appearance of any building, works or materials.
- Emission of noise, artificial light, vibration, smell, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.

34.01-3 Subdivision

31/07/2018
VC148

A permit is required to subdivide land.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if:	Clause 59.02

Class of application	Information requirements and decision guidelines
▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	

34.01-4 Buildings and works

01/12/2023
VC217

A permit is required to construct a building or construct or carry out works.

This does not apply to:

- The installation of an automatic teller machine.
- An alteration to an existing building façade provided:
  - The alteration does not include the installation of an external roller shutter.
  - At least 80 per cent of the building facade at ground floor level is maintained as an entry or window with clear glazing.
- An awning that projects over a road if it is authorised by the relevant public land manager.

An apartment development must meet the requirements of Clause 58.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $500,000 where the land is not: ▪ Within 30 metres of land (not a road) which is in a residential zone. ▪ Used for a purpose listed in the table to Clause 53.10. ▪ Used for an Adult sex product shop.	Clause 59.04

Transitional provisions

Clause 58 does not apply to:

- An application for a planning permit lodged before the approval date of Amendment VC136.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before the approval date of Amendment VC136.

Maintenance

All buildings and works must be maintained in good order and appearance to the satisfaction of the responsible authority.

34.01-5 Site description and design response

08/09/2025
VC282

An application for any of the following must be accompanied by a site description and a design response as described in Clause 54.01, 55.01 or 57.01, as appropriate:

- Construction or extension of one dwelling on a lot of less than 300 square metres.
- Construction of a dwelling if there is at least one dwelling existing on the lot.
- Construction of two or more dwellings on a lot.
- Extension of a dwelling if there are two or more dwellings on the lot.
- Construction or extension of a dwelling on common property.
- Construction or extension of a residential building.

Clause 34.01-5 does not apply to an apartment development.

34.01-6 Application requirements

14/01/2025
VC237

Use

An application to use land must be accompanied by the following information, as appropriate:

- The purpose of the use and the types of activities which will be carried out.
- The likely effects, if any, on adjoining land, including noise levels, traffic, the hours of delivery and despatch of goods and materials, hours of operation and light spill, solar access and glare.
- The means of maintaining land not required for immediate use.
- If an industry or warehouse:
  - The type and quantity of goods to be stored, processed or produced.
  - Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority.
  - Whether a notification under the Occupational Health and Safety Regulations 2017 is required, a licence under the *Dangerous Goods Act 1985* is required, or a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022 is exceeded.
  - The likely effects on adjoining land, including air-borne emissions and emissions to land and water.

Buildings and works

An application to construct a building or construct or carry out works must be accompanied by the following information, as appropriate:

- A plan drawn to scale which shows:
  - The boundaries and dimensions of the site.
  - Adjoining roads.
  - The location, height and purpose of buildings and works on adjoining land.
  - Relevant ground levels.
  - The layout of existing and proposed buildings and works.
  - All driveway, car parking and loading areas.
  - Proposed landscape areas.
  - All external storage and waste treatment areas.
  - Areas not required for immediate use.

- Elevation drawings to scale showing the colour and materials of all buildings and works.
- Construction details of all drainage works, driveways, vehicle parking and loading areas.
- A landscape layout which includes the description of vegetation to be planted, the surfaces to be constructed, site works specification and method of preparing, draining, watering and maintaining the landscape area.

An application to construct or extend an apartment development, or to construct or extend a dwelling in or forming part of an apartment development, must be accompanied by an urban context report and design response as required in Clause 58.01.

34.01-7 Exemption from notice and review

31/07/2018
VC148

An application to subdivide land or construct a building or construct or carry out works is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to land within 30 metres of land (not a road) which is in a residential zone, land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a hospital or an education centre.

34.01-8 Decision guidelines

08/09/2025
VC282

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General

- The Municipal Planning Strategy and the Planning Policy Framework.
- The interface with adjoining zones, especially the relationship with residential areas.

Use

- The effect that existing uses may have on the proposed use.
- The drainage of the land.
- The availability of and connection to services.
- The effect of traffic to be generated on roads.
- The interim use of those parts of the land not required for the proposed use.

Subdivision

- Provision for vehicles providing for supplies, waste removal and emergency services and public transport.
- The effect the subdivision will have on the potential of the area to accommodate the uses which will maintain or enhance its competitive strengths.

Building and works

- The movement of pedestrians and cyclists, and vehicles providing for supplies, waste removal, emergency services and public transport.
- The provision of car parking.
- The streetscape, including the conservation of buildings, the design of verandahs, access from the street front, protecting active frontages to pedestrian areas, the treatment of the fronts and backs of buildings and their appurtenances, illumination of buildings or their immediate spaces and the landscaping of land adjoining a road.
- The storage of rubbish and materials for recycling.

- Defining the responsibility for the maintenance of buildings, landscaping and paved areas.
- Consideration of the overlooking and overshadowing as a result of building or works affecting adjoining land in a General Residential Zone, Housing Choice and Transport Zone, Neighbourhood Residential Zone, Residential Growth Zone or Township Zone.
- The impact of overshadowing on existing rooftop solar energy systems on dwellings on adjoining lots in a General Residential Zone, Housing Choice and Transport Zone, Mixed Use Zone, Neighbourhood Residential Zone, Residential Growth Zone or Township Zone.
- The availability of and connection to services.
- The design of buildings to provide for solar access.
- The objectives, standards and decision guidelines of Clause 54, Clause 55 and Clause 57. This does not apply to an apartment development.
- For an apartment development, the objectives, standards and decision guidelines of Clause 58.

Transitional provisions

The objectives, standards and decision guidelines of Clause 55 of this scheme, as in force immediately before the approval date of Amendment VC136, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clauses 55 and 58 of this scheme, as in force immediately before the approval date of Amendment VC174, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 55 of this planning scheme, as in force immediately before the approval date of Amendment VC267, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 54 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

34.01-9 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 1.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 34.01 COMMERCIAL 1 ZONE

1.0 Maximum leasable floor area requirements

08/07/2021
C211brim

Land	Maximum leasable floor area for Office (square metres)	Maximum leasable floor area for Shop (other than Restricted retail premises) (square metres)
None specified	None specified	None specified

34.02 COMMERCIAL 2 ZONE

31/07/2018
VC148

Shown on the planning scheme map as **B3Z**, **B4Z** or **C2Z**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To encourage commercial areas for offices, appropriate manufacturing and industries, bulky goods retailing, other retail uses, and associated business and commercial services.

To ensure that uses do not affect the safety and amenity of adjacent, more sensitive uses.

34.02-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Art and craft centre	
Art gallery	
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Cinema	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Cinema based entertainment facility	The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Food and drink premises	The leasable floor area must not exceed 100 square metres.
Industry (other than Materials recycling and Transfer station)	Must not be a purpose listed in the table to Clause 53.10 with no threshold specified. The land must be at least the following distances from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution: ▪ The threshold distance, for a purpose listed in the table to Clause 53.10. ▪ 30 metres, for a purpose not listed in the table to Clause 53.10. Must not: ▪ Exceed a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022. ▪ Require a notification under the Occupational Health and Safety Regulations 2017. ▪ Require a licence under the Dangerous Goods (Explosives) Regulations 2011. ▪ Require a licence under the Dangerous Goods (HCDG) Regulations 2016.
Informal outdoor recreation	

Use	Condition
Mail centre	
Museum	
Office	
Postal agency	
Railway	
Restricted retail premises	
Shop (other than Adult sex product shop, Restricted retail premises and Supermarket)	Must adjoin, or be on the same land as, a supermarket when the use commences. The combined leasable floor area for all shops adjoining or on the same land as the supermarket must not exceed 500 square metres. The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Supermarket	The leasable floor area must not exceed 1800 square metres. The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3. Must be on land within the City of Greater Geelong or within an urban growth boundary in metropolitan Melbourne.
Trade supplies	
Tramway	
Warehouse (other than Mail centre)	Must not be a purpose listed in the table to Clause 53.10 with no threshold distance specified. The land must be at least the following distances from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or corrective institution: ▪ The threshold distance, for a purpose listed in the table to Clause 53.10. ▪ 30 metres, for a purpose not listed in the table to Clause 53.10. Must not: ▪ Exceed a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022. ▪ Require a notification under the Occupational Health and Safety Regulations 2017. ▪ Require a licence under the Dangerous Goods (Explosives) Regulations 2011. ▪ Require a licence under the Dangerous Goods (HCDG) Regulations 2016.

Use	Condition
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Adult sex product shop	Must be at least 200 metres (measured by the shortest route reasonably accessible on foot) from a residential zone, land used for a hospital, primary school or secondary school or land in a Public Acquisition Overlay to be acquired for a hospital, primary school or secondary school.
Agriculture (other than Animal production and Apiculture)	
Caretaker's house	
Container deposit scheme centre	
Education centre	
Grazing animal production	
Leisure and recreation (other than Informal outdoor recreation, Major sports and recreation facility and Motor racing track)	
Materials recycling	
Place of assembly (other than Art gallery, Carnival, Cinema, Cinema based entertainment facility, Circus and Museum)	
Residential hotel	
Retail premises (other than Food and drink premises, Postal agency, Restricted retail premises, Supermarket and Trade supplies)	
Supermarket – if the Section 1 conditions are not met	The leasable floor area must not exceed 1800 square metres unless on land within the City of Greater Geelong or within an urban growth boundary in metropolitan Melbourne. The site must adjoin, or have access to, a road in a Transport Zone 2 or a Transport Zone 3.
Transfer station (other than Automated collection point and Container deposit scheme centre)	The land must be at least 30 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution.

Use	Condition
Utility installation (other than Minor utility installation and Telecommunications facility)	
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Accommodation (other than Caretaker's house and Residential hotel)
Animal production (other than Grazing animal production)
Hospital
Major sports and recreation facility
Motor racing track

34.02-2 Use of land

15/07/2013
VC100

A use must not detrimentally affect the amenity of the neighbourhood, including through the:

- Transport of materials, goods or commodities to or from the land.
- Appearance of any building, works or materials.
- Emission of noise, artificial light, vibration, smell, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.

34.02-3 Subdivision

31/07/2018
VC148

A permit is required to subdivide land.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02

Class of application	Information requirements and decision guidelines
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

34.02-4 Buildings and works

01/12/2023
VC217

A permit is required to construct a building or construct or carry out works.

This does not apply to:

- The installation of an automatic teller machine.
- An alteration to an existing building façade provided:
  - The alteration does not include the installation of an external roller shutter.
  - At least 80 per cent of the building facade at ground floor level is maintained as an entry or window with clear glazing.
- An awning that projects over a road if it is authorised by the relevant public land manager.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $500,000 where the land is not: ▪ Within 30 metres of land (not a road) which is in a residential zone. ▪ Used for a purpose listed in the table to Clause 53.10. ▪ Used for an Adult sex product shop.	Clause 59.04

Maintenance

All buildings and works must be maintained in good order and appearance to the satisfaction of the responsible authority.

34.02-5 Application requirements

14/01/2025
VC237

Use

An application to use land must be accompanied by the following information, as appropriate:

- The purpose of the use and the types of activities which will be carried out.

- The likely effects, if any, on adjoining land, including noise levels, traffic, the hours of delivery and despatch of goods or materials, hours of operation and light spill, solar access and glare.
- The means of maintaining areas not required for immediate use.
- If an industry or warehouse:
  - The type and quantity of goods to be stored, processed or produced.
  - Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority.
  - Whether a notification under the Occupational Health and Safety Regulations 2017 is required, a licence under the *Dangerous Goods Act 1985* is required, or a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022 is exceeded.
  - The likely effects on adjoining land, including air-borne emissions and emissions to land and water.

Building and works

An application to construct a building or construct or carry out works must be accompanied by the following information, as appropriate:

- A plan drawn to scale which shows:
  - The boundaries and dimensions of the site.
  - Adjoining roads.
  - The location, height and purpose of buildings and works on adjoining land.
  - Relevant ground levels.
  - The layout of existing and proposed buildings and works.
  - All driveway, car parking and loading areas.
  - Proposed landscape areas.
  - All external storage and waste treatment areas.
  - Areas not required for immediate use.
- Elevation drawings to scale showing the colour and materials of all buildings and works.
- Construction details of all drainage works, driveways, vehicle parking and loading areas.
- A landscape layout which includes the description of vegetation to be planted, the surfaces to be constructed, site works specification and method of preparing, draining, watering and maintaining the landscape area.

34.02-6 Exemption from notice and review

31/07/2018
VC148

An application to subdivide land or construct a building or construct or carry out works is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to land within 30 metres of land (not a road) which is in a residential zone, land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a hospital or an education centre.

34.02-7 Decision guidelines

31/07/2018
VC148

General

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The interface with adjoining zones, especially the relationship with residential areas.

Use

- The effect that existing uses may have on the proposed use.
- The drainage of the land.
- The availability of and connection to services.
- The effect of traffic to be generated on roads.
- The interim use of those parts of the land not required for the proposed use.
- If an industry or warehouse, the effect that the use may have on nearby existing or proposed residential areas or other uses which are sensitive to industrial off-site effects, having regard to any comments or directions of the referral authorities.

Subdivision

- The effect the subdivision will have on the potential of the area to accommodate the uses which will maintain or enhance its competitive strengths.
- Any natural or cultural values on or near the land.
- Streetscape character.
- Landscape treatment.

Building and works

- The movement of pedestrians and cyclists, and vehicles providing for supplies, waste removal, emergency services and public transport.
- The provision of car parking.
- The streetscape, including the conservation of buildings, the design of verandahs, access from the street front, protecting active frontages to pedestrian areas, the treatment of the fronts and backs of buildings and their appurtenances, illumination of buildings or their immediate spaces and landscaping of land adjoining a road.
- Defining the responsibility for the maintenance of buildings, landscaping and paved areas.
- The availability of and connection to services.
- Any natural or cultural values on or nearby the land.
- Outdoor storage, lighting, and stormwater discharge.
- The design of buildings to provide for solar access.

34.02-8 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 1.

35 RURAL ZONES

19/01/2006
VC37

35.04 GREEN WEDGE ZONE

31/07/2018
VC148

Shown on the planning scheme map as **GWZ** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide for the use of land for agriculture.

To recognise, protect and conserve green wedge land for its agricultural, environmental, historic, landscape, recreational and tourism opportunities, and mineral and stone resources.

To encourage use and development that is consistent with sustainable land management practices.

To encourage sustainable farming activities and provide opportunity for a variety of productive agricultural uses.

To protect, conserve and enhance the cultural heritage significance and the character of open rural and scenic non-urban landscapes.

To protect and enhance the biodiversity of the area.

35.04-1 Table of uses

15/08/2025
VC290

Section 1 - Permit not required

Use	Condition
Abattoir	Must be used in conjunction with Animal production on the same land or contiguous land in the same ownership. Must not have a gross floor area more than 200 square metres. Must not slaughter or process animals, including birds, at a designed throughput of greater than 120 tonnes of product per year. Must not exceed a wastewater design or actual flow rate of greater than 5,000 litres per day. Must not be within 100 metres of a dwelling in separate ownership. The land must be at least 100 metres from land (not a road) which is in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone, Rural Living Zone, land used for a hospital, an education centre or a corrective institution or land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution. Must not be a purpose listed in the table to Clause 53.10 with no threshold distance.
Agriculture (other than Animal production, Apiculture, Domestic animal husbandry, Racing dog husbandry, Rice growing and Timber production)	
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Bed and breakfast	No more than 10 persons may be accommodated away from their normal place of residence.

Use	Condition
	At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence. Must be located more than 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.
Domestic animal husbandry (other than Domestic animal boarding)	Must be no more than 5 animals.
Grazing animal production	
Home based business	
Informal outdoor recreation	
Poultry farm	Must be no more than 100 poultry (not including emus or ostriches). Must be no more than 10 emus and ostriches.
Primary produce sales	Must not be within 100 metres of a dwelling in separate ownership. The area used for the display and sale of primary produce must not exceed 50 square metres.
Racing dog husbandry	Must be no more than 5 animals.
Railway	
Rural store	Must be used in conjunction with Agriculture. Must be in a building, not a dwelling and have a gross floor area of less than 100 square metres. Must be the only Rural store on the lot.
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Animal production (other than Cattle feedlot, Grazing animal production and Poultry farm)	
Broiler farm - if the Section 1 condition to Poultry farm is not met	Must meet the requirements of Clause 53.09.
Camping and caravan park	
Car park	Must be used in conjunction with another use in Section 1 or 2.
Cattle feedlot	Must meet the requirements of Clause 53.08. The site must be located outside a catchment area listed in Appendix 2 of the Victorian Code for Cattle Feedlots – August 1995.

Use	Condition
Domestic animal boarding	
Dwelling (other than Bed and breakfast)	Must be the only dwelling on the lot. This does not apply to the replacement of an existing dwelling if the existing dwelling is removed or altered (so it can no longer be used as a dwelling) within one month of the occupation of the replacement dwelling. Must meet the requirements of Clause 35.04-2.
Exhibition centre	
Freezing and cool storage	The goods stored must be agricultural produce, or products used in agriculture.
Function centre	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. The number of patrons present at any time must not exceed the number specified in a schedule to the zone or 150 patrons, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 hectares.
Group accommodation	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry, or Winery. The number of dwellings must not exceed the number specified in a schedule to the zone or 40 dwellings, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 hectares.
Hall	
Host farm	
Indoor recreation facility	Must be for equestrian based leisure, recreation or sport.
Leisure and recreation (other than Indoor recreation facility, Informal outdoor recreation, Major sports and recreation facility and Motor racing track)	
Major sports and recreation facility	Must be for outdoor leisure, recreation or sport.
Manufacturing sales	Must be an incidental part of Rural industry.
Market	
Materials recycling	Must be used in conjunction with Refuse disposal or Transfer station. Must not include the collecting, dismantling, storing, recycling or selling of used or scrap construction and demolition materials.
Milk depot	

Use	Condition
Place of assembly (other than Carnival, Cinema based entertainment facility, Circus, Exhibition centre, Function centre, Hall, Nightclub and Place of worship)	Must not be used for more than 10 days in a calendar year.
Place of worship	
Plant nursery	
Primary school	
Racing dog husbandry – if the Section 1 condition is not met	Must meet the requirements of Clause 53.12.
Refuse disposal	
Research and development centre	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 hectares.
Research centre	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 hectares.
Residential building (other than Residential hotel)	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. Must be used to provide accommodation for persons away from their normal place of residence. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 hectares.
Residential hotel	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. The number of bedrooms must not exceed the number specified in a schedule to the zone or 80 bedrooms, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 hectares.
Restaurant	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. The number of patrons present must not exceed the number specified in a schedule to the zone or 150 patrons, whichever is the lesser.

Use	Condition
	If used in conjunction with Function centre, the total number of patrons present at any time must not exceed the number specified in a schedule to the zone or 150 patrons, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 hectares.
Restricted place of assembly	Must not be used for more than 30 days in a calendar year.
Rice growing	
Rural industry (other than Abattoir)	
Secondary school	
Solid fuel depot	
Small second dwelling	Must be no more than one dwelling existing on the lot. Must be the only small second dwelling on the lot. Reticulated natural gas must not be supplied to the building, or part of a building, used for the small second dwelling. Must meet the requirements of Clause 35.04-2.
Timber production	Must meet the requirements of Clause 53.11.
Transfer station (other than Automated collection point)	Must not include the collecting, storing or processing of used or scrap construction and demolition materials.
Utility installation (other than Minor utility installation and Telecommunications facility)	
Vehicle store	
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Accommodation (other than Camping and caravan park, Group accommodation, Host farm, Residential building and Small second dwelling)
Cinema based entertainment facility
Display home centre
Education centre (other than Primary school and Secondary school)
Freeway service centre
Funeral parlour
Hospital

Use
Industry (other than Materials recycling, Refuse disposal, Transfer station, Research and development centre and Rural industry)
Motor racing track
Office
Nightclub
Retail premises (other than Manufacturing sales, Market, Plant nursery, Primary produce sales and Restaurant)
Service station
Warehouse (other than Freezing and cool storage, Milk depot, Rural store, Solid fuel depot and Vehicle store)

35.04-2 Use of land for a dwelling or small second dwelling

14/12/2023
VC253

A lot used for a dwelling or small second dwelling must meet the following requirements:

- Access to the dwelling or small second dwelling must be provided via an all-weather road with dimensions adequate to accommodate emergency vehicles.
- The dwelling or small second dwelling must be connected to reticulated sewerage, if available. If reticulated sewerage is not available, all wastewater from the dwelling must be treated and retained within the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017* for an on-site wastewater management system.
- The dwelling or small second dwelling must be connected to a reticulated potable water supply or have an alternative potable water supply with adequate storage for domestic use as well as for fire fighting purposes.
- The dwelling or small second dwelling must be connected to a reticulated electricity supply or have an alternative energy source.

35.04-3 Subdivision

14/12/2023
VC253

A permit is required to subdivide land.

Each lot must be at least the area specified for the land in a schedule to this zone. If no area is specified, each lot must be at least 40 hectares.

A permit may be granted to create smaller lots if any of the following apply:

- The subdivision is the re-subdivision of existing lots, the number of lots is not increased, and the number of dwellings that the land could be used for does not increase.
- The subdivision is by a public authority or utility service provider to create a lot for a utility installation.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ Each new lot is at least the area specified for the land in the zone or the schedule to the zone. ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into 2 lots where each new lot is at least the area specified for the land in the zone or the schedule to the zone.	Clause 59.12

35.04-4 Long term lease or licence for accommodation

05/09/2013
VC103

A permit is required to lease or license a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation.

Each portion of a lot leased or licensed for the purpose of Accommodation must be at least the minimum subdivision area specified for the land in a schedule to this zone. If no area is specified, each portion of a lot leased or licensed for the purpose of Accommodation must be at least 40 hectares.

35.04-5 Buildings and works

14/12/2023
VC253

A permit is required to construct or carry out any of the following:

- A building or works associated with a use in Section 2 of Clause 35.04-1. This does not apply to:
  - An alteration or extension to an existing dwelling with a floor area of no more than the area specified in a schedule to this zone or, if no area is specified, 50 square metres.
  - An alteration or extension to a small second dwelling.
  - An alteration or extension to an existing building used for agriculture with a floor area of no more than the area specified in a schedule to this zone or, if no area is specified, 100 square metres. The building must not be used to keep, board, breed or train animals.
  - A rainwater tank.
- Earthworks specified in a schedule to this zone, if on land specified in a schedule.
- A building which is within any of the following setbacks:
  - 100 metres from a Transport Zone 2 or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority and the purpose of the acquisition is for a road.
  - 40 metres from a Transport Zone 3 or land in a Public Acquisition Overlay for a road if the Head, Transport for Victoria is not the acquiring authority.
  - 20 metres from any other road.
  - 5 metres from any other boundary.
  - 100 metres from a dwelling or small second dwelling not in the same ownership.
  - 100 metres from a waterway, wetlands or designated flood plain.
- Permanent or fixed feeding infrastructure for season or supplementary feeding for grazing animal production constructed within 100 metres of:

  - A waterway, wetland or designated flood plain.
  - A dwelling not in the same ownership.
  - A residential or urban growth zone.
- A building or works associated with accommodation located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $250,000 where: ▪ The land is not used for Domestic animal husbandry, Intensive animal production, Pig farm, Poultry farm, Poultry hatchery, Racing dog husbandry or Rural industry. ▪ The land is not within 30 metres of land (not a road) which is in a residential zone. ▪ The building or works are not associated with accommodation located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*. Any works must not be earthworks specified in the schedule to the zone.	Clause 59.13

35.04-6 Decision guidelines

22/03/2022
VC219

Before deciding on an application to use or subdivide land, lease or license a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation, construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General issues

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any Regional Catchment Strategy and associated plan applying to the land.
- The capability of the land to accommodate the proposed use or development.
- How the use or development relates to rural land use, rural diversification, natural resource management, natural or cultural heritage management, recreation or tourism.
- Whether the site is suitable for the use or development and the compatibility of the proposal with adjoining land uses.
- Whether the use or development is essential to the health, safety or well-being of the State or area but is not appropriate to locate in an urban area because of the effect it may have on existing or proposed urban areas or the effect that existing or proposed urban areas may have on the proposed use or development.

- The need to minimise adverse impacts on the character and appearance of the area or features of architectural, scientific or cultural heritage significance, or of natural scenic beauty.
- The potential for accommodation to be adversely affected by vehicular traffic, noise, blasting, dust and vibration from an existing or proposed extractive industry operation if it is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990.*

Rural issues

- The maintenance of agricultural production and the impact on the rural economy.
- The environmental capacity of the site to sustain the rural enterprise.
- The need to prepare an integrated land management plan.
- The impact on the existing and proposed rural infrastructure.
- The potential for the future expansion of the use or development and the impact of this on adjoining and nearby agriculture and other land uses.
- The protection and retention of land for future sustainable agricultural activities.

Environmental issues

- The impact of the use or development on the flora and fauna on the site and its surrounds.
- The need to protect and enhance the biodiversity of the area, including the retention of vegetation and faunal habitat and the need to revegetate land including riparian buffers along waterways, gullies, ridgelines, property boundaries and saline discharge and recharge area.
- How the use or development relates to sustainable land management and the need to prepare an integrated land management plan.
- The location of on site effluent disposal areas to minimise impact of nutrient loads on waterways and native vegetation.

Design and siting issues

- The need to minimise any adverse impacts of siting, design, height, bulk, and colours and materials to be used, on landscape features, major roads and vistas.
- The location and design of existing and proposed infrastructure services which minimises the visual impact on the landscape.
- The need to minimise adverse impacts on the character and appearance of the area or features of archaeological, historic or scientific significance or of natural scenic beauty or importance.
- The need to locate and design buildings used for accommodation to avoid or reduce the impact from vehicular traffic, noise, blasting, dust and vibration from an existing or proposed extractive industry operation if it is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

Primary school or secondary school issues

- Access being provided via an all-weather road with dimensions adequate to accommodate emergency vehicles and not rely on local residential streets for access.
- Access by public transport, or if public transport is not available or adequate, transport may be provided by the school. Where transport is provided by the school the parking of buses should be accommodated on site.

- Connection to reticulated sewerage if available or if not available, the wastewater must be treated and retained on-site in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017* for an on-site wastewater management system.
- In the absence of reticulated sewerage, a Land Capability Assessment on the risks to human health and the environment of an on-site wastewater management system constructed, installed or altered on the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017*.
- Connection to a reticulated potable water supply or an alternative potable water supply with adequate storage for school use as well as for fire fighting purposes.
- Connection to a reticulated electricity supply or an alternative energy source.

35.04-7 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 3.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 35.04 GREEN WEDGE ZONE

Shown on the planning scheme map as **GWZ.**

1.0 Subdivision and other requirements

08/07/2021
C211brim

	Land	Area/Dimensions/Number
Minimum subdivision area (hectares)	Land generally bounded by the Calder Freeway and the Maribyrnong River	40 ha
	Land bounded by the Sydenham railway line, the Calder Freeway and the Calder Park Thunderdome	40 ha
	Land located at the north west corner of the proposed Kings Road extension interchange generally between the Calder Freeway and Jacksons Creek, Keilor shown on Plan Number PS429241L	20 ha
Function centre (number of patrons)	None specified	None specified
Group accommodation (number of dwellings)	None specified	None specified
Residential hotel (number of bedrooms)	None specified	None specified
Restaurant (number of patrons)	None specified	None specified
Minimum area for which no permit is required to alter or extend an existing dwelling (square metres)	None specified	None specified
Minimum area for which no permit is required to alter or extend an existing building used for agriculture (square metres).	None specified	None specified

Permit requirement for earthworks	Land
Earthworks which change the rate of flow or the discharge point of water across a property boundary	None specified
Earthworks which increase the discharge of saline groundwater	None specified

35.05 GREEN WEDGE A ZONE

31/07/2018
VC148

Shown on the planning scheme map as **GWAZ** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide for the use of land for agriculture.

To protect, conserve and enhance the biodiversity, natural resources, scenic landscapes and heritage values of the area.

To ensure that use and development promotes sustainable land management practices and infrastructure provision.

To protect, conserve and enhance the cultural heritage significance and the character of rural and scenic non-urban landscapes.

To recognise and protect the amenity of existing rural living areas.

35.05-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Agriculture (other than Animal production, Apiculture, Domestic animal husbandry, Racing dog husbandry, Rice growing and Timber production)	
Bed and breakfast	No more than 10 persons may be accommodated away from their normal place of residence. At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence. Must be located more than 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.
Domestic animal husbandry (other than Domestic animal boarding)	Must be no more than 2 animals.
Home based business	
Informal outdoor recreation	
Poultry farm	Must be no more than 100 poultry (not including emus or ostriches). Must be no more than 10 emus and ostriches.
Primary produce sales	Must not be within 100 metres of a dwelling in separate ownership. The area used for the display and sale of primary produce must not exceed 50 square metres.
Racing dog husbandry	Must be no more than 2 animals.

Use	Condition
Railway	
Rural store	Must be used in conjunction with Agriculture. Must be in a building, not a dwelling and have a gross floor area of less than 100 square metres. Must be the only Rural store on the lot.
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Animal production (other than Intensive animal production and Poultry farm)	
Broiler farm - if the Section 1 condition to Poultry farm is not met	Must be no more than 10,000 chickens.
Camping and caravan park	
Car park	Must be used in conjunction with another use in Section 1 or 2.
Domestic animal boarding	
Dwelling (other than Bed and breakfast)	Must be the only dwelling on the lot. This does not apply to the replacement of an existing dwelling if the existing dwelling is removed or altered (so it can no longer be used as a dwelling) within one month of the occupation of the replacement dwelling. Must meet the requirements of Clause 35.05-2.
Exhibition centre	
Freezing and cool storage	The goods stored must be agricultural produce, or products used in agriculture. Must be in a building, not a dwelling, and used to store equipment, goods, or motor vehicles used in conjunction with the occupation of a resident of a dwelling on the lot.
Function centre	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. The number of patrons present at any time must not exceed the number specified in a schedule to the zone or 150 patrons, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 8 hectares.

Use	Condition
Group accommodation	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry, or Winery. The number of dwellings must not exceed the number specified in a schedule to the zone or 40 dwellings, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 8 hectares.
Hall	
Host farm	
Indoor recreation facility	Must be for equestrian based leisure, recreation or sport.
Leisure and recreation (other than Informal outdoor recreation, Indoor recreation facility, Major sports and recreation facility and Motor racing track)	
Major sports and recreation facility	Must be for outdoor leisure, recreation or sport.
Market	
Place of worship	
Plant nursery	
Primary school	
Racing dog husbandry - if the Section 1 condition is not met	Must meet the requirements of Clause 53.12.
Research centre	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 8 hectares.
Residential building (other than Residential hotel)	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. Must be used to provide accommodation for persons away from their normal place of residence. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 8 hectares.
Restaurant	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. The number of patrons present must not exceed the number specified in a schedule to the zone or 150 patrons, whichever is the lesser.

Use	Condition
	If used in conjunction with Function centre, the total number of patrons present at any time must not exceed the number specified in a schedule to the zone or 150 patrons, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 8 hectares.
Restricted place of assembly	Must not be used for more than 30 days in a calendar year.
Rural industry (other than Abattoir and Sawmill)	
Rice growing	
Rural store – if the Section 1 condition is not met	Must be in a building, not a dwelling, and used to store equipment, goods, or motor vehicles used in conjunction with the occupation of a resident of a dwelling on the lot.
Secondary school	
Small second dwelling	Must be no more than one dwelling existing on the lot. Must be the only small second dwelling on the lot. Reticulated natural gas must not be supplied to the building, or part of a building, used for the small second dwelling. Must meet the requirements of Clause 35.05-2.
Timber production	Must meet the requirements of Clause 53.11.
Utility installation (other than Minor utility installation and Telecommunications facility)	
Vehicle store	Must be in a building not a dwelling and used to store motor vehicles used in conjunction with the occupation of a resident of a dwelling on the lot.
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Abattoir
Accommodation (other than Camping and caravan park, Dwelling, Group accommodation, Host farm, Residential building and Small second dwelling)
Display home centre
Education centre (other than Primary school and Secondary school)
Freeway service centre
Funeral parlour

Use
Hospital
Industry (other than Rural industry)
Intensive animal production
Motor racing track
Office
Place of assembly (other than Carnival, Circus, Exhibition centre, Function centre, Hall, Place of worship and Restricted place of assembly)
Retail premises (other than Market, Plant nursery, Primary produce sales and Restaurant)
Saleyard
Sawmill
Service station
Transport terminal
Warehouse (other than Freezing and cool storage, Rural store and Vehicle store)

35.05-2 Use of land for a dwelling or small second dwelling

14/12/2023
VC253

A lot used for a dwelling or small second dwelling must meet the following requirements:

- Access to the dwelling or small second dwelling must be provided via an all-weather road with dimensions adequate to accommodate emergency vehicles.
- The dwelling or small second dwelling must be connected to reticulated sewerage, if available. If not available, all wastewater must be treated and retained within the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017* for the construction, installation or alteration of an on-site wastewater management system.
- The dwelling or small second dwelling must be connected to a reticulated potable water supply or have an alternative potable water supply with adequate storage for domestic use as well as for fire fighting purposes.
- The dwelling or small second dwelling must be connected to a reticulated electricity supply or have an alternative energy source.

35.05-3 Subdivision

14/12/2023
VC253

A permit is required to subdivide land.

Each lot must be at least the area specified for the land in a schedule to this zone. If no area is specified, each lot must be at least 8 hectares.

A permit may be granted to create smaller lots if any of the following apply:

- The subdivision is the re-subdivision of existing lots, the number of lots is not increased, and the number of dwellings that the land could be used for does not increase.
- The subdivision is by a public authority or utility service provider to create a lot for a utility installation.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ Each new lot is at least the area specified for the land in the zone or the schedule to the zone. ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into 2 lots where each new lot is at least the area specified for the land in the zone or the schedule to the zone.	Clause 59.12

35.05-4 Long term lease or licence for accommodation

05/09/2013
VC103

A permit is required to lease or license a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation.

Each portion of a lot leased or licensed for the purpose of Accommodation must be at least the minimum subdivision area specified for the land in a schedule to this zone. If no area is specified, each portion of a lot leased or licensed for the purpose of Accommodation must be at least 8 hectares.

35.05-5 Buildings and works

14/12/2023
VC253

A permit is required to construct or carry out any of the following:

- A building or works associated with a use in Section 2 of Clause 35.05-1. This does not apply to:
  - An alteration or extension to an existing dwelling with a floor area of no more than the area specified in a schedule to this zone or, if no area is specified, 50 square metres.
  - An alteration or extension to a small second dwelling.
  - A rainwater tank.
- Earthworks specified in a schedule to this zone, if on land specified in a schedule.
- A building which is within any of the following setbacks:
  - 30 metres from a Transport Zone 2 or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority and the purpose of the acquisition is for a road.
  - 20 metres from a Transport Zone 3 or land in a Public Acquisition Overlay for a road if the Head, Transport for Victoria is not the acquiring authority.
  - 10 metres from any other road.

- 5 metres from any other boundary.
- 30 metres from a dwelling or small second dwelling not in the same ownership.
- 100 metres from a waterway, wetlands or designated flood plain.

- A building or works associated with accommodation located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $250,000 where: ▪ The land is not used for Domestic animal husbandry, Pig farm, Poultry farm, Poultry hatchery, Racing dog husbandry or Rural industry. ▪ The land is not within 30 metres of land (not a road) which is in a residential zone. ▪ The building or works are not associated with accommodation located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*. Any works must not be earthworks specified in the schedule to the zone.	Clause 59.13

35.05-6 Decision guidelines

14/12/2023
VC253

Before deciding on an application to use or subdivide land, lease or license a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation, construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General issues

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any Regional Catchment Strategy and associated plan applying to the land.
- The capability of the land to accommodate the proposed use or development, addressing site quality attributes including soil type, soil fertility, soil structure, soil permeability, aspect, contour and drainage patterns.
- How the use or development relates to agricultural land use, rural diversification and natural resource management.
- Whether the site is suitable for the use or development and whether the proposal will have an adverse impact on surrounding land uses.
- The need to protect the amenity of existing residents.

- The need to minimise adverse impacts on the character and appearance of the area or features of architectural, scientific or cultural heritage significance, or of natural scenic beauty or importance.
- The potential for accommodation to be adversely affected by vehicular traffic, noise, blasting, dust and vibration from an existing or proposed extractive industry operation if it is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990.*

Rural issues

- The maintenance of agricultural production and the impact on the local rural economy.
- The need to prepare an integrated land management plan.
- The impact on the existing and proposed rural infrastructure.
- The potential for the future expansion of the use or development and the impact of this on adjoining and nearby agricultural and other land uses.
- Protection and retention of land for future sustainable agricultural activities.

Environmental issues

- The impact of the use or development on the flora and fauna on the site and its surrounds.
- An assessment of the likely environmental impact on the natural physical features and resources of the area and in particular any impact caused by the proposal on soil and water quality and by the emission of effluent, noise, dust and odours.
- The need to protect and enhance the biodiversity of the area, including the retention of vegetation and fauna habitat and the revegetation of land including riparian buffers along waterways, gullies, ridge lines, property boundaries and saline recharge and discharge areas.
- How the use or development relates to sustainable land management and the need to prepare a sustainable land management plan.
- The location of on site effluent disposal areas to minimise impact of nutrient loads on waterways and native vegetation.

Design and siting issues

- The need to minimise adverse impacts of the siting, design, height, bulk, colours and materials to be used on major roads, landscape features and vistas.
- The location and design of existing and proposed infrastructure services including gas, water, drainage, telecommunications and sewerage facilities which minimise the visual impact on the landscape.
- The location and design of existing and proposed roads and their impact on the landscape and whether the use or development will require traffic management programs.
- The need to locate and design buildings used for accommodation to avoid or reduce the impact from vehicular traffic, noise, blasting, dust and vibration from an existing or proposed extractive industry operation if it is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

Primary school or secondary school issues

- Access being provided via an all-weather road with dimensions adequate to accommodate emergency vehicles and not rely on local residential streets for access.

- Access by public transport, or if public transport is not available or adequate, transport may be provided by the school. Where transport is provided by the school the parking of buses should be accommodated on site.
- Connection to a reticulated sewerage system if available or if not available, the wastewater must be treated and retained on-site in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017* for an on-site waste water management system.
- In the absence of reticulated sewerage, a Land Capability Assessment on the risks to human health and the environment of an on-site wastewater management system constructed, installed or altered on the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017*.
- Connection to a reticulated potable water supply or an alternative potable water supply with adequate storage for school use as well as for fire fighting purposes.
- Connection to a reticulated electricity supply or an alternative energy source.

35.05-7 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 3.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 35.05 GREEN WEDGE A ZONE

Shown on the planning scheme map as **GWAZ.**

1.0 Subdivision and other requirements

08/07/2021
C211brim

	Land	Area/Dimensions/Number
Minimum subdivision area (hectares)	Land north of the Calder Freeway and west of Overnewton Road, North Keilor	8 ha
Function centre (number of patrons)	None specified	None specified
Group accommodation (number of dwellings)	None specified	None specified
Residential building (number of bedrooms)	None specified	None specified
Restaurant (number of patrons)	None specified	None specified
Minimum area for which no permit is required to alter or extend an existing dwelling (square metres)	None specified	None specified

Permit requirement for earthworks	Land
Earthworks which change the rate of flow or the discharge point of water across a property boundary	None specified
Earthworks which increase the discharge of saline groundwater	None specified

35.06 RURAL CONSERVATION ZONE

31/07/2018
VC148

Shown on the planning scheme map as **RCZ** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To conserve the values specified in a schedule to this zone.

To protect and enhance the natural environment and natural processes for their historic, archaeological and scientific interest, landscape, faunal habitat and cultural values.

To protect and enhance natural resources and the biodiversity of the area.

To encourage development and use of land which is consistent with sustainable land management and land capability practices, and which takes into account the conservation values and environmental sensitivity of the locality.

To provide for agricultural use consistent with the conservation of environmental and landscape values of the area.

To conserve and enhance the cultural significance and character of open rural and scenic non urban landscapes.

35.06-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Bed and breakfast	No more than 10 persons may be accommodated away from their normal place of residence. At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence. Must be located more than 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.
Domestic animal husbandry (other than Domestic animal boarding)	Must be no more than 2 animals.
Home based business	
Informal outdoor recreation	
Poultry farm	Must be no more than 100 poultry (not including emus or ostriches). Must be no more than 10 emus and ostriches.
Racing dog husbandry	Must be no more than 2 animals.
Railway	
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Agriculture (other than Apiculture, Domestic animal husbandry, Intensive animal production, Poultry farm, Racing dog husbandry, Rice growing and Timber production)	
Broiler farm - if the Section 1 condition to Poultry farm is not met	Must be no more than 10,000 chickens.
Car park	Must be used in conjunction with another use in Section 1 or 2.
Domestic animal boarding	
Dwelling (other than Bed and breakfast)	Must be the only dwelling on the lot. This does not apply to the replacement of an existing dwelling if the existing dwelling is removed or altered (so it can no longer be used as a dwelling) within one month of the occupation of the replacement dwelling. Must meet the requirements of Clause 35.06-2.
Emergency services facility	
Freezing and cool storage	
Group accommodation	
Host farm	
Landscape gardening supplies	
Market	
Primary produce sales	
Primary school	
Racing dog husbandry - if the Section 1 condition is not met	Must meet the requirements of Clause 53.12.
Recreational boat facility	
Renewable energy facility (other than Wind energy facility)	Must meet the requirements of Clause 53.13.
Residential hotel	
Restaurant	
Rural industry (other than Abattoir and Sawmill)	
Rural store	
Secondary school	

Use	Condition
Small second dwelling	Must be no more than one dwelling existing on the lot. Must be the only small second dwelling on the lot. Reticulated natural gas must not be supplied to the building, or part of a building, used for the small second dwelling. Must meet the requirements of Clause 35.06-2.
Timber production	Must meet the requirements of Clause 53.11.
Utility installation (other than Minor utility installation and Telecommunications facility)	
Wind energy facility	Must meet the requirements of Clause 52.32.
Winery	
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Abattoir
Accommodation (other than Bed and breakfast, Dwelling, Group accommodation, Host farm, Residential hotel and Small second dwelling)
Amusement parlour
Education centre (other than Primary school and Secondary school)
Industry (other than Rural industry)
Intensive animal production
Office
Leisure and recreation (other than Informal outdoor recreation)
Place of assembly (other than Carnival and Circus)
Retail premises (other than Landscape gardening supplies, Market, Primary produce sales and Restaurant)
Rice growing
Sawmill
Transport terminal
Warehouse (other than Freezing and cool storage and Rural store)

35.06-2 Use of land for a dwelling or small second dwelling

14/12/2023
VC253

A lot used for a dwelling or small second dwelling must meet the following requirements:

- Access to the dwelling or small second dwelling must be provided via an all-weather road with dimensions adequate to accommodate emergency vehicles.
- The dwelling or small second dwelling must be connected to reticulated sewerage if available. If reticulated sewerage is not available, all wastewater from the dwelling must be treated and retained within the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017* for an on-site wastewater management system.
- The dwelling or small second dwelling must be connected to a reticulated potable water supply or have an alternative potable water supply with adequate storage for domestic use as well as for fire fighting purposes.
- The dwelling or small second dwelling must be connected to a reticulated electricity supply or have an alternative energy source.

35.06-3 Subdivision

14/12/2023
VC253

A permit is required to subdivide land.

Each lot must be at least the area specified for the land in a schedule to this zone. If no area is specified, each lot must be at least 40 hectares.

A permit may be granted to create smaller lots if any of the following apply:

- The subdivision is the re-subdivision of existing lots, the number of lots is not increased, and the number of dwellings that the land could be used for does not increase.
- The subdivision is by a public authority or utility service provider to create a lot for a utility installation.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ Each new lot is at least the area specified for the land in the zone or the schedule to the zone. ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into 2 lots where each new lot is at least the area specified for the land in the zone or the schedule to the zone.	Clause 59.12

35.06-4 Long term lease or licence for accommodation

05/09/2013
VC103

A permit is required to lease or license a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation.

Each portion of a lot leased or licensed for the purpose of Accommodation must be at least the area specified as the minimum subdivision area for the land in a schedule to this zone. If no area is specified, each portion of a lot leased or licensed for the purpose of Accommodation must be at least 40 hectares.

This provision only applies to land in Metropolitan Melbourne.

35.06-5 Buildings and works

14/12/2023
VC253

A permit is required to construct or carry out any of the following:

- A building or works associated with a use in Section 2 of Clause 35.06-1. This does not apply to:
  - An alteration or extension to an existing dwelling provided the floor area of the alteration or extension does not exceed the area specified in a schedule to this zone or, if no area is specified, 100 square metres. Any area specified must be more than 100 square metres.
  - An alteration or extension to a small second dwelling.
  - An out-building associated with an existing dwelling provided the floor area of the out-building does not exceed the area specified in a schedule to this zone or, if no area is specified, 100 square metres. Any area specified must be more than 100 square metres.
  - An alteration or extension to an existing building used for agriculture provided the floor area of the alteration or extension does not exceed the area specified in a schedule to this zone or, if no area is specified, 100 square metres. Any area specified must be more than 100 square metres. The building must not be used to keep, board, breed or train animals.
  - A rainwater tank.
- Earthworks specified in a schedule to this zone, if on land specified in a schedule.
- A building which is within any of the following setbacks:
  - 100 metres from a Transport Zone 2 or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority and the purpose of the acquisition is for a road.
  - 40 metres from a Transport Zone 3 or land in a Public Acquisition Overlay for a road if the Head, Transport for Victoria is not the acquiring authority.
  - 20 metres from any other road.
  - 5 metres from any other boundary.
  - 100 metres from a dwelling or small second dwelling not in the same ownership.
  - 100 metres from a waterway, wetlands or designated flood plain.
- A building or works associated with accommodation located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $250,000 where: ▪ The land is not used for Domestic animal husbandry, Pig farm, Poultry farm, Poultry hatchery, Racing dog husbandry or Rural industry. ▪ The land is not within 30 metres of land (not a road) which is in a residential zone. ▪ The building or works are not associated with accommodation located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*. Any works must not be earthworks specified in the schedule to the zone.	Clause 59.13

35.06-6 Decision guidelines

22/03/2022
VC219

Before deciding on an application to use or subdivide land, lease or license a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation, construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General issues

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any Regional Catchment Strategy and associated plan applying to the land.
- The capability of the land to accommodate the proposed use or development.
- How the use or development conserves the values identified for the land in a schedule.
- Whether use or development protects and enhances the environmental, agricultural and landscape qualities of the site and its surrounds.
- Whether the site is suitable for the use or development and the compatibility of the proposal with adjoining land uses.

Rural issues

- The environmental capacity of the site to sustain the rural enterprise.
- The need to prepare an integrated land management plan.
- The impact on the existing and proposed infrastructure.
- Whether the use or development will have an adverse impact on surrounding land uses.

Environmental issues

- An assessment of the likely environmental impact on the biodiversity and in particular the flora and fauna of the area.
- The protection and enhancement of the natural environment of the area, including the retention of vegetation and faunal habitats and the need to revegetate land including riparian buffers along waterways, gullies, ridgelines, property boundaries and saline discharge and recharge areas.

- How the use and development relates to sustainable land management and the need to prepare an integrated land management plan which addresses the protection and enhancement of native vegetation and waterways, stabilisation of soil and pest plant and animal control.
- The location of on site effluent disposal areas to minimise the impact of nutrient loads on waterways and native vegetation.

Accommodation issues

- Whether the dwelling will result in the loss or fragmentation of productive agricultural land.
- Whether the dwelling will be adversely affected by agricultural activities on adjacent and nearby land due to dust, noise, odour, use of chemicals and farm machinery, traffic and hours of operation.
- Whether the dwelling will adversely affect the operation and expansion of adjoining and nearby agricultural uses.
- The potential for accommodation to be adversely affected by vehicular traffic, noise, blasting, dust and vibration from an existing or proposed extractive industry operation if it is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990.*

Design and siting issues

- The need to minimise any adverse impacts of siting, design, height, bulk, and colours and materials to be used, on landscape features, major roads and vistas.
- The location and design of existing and proposed infrastructure services which minimises the visual impact on the landscape.
- The need to minimise adverse impacts on the character and appearance of the area or features of archaeological, historic or scientific significance or of natural scenic beauty or importance.
- The location and design of roads and existing and proposed infrastructure services to minimise the visual impact on the landscape.
- The need to locate and design buildings used for accommodation to avoid or reduce the impact from vehicular traffic, noise, blasting, dust and vibration from an existing or proposed extractive industry operation if it is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990.*

35.06-7 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 4.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 35.06 RURAL CONSERVATION ZONE

Shown on the planning scheme map as **RCZ.**

CONSERVATION VALUES

To protect and conserve places of natural heritage and archaeological significance.

1.0 Subdivision and other requirements

08/07/2021
C211brim

	Land	Area/Dimensions/Number
Minimum subdivision area (hectares)	Land bounded by the Old Calder Highway and the Calder Freeway Land bounded by the Calder Freeway and the Maribyrnong River Land generally south east of Burrowye Crescent and north of Green Gully Reserve	40 ha
	Land located at the north west corner of the proposed Kings Road extension interchange generally between the Calder Freeway and Jacksons Creek, Keilor shown on Plan Number PS429241L	20 ha
Maximum floor area for which no permit is required to alter or extend an existing dwelling (square metres)	None specified	None specified
Maximum floor area for which no permit is required to construct an out-building associated with a dwelling (square metres)	None specified	None specified
Maximum floor area for which no permit is required to alter or extend an existing building used for agriculture (square metres).	None specified	None specified

Permit requirement for earthworks	Land
Earthworks which change the rate of flow or the discharge point of water across a property boundary	None specified
Earthworks which increase the discharge of saline groundwater	None specified

36 PUBLIC LAND ZONES

19/01/2006
VC37

36.01 PUBLIC USE ZONE

31/07/2018
VC148

Shown on the planning scheme map as **PUZ** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To recognise public land use for public utility and community services and facilities.

To provide for associated uses that are consistent with the intent of the public land reservation or purpose.

36.01-1 Table of uses

14/11/2022
VC227

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Railway	
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.
Any other use	The use must be for the purpose described in the table to Clause 36.01-6 which corresponds to the notation on the planning scheme map. The use must be carried out by or on behalf of the public land manager.

Section 2 - Permit required

Use	Condition

Section 3 - Prohibited

Use
Nil

36.01-2 Permit requirement

19/01/2006
VC37

A permit is required to:

- Construct a building or construct or carry out works for any use in Section 2 of Clause 36.01-1. This does not apply to navigational beacons and aids.
- Subdivide land.

36.01-3 Application requirements

19/01/2006
VC37

An application for a permit by a person other than the relevant public land manager must be accompanied by the written consent of the public land manager, indicating that the public land manager consents generally or conditionally either:

- To the application for permit being made.
- To the application for permit being made and to the proposed use or development.

36.01-4 Decision guidelines

31/07/2018
VC148

Before deciding on an application to use or subdivide land, construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The comments of any Minister or public land manager having responsibility for the care or management of the land or adjacent land.
- Whether the development is appropriately located and designed, including in accordance with any relevant use, design or siting guidelines.

36.01-5 Permit not required

19/01/2006
VC37

A permit is not required to use land, or to construct a building or construct or carry out works on land, listed in a schedule to this zone, provided any condition in the schedule is complied with.

36.01-6 Table of public land use

14/01/2025
VC237

Shown on the planning scheme map	Purpose of public land use
PUZ1	Service & Utility
PUZ2	Education
PUZ3	Health & Community
PUZ5	Cemetery/Crematorium
PUZ6	Local Government
PUZ7	Other public use

36.01-7 Signs

20/01/2022
VC205

Sign requirements are at Clause 52.05. This zone is in Category 4 unless a different requirement is specified in the schedule to this zone.

Where a Transport Zone 2 or a Transport Zone 3 is the nearest adjoining zone, a permit is required to display a sign.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 36.01 PUBLIC USE ZONE

1.0 Permit exemptions and conditions

08/07/2021
C211brim

Public land	Use or development	Conditions
None specified	None specified	None specified

2.0 Sign requirements

08/07/2021
C211brim

Land	Sign Category
474-478 Ballarat Road, Sunshine North	Category 2
26S Glenbrook Avenue and 147A Cairnlea Drive, Cairnlea	Category 1

36.02 PUBLIC PARK AND RECREATION ZONE

31/07/2018
VC148

Shown on the planning scheme map as **PPRZ**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To recognise areas for public recreation and open space.

To protect and conserve areas of significance where appropriate.

To provide for commercial uses where appropriate.

36.02-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Informal outdoor recreation	
Open sports ground	Must be conducted by or on behalf of the public land manager. Must not be on coastal Crown land under the *Marine and Coastal Act 2018*.
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.
Contractor's depot **Heliport** **Office** **Retail premises** **Store** **Any other use not in Section 3**	Must be either of the following: A use conducted by or on behalf of a public land manager, Parks Victoria or the Great Ocean Road Coast and Parks Authority, under the relevant provisions of the *Local Government Act 2020*, the *Reference Areas Act 1978*, the *National Parks Act 1975*, the *Fisheries Act 1995*, the *Wildlife Act 1975*, the *Forest Act 1958*, the *Water Industry Act 1994*, the *Water Act 1989*, the *Marine Safety Act 2010*, the *Port Management Act 1995*, or the *Crown Land (Reserves) Act 1978*. A use specified in an Incorporated plan in a schedule to this zone.

Section 2 - Permit required

Use	Condition
Contractor's depot - if the Section 1 condition is not met	Must be associated with the public land use.
Heliport - if the Section 1 condition is not met	Must be associated with the public land use.
Office - if the Section 1 condition is not met	Must be associated with the public land use.
Retail premises - if the Section 1 condition is not met	Must be associated with the public land use.

Use	Condition
Store - if the Section 1 condition is not met	Must be associated with the public land use.

Section 3 - Prohibited

Use
Cinema based entertainment facility
Corrective institution
Display home centre
Funeral parlour
Industry (other than Automated collection point)
Saleyard
Transport terminal (other than Heliport)
Veterinary centre
Warehouse (other than Store)

36.02-2 Permit requirement

14/01/2025
VC237

A permit is required to:

- Construct a building or construct or carry out works. This does not apply to:
  - Pathways, trails, seating, picnic tables, drinking taps, shelters, barbeques, rubbish bins, security lighting, irrigation, drainage or underground infrastructure.
  - Playground equipment or sporting equipment, provided these facilities do not occupy more than 10 square metres of parkland.
  - Navigational beacons and aids.
  - Planting or landscaping.
  - Fencing that is 1 metre or less in height above ground level.
  - A building or works shown in an Incorporated plan which applies to the land.
  - A building or works carried out by or on behalf of a public land manager, Parks Victoria or the Great Ocean Road Coast and Parks Authority, under the *Local Government Act 2020*, the *Reference Areas Act 1978*, the *National Parks Act 1975*, the *Fisheries Act 1995*, the *Wildlife Act 1975*, the *Forest Act 1958*, the *Water Industry Act 1994*, the *Water Act 1989*, the *Marine Safety Act 2010*, the *Port Management Act 1995* or the *Crown Land (Reserves) Act 1978*.
- Subdivide land.

36.02-3 Application requirements

19/01/2006
VC37

An application for a permit by a person other than the relevant public land manager must be accompanied by the written consent of the public land manager, indicating that the public land manager consents generally or conditionally either:

- To the application for permit being made.

- To the application for permit being made and to the proposed use or development.

36.02-4 Exemption from notice and review

31/07/2018
VC148

An application to subdivide land which is consistent with an Incorporated plan is exempt from the notice requirements of section 52(1) (a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act.

36.02-5 Decision guidelines

31/07/2018
VC148

Before deciding on an application to use or subdivide land, construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The comments of any public land manager or other relevant land manager having responsibility for the care or management of the land or adjacent land.
- Whether the development is appropriately located and designed, including in accordance with any relevant use, design or siting guidelines.

36.02-6 Incorporated plan

19/01/2006
VC37

An Incorporated plan is a plan which shows the way the land is to be used and developed. An Incorporated plan may include the following information:

- Recognition of existing use and how the area is to be developed.
- The building envelope of any proposed buildings.
- Details of any proposed buildings or works.
- The location of pedestrian or vehicle access points or car parking areas.
- The location of any areas for specific uses or a schedule of specific uses which are allowed without permit.
- Topographic details including any proposed cut and fill.
- The location of existing and proposed features.
- The location of existing native and other vegetation and any proposed landscaping works or areas of vegetation to be added or removed.
- The identification of sites of flora or fauna significance (including, in particular, any potentially threatened species or significant habitat) or other places of cultural heritage or scientific value.

The Incorporated plan must be consistent with the intent of the public land reservation under any Act and make reference to relevant policies and guidelines.

An Incorporated plan may be prepared in parts or stages.

36.02-7 Use and development of land identified in a schedule

19/01/2006
VC37

Land identified in a schedule to this zone may be used and developed in accordance with the schedule or the specific controls contained in an incorporated document corresponding to the land, provided any condition in the schedule or incorporated document is complied with.

36.02-8 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 4 unless a different requirement is specified in the schedule to this zone.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 36.02 PUBLIC PARK AND RECREATION ZONE

1.0 Permit exemptions and conditions

08/07/2021
C211brim

Public land	Use or development	Conditions
None specified	None specified	None specified

2.0 Sign requirements

08/07/2021
C211brim

Land	Sign Category
None specified	None specified

3.0 Use and development of land specified in an Incorporated Plan

08/07/2021
C211brim

None specified.

36.03 PUBLIC CONSERVATION AND RESOURCE ZONE

31/07/2018
VC148

Shown on the planning scheme map as **PCRZ**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To protect and conserve the natural environment and natural processes for their historic, scientific, landscape, habitat or cultural values.

To provide facilities which assist in public education and interpretation of the natural environment with minimal degradation of the natural environment or natural processes.

To provide for appropriate resource based uses.

36.03-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Apiculture	Must meet the requirements of the Apiary Code of Practice, May 2011.
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Boat launching facility **Camping and caravan park** **Caretaker's house** **Car park** **Informal outdoor recreation** **Interpretation centre** **Jetty** **Kiosk** **Marine dredging** **Mooring pole** **Open sports ground** **Pier** **Pontoon** **Road** **Utility installation (other than Telecommunications facility)**	Must be either of the following: ▪ A use conducted by or on behalf of a public land manager, Parks Victoria or the Great Ocean Road Coast and Parks Authority, under the relevant provisions of the *Local Government Act 2020*, the *Reference Areas Act 1978*, the *National Parks Act 1975*, the *Fisheries Act 1995*, the *Wildlife Act 1975*, the *Forests Act 1958*, the *Water Industry Act 1994*, the *Water Act 1989*, the *Marine Safety Act 2010*, the *Port Management Act 1995* or the *Crown Land (Reserves) Act 1978*. ▪ Specified in an Incorporated plan in a schedule to this zone.
Any use listed in Clause 62.01 (other than Apiculture)	

Use	Condition
Any other use not in Section 2 or 3	▪ Must be a use conducted by or on behalf of a public land manager, Parks Victoria or the Great Ocean Road Coast and Parks Authority, under the relevant provisions of the *Local Government Act 2020*, the *Reference Areas Act 1978*, the *National Parks Act 1975*, the *Fisheries Act 1995*, the *Wildlife Act 1975*, the *Forests Act 1958*, the *Water Industry Act 1994*, the *Water Act 1989*, the *Marine Safety Act 2010*, the *Port Management Act 1995* or the *Crown Land (Reserves) Act 1978*.

Section 2 - Permit required

Use	Condition
Emergency services facility	
Renewable energy facility (other than Wind energy facility)	Must not be located on land reserved under the *National Parks Act 1975*. Must meet the requirements of Clause 53.13.
Wind energy facility	Must not be located on land described in a schedule to the *National Parks Act 1975*. This does not apply where the Wind energy facility is principally used to supply electricity to a facility used in conjunction with conservation, recreation, administration or accommodation use of the land. Must meet the requirements of Clause 52.32.

Section 3 - Prohibited

Use
The use in Section 1 described as 'Any other use not in Section 2 or 3' – if the Section 1 condition is not met

36.03-2 Permit requirement

14/01/2025
VC237

A permit is required to:

- Construct a building or construct or carry out works. This does not apply to:
  - A building or works shown in an Incorporated plan which applies to the land.
  - A building or works specified in Clause 62.02-1 or 62.02-2 carried out by or on behalf of a public authority or municipal council, if the public authority or municipal council is carrying out functions, powers or duties conferred by or under the *Local Government Act 2020*, the *Reference Areas Act 1978*, the *National Parks Act 1975*, the *Fisheries Act 1995*, the *Wildlife Act 1975*, the *Forests Act 1958*, the *Water Industry Act 1994*, the *Water Act 1989*, the *Marine Safety Act 2010*, the *Port Management Act 1995* or the *Crown Land (Reserves) Act 1978*.
  - A building or works carried out by or on behalf of a public land manager, Parks Victoria or the Great Ocean Road Coast and Parks Authority, under the *Local Government Act 2020*, the *Reference Areas Act 1978*, the *National Parks Act 1975*, the *Fisheries Act 1995*, the

Wildlife Act 1975, the *Forests Act 1958*, the *Water Industry Act 1994*, the *Water Act 1989*, the *Marine Safety Act 2010*, the *Port Management Act 1995,* the *Crown Land (Reserves) Act 1978*, or the *Road Management Act 2004*.

- Subdivide land.

36.03-3 Application requirements

20/03/2023
VC229

An application for a permit by a person other than the relevant public land manager must be accompanied by the written consent of the public land manager, indicating that the public land manager consents generally or conditionally either:

- To the application for permit being made.
- To the application for permit being made and to the proposed use or development.

Where there is no public land manager, an application for a permit must be accompanied by the written consent of the Secretary to the Department of Energy, Environment and Climate Action.

36.03-4 Exemption from notice and review

31/07/2018
VC148

An application to subdivide land which is consistent with an Incorporated plan is exempt from the notice requirements of section 52(1) (a), (b), and (d), the decision requirements of sections 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

36.03-5 Referral of applications

18/06/2010
VC62

An application to use or develop land for the purpose of an emergency services facility must be referred under Section 55 of the Act to the person or body specified as the referral authority in Clause 66.03.

36.03-6 Decision guidelines

31/07/2018
VC148

Before deciding on an application to use or subdivide land, construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The comments of any public land manager or other relevant land manager having responsibility for the care or management of the land or adjacent land.
- Whether the development is appropriately located and designed, including in accordance with any relevant use, design or siting guidelines.

36.03-7 Incorporated plan

18/06/2010
VC62

An Incorporated plan is a plan which shows the way the land is to be used and developed. An Incorporated plan may include the following information:

- Recognition of existing use and how the area is to be developed.
- The building envelope of any proposed buildings.
- Details of proposed buildings or works.
- The location of pedestrian or vehicle access points or car parking areas.
- The location of any areas for specific uses and a schedule of specific uses which are allowed without permit.
- Topographic details including any proposed cut and fill.
- The location of existing and proposed features.

- The location of existing native or other vegetation and any proposed landscaping works or areas of vegetation to be added or removed.
- The identification of sites of flora or fauna significance (including, in particular, any potentially threatened species or significant habitat) or other places of cultural, heritage or scientific value.

The Incorporated plan must be consistent with the intent of the public land reservation under any Act and make reference to relevant policies and guidelines.

An Incorporated plan may be prepared in parts or stages.

36.03-8 Use and development of land identified in a schedule

18/06/2010
VC62

Land identified in a schedule to this zone may be used and developed in accordance with the schedule or the specific controls contained in an incorporated document corresponding to the land, provided any condition in the schedule or incorporated document is complied with.

36.03-9 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 4 unless a different requirement is specified in the schedule to this zone.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 36.03 PUBLIC CONSERVATION AND RESOURCE ZONE

1.0 Permit exemptions and conditions

08/07/2021
C211brim

Public land	Use or development	Conditions
None specified	None specified	None specified

2.0 Sign requirements

08/07/2021
C211brim

Land	Sign Category
None specified	None specified

3.0 Use and development of land specified in an Incorporated Plan

08/07/2021
C211brim

None specified.

36.04 TRANSPORT ZONE

20/01/2022
VC205

Shown on the planning scheme map as **TRZ** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide for an integrated and sustainable transport system.

To identify transport land use and land required for transport services and facilities.

To provide for the use and development of land that complements, or is consistent with, the transport system or public land reservation.

To ensure the efficient and safe use of transport infrastructure and land comprising the transport system.

36.04-1 Table of uses

15/03/2024
VC256

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Railway	
Railway station	The combined leasable floor area for the selling of food, drink and other convenience goods and services must not exceed 800 square metres.
Tramway	
Transport terminal (other than Railway station)	The use must be carried out by or on behalf of a relevant transport manager.
Utility installation (other than Minor utility installation and Telecommunications facility)	The use must be carried out by or on behalf of a relevant transport manager.
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.
Any other use	The use must be for a transport purpose and carried out by or on behalf of a relevant transport manager.

Section 2 - Permit required

Use	Condition

Section 3 - Prohibited

Use
Nil

36.04-2 Permit requirement

20/01/2022
VC205

A permit is required to:

- Construct a building or construct or carry out works for any use in Section 2 of Clause 36.04-1. This does not apply to navigational beacons and aids.
- Subdivide land.

36.04-3 Application requirements

20/01/2022
VC205

An application by a person other than a relevant transport manager on land shown on a planning scheme map as TRZ1 or TRZ2 must be accompanied by the written consent of the Head, Transport for Victoria, indicating that the Head, Transport for Victoria consents generally or conditionally to either:

- The application being made.
- The application being made and to the proposed use or development.

36.04-4 Table of transport uses

20/01/2022
VC205

Shown on the planning scheme map	Purpose of transport use
TRZ1	State transport infrastructure
TRZ2	Principal road network
TRZ3	Significant municipal road
TRZ4	Other transport use

36.04-5 Decision guidelines

20/01/2022
VC205

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The effect of the proposal on the development, operation and safety of the transport system.
- Whether the development is appropriately located and designed, including in accordance with any relevant use, design or siting guidelines.

36.04-6 Signs

12/02/2024
VC254

Sign requirements are at Clause 52.05.

A permit is required to construct or put up for display a sign:

- over a road carriageway or over land within 600 millimetres of a carriageway.
- on land in a Transport Zone 1, if a Transport Zone 2 or Transport Zone 3 is the adjoining zone.

For all other land in this zone, the sign category which applies is the category which applies to the adjoining zone nearest to the land. If land is equidistant from two or more adjoining zones, the least restrictive category applies.

37 SPECIAL PURPOSE ZONES

19/01/2006
VC37

37.01 SPECIAL USE ZONE

31/07/2018
VC148

Shown on the planning scheme map as **SUZ** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To recognise or provide for the use and development of land for specific purposes as identified in a schedule to this zone.

37.01-1 Table of uses

19/01/2006
VC37

Section 1 - Permit not required

Use	Condition
Any use in Section 1 of the schedule to this zone	Must comply with any condition in Section 1 of the schedule to this zone

Section 2 - Permit required

Use	Condition
Any use in Section 2 of the schedule to this zone	Must comply with any condition in Section 2 of the schedule to this zone.
Any other use not in Section 1 or 3 of the schedule to this zone	

Section 3 - Prohibited

Use
Any use in Section 3 of the schedule to this zone

37.01-2 Use of land

31/07/2018
VC148

Any requirement in the schedule to this zone must be met.

Application requirements

An application to use land must be accompanied by any information specified in the schedule to this zone.

Exemption from notice and review

The schedule to this zone may specify that an application is exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any guidelines in the schedule to this zone.

37.01-3 Subdivision

14/12/2023
VC253

Permit requirement

A permit is required to subdivide land.

Any requirement in the schedule to this zone must be met.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

Application requirements

An application to subdivide land must be accompanied by any information specified in the schedule to this zone.

Exemption from notice and review

The schedule to this zone may specify that an application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any guidelines in the schedule to this zone.

37.01-4 Buildings and works

20/12/2021
VC174

Permit requirement

A permit is required to construct a building or construct or carry out works unless the schedule to this zone specifies otherwise.

Any requirement in the schedule to this zone must be met.

An apartment development must meet the requirements of Clause 58.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $500,000 and the land is not: ▪ Within 30 metres of land (not a road) which is in a residential zone. ▪ Used for a purpose listed in the table to Clause 53.10.	Clause 59.04

Transitional provisions

Clause 58 does not apply to:

- An application for a planning permit lodged before the approval date of Amendment VC136.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before the approval date of Amendment VC136.

Clause 58 of this scheme, as in force immediately before the approval date of Amendment VC174, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Application requirements

An application to construct a building or construct or carry out works must be accompanied by any information specified in the schedule to this zone.

An application to construct or extend an apartment development, or to construct or extend a dwelling in or forming part of an apartment development, must be accompanied by an urban context report and design response as required in Clause 58.01.

Exemption from notice and review

The schedule to this zone may specify that an application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- For an apartment development, the objectives, standards and decision guidelines of Clause 58.
- Any guidelines in the schedule to this zone.

37.01-5 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 3 unless a schedule to this zone specifies a different category.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 37.01 SPECIAL USE ZONE

Shown on the planning scheme map as **SUZ1.**

RACECOURSE AND SHOWGROUNDS AREAS, PRIVATE SPORTSGROUNDS, RELIGIOUS AND EDUCATION ESTABLISHMENT

Purpose

To provide for areas in private ownership to be used as private sports grounds and religious and educational institutions.

To provide for areas to be used as racecourses and showgrounds.

1.0
01/12/2023
VC217

Table of uses

Section 1 - Permit not required

Use	Condition
Agriculture	
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Caretaker's house **Education centre** **Home based business** **Informal outdoor recreation** **Mineral exploration**	
Mining	Must meet the conditions of Clause 52.08.
Place of worship **Railway**	
Search for Stone	Must not be costeaning or bulk sampling.
Tramway **Veterinary centre**	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01

Section 2 - Permit required

Use	Condition
Animal husbandry **Car park** **Leisure and recreation** **Major sports and recreation facility** **Mining - if the Section 1 condition is not met**	

Use	Condition
Minor utility installation	
Motor racing track	
Office	The floor area must not exceed 500sqm
Place of assembly	
Residential building	Must be used in association with Place of worship
Search for stone - if the Section 1 condition is not met	
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Accommodation
Amusement Parlour
Cemetery
Crematorium
Extractive Industry
Industry (other than Automated collection point and Car wash)
Retail premises (other than Convenience shop, Food and drink premises, Market and Plant nursery)
Service Station
Utility Installation (except Minor utility installation)
Warehouse

2.0 Use of land

08/07/2021
C211brim

None specified.

3.0 Subdivision

08/07/2021
C211brim

None specified.

4.0 Buildings and works

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 37.01 to construct a building or carry out works, in addition to those specified in Clause 37.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The location and type of access to the site.
- The provision for car parking.
- The provision of land for landscaping and beautification and the type of landscaping proposed.
- The appearance and bulk of a building as seen from outside the land, having regard to the nature of surrounding zones and uses.

- The effect of the proposed buildings and works on the amenity of the neighbouring properties, including the effects of noise, lighting and overshadowing.
- The effect of the proposed use on the privacy of neighbours.

5.0 Signs

08/07/2021
C211brim

Sign requirements are at Clause 52.05. All land located within this Schedule is in Category 3.

08/07/2021
C211brim

SCHEDULE 2 TO CLAUSE 37.01 SPECIAL USE ZONE

Shown on the planning scheme map as **SUZ2**.

PRIVATE UTILITY INSTALLATIONS

Purpose

To provide for areas in private ownership to be used for the purposes of essential service utility installations.

To ensure that the development of these facilities takes place in an orderly and proper manner and does not cause a loss of amenity to the surrounding neighbourhood.

1.0
01/12/2023
VC217

Table of uses

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Mineral exploration	
Mining	Must meet the conditions of Clause 52.08
Railway	
Search for Stone	Must not be costeaning or bulk sampling
Tramway	
Utility installation	Must be in accordance with the Development Plan approved pursuant to Clause 4.0 of this schedule.
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01

Section 2 - Permit required

Use	Condition
Accommodation **Agriculture** **Caretaker's house**	
Convenience shop	The leasable floor area must not exceed 80 sqm.
Home based business **Leisure and recreation (other than Motor racing track)** **Mining – if the Section 1 condition is not met.**	
Office	The floor area must not exceed 500 sqm.
Plant nursery	

Use	Condition
Search for stone – if the Section 1 condition is not met.	
Utility installation – if the Section 1 condition is not met.	
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Amusement Parlour
Animal Boarding
Animal Training
Cemetery
Convenience Restaurant
Crematorium
Extractive Industry
Food and Drink Premises
Horse Stables
Industry (Other than Automated collection point and Car wash)
Intensive Animal Husbandry
Market
Motor Racing Track
Nightclub
Retail Premises (other than Convenience shop, Market, and Plant nursery)
Saleyard
Service Station
Take Away Food Premises
Transport Terminal
Warehouse (other than Store)

2.0 Use of land

08/07/2021
C211brim

Application Requirements

The following application requirements apply to an application for a permit under Clause 37.01, in addition to those specified in Clause 37.01 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- The purpose of the use and types of activities which will be carried out; and
- The likely effects, if any, on the adjacent land including noise levels, traffic and hours of operation.

Decision Guidelines

The following decision guidelines apply to an application for a permit under Clause 37.01, in addition to those specified in Clause 37.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The effect that the proposed use may have on existing uses; and
- The effect that the proposed use may have on the amenity of the neighbourhood.

3.0 Subdivision

08/07/2021
C211brim

Application Requirements

The following application requirements apply to an application for a permit under Clause 37.01, in addition to those specified in Clause 37.01 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- The purpose of the subdivision; and
- The likely effects of the subdivision on the adjacent land.

Decision Guidelines

The following decision guidelines apply to an application for a permit under Clause 37.01, in addition to those specified in Clause 37.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The effect that the proposed subdivision may have on existing uses; and
- The effect that the proposed subdivision may have on the amenity of the neighbourhood.

4.0 Requirement for development plan

19/01/2006
VC37

Before the construction of any buildings and works, or before the use commences, a development plan must be approved by the Responsible Authority. The plan must show:

- The layout and use of the existing and proposed buildings and works, driveways, car parking and loading areas;
- Construction details of all drainage works, site access arrangements, vehicle parking and loading areas;
- Details of existing and proposed landscaping, including perimeter landscaping treatments;
- The appearance and bulk of buildings having regard to the adjoining zones, especially the relationship with residential areas; and
- The effect of the proposed buildings and works on the amenity of the neighbourhood, including the effects of noise, lighting, overshadowing and privacy.

08/07/2021
C211brim

SCHEDULE 3 TO CLAUSE 37.01 SPECIAL USE ZONE

Shown on the planning scheme map as **SUZ3.**

EARTH AND ENERGY RESOURCES INDUSTRY

Purpose

To recognise or provide for the use and development of land for earth and energy resources industry.

To encourage interim use of the land compatible with the use and development of nearby land.

To encourage land management practice and rehabilitation that minimises adverse impact on the use and development of nearby land.

1.0
01/12/2023
VC217

Table of uses

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Extensive animal husbandry **Home based business** **Informal outdoor recreation** **Railway** **Tramway**	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01

Section 2 - Permit required

Use	Condition
Agriculture (other than Animal keeping, Animal training, Apiculture, Extensive animal husbandry, Horse stables, and Intensive animal husbandry)	
Animal keeping (other than Animal boarding)	Must be no more than four animals.
Caretaker's house **Dependent person's unit**	
Industry (other than Materials recycling, Refuse disposal, and Transfer station)	Must not be a purpose listed in the table to Clause 53.10.
Landscape gardening supplies **Leisure and recreation (other than Informal outdoor recreation)** **Manufacturing sales** **Materials recycling**	

Use	Condition
Place of assembly (other than Amusement parlour and Nightclub)	
Refuse disposal	
Transfer station (other than Automated collection point)	
Utility installation (other than Minor utility installation)	
Warehouse	Must not be a purpose listed in the table to Clause 53.10.
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Accommodation (other than Caretaker's house and Dependent person's unit)
Amusement parlour
Animal boarding
Animal training
Cinema based entertainment facility
Horse stables
Intensive animal husbandry
Nightclub
Office
Retail premises (other than Landscape gardening supplies and Manufacturing sales)
Saleyard
Service station
Transport terminal
Veterinary centre

2.0 Use of land

08/07/2021
C211brim

None specified.

3.0 Subdivision

08/07/2021
C211brim

None specified.

4.0 Buildings and works

08/07/2021
C211brim

No permit is required to construct a building or construct or carry out works for the following:

- A modification necessary to comply with a direction or licence under the Dangerous Goods Act 1985 or a Waste Discharge Licence, Works Approval or Pollution Abatement Notice under the Environment Protection Act 1970.

5.0 Signs

08/07/2021
C211brim

None specified.

08/07/2021
C211brim

SCHEDULE 4 TO CLAUSE 37.01 SPECIAL USE ZONE

Shown on the planning scheme map as **SUZ4.**

PRIVATE SPORTS GROUNDS

Purpose

To provide for the use and development of land in private ownership for private sports grounds and recreation centres.

1.0 Table of uses

01/12/2023
VC217

Section 1 - Permit not required

Use	Condition
Agriculture	
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Caretaker's house **Education centre** **Informal outdoor recreation** **Mineral exploration**	
Mining	Must meet the requirements of Clause 52.08
Railway	
Search for stone	Must not be costeaning or bulk sampling
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01

Section 2 - Permit required

Use	Condition
Car park	
Convenience shop	The leasable floor area must not exceed 100 sqm
Leisure and recreation **Major sports and recreation facility** **Mining – if the Section 1 condition is not met** **Minor utility installation**	
Office	The floor area must not exceed 500 sqm
Place of assembly **Residential building**	

Use	Condition
Telecommunications facility	
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Accommodation
Amusement Parlour
Cemetery
Crematorium
Extractive Industry
Industry (other than Automated collection point and Car wash)
Retail premises (other than Food and Drink Premises, Market and Plant Nursery
Service Station
Utility Installation (except Minor utility installation)
Warehouse

2.0 Use of land

08/07/2021
C211brim

None specified.

3.0 Subdivision

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 37.01 to subdivide land, in addition to those specified in Clause 37.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The location and type of access to the site.
- The provision for car parking.
- The provision of land for landscaping and beautification and the type of landscaping proposed.
- The appearance and bulk of a building as seen from outside the land, having regard to the nature of surrounding zones and uses.
- The effect of the proposed buildings and works on the amenity of the neighbouring properties, including the effects of noise, lighting and overshadowing.

4.0 Buildings and works

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 37.01 to construct a building or carry out works, in addition to those specified in Clause 37.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The location and type of access to the site.
- The provision for car parking.
- The provision of land for landscaping and beautification and the type of landscaping proposed.

- The appearance and bulk of a building as seen from outside the land, having regard to the nature of surrounding zones and uses.
- The effect of the proposed buildings and works on the amenity of the neighbouring properties, including the effects of noise, lighting and overshadowing.

5.0 Signs

08/07/2021
C211brim

Sign requirements are at Clause 52.05. All land located within this Schedule is in Category 3.

08/07/2021
C211brim

SCHEDULE 5 TO CLAUSE 37.01 SPECIAL USE ZONE

Shown on the planning scheme map as **SUZ5**.

OVERNEWTON ANGLICAN COMMUNITY COLLEGE, KEILOR CAMPUS

Purpose

To implement the Municipal Planning Strategy and Planning Policy Framework, including local planning policies.

To provide for the continued use and development of land for an education centre.

To provide for the use and development of the land in accordance with the *Overnewton Anglican Community College Keilor Campus Master Plan, March 2006*.

To protect and enhance the natural environment and natural processes for their historic, archaeological and scientific interest, landscape, faunal habitat and cultural values.

To protect and enhance natural resources and the biodiversity of the site.

To encourage development and use of the land which is consistent with suitable land management and land capacity practices, and which takes into account the conservation values and environmental sensitivity of the locality.

1.0 Table of uses

14/11/2022
VC227

Section 1 - Permit not required

Use	Condition
Animal keeping (other than Animal boarding)	Must be no more than 2 animals.
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Bed and breakfast	No more than 6 persons may be accommodated away from their normal place of residence. At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence.
Education centre	Must be generally in accordance with the *Overnewton Anglican Community College Keilor Campus Master Plan, March 2006.* The number of students enrolled at anytime must not exceed 1450 students.
Geothermal energy extraction	Must meet the requirements of Clause 52.08
Home based business **Informal outdoor recreation** **Mineral exploration**	
Mining	Must meet the conditions of Clause 52.08
Railway	

Use	Condition
Search for Stone	Must not be costeaning or bulk sampling
Tramway	
Any use listed as Clause 62.01	Must meet the requirements of Clause 62.01

Section 2 - Permit required

Use	Condition
Agriculture (other than Animal keeping, Apiculture, Intensive animal husbandry, and Timber production)	
Car park	Must be in conjunction with another use in Section 1 or 2
Dependent person's unit	Must be the only dependent persons unit on the lot. Must meet the requirements of Clause 35.06-2.
Dwelling (other than Bed & breakfast)	Must be the only dwelling on the lot. This does not apply to the replacement of an existing dwelling if the existing dwelling is removed or altered (so it can no longer be used as a dwelling) within one month of the occupation of the replacement dwelling. Must meet the requirements of Clause 35.06-2.
Emergency services facility	
Freezing and cool storage	The goods stored must be agricultural produce, or products used in agriculture.
Group accommodation	Must be used in conjunction with Agriculture, Rural industry, or Winery. Must be no more than 6 dwellings. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 ha. This condition only applies to land in Metropolitan Melbourne.
Host Farm **Interpretation centre**	
Market **Mineral, stone or soil extraction (other than Mineral exploration, Geothermal energy extraction, Mining, and Search for stone)**	

Use	Condition
Plant nursery	
Primary produce sales	
Recreational boat facility	
Residential hotel	Must be used in conjunction with Agriculture, Rural industry or Winery. The number of bedrooms must not exceed the number specified in a schedule to the zone or 80 bedrooms, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 ha. This condition only applies to land in Metropolitan Melbourne.
Restaurant	Must be used in conjunction with Agriculture, Rural industry or Winery. The number of patrons present must not exceed the number specified in a schedule to the zone or 150 patrons, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 ha. This condition only applies to land in Metropolitan Melbourne.
Rural Industry (other than Abattoir and Sawmill)	
Rural Store	
Timber production	Must meet the requirements of Clause 53.11.
Utility installation (other than Minor utility installation and Telecommunications facility)	
Wind energy facility	
Winery	

Section 3 - Prohibited

Use
Abattoir
Accommodation (other than Dependent person's unit, Dwelling, Group accommodation, Host farm and Residential hotel)
Animal boarding
Industry (other than Automated collection point and Rural industry)
Intensive animal husbandry

Use
Leisure and recreation (other than Informal outdoor recreation)
Retail premises (other than Market, Plant Nursery, Primary produce sales, and Restaurant)
Place of assembly (other than Carnival and Circus)
Sawmill
Warehouse (other than Freezing and cool storage, and Rural store)
Any other use not in Section 1 or 2

2.0 Application requirements for use of land

08/07/2021
C211brim

The following application requirements apply to an application for a permit under Clause 37.01, in addition to those specified in Clause 37.01 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- The purpose of the use and types of activities which will be carried out; and
- The likely effects, if any, on the adjoining land including noise levels, traffic and hours of operation and spill of light.

3.0 Use of land for a dwelling

20/11/2008
C81

A lot used for a dwelling must meet the following requirements:

- Access to the dwelling must be provided via an all-weather road with dimensions adequate to accommodate emergency vehicles.
- The dwelling must be connected to a reticulated sewerage system or if not available, the waste water must be treated and retained on-site in accordance with the State Environment Protection Policy (Waters of Victoria) under the *Environment Protection Act 1970*.
- The dwelling must be connected to a reticulated potable water supply or have an alternative potable water supply with adequate storage for domestic use as well as for fire fighting purposes.
- The dwelling must be connected to a reticulated electricity supply or have an alternative energy source.

These requirements also apply to a dependent person's unit.

4.0 Subdivision

20/11/2008
C81

A permit is required to subdivide land.

Each lot must be at least the area specified for the land in a schedule to this zone. If no area is specified, each lot must be at least 40 hectares.

A permit may be granted to create smaller lots if any of the following apply:

- The subdivision is the re-subdivision of existing lots, the number of lots is not increased, the number of dwellings that the land could be used for does not increase. An agreement under Section 173 of the Act must be entered into with the owner of each lot created which ensures that the land may not be further subdivided so as to increase the number of lots. The agreement must be registered on the title. The requirement to enter into an agreement only applies to a lot which could be further subdivided in accordance with this scheme.
- The subdivision is by a public authority or utility service provider to create a lot for a utility installation.

5.0 Long term lease or licence for Accommodation

20/11/2008
C81

A permit is required to lease or licence a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation.

Each portion of a lot leased or licensed for the purpose of Accommodation must be at least the area specified as the minimum subdivision area for the land in a schedule to this zone. If no area is specified, each portion of a lot leased or licensed for the purpose of Accommodation must be at least 40 hectares.

This provision only applies to land in Metropolitan Melbourne.

6.0 Buildings and works

20/01/2022
VC205

A permit is required to construct or carry out any of the following:

- Any building or works associated with an education centre which is in accordance with the Overnewton Anglican Community College Keilor Campus Master Plan, March 2006. Such buildings and works must be generally in accordance with the Overnewton Anglican Community College Keilor Campus Master Plan, March 2006.
- A building or works associated with a use in Section 2 of this clause. This does not apply to:
  - An alteration or extension to an existing dwelling with a floor area of no more than the area specified in a schedule to this zone, or if no area is specified, 50 square metres. Any area specified must be more than 50 square metres.
  - An out-building associated with an existing dwelling provided the floor area of the out-building does not exceed the area specified in a schedule to this zone or, if no area is specified, 50 square metres. Any area specified must be more than 50 square metres.
  - An alteration or extension to an existing building used for agriculture with a floor area of no more than the area specified in a schedule to this zone, or if no area is specified, 50 square metres. Any area specified must be more than 50 square metres. The building must not be used to keep, board, breed or train animals.
  - A rainwater tank.
- Earthworks specified in a schedule to this zone, if on land specified in a schedule.
- A building which is within any of the following setbacks:
  - 100 metres from a Transport Zone 2 or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority; and the purpose of the acquisition is for a road.
  - 40 metres from a Transport Zone 3 or land in a Public Acquisition Overlay if the Head, Transport for Victoria is not the acquiring authority; and the purpose of the acquisition is for a road.
  - 20 metres from any other road.
  - 5 metres from any other boundary.
  - 100 metres from a dwelling not in the same ownership.
  - 100 metres from a waterway, wetlands or designated flood plain.

Application requirements

An application to construct a building or construct or carry out works for a section 1 use which is in accordance with the Overnewton Anglican Community College Keilor Campus Master Plan must be accompanied by the following information, where appropriate:

- A written assessment of the proposal against the Brimbank Planning Scheme and in particular this schedule.
- A plan, drawn to scale, which shows:
  - The boundaries and dimensions of the site.
  - Relevant ground levels.
  - Adjoining roads.
  - The location, height and purpose of buildings and works on adjoining land.
  - The layout and use of existing and proposed buildings and works, including driveways, car parking and loading areas.
  - Elevation drawings indicating the colour, material of all proposed buildings and works.
  - Construction details of all drainage works, driveways, car parking and loading areas.
  - Details of existing and proposed landscaping.

Exemption from notice and review

An application to construct a building or construct or carry out works associated with a section 1 use which is in accordance with the Overnewton Anglican Community College Keilor Campus Master Plan, March 2006 is exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

7.0 Decision guidelines

08/07/2021
C211brim

Before deciding on an application to use or subdivide land, lease or license a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation, construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General issues

- The Municipal Planning Strategy and Planning Policy Framework, including local planning policies.
- The purpose of the Schedule.
- The *Overnewton Anglican Community College Keilor Campus Master Plan, March 2006* and *Overnewton Anglican Community College Keilor Campus Development Guidelines.*
- Any Regional Catchment Strategy and associated plan applying to the land.
- The capability of the land to accommodate the proposed use or development.
- How the use or development conserves the values identified for the land in the schedule.
- Whether use or development protects and enhances the environment and landscape qualities of the site and its surrounds.
- Whether the site is suitable for the use or development and the compatibility of the proposal with adjoining land uses.
- Whether the proposed use of the site has regard for the amenity of the neighbourhood
- Any traffic and parking issues which will result from the proposal.

Rural issues

- The environmental capacity of the site to sustain the development.

- The need to prepare an integrated land management plan.
- The impact on the existing and proposed infrastructure.
- Whether the use or development will have an adverse impact on the surrounding land uses.

Environmental issues

- An assessment of the likely environmental impact on the biodiversity and in particular the flora and fauna of the area.
- The protection and enhancement of the natural environment of the area, including the retention of vegetation and faunal habitats and the need to revegetate land including riparian buffers along waterways, gullies, ridgelines, property boundaries and the saline discharge and recharge areas.
- How the use and development relates to sustainable land management and the need to prepare an integrated land management plan which addresses the protection and the enhancement of native vegetation and waterways, stabilisation of soil and pest plants and animal control.
- The location of site effluent areas to minimise the impact of nutrient loads on waterways and native vegetation.

Design and siting issues

- The need to minimise any adverse impacts of siting, design, height, bulk and colours and materials to be used on the landscape qualities of the Maribyrnong River Valley and the Calder Freeway.
- The location and design of existing and proposed infrastructure services which minimises the visual impacts on the landscape.
- The need to minimise adverse impacts on the character and appearance of the area or features of archaeological, historic or scientific or of natural scenic beauty or importance.
- The location and design of roads and existing and proposed infrastructure services to minimise the visual impact on the landscape.
- The need for high quality designed buildings that relate to the site, the river valley and the Calder Freeway.
- The buildings should have a contemporary design.
- The design of building will achieve environmental sustainable design principle objectives.
- The need for earthworks, waste and sediment created during the construction to be managed to minimise environmental impacts.

8.0 Signs

08/07/2021
C211brim

Sign requirements are at Clause 52.05. All land located within this Schedule is in Category 3.

Background document

Overnewton Anglican Community College Keilor Campus Development Guidelines, Haskell Architects and Planisphere

Incorporated document

Overnewton Anglican Community College Keilor Campus Master Plan, Haskell Architects and Planisphere, March 2006.

08/07/2021
C211brim

SCHEDULE 6 TO CLAUSE 37.01 SPECIAL USE ZONE

Shown on the planning scheme map as **SUZ6**.

LOWTHER HALL ANGLICAN GRAMMAR SCHOOL EDUCATION CENTRE AND SPORTING CAMPUS

Purpose

To implement the Municipal Planning Strategy and Planning Policy Framework, including local planning policies.

To provide for the continued use and development of the land in accordance with an approved Master Plan.

To protect and enhance natural resources and the biodiversity of the area.

To encourage development and use of land which is consistent with sustainable land management and land capability practices, and which takes into account the conservation values and environmental sensitivity of the locality.

To ensure that the scale of use is compatible with the non-urban character of the surrounding metropolitan green wedge land.

1.0 Table of uses

14/11/2022
VC227

Section 1 - Permit not required

Use	Condition
Animal keeping (other than animal boarding)	Must be no more than 2 animals.
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Bed & breakfast	No more than 6 persons may be accommodated away from their normal place of residence. At least 1 car parking space must be provided for each 2 persons able to be accommodated away from their normal place of residence.
Car park	Must be generally in accordance with a Master Plan approved by the responsible authority.
Geothermal energy extraction	Must meet the requirements of Clause 52.08.
Home based business	
Indoor recreation facility	Must be generally in accordance with a Master Plan approved by the responsible authority.
Informal outdoor recreation	
Mineral exploration	
Mining	Must meet the requirements of Clause 52.08.
Outdoor recreation facility	Must be generally in accordance with a Master Plan approved by the responsible authority.

Use	Condition
Railway	
Search for stone	Must not be costeaning or bulk sampling.
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01

Section 2 - Permit required

Use	Condition
Agriculture (other than Animal keeping, Apiculture, Intensive animal husbandry and Timber production)	
Dependent person's unit	Must be the only dependent person's unit on the lot. Must meet the requirements of Clause 35.06- 2.
Dwelling (other than bed & breakfast)	Must be the only dwelling on the lot. This does not apply to the replacement of an existing dwelling if the existing dwelling is removed or altered (so it can no longer be used as a dwelling) within one month of the occupation of the replacement dwelling. Must meet the requirements of Clause 35.06-2.
Education centre	Must not be on land covered by the Melbourne Airport Environs Overlay Schedule 1 (MAEO1) Must be generally in accordance with a Master Plan approved by the responsible authority.
Emergency services facility	
Freezing and cool storage	The goods stored must be agricultural produce, or products used in agriculture.
Group Accommodation	Must be in conjunction with Agriculture, Rural Industry or Winery. Must be no more than 6 dwellings. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to the zone. If no area is specified, the lot must be at least 40 ha. This condition only applies to land in Metropolitan Melbourne.
Host farm **Interpretation centre** **Mineral, stone or soil extraction (other than Mineral exploration, Mining, and search for stone)**	
Market **Plant nursery**	

Use	Condition
Primary produce sales	
Recreational boat facility	
Residential hotel	Must be in conjunction with Agriculture, Rural Industry or Winery. The number of bedrooms must not exceed the number specified in a schedule to the zone or 80 bedrooms, whichever is the lesser. The lot on which the use is conducted must be at least the minimum subdivision area specified in a schedule to the zone. If no area is specified, the lot must be at least 40 ha. This condition only applies to land in Metropolitan Melbourne.
Restaurant	Must be used in conjunction with Agriculture, Rural industry, or Winery. The number of patrons present must not exceed the number specified in a schedule to the zone or 150 patrons, whichever is the lesser. The lot on which the use is conducted must be lat lest the minimum subdivision area specified in a schedule to this zone. If no area is specified, the lot must be at least 40 ha. This condition only applies to land in Metropolitan Melbourne.
Rural industry (other than Abattoir and Sawmill)	
Rural store	
Timber production	Must meet the requirements of Clause 53.11.
Utility installation (other than Minor utility installation and telecommunications facility)	
Wind energy facility	
Winery	

Section 3 - Prohibited

Use
Abattoir
Accommodation (other than Dependent person's unit, Dwelling, Group accommodation, Host farm and Residential hotel)
Animal boarding
Industry (other than Automated collection point and Rural industry)
Intensive animal husbandry
Leisure and recreation (other than Informal outdoor recreation, Indoor recreation facility and Outdoor recreation facility)
Retail premises (other than Market, Plant nursery, Primary produce sales and Restaurant)

Use
Place of assembly (other than Carnival and Circus)
Sawmill
Warehouse (other than Freezing and cool storage, and Rural store)
Any other use not in Sections 1 or 2

2.0 Master Plan

27/05/2010
C86

Before a new use or development commences a Master Plan must be approved to the satisfaction of the responsible authority.

Before the approval of the Master Plan, or any amendments to the Master Plan, the responsible authority must consider the views of Australia Pacific Airports (Melbourne).

Details of landscaping must be included in the Master Plan and must exclude potential bird attracting species. The *Melbourne Airport Urban Landscape Plantings* guide should be used as a reference to determine appropriate landscape species. The views of Australia Pacific Airports (Melbourne) must be considered in relation to the landscape species.

3.0 Application requirements for use of land

08/07/2021
C211brim

An application to use land must be generally in accordance with the approved Master Plan.

Application requirements

The following application requirements apply to an application for a permit under Clause 37.01, in addition to those specified in Clause 37.01 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- The purpose of the use and types of activities which will be carried out; and
- The likely effects, if any, on the adjoining land including noise levels, traffic and hours of operation and spill of light.

4.0 Use of land for a dwelling

27/05/2010
C86

A lot used for a dwelling must meet the following requirements:

- Access to the dwelling must be provided via an all-weather road with dimensions adequate to accommodate emergency vehicles;
- The dwelling must be connected to a reticulated sewerage system or if not available, the waste water must be treated and retained on-site in accordance with the State Environment Protection Policy (Waters of Victoria) under the Environment Protection Act 1970;
- The dwelling must be connected to a reticulated potable water supply or have an alternative potable water supply with adequate storage for domestic use as well as for fire fighting purposes;
- The dwelling must be connected to a reticulated electricity supply or have an alternative energy source.

These requirements also apply to a dependent person's unit

5.0 Subdivision

27/05/2010
C86

A permit is required to subdivide land.

Each lot must be at least 40 hectares.

A permit may be granted to create smaller lots if any of the following apply:

- The subdivision is the re-subdivision of existing lots, the number of lots is not increased, and the number of dwellings that the land could be used for does not increase. An agreement under Section 173 of the Act must be entered into with the owner of each lot created which ensures that the land may not be further subdivided so as to increase the number of lots. The agreement must be registered on title. The requirement to enter into an agreement only applies to a lot which could be further subdivided in accordance with this scheme.
- The subdivision is by a public authority or utility service provider to create a lot for a utility installation

6.0 Long term lease or licence for Accommodation

27/05/2010
C86

A permit is required to lease or licence a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation.

Each portion of a lot leased or licensed for the purpose of Accommodation must be at least 40 hectares.

This provision only applies to land in Metropolitan Melbourne.

7.0 Buildings and works

20/01/2022
VC205

A permit is not required to construct or carry out any buildings and works other than:

- A building which is within any of the following setbacks:
  - 100 metres from a Transport Zone 2 or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority and the purpose of the acquisition is for a road.
  - 40 metres from a Transport Zone 3 or land in a Public Acquisition Overlay if the Head, Transport for Victoria is not the acquiring authority and the purpose of the acquisition is for a road.
  - 20 metres from any other road.
  - 5 metres from any other boundary.
  - 100 metres from a dwelling not in the same ownership.
  - 100 metres from a waterway, wetlands or designated flood plain.
- A building or works associated with a use in Section 2 of this clause other than:
  - An alteration or extension to an existing dwelling if the floor area is no more than the 50 square metres.
  - An out-building associated with an existing dwelling provided the floor area of the out-building does not exceed 50 square metres.
  - An alteration or extension to an existing building used for agriculture with a floor area of no more than 50 square metres. The building must not be used to keep, board, breed or train animals.
  - A rainwater tank.

Application Requirements

The following application requirements apply to an application for a permit under Clause 37.01, in addition to those specified in Clause 37.01 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A written assessment of the proposal against the provisions of the Brimbank Planning Scheme;
- Plans drawn to scale, which show:

- The boundaries and dimensions of the site;
- Relevant ground levels;
- Adjoining roads;
- The location, height and purpose of buildings and works on the subject land;
- The location, height and purpose of buildings and works on adjoining land;
- The layout and use of existing and proposed buildings and works, including driveways and car parking and loading areas;
- Elevation drawings including a schedule of the colour, finishes and construction materials of all proposed buildings and works;
- Construction details of all drainage works, driveways and car parking and loading areas;
- A schedule of existing and proposed landscaping of the site, including a maintenance programme for the landscaped areas.

Exemption from notice and review

An application to construct or carry out works for an education centre generally in accordance with a Master Plan approved by the responsible authority is exempt from the notice requirements of Section 52(1) (a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act.

8.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 37.01 to use or subdivide land, lease or license a portion of a lot for a period of more than 10 years if the portion is to be leased or licensed for the purpose of Accommodation, construct a building or construct or carry out works, in addition to those specified in Clause 37.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

General Issues

- The Municipal Planning Strategy and Planning Policy Framework, including local planning policies.
- The purpose of this Schedule.
- The Master Plan approved under Clause 2.0 of this Schedule.
- Any Regional Catchment Strategy and associated plan applying to the land.
- The capability of the land to accommodate the proposed use or development.
- Whether use or development protects and enhances the environmental, agricultural and landscape qualities of the site and its surrounds.
- Whether the site is suitable for the use or development and the compatibility of the proposal with adjoining land uses.
- Whether the proposed use of the site has regard for the amenity of the neighbourhood.
- Any traffic or parking issues which will result from the proposal.
- The views of Australia Pacific Airports (Melbourne) for applications for use of land as an education centre.

Rural Issues

- The environmental capacity of the site to sustain the proposal.
- The need to prepare an integrated land management plan where a rural enterprise is proposed.

- The impact on the existing and proposed infrastructure.
- Whether the use or development will have an adverse impact on surrounding land uses.

Environmental Issues

- An assessment of the likely environmental impact on the biodiversity and in particular the flora and fauna of the area.
- The protection and enhancement of the natural environment of the area, including the retention of vegetation and faunal habitats and the need to revegetate land including riparian buffers along waterways, gullies, ridgelines, property boundaries and saline discharge and recharge areas.
- How the use and development relates to sustainable land management and the need to prepare an integrated land management plan which addresses the protection and enhancement of native vegetation and waterways, stabilisation of soil and pest plant and animal control.
- The location of on site effluent disposal areas to minimise the impact of nutrient loads on waterways and native vegetation.

Design and Siting Issues

- The need to minimise any adverse impacts of siting, design, height, bulk, and colours and materials to be used, on adjoining land uses, the Maribyrnong River Valley and the Calder Freeway.
- The need to ensure that new buildings are of a high quality articulated design that responds appropriately to the topography of the site.
- The location and design of existing and proposed infrastructure services which minimises the visual impact on the landscape.
- The need to minimise adverse impacts on the character and appearance of the area or features of archaeological, historic or scientific significance or of natural scenic beauty or importance.
- The location and design of roads and existing and proposed infrastructure services to minimise the visual impact on the landscape.
- The need for earthworks, waste and sediment created during the construction to be managed to minimize environmental impacts.

9.0 Signs

08/07/2021
C211brim

Sign requirements are at Clause 52.05. All land located within this Schedule is in Category 4.

37.02 COMPREHENSIVE DEVELOPMENT ZONE

31/07/2018
VC148

Shown on the planning scheme map as **CDZ** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To provide for a range of uses and the development of land in accordance with a comprehensive development plan incorporated in this scheme.

37.02-1 Table of uses

19/01/2006
VC37

Section 1 - Permit not required

Use	Condition
Any use in Section 1 of the schedule to this zone	Must comply with any condition in Section 1 of the schedule to this zone.

Section 2 - Permit required

Use	Condition
Any use in Section 2 of the schedule to this zone	Must comply with any condition in Section 2 of the schedule to this zone.
Any other use not in Section 1 or 3 of the schedule to this zone	

Section 3 - Prohibited

Use
Any use in Section 3 of the schedule to this zone

37.02-2 Use of land

31/07/2018
VC148

Any requirement in the schedule to this zone must be met.

Application requirements

An application to use land must be accompanied by any information specified in the schedule to this zone.

Exemption from notice and review

The schedule to this zone may specify that an application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any guidelines in the schedule to this zone.

37.02-3 Subdivision

15/03/2024
VC256

Permit requirement

A permit is required to subdivide land.

An application to subdivide land for residential development, other than an application to subdivide land into lots each containing an existing dwelling or car parking space, must meet the requirements of Clause 56 and:

- Must meet all of the objectives included in the clauses specified in the following table.
- Should meet all of the standards included in the clauses specified in the following table.

Class of subdivision	Objectives and standards to be met
60 or more lots	All except Clause 56.03-5.
16 – 59 lots	All except Clauses 56.03-1 to 56.03-3, 56.03-5, 56.06-1 and 56.06-3.
3 – 15 lots	All except Clauses 56.02-1, 56.03-1 to 56.03-4, 56.05-2, 56.06-1, 56.06-3 and 56.06-6.
2 lots	Clauses 56.03-5, 56.04-2, 56.04-3, 56.04-5, 56.06-8 to 56.09-2.

Any requirement in the schedule to this zone must be met.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: - The area of either lot is reduced by less than 15 percent. - The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: - The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. - An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: - The construction of a building or the construction or carrying out of works on the land:	Clause 59.02

Class of application	Information requirements and decision guidelines
– Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	

Application requirements

An application to subdivide land must be accompanied by any information specified in the schedule to this zone.

Exemption from notice and review

The schedule to this zone may specify that an application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The objectives and standards of Clause 56.
- Any guidelines in the schedule to this zone.

37.02-4 Buildings and works

20/12/2021
VC174

Permit requirement

A permit is required to construct a building or construct or carry out works unless the schedule to this zone specifies otherwise.

Any requirement in the schedule to this zone must be met.

An apartment development must meet the requirements of Clause 58.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $500,000 and the land is not: ▪ Within 30 metres of land (not a road) which is in a residential zone. ▪ Used for a purpose listed in the table to Clause 53.10.	Clause 59.04

Transitional provisions

Clause 58 does not apply to:

- An application for a planning permit lodged before the approval date of Amendment VC136.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before the approval date of Amendment VC136.

Clause 58 of this scheme, as in force immediately before the approval date of Amendment VC174, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Application requirements

An application to construct a building or construct or carry out works must be accompanied by any information specified in the schedule to this zone.

An application to construct or extend an apartment development, or to construct or extend a dwelling in or forming part of an apartment development, must be accompanied by an urban context report and design response as required in Clause 58.01.

Exemption from notice and review

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if it is generally consistent with the comprehensive development plan.

The schedule to this zone may specify that other applications are also exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- For an apartment development, the objectives, standards and decision guidelines of Clause 58.
- Any guidelines in the schedule to this zone.

37.02-5 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 3 unless a schedule to this zone specifies a different category.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 37.02 COMPREHENSIVE DEVELOPMENT ZONE

Shown on the planning scheme map as **CDZ1.**

SYDENHAM REGIONAL ACTIVITY CENTRE

Land

Sydenham Activity Centre

Purpose

To facilitate development of the regional centre satisfying the needs of the existing and future population.

To encourage the provision of a comprehensive and balanced range of activities, services and facilities to meet the needs of the local and regional community.

To promote the regional centre as a community focal point and town centre.

To ensure that the regional centre is accessible to the community twenty-four hours a day.

To promote activities which will attract people to the regional centre after normal shopping and working hours.

To encourage development of a high quality, attractive environment.

To ensure that the various land use activities in and adjacent to the regional centre are physically and functionally integrated.

To provide sufficient flexibility to enable changes to occur to the range of activities accommodated in the regional centre to satisfy changing demands in the community over time.

To provide for medium density housing to best utilise the proximity to the regional centre.

To enable provision of community and service infrastructure related to the regional centre.

To provide for an integrated public transport system to serve the regional centre.

To provide certainty of approvals for development and uses which comply with the Structure Plan.

1.0 Table of uses

01/12/2023
VC217

Section 1 - Permit not required

Use	Condition
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
See Table to Clause 1.0	All uses must comply with the Sydenham Regional Activity Structure Plan which is incorporated into the scheme.
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition

Section 3 - Prohibited

Use
Any use not in Section 1 or 2.

1.1 Table to Clause 1.0

08/07/2021
C211brim

Precinct	Use	Conditions
F. **Transport Terminal**	Car Park Vehicle Store Informal Outdoor Recreation Railway Transport Terminal Office Convenience Restaurant Convenience Store Restaurant Shop Take-Away Food Premises	
H. **Emergency Services**	Ambulance Station Car Park Community Service Purpose Court Emergency Services Fire Station Informal Outdoor Recreation Police Station	
	Restricted Retail Premises (Must only be Automotive Parts & Accessory Sales) Motor Vehicle, Boat and Caravan Sales Commercial Display Area Car Wash Motor Repairs	The maximum number of individual tenancies within the Precinct is 5.
I. **Fringe Commercial**	Restricted Retail Premises Commercial Display Area Car Wash Motor Repairs Motor Vehicle, Boat & Caravan Sales	Must only be Automotive Parts & Accessory Sales
	Car Park	

Precinct	Use	Conditions
	Restricted Retail Premises - only for the sale or hire of party supplies or materials, tools, equipment or machinery for use in industry, commerce, the building or automotive trades, the medical profession, landscape gardening or primary production. Trade Supplies	
J. **Fast Food**	Restricted Retail Premises Commercial Display Area Car Wash Motor Repairs Motor Vehicle, Boat & Caravan Sales	Must only be automotive parts and accessory sales The maximum number of individual tenancies within the Precinct including Cafe, Restaurant and Take-Away Food Premises is 5.
	Car Park Convenience Restaurant Informal Outdoor Recreation Restaurant Take-Away Food Premises	
K. **Convenience Store**	Convenience Store Car Wash Service Station	
L. **Office Accommodation Park**	Commercial Display Area	The display of all goods must be contained in the building. At least 50% of the floor area must be used for the purpose of Office.
	Dwelling Motel Office Place of Assembly Reception Centre Residential Building Retirement Village	
M. **Education/ Worship Residential**	Dwelling	The density must be at least 25 dwellings per hectare net.
	Outdoor Recreation Facility Child Care Centre Education Centre	

Precinct	Use	Conditions
	Hospital	
	Corrective Institution	
	Medical Centre	
	Place of Worship	
	Retirement Village	
N. **Town Centre** **Residential 1**	Dwelling	The use must occupy at least half the land in the Precinct. The density must be at least 25 dwellings per hectare net.
	Outdoor Recreation Facility	
	Child Care Centre	
	Funeral Parlour	
	Hospital	
	Corrective Institution	
	Medical Centre	
	Place of Assembly	
	Place of Worship	
	Reception Centre	
	Residential Building	
	Retirement Village	
	Veterinary Centre	
O. **Town Centre** **Residential 2**	Dwelling	The density must be to the satisfaction of the Responsible Authority.
	Outdoor Recreation Facility	
	Child Care Centre	
	Hospital	
	Corrective Institution	
	Medical Centre	
	Place of Worship	
	Retirement Village	

2.0 Requirement for concept plan

08/07/2021
C211brim

No new buildings or works may be constructed within a Precinct until a Concept Plan for that Precinct is prepared to the satisfaction of the Responsible Authority after taking into account the comments (if any) of a relevant public authority (including - the Department of Planning and Community Development for urban design matters in Precincts O, M, F and N; Melbourne Water

Corporation for drainage, flooding and waterway management matters, VicRoads for traffic and access arrangements on the arterial road network and Department of Transport for public transport matters).

A Concept Plan must show the proposed uses and development of the Precinct and must be generally in accordance with the Structure Plan, to the satisfaction of the Responsible Authority.

Within Precincts M, N and O, the Concept Plan must show the layout of the whole Precinct and its relationship with adjacent residential and non-residential land.

The Responsible Authority may approve modifications to a Concept Plan after having referred any such modifications to and after taking into account the comments (if any) of any relevant public authority and the owner/s of the land.

3.0 Subdivision

19/05/2011
C117

Permit requirement

Arrangements for water supply, sewerage and drainage must be to the satisfaction of the relevant referral authority listed in Clause 66.01.

Application requirements

For land in Precincts I, J and L (separately), any subdivision must provide for the creation of a Body Corporate to assume responsibility for the maintenance of all public areas within such Precincts to the satisfaction of the Responsible Authority.

For subdivision in Precincts M, N and O, either 8 per cent of the land must be provided as public open space or cash in lieu of this provision made, to the satisfaction of the Responsible Authority.

4.0 Buildings and works

19/01/2006
VC37

Permit requirement

A permit is not required to construct a building or to construct or carry out works.

All buildings and works must be constructed and carried out in accordance with Buildings and Works Plans prepared to the satisfaction of the Responsible Authority and generally in accordance with the Concept Plan.

5.0 Car parking

08/07/2021
C211brim

Provision must be made for car parking in accordance with the Table to this sub-clause. For any use not listed, provision must be in accordance with Clause 52.06.

Use	Parking (Spaces) Required
Motor Vehicle, Boat & Caravan Sales	1.0 space/100 square metres of site area
Nightclub **Reception Centre** **Tavern**	0.3 spaces/seat or 0.3 spaces/ square metre of floor area available to the public
Cinema	0.3 spaces/seat
Medical Centre **Health Centre**	5 spaces/practitioner
Hotel	0.8 spaces/room plus 1 space/residential employee plus 0.3 spaces/square metre of floor area available to the public

Use	Parking (Spaces) Required
Motel	1 space/unit plus 1 space/residential employee plus 2 spaces/100 square metres of Motel service floor area not available for use by guests
Office	3.5 spaces/100 square metres of floor area
Restricted Retail Premises	2.5 spaces/100 square metres of floor area
Restaurant	0.45 spaces/seat
Shop - Supermarket, Department Store, Discount Department Store and the like.	6.5 spaces/100 square metres of gross leasable floor area
Shop - Other than Supermarket, Department Store, Discount Department Store and the like.	4.0 spaces/100 square metres of gross leasable floor area.
Take-Away Food Premises	15 spaces/100 square metres of floor area available to the public.

The Responsible Authority may consent to a lesser provision if it is satisfied that the number of spaces required is unnecessary in the circumstances or can be provided on other land in the locality in accordance with the Structure Plan.

6.0 Transport plan

08/07/2021
C211brim

For any new buildings or works a Transport Plan must be prepared to the satisfaction of the Responsible Authority if requested in writing by the Responsible Authority.

Details of the Transport Plan concerning traffic and access arrangements on the arterial road network must be referred to the Roads Corporation for comment.

Details of the Transport Plan concerning public transport matters must be referred to the Public Transport Corporation for comment.

The Transport Plan must include a full traffic analysis, traffic management and traffic control works to be carried out as a consequence of the new use or development. Such works must be consistent with the Structure Plan and Concept Plan and provide appropriate access and circulation to the site and within the site.

The Transport Plan must identify works to be undertaken and responsibility for and timing of their implementation.

When works designated by the Transport Plan are to be undertaken solely by the owner then all such works must be carried out or security given before the issue of any Certificate of Occupancy under the Building Regulations 1994 for any part of the relevant development.

When works designated by the Transport Plan are to be undertaken by the owner and other persons or authorities, the obligations of the owner will be satisfied either when the owner has completed the works identified as the owners responsibility or when payment of the required contribution for such works is made by the owner to the relevant authority.

The works to be carried out must be in accordance with the Transport Plan.

7.0 Agreement

19/01/2006
VC37

Before the development commences, the owner/s of the land must enter into an agreement pursuant to Section 173 of the Planning & Environment Act providing for contribution towards on-site community facilities and services, public transport and off-site road and traffic improvements directly related to the development.

8.0 Signs

08/07/2021
C211brim

Signs requirements are at Clause 52.05.

This zone is in the following categories of Clause 52.05.

Precinct	Category
F	1
H-L (Inclusive)	2
M-O (Inclusive)	4

08/07/2021
C211brim

SCHEDULE 2 TO CLAUSE 37.02 COMPREHENSIVE DEVELOPMENT ZONE

Shown on the planning scheme map as **CDZ2**.

WATERGARDENS TOWN CENTRE

Land

This schedule applies to the land bounded by Melton Highway, Kings Road and Bendigo – Melbourne Rail Line, as identified in the incorporated plan, the *Watergardens Town Centre Framework Plan* (March 2009) set out below.

Map 1 to Schedule 2 to Clause 37.02



Purpose

To provide for the integrated use and development of land generally in accordance with the *Watergardens Town Centre Framework Plan* (March 2009) and the design and development principles set out in this schedule.

To create a town centre as a central component of the Sydenham Principal Activity Centre by broadening the mix of activity to include residential, commercial, retail, community, entertainment and civic linked to public transport infrastructure in accordance with Principal Activity Centre objectives, to meet the needs of the local and regional community.

To ensure safe and attractive 24 hour pedestrian access is provided throughout the Watergardens Town Centre including along the general alignment of Taylors Creek.

To ensure that best practice urban design principles are an integral component of the design of the Town Centre, including innovative architecture that will result in good quality, environmentally sustainable buildings and interactive spaces.

To integrate Taylors Creek as a key feature of Watergardens Town Centre and ensure its drainage, flood control and open space functions are preserved and enhanced.

1.0 Table of uses

14/11/2022
VC227

Section 1 - Permit not required

Use	Condition
Accommodation (other than Corrective Institution)	
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Betting agency	
Bottle Shop	
Car Park	
Car Wash	
Child Care Centre	
Cinema based entertainment facility	
Convenience Shop	
Education Centre	
Electoral Office	May be used for only 4 months before an election and 2 weeks after an election.
Food and Drink Premises	
Home based business	
Informal Outdoor Recreation	
Landscape Gardening Supplies	
Market	
Mineral exploration	
Mining	Must meet the requirements of Clause 52.08.
Office (other than electoral office)	
Outdoor Recreation Facility	
Place of Assembly (other than carnival or circus)	
Postal Agency	
Railway	
Search for stone	Must not be costeaning or bulk sampling
Service Station	

Use	Condition
Shop	
Trade Supplies	
Tramway	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01

Section 2 - Permit required

Use	Condition
Extractive industry	
Industry (other than Automated collection point)	Must not be a purpose listed in the table to Clause 53.10.
Warehouse	Must not be a purpose listed in the table to Clause 53.10.
Any other use not in Section 1 or 3	

Section 3 - Prohibited

Use
Corrective institution
Intensive animal husbandry
Major sports and recreation facility
Motor racing track

2.0 Use of land

08/07/2021
C211brim

Amenity

A use must not detrimentally affect the amenity of the Town Centre, including through the:

- Transport of materials, goods or commodities to or from the land.
- Appearance of any building, works or materials.
- Emission of noise, artificial light, vibration, smell, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.

Application requirements

The following application requirements apply to an application for a permit under Clause 37.02, in addition to those specified in Clause 37.02 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- The purpose of the use and the type of activities which will be carried out;
- The likely effects, if any, on adjoining land including noise levels, water and air-borne emissions, traffic, hours of operation, hours of delivery and despatch, light spill and solar access;
- The means of maintaining land not required for immediate use.

Exemption from notice and review

An application is exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act. This exemption does not apply to an application within 30 metres of land (not a road) which is in a residential zone or Business 5 Zone, land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a Hospital or an education centre.

3.0 Subdivision

08/07/2021
C211brim

Application requirements

The following application requirements apply to an application for a permit under Clause 37.02, in addition to those specified in Clause 37.02 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A plan drawn to scale which shows:
  - The boundaries and dimensions of the site;
  - Adjoining roads;
  - Areas of subdivision, including any areas of common property.

Exemption from notice and review

An application is exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act .

4.0 Buildings and works

19/05/2011
C117

Permit requirement

A permit is required to construct a building or to construct or carry out works unless the responsible authority is satisfied that the buildings or works are minor in nature, such as:

- The installation of an automatic teller machine.
- An alteration to an existing building façade provided:
  - The alteration does not include the installation of an external roller shutter.
  - At least 80 per cent of the building facade at ground floor level is maintained as an entry or window with clear glazing.
- An awning that projects over a road if it is authorised by the relevant public land manager
- Buildings and works associated with a section 1 use of less than 500 sqm of leasable floor space, which are consistent with the Design and Development Principles at Clause 8 of this schedule.

Exemption from notice and review

An application is exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act. This exemption does not apply to an application for a building or works within 30 metres of land (not a road) which is in a residential zone or Business 5 Zone, land used for a hospital or an education centre or land in a Public Acquisition Overlay to be acquired for a Hospital or an education centre.

5.0 Car parking

19/05/2011
C117

Car parking must be provided in accordance with this table. Where the use is not listed, provision must be made in accordance with Clause 52.06. The responsible authority may consent to a different provision if it is satisfied that the number of spaces proposed is appropriate.

Use	Parking (spaces) required
Dwelling	1 space to each 1-2 bedroom apartment and 1.5 spaces to each 3 or more bedroom apartment
Shop	4 spaces/100 sqm of leasable floor area
Office	3 spaces/100 sqm of leasable floor area
Restricted Retail	2 spaces/100 sqm of leasable floor area
Hotel	0.6 spaces / room
Tavern	0.2 spaces/patron or 20 spaces/100 sqm available to the public
Restaurant	0.25 spaces/seat
Cinema	0.3 spaces/seat
Medical Centre	3.5 spaces/practitioner

6.0 Signs

08/07/2021
C211brim

Sign requirements are at Clause 52.05. All land located within this Schedule is in Category 1.

7.0 Notice requirement

19/05/2011
C117

Notice of an application to use land or to construct a building or to construct or carry out works must be given under section 52(1)(c) of the Planning and Environment Act 1987 to the person or body specified as a person or body to be notified in Clause 66.06 or a schedule to that clause.

8.0 Design and development principles

19/05/2011
C117

An application must address the following design and development principles, as appropriate:

Access and movement/circulation

- Improve walking and cycling opportunities within and through the site, ensuring connections to existing trails and networks outside the Town Centre environs.
- Provide clear 24 hour continuous pedestrian linkages along and across Taylors Creek, connecting Watergardens Station and transit interchange, and signalised entry points.
- Provide an at-grade intersection between the Creek link and the Creek crossing at the centre's east end.

Vehicle access and car parking

- Provide a safe, efficient and legible circulation network for, pedestrians, cyclists, public transport and vehicles into and within the Town Centre.
- Design multi level car parks to be sensitive to surrounding development, with facades that contribute to the visual amenity and built form of the centre, and which as far as possible include ground level commercial uses/active frontages.
- Provide secure bicycle parking in convenient, central locations.

- Provide clearly identified long and short term parking areas.
- Enable direct bus access to the rail station
- Ensure parking provision supports sustainable transport modes

Built form

- Ensure built form comprises contemporary architecture that makes a positive contribution to the streetscape using generous building articulation, a mix of building materials and good quality finishes.
- Avoid excessive overshadowing of the Taylors Creek environs or other public open space areas.
- Avoid siting loading, service areas and blank walls adjacent to public and open space areas and use dense landscaping, architectural treatments, artwork or activation to screen existing non-active frontages, as appropriate.
- Design buildings that respond to the site, its surrounding context and microclimate, including preserving and enhancing views into and from the site and along Taylors Creek.
- Where possible make provision, through footings, roof designs and ground level access points, for future upper level use and development.

Ground level building frontages and orientation

- At ground level, provide active building frontages to streets and public realm areas.
- Adopt building designs and ground level uses that foster activity and natural surveillance of public spaces.
- Provide weather protection to open to air pedestrian routes within the retail core.

Mixed use

- Adopt building designs and site layouts that do not prevent the inclusion of a mix of uses to meet Principal Activity Centre objectives and the needs of the local and regional community.
- Ensure the vertical and horizontal integration of office, residential and other complementary uses throughout the site.

Open space and landscape design

- Establish a network of well designed public gathering spaces within and adjacent to the retail core, including spaces suitable for community events.
- Use landscaping to reinforce the urban structure, sense of place, connectivity and legibility of the town centre and Taylors Creek.
- Maximise views into and within the site and at key entrances, including through the use of planting to create and frame views.

Creek crossings

- Design creek crossings to enable continuity between retail precincts while also providing open, visual connection to the creek corridor and waterway.
- Minimise the extent of creek covering to ensure waterway health and to provide the opportunity to celebrate the creek as a key component of the centre.
- Use changes in form and materials to distinguish between buildings and creek crossing elements in ways that emphasise the creek.
- Design creek crossings to ensure there is capacity to convey stormwater flows meeting requirements for protection of the adjacent buildings including appropriate freeboard.
- Design the creek crossing to ensure maintenance access to the waterway.

Environmental design

- Use building design, orientation, servicing and construction that incorporates Environmentally Sustainable Design Principles, to address:
  - reductions in energy and water use during construction and operation
  - energy generation opportunities
  - water and waste management
  - materials selection and reuse

9.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 37.02, in addition to those specified in Clause 37.02 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- How the application contributes towards the achievement of an appropriate mix of uses, including housing and employment generating uses, supportive of the Town Centre's Principal Activity Centre status.
- The *WatergardensTown Centre Framework Plan* (March 2009).
- The Design and Development Principles at Clause 8 of this schedule.
- Activity Centre Design Guidelines (Department of Sustainability & Environment 2005).

37.03 URBAN FLOODWAY ZONE

01/07/2021
VC203

Shown on the planning scheme map as **UFZ**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify waterways, major floodpaths, drainage depressions and high hazard areas within urban areas which have the greatest risk and frequency of being affected by flooding.

To ensure that any development maintains the free passage and temporary storage of floodwater, minimises flood damage and is compatible with flood hazard, local drainage conditions and the minimisation of soil erosion, sedimentation and silting.

To reflect any declarations under Division 4 of Part 10 of the *Water Act, 1989*.

To protect water quality and waterways as natural resources by managing urban stormwater, protecting water supply catchment areas and managing saline discharges to minimise the risks to the environmental quality of water and groundwater.

37.03-1 Table of uses

14/01/2025
VC237

Section 1 - Permit not required

Use	Condition
Informal outdoor recreation	
Any use listed in Clause 62.01	Must meet the requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Agriculture (other than Animal production and Apiculture)	
Grazing animal production	
Leisure and recreation (other than Informal outdoor recreation, Indoor recreation facility, and Motor racing track)	
Road	
Utility installation (other than Telecommunications facility)	
Any use listed in Clause 62.01 if any requirement is not met	

Section 3 - Prohibited

Use
Animal production (other than Grazing animal production)
Indoor recreation facility
Motor racing track
Any other use not in Section 1 or 2

37.03-2 Buildings and works

17/02/2022
VC200

A permit is required to construct a building or construct or carry out works, including:

- A fence.
- Roadworks, if the water flowpath is redirected or obstructed.
- Bicycle pathways and trails, if the water flowpath is redirected or obstructed.
- Public toilets.
- A domestic swimming pool or spa and associated mechanical and safety equipment if associated with one dwelling on a lot.
- A pergola or verandah, including an open-sided pergola or verandah to a dwelling with a finished floor level not more than 800mm above ground level and a maximum building height of 3 metres above ground level.
- A deck, including a deck to a dwelling with a finished floor level not more than 800mm above ground level.
- A non-domestic disabled access ramp.

This does not apply to:

- Roadworks or bicycle paths and trails constructed or carried out by or on behalf of the Head, Transport for Victoria, to the satisfaction of the relevant floodplain management authority.
- Flood mitigation works carried out by the responsible authority or floodplain management authority.
- The following works in accordance with plans prepared to the satisfaction of the responsible authority:
  - The laying of underground sewerage, water and gas mains, oil pipelines, underground telephone lines and underground power lines provided they do not alter the topography of the land.
  - The erection of telephone or power lines provided they do not involve the construction of towers or poles.
- Post and wire and post and rail fencing.

37.03-3 Subdivision

14/12/2023
VC253

A permit is required to subdivide land. A permit may only be granted to subdivide land if the following apply:

- The subdivision does not create any new lots, which are entirely within this zone. This does not apply if the subdivision creates a lot, which by agreement between the owner and the relevant floodplain management authority, is to be transferred to an authority for a public purpose.
- The subdivision is the resubdivision of existing lots and the number of lots is not increased, unless a local floodplain development plan incorporated into this scheme specifically provides otherwise.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

37.03-4 Application requirements

31/07/2018
VC148

General

An application must be accompanied by any information specified in the schedule to this zone.

Local floodplain development plan

If a local floodplain development plan has been developed for the area and has been incorporated into this scheme, an application must be consistent with the plan.

Flood risk report

If a local floodplain development plan for the area has not been incorporated into this scheme, an application must be accompanied by a flood risk report to the satisfaction of the responsible authority. The flood risk report must consider the following, where applicable:

- The existing use and development of the land.
- Whether the proposed use or development could be located on flood-free land or land with a lesser flood hazard outside this zone.
- The susceptibility of the development to flooding and flood damage.
- The potential flood risk to life, health and safety associated with the development. Flood risk factors to consider include:
  - The frequency, duration, extent, depth and velocity of flooding of the site and accessway.
  - The flood warning time available.
  - The danger to the occupants of the development, other floodplain residents and emergency personnel if the site or accessway is flooded.
- The effect of the development on redirecting or obstructing floodwater, stormwater or drainage water and the effect of the development on reducing flood storage and increasing flood levels and flow velocities.
- The effects of the development on environmental values such as natural habitat, stream stability, erosion, water quality and sites of scientific significance.

37.03-5 Referral of applications

19/01/2006
VC37

An application must be referred to the relevant floodplain management authority under Section 55 of the Act unless in the opinion of the responsible authority the proposal satisfies requirements or conditions previously agreed in writing between the responsible authority and the floodplain management authority.

37.03-6 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The local floodplain development plan or flood risk report.
- Any comments of the relevant floodplain management authority.
- Any other matters specified in the schedule to this zone.

37.03-7 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 4 unless the schedule to this zone specifies a different category.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 37.03 URBAN FLOODWAY ZONE

1.0 Application requirements

08/07/2021
C211brim

None specified.

2.0 Decision guidelines

08/07/2021
C211brim

None specified.

3.0 Signs

08/07/2021
C211brim

Land	Sign Category
None specified	

37.08 ACTIVITY CENTRE ZONE

31/07/2018
VC148

Shown on the planning scheme map as **ACZ** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To encourage a mixture of uses and the intensive development of the activity centre:

- As a focus for business, shopping, working, housing, leisure, transport and community facilities.
- To support sustainable urban outcomes that maximise the use of infrastructure and public transport.

To deliver a diversity of housing at higher densities to make optimum use of the facilities and services.

To create through good urban design an attractive, pleasant, walkable, safe and stimulating environment.

To facilitate use and development of land in accordance with the Development Framework for the activity centre.

37.08-1 Operation

17/09/2009
VC59

A schedule to this zone comprises the Development Framework for the activity centre.

A schedule to this zone must contain:

- A framework plan for the activity centre.
- A statement of the activity centre land use and development objectives to be achieved.

A schedule to this zone may contain:

- Centre-wide provisions.
- Precinct provisions.

37.08-2 Table of uses

17/09/2009
VC59

Section 1 - Permit not required

Use	Condition
Any use in Section 1 of the schedule to this zone	Must comply with any condition in Section 1 of the schedule to this zone.

Section 2 - Permit required

Use	Condition
Any use in Section 2 of the schedule to this zone	Must comply with any condition in Section 2 of the schedule to this zone.

Section 3 - Prohibited

Use
Any use in Section 3 of the schedule to this zone

37.08-3 Use of land

17/09/2009
VC59

Any requirement in the schedule to this zone must be met.

37.08-4 Subdivision

14/12/2023
VC253

A permit is required to subdivide land.

Any requirement in the schedule to this zone must be met.

A permit must not be granted which would allow a separate lot to be created for land containing a small second dwelling.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.02
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

37.08-5 Buildings and works

31/07/2018
VC148

A permit is required to construct a building or construct or carry out works unless the schedule to this zone specifies otherwise.

An apartment development must meet the requirements of Clause 58.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works with an estimated cost of up to $500,000 and the land is not: ▪ Within 30 metres of land (not a road) which is in a residential zone. ▪ Used for a purpose listed in the table to Clause 53.10.	Clause 59.04

Transitional provisions

Clause 58 does not apply to:

- An application for a planning permit lodged before the approval date of Amendment VC136.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before the approval date of Amendment VC136.

37.08-6 Design and development

17/09/2009
VC59

A schedule to this zone may include requirements relating to:

- Building setbacks.
- Building height.
- Building materials.
- Access.
- Landscaping.
- Public realm.
- Any other requirements or guidelines relating to the design or built form of new development.

A permit may be granted to construct a building or construct or carry out works which is not in accordance with any design and development requirement in the schedule to this zone unless the schedule to this zone specifies otherwise.

37.08-7 Application requirements

14/01/2025
VC237

Use

An application to use land must be accompanied by the following information, as appropriate:

- A description of the proposed use and the types of activities which will be carried out and any proposed staging of use and activities on the land.
- Plans drawn to scale and dimensioned which show:
  - The siting and use of buildings.
  - Areas not required for immediate use.
  - Adjacent buildings and uses.
- The likely effects, if any, on adjoining land, including noise levels, traffic, the hours of delivery and despatch of goods and materials, hours of operation and light spill, solar access, glare, air-borne emissions and emissions to land and water.
- If an industry or warehouse:
  - The type and quantity of goods to be stored, processed or produced.

  - Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority.
  - Whether a notification under the Occupational Health and Safety Regulations 2017 is required, a licence under the *Dangerous Goods Act 1985* is required, or a fire protection quantity under the Dangerous Goods (Storage and Handling) Regulations 2022 is exceeded.
- Any other information specified in the schedule to this zone.

Subdivision

An application to subdivide land must be accompanied by the following information, as appropriate:

- Plans drawn to scale and dimensioned which show:
  - Site shape, size, dimensions and orientation.
  - The pattern of subdivision of the surrounding area.
  - Easements.
  - Location of drainage and other utilities.
  - Street frontage features such as poles, street trees and kerb crossovers.
  - Access points.
  - Any natural features.
- Any other information specified in the schedule to this zone.

Buildings and works

An application to construct a building or construct or carry out works must be accompanied by the following information, as appropriate:

- Plans drawn to scale and dimensioned which show:
  - The boundaries and dimensions of the site.
  - Adjoining roads.
  - The location, height and use of buildings and works on adjoining land.
  - Levels of the site and the difference in levels between the site and surrounding properties to a defined point at the site boundaries or to Australian Height Datum (AHD).
  - Any contaminated soils and filled areas, where known.
  - The layout of existing and proposed buildings and works.
  - The internal layout and use of the proposed development.
  - All access and pedestrian areas.
  - All driveway, car parking and loading areas.
  - Existing vegetation and proposed landscape areas.
  - All external storage and waste treatment areas.
  - The location of easements and services.
- Elevation plans drawn to scale and dimensioned which show:
  - The building form and scale.

  - Setbacks to property boundaries.
  - Finished floor levels and building heights to a defined point at the site boundaries or to Australian Height Datum (AHD).
- Shadow diagrams based on the equinox shown for existing conditions and the proposed development.
- A schedule of finishes for the proposed development detailing materials and colours of external surfaces including walls, roofs and fences.
- A written statement providing an assessment of the proposal against the relevant sections of the Planning Policy Framework, Activity Centre Zone and any relevant overlays.
- An assessment of the characteristics of the area including:
  - Any environmental features such as vegetation, topography and significant views.
  - Street design and landscape.
  - The pattern of development.
  - Building form, scale and rhythm.
  - Architectural style, building details and materials.
  - Connection to the public realm.
  - Any significant noise, odour, fume and vibration sources to and/or from the development.
- A landscape plan which includes the description of vegetation to be planted, the surfaces to be constructed, site works specification and method of preparing, draining, watering and maintaining the landscape area.
- Construction details of all drainage works, driveways, vehicle parking and loading areas.
- An urban context report and design response as required in Clause 58.01 for an application to construct or extend an apartment development, or to construct or extend a dwelling in or forming part of an apartment development.
- Any other information specified in the schedule to this zone.

37.08-8 Exemption from notice and review

31/07/2018
VC148

An application under Clauses 37.08-2, 37.08-4, 37.08-5 or 37.08-6 is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act unless the schedule to this zone specifies otherwise.

A schedule to this zone may specify an application in respect of land in an Activity Centre Zone under any other specified provision of this scheme is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

37.08-9 Decision guidelines

08/09/2025
VC282

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

General

- The Municipal Planning Strategy and the Planning Policy Framework.
- The development framework plan set out in the schedule to this zone.
- The land use and development objectives set out in the schedule to this zone.

- The extent that the layout and design of the new use or development minimises the potential for off-site impacts, including from noise, fumes, odour or vibrations, ensuring that:
  - existing uses are not compromised by a new development, or
  - a new development is designed to address amenity impacts from existing uses.
- Any requirements set out in the schedule to this zone.
- Any other decision guidelines specified in the schedule to this zone.

Access

- Movements systems through and around the site including the movement of pedestrians and cyclists, and vehicles providing for supplies, waste removal, emergency services and public transport.
- The provision of car parking, loading of vehicles and access to parking spaces and loading bays.

Use

- The interim use of those parts of the land not required for the proposed use.
- Whether the use is compatible with adjoining and nearby land uses.

Subdivision

- The pattern of subdivision and its effect on the spacing of buildings.
- For subdivision of land for residential development, the objectives and standards of Clause 56.

Design and built form

- The design, scale, height, setback, appearance and material of the proposed buildings and works.
- The provision for solar access to the building and on the public realm.
- The design of the public realm.
- The relationship between the proposed building and the public realm.
- The streetscape, including the conservation of buildings, the design of verandas, access from the street front, provision of active frontages to pedestrian areas, the treatment of the fronts and backs of buildings and their appurtenances, illumination of buildings or their immediate spaces and the landscaping of land adjoining a road.
- The interface with adjoining zones, especially the relationship with residential zones.
- The objectives, standards and decision guidelines of Clause 54. Clause 55 and Clause 57. This does not apply to an apartment development.
- For an apartment development, the objectives, standards and decision guidelines of Clause 58.
- The storage of rubbish and materials for recycling.

Transitional provisions

The objectives, standards and decision guidelines of Clause 55 of this scheme, as in force immediately before the approval date of Amendment VC136, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clauses 55 and 58 of this scheme, as in force immediately before the approval date of Amendment VC174, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 55 of this planning scheme, as in force immediately before the approval date of Amendment VC267, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

Clause 54 of this planning scheme, as in force immediately before the commencement of Amendment VC282, continue to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

37.08-10 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05. This zone is in Category 1 unless a schedule to this zone specifies a different category.

37.08-11 Other provisions of the scheme

17/09/2009
VC59

The schedule to this zone may specify that other provisions of the scheme do not apply.

29/11/2018
C188Pt1

SCHEDULE 1 TO CLAUSE 37.08 ACTIVITY CENTRE ZONE


Shown on the planning scheme map as **ACZ1**.

SUNSHINE TOWN CENTRE

1.0 Sunshine Town Centre Framework Plan

29/11/2018
C188Pt1

Diagram 1: Sunshine Town Centre Structure Plan



2.0 Land use and development objectives to be achieved

10/11/2016
C185

General

- To develop the Sunshine Town Centre as the primary Activity Centre within the Brimbank municipality.
- To support Sunshine's role as an emerging National Employment Cluster.
- To develop the Sunshine Town Centre as a vibrant hub for the local community and an important regional hub for metropolitan Melbourne's west and western Victoria.
- To encourage development that provides an economically vibrant, socially and environmentally sustainable Sunshine Town Centre, with a sense of community and place.

Activities and land use

- To establish higher-density mixed-use development along Ballarat Road, around the Sunshine Railway Station and in the Albion Station precinct.
- To consolidate large-format, restricted retail premises in the Ballarat Road Precinct.
- To concentrate retail, community and entertainment uses within the Main Street Precinct, particularly around the Sunshine Railway Station.
- To support the rehabilitation and redevelopment of former industrial land.
- To establish higher-density housing above ground floor commercial uses.

Subdivision

- To provide or otherwise not compromise the future provision of new streets and accessways, including pedestrian and bicycle paths, identified in the Sunshine Town Centre Framework Plan at clause 1.0.
- To discourage the subdivision of land with an existing low rise or low intensity use or development to prevent the further fragmentation of land ownership.
- To encourage the consolidation of lots to facilitate the creation of viable development sites that support the objectives of this schedule.

Built form and heritage

- To maintain a human scale built form at street level through the use of podiums.
- To ensure that new development supports Sunshine's distinctive sense of place through a legible and high quality built form and public realm.
- To focus more intensive built form around the Sunshine Railway Station.
- To reinforce the 'main street' character of Hampshire Road between the Sunshine Railway Station and Ballarat Road.
- To use built form design to indicate the major entries to the Sunshine Town Centre located on the corner of Ballarat Road and Hampshire Road and at the Sunshine Railway Station (including the bus interchange).
- To manage the built form transition between areas of change and established residential areas.
- To facilitate the redevelopment and reuse of heritage buildings.
- To enhance the heritage character of traditional (early 20th Century) shopping strips and historic pedestrian connections between the Sunshine Railway Station, the former Sunshine Harvester Site, McKay Gardens, Sun Crescent and City Place.
- To ensure new buildings connect to and provide opportunities for surveillance over streets, accessways and public spaces.

- To encourage the creation of boulevards of large canopy trees along main roads.

Movement and transport

- To improve the priority of pedestrians and cyclists in the public realm.
- To encourage the creation of a new public realm network including streets, accessways and public open spaces as part of the development of larger sites.
- To promote walking and cycling to and through the Sunshine Town Centre.
- To physically and visually connect the Sunshine Railway Station, including the bus interchange area, to Hampshire Road.
- To encourage activation of public transport nodes to improve amenity, safety and passive surveillance.
- To better manage traffic flow throughout the Sunshine Town Centre.
- To consolidate car parking throughout the Sunshine Town Centre to encourage the use of more sustainable forms of transport.

3.0 Table of uses

15/03/2024
VC256

Section 1 - Permit not required

Use	Condition
Accommodation (other than Corrective institution)	Any frontage at ground floor level within the Core Commercial Area or Mixed Use Area must not exceed 2 metres (other than a Bed and breakfast and Caretaker's house).
Animal keeping	Must be no more than 5 animals.
Automated collection point	Must meet the requirements of Clause 52.13-3 and 52.13-5. The gross floor area of all buildings must not exceed 50 square metres.
Bottle shop	Must be located in a Core Commercial Area.
Child care centre	
Cinema based entertainment facility	Must be located in a Core Commercial area.
Education centre	Must be located in a Core Commercial Area or Mixed Use Area.
Exhibition centre	Must be located in a Core Commercial Area or Mixed Use Area.
Food and drink premises (other than Hotel and Tavern)	Must be located in a Core Commercial Area or Mixed Use Area.
Home occupation	
Hotel	Must be located in the Core Commercial Area.
Informal outdoor recreation	
Office	Must be located in the Core Commercial Area or Mixed Use Area or on the land identified as the Darling Flour Mill site in clause 5.4 of this schedule.

Use	Condition
Postal agency	
Railway	
Restricted retail premises	Must be located in a Mixed Use Area.
Shop (other than Adult sex bookshop, Bottle shop, Restricted retail premises and Supermarket)	Must be located in a Core Commercial Area or Mixed Use Area.
Supermarket	Must be located in a Core Commercial Area. If in a Mixed Use Area must be no greater than 1800 square metres in area.
Tavern	Must be located in the Core Commercial Area.
Tramway	
Any use listed in Clause 62.01	Must meet requirements of Clause 62.01.

Section 2 - Permit required

Use	Condition
Adult sex bookshop	Must be located in a Core Commercial Area. Must be at least 200 metres measured by the shortest route reasonably accessible on foot from a residential zone or Residential Growth Area, or land used for a Hospital, Primary school or Secondary school, or land in a Public Acquisition Overlay to be acquired for a Hospital, Primary school or Secondary school.
Amusement parlour	Must be located in a Core Commercial or Mixed Use Area.
Bottle shop – if Section 1 condition is not met	Must be located in a Mixed Use Area.
Car park	In a Residential Growth Area: ▪ must be used in conjunction with another use in Section 1 or 2.
Car wash	In a Residential Growth Area: ▪ the site must adjoin, or have access to, a road in a Transport Zone 2 or Transport Zone 3.
Community market	
Convenience restaurant	In a Residential Growth Area: ▪ the site must adjoin, or have access to, a road in a Transport Zone 2 or Transport Zone 3.
Food and drink premises (other than Convenience restaurant) – if Section 1 condition not met	

Use	Condition
Industry (other than Car wash, Materials recycling, Refuse disposal, Rural industry and Transfer station)	Must be located in a Core Commercial Area or Mixed Use Area. Must not be a purpose listed in the table to Clause 52.10.
Leisure and recreation (other than Informal outdoor recreation, Motor racing track)	
Nightclub	Must be located in a Core Commercial Area.
Office (other than Medical centre) – if Section 1 condition is not met	In a Residential Growth Area: ▪ must be located within 100 metres of a Core Commercial Area or Commercial Zone ▪ must have the same street frontage as the land in the Mixed Use Area or Mixed Use Zone ▪ the leasable floor area must not exceed 250 square metres.
Place of assembly (other than Amusement parlour and Nightclub)	
Plant nursery	
Retail premises (other than Convenience restaurant, Community market, Food and drink premises, Plant nursery and Postal agency)	Must be located in a Core Commercial Area or Mixed Use Area.
Service station	Must be located in a Core Commercial Area or Mixed Use Area.
Supermarket	Must not be located in Residential Growth Area.
Transport terminal	Must be located in a Core Commercial Area.
Warehouse	Must be located in a Core Commercial Area or Mixed Use Area. Must not be a purpose listed in the table to Clause 52.10.
Any other use not in Section 1 or 3	

Section 3 – Prohibited

Use
Agriculture (other than Animal keeping and Apiculture)
Corrective institution
Materials recycling
Motor racing track
Refuse disposal

Use
Rural industry
Saleyard
Transfer station (other than Automated collection point)

4.0 Centre-wide provisions

10/12/2015
C105

4.1 Use of land

10/12/2015
C105

For the purposes of clause 3.0 to this schedule, the land use areas referred to in the Table of uses are those land use areas identified in clause 1.0 to this schedule as Core Commercial Area, Residential Growth Area and Mixed Use Area.

4.2 Buildings and works

10/12/2015
C105

No permit is required to:

- Install an automatic teller machine provided that at least 80 per cent of the building facade of the building at ground floor level is maintained as an entry or window with clear glazing, excluding a building within a Heritage Overlay.

4.3 Design and development

10/12/2015
C105

All buildings and works must be generally in accordance with the following design and development requirements.

The scale, bulk and quality of new development should support Sunshine's distinctive sense of place through legible and high quality built form.

Development should:

- Adopt an architectural form that is contemporary and innovative.
- Integrate with sites of heritage significance.
- Complement the existing character of the residential edges of the centre.
- Adopt environmentally sustainable design principles.

Maximum building height

Buildings and works should not exceed the relevant preferred maximum building height specified in the relevant precinct map in clause 5.0 to this schedule.

The preferred maximum building height does not apply to plant and service equipment, including plant rooms, lift overruns, solar collectors and other such equipment, provided the equipment is located, designed and screened to the satisfaction of the responsible authority.

Where a building or works exceeds the relevant preferred maximum building height, an assessment of the proposal against the relevant precinct objectives must be provided and the decision guidelines at clause 8.0 of the schedule will apply.

Street wall height

The preferred maximum street wall height is specified in the relevant precinct map in clause 5.0 to this schedule.

Where a building or works does not meet the preferred maximum street wall height the building or works must achieve the relevant precinct objectives and provide consistency and continuity in the streetscape.

Setbacks from a street

The setback of a building from a boundary with a street should be in accordance with the applicable setback specified in the relevant precinct map in clause 5.0 to this schedule. This does not apply to land within a Heritage Overlay.

Where the precinct map specifies a street wall along a boundary with a street, a building should be located with a zero setback from that boundary where non-residential uses are proposed at ground level.

In order to maintain a clearly defined street wall edge, balconies, terraces, decks or other forms of private open space should not project forward of a street wall.

Minor buildings or works such as porches, verandahs, balconies, pergolas sunshades, screens, architectural features, artworks and street furniture may be constructed within the setback area provided the following criteria are met:

- The building or works integrate with the design of the building.
- The building or works will not have an inappropriate visual impact when viewed from the street, public realm and adjoining properties.
- The building or works will not have an inappropriate impact on the amenity of the street, public realm and adjoining properties.

Upper level setback

Where a building is higher than the maximum street wall height, the higher section of the building should be setback a minimum of six metres from the line of the street wall. This setback may be reduced on the northern street frontage of a building.

Setbacks from side and rear boundaries

A building or works may be built to a side or rear boundary at podium level. On upper floors, consideration should be given to daylight access, privacy, built form and the extent of overshadowing of the public realm.


This does not apply to a side or rear boundary that is a boundary with a street and / or where the relevant precinct map in clause 5.0 to this schedule specifies a setback from that street boundary.

4.4 Objectives for Development Plan Areas

10/12/2015
C105

- To provide an integrated approach to the future use and development of strategic redevelopment sites and precincts.
- To identify areas that require the form and conditions of future use and development to be shown on a development plan before a permit may be granted to use or develop the land.
- To ensure use and development is generally in accordance with a development plan and the land use and development objectives for the activity centre.

Diagram 2: Development Plan Areas



Development plan requirements

A development plan must be prepared for each area identified in this schedule, to the satisfaction of the responsible authority.

The development plan may be prepared and approved in stages provided that the future subdivision, use and development of the land in an integrated manner will not be prejudiced. This is to be demonstrated to the satisfaction of the responsible authority.

A development plan must include:

- Location and site context.
- Site layout.
- Access and circulation plan.
- Staging of development.

- Indicative land uses.
- A record sheet that documents and summarises changes to the plan by document number, version number and approval date.
- A sunset clause specifying the trigger at which point the plan ceases to have effect.

A development plan should provide detail on the following matters, as applicable:

- Urban structure, including:
  - location and hierarchy of the movement and access network including future roads and accessways
  - pedestrian circulation
  - vehicular circulation
  - activity nodes
  - parking and loading arrangements.
- Public realm, including:
  - location and details of open spaces, squares, plazas and parks
  - works, services, facilities or other infrastructure to be provided.
- Built form, including:
  - location of buildings
  - building heights, including street wall and podium heights
  - building setbacks, from the street and between buildings
  - active edges.
- Solar access and overshadowing.

A development plan may require:

- A traffic assessment report that addresses the impact of the future use and development of the land on the surrounding road network and identifying any works required to mitigate the impact.
- A landscape master plan setting out the landscape design for the development plan area.

If in the opinion of the responsible authority a requirement of this clause is not relevant, the responsible authority may waive or reduce the requirement.

An approved development plan may be amended to the satisfaction of the responsible authority.

Requirements before a permit is granted

A permit must not be granted to use or subdivide land, construct a building or construct or carry out works on land identified until a development plan has been prepared to the satisfaction of the responsible authority.

Where a development plan is being prepared and approved in stages a permit may be issued within any approved stage prior to the approval of any subsequent stage of the development plan.

This does not apply to the following, for which a permit may be granted before a development plan has been prepared to the satisfaction of the responsible authority:

- Any building or works associated with the remediation of the land in accordance with or for the purpose of obtaining a Certificate or Statement of Environmental Audit under the *Environment Protection Act 1970*.

- Any building or works associated with an existing use being carried out on the site provided that the building or works will not prejudice the preparation and approval of the development plan or the future use or development of the land in accordance with this schedule.
- Consolidation of land.
- Removal or creation of easements or restrictions provided that this will not prejudice the preparation and approval of the development plan or the future use or development of the land in accordance with this schedule.
- A change in the hours of operation or conditions of use of an existing use of the land.

Where a development plan has been prepared and approved under this schedule to the satisfaction of the responsible authority a permit:

- Must be consistent with the objectives and provisions of this schedule.
- Must be generally in accordance with the development plan.
- Must not impose conditions or requirements that are inconsistent with the development plan.
- May allow buildings and works that are not in general accordance with the development plan provided they are associated with an existing use and do not prejudice the future implementation of the development plan.

Where there is an inconsistency between a provision of this schedule and the development plan, the provisions of the development plan prevail.

5.0 Precinct provisions


10/12/2015
C105

5.1 Precinct 1 – Main Street

10/12/2015
C105

5.1-1 Precinct map

Diagram 3: Precinct 1 – Main Street precinct map



5.1-2 Precinct objectives

Use

- To develop and maintain the Main Street precinct as a focal point for retail, as well as civic, business and community activities.
- To develop Hampshire Road, between Service Street and Dickson Street, as the retail promenade within the Sunshine Town Centre.

Development

- To protect, enhance and extend the traditional two-storey 'main street' built form along and adjacent to Hampshire Road, between the Sunshine Railway Station and Service Street.
- To facilitate the redevelopment of the Sunshine Marketplace shopping centre.
- To create a distinctive town square at the junction of the Sunshine Marketplace and Sunshine Plaza shopping centres and Hampshire Road.
- To strengthen pedestrian and cycling connections between the Sunshine Marketplace shopping centre and the surrounding street network.
- To retain and integrate the heritage garden character of the east side of Hampshire Road between Hertford Road and Ballarat Road within the Main Street public realm.
- To improve the physical and visual connections between Hampshire Road and Clarke Street and the Sunshine Railway Station and bus interchange.
- To provide high quality active street walls to the surrounding street network and to create mid-block open spaces between Dawson and Kennedy Streets.

5.1-3 Precinct requirements

Land in a Development Plan Area is subject to clause 4.4 to this schedule, as applicable.

5.1-4 Precinct guidelines

Use

Proposals that support the consolidation of retail, commercial, community and entertainment uses within the Main Street Precinct, particularly around Hampshire Road between the railway corridor to the south and Foundry and Hertford Roads to the north are encouraged.

The provision of residential uses above ground floor level is encouraged.

Mixed-use development located along the railway corridor, southeast of the Sunshine Railway Station is encouraged; this may include residential uses located at ground floor level.

Uses that promote or support pedestrian activity, particularly along Hampshire Road and in locations close to the Sunshine Railway Station, are encouraged. This may include:

- Outdoor restaurants and cafes.
- Uses that operate in the evening and late night.

Uses, including facilities and services, that can draw students and staff from the Victoria University into the Main Street precinct are encouraged.

Development

Large format buildings with a frontage to Hampshire Road should provide high quality landmark built form frontages and entrances to Hampshire Road.

5.1-5 Any other requirements

Development Plan Area A: Sunshine Marketplace

In addition to any other requirements for a development plan specified in clause 4.4 to this schedule, the development plan for the Sunshine Marketplace must:


- Include arrangements for the integration of the Sunshine Marketplace shopping centre with Hampshire Road through the provision of an active interface and streetscape setback as shown in the relevant precinct map at clause 5.1.
- Include an expanded pedestrian and public realm network between Hampshire Road and Harvester Road, and north to Foundry Road.
- Allow for reinstatement of the pedestrian connection between the gates of the former McKay Harvester factory on Devonshire Road and the former bulk store (Visy Cares Hub).
- Show the location of and arrangements for car parking areas, including opportunities for the relocation or consolidation of car parking.
- Include new east/west and north/south connecting streets and pedestrian pathways or provide for the formalisation of the existing private road network in the precinct.
- Include a new area of functional public open space of a minimum value of five per cent of the Sunshine Marketplace site.

5.2 Precinct 2 – Ballarat Road

10/12/2015
C105

5.2-1 Precinct map

Diagram 4: Precinct 2 – Ballarat Road precinct map



5.2-2 Precinct objectives

Use

- To integrate the Ballarat Road frontages of the precinct with the Main Street precinct.
- To encourage a mix of land uses complementary to existing education and legal uses within the precinct.

Development

- To create a gateway to the Sunshine Town Centre through built form and public realm enhancements at the northern end of Hampshire Road.
- To ensure that new development incorporates links and a gateway to the Sunshine Town Centre.
- To ensure future development has an active frontage to McIntyre Road and Anderson Road.
- To encourage the provision of street tree planting along McIntyre Road.

5.2-3 Precinct requirements

Development

Land in a Development Plan Area is subject to clause 4.4 to this schedule, as applicable.

On lots adjoining Ballarat Road, the setback area between a building and the boundary with Ballarat Road should be five metres except for land on the south side of Ballarat Road between Hampshire Road and Stonemark Street where the setback may be reduced to three metres. The setback area between a building and the boundary with Ballarat Road is to be landscaped to reinforce a boulevard theme.

Where possible, vehicle access is to be provided to streets other than McIntyre Road or Anderson Road, to minimise vehicle conflict along these Roads.

5.2-4 Precinct guidelines

Use

Proposals that support the core functions of the Main Street precinct and provision of a mix of uses to draw people between Ballarat Road and Sunshine railway station are encouraged.

Proposals that support a mix of education, civic, residential and bulky goods retail land uses at ground floor level are encouraged.

The provision of higher density housing, primarily through residential uses above ground floor level, is encouraged.

Development

Encourage the development of taller buildings with significant landscaping along Ballarat Road, reinforcing its broad street proportions.

The development of high quality, visually prominent built forms on Ballarat Road at key intersections at Hampshire, Harvester and Anderson Roads, that create a distinctive address and gateway to the Sunshine Town Centre are encouraged.

Development that supports street oriented activity in key locations within the pedestrian movement network, with an emphasis on Foundry Road, is encouraged.

5.2-5 Any other requirements

Development Plan Area B: Sunshine Gateway site

In addition to any other requirements for a development plan specified in clause 4.4 to this schedule, the development plan for the Sunshine Gateway site must:


- Provide for intensive mixed-use development.
- Incorporate landmark buildings that mark the gateway to the Sunshine Town Centre.
- Provide a site layout and internal road configuration that has regard to the existing subdivision pattern and capacity to stage the development across individual lots. Internal roads are to be to Council standards.
- Provide the primary road access from Harvester Road.
- Support the establishment of a strong pedestrian connection to Albion railway station along Ballarat Road and the extension of St Albans Road. Pedestrian pathways are to be to Council standards.
- Locate buildings to have a minimum setback of three metres from Foundry Road.
- Include the creation of a boulevard frontage along Ballarat Road.
- Provide for separation distances between building towers to enable adequate solar penetration to the centralised public plaza or open space area between the hours of 11am and 1pm at the equinox.
- Include active frontages along a substantial proportion of all streets at ground level.
- Include a new area of functional public open space of a minimum value of five per cent of the Sunshine Gateway site.

5.3 Precinct 3 – South Village

10/12/2015
C105

5.3-1 Precinct map

Diagram 5: Precinct 3 – South Village precinct map



5.3-2 Precinct objectives

Use

- To reinforce Sun Crescent and City Place as the Village centre.
- To provide for a range of residential and commercial uses that capitalise on the proximity to Sunshine Railway Station.
- To extend the street network within the precinct.

Development

- To enhance the existing traditional (early 20th Century) retail character of Sun Crescent and City Place.
- To encourage the conservation and enhancement of the heritage character of Sun Crescent and City Place.
- To enhance the southern entry to the Sunshine Town Centre along Hampshire Road.

5.3-3 Precinct requirements

Use

Residential uses should be located above ground floor level.

Development

The development of the former industrial and rail corridor land declared surplus to the east of Hampshire Road, and south-west of the railway corridor, should include:

- An extension of Sun Crescent from the intersection with Hampshire Road through to Stanford Street.
- The creation of a fine-grain movement and access network and block pattern.

5.3-4 Precinct guidelines

Use

The extension of the Village commercial area through increased local retail, service and entertainment uses along Hampshire Road to Derby Road is encouraged.

Uses that promote or support pedestrian activity, activate street frontages and promote a village feel are encouraged, particularly in locations close to the Sunshine Railway Station. This may include:

- Local convenience retail uses.
- Restaurants and cafes.
- Uses that operate in the evening.

Community and cultural uses, such as art studios, theatres and galleries, are encouraged.

The transition of existing industrial areas to commercial or residential uses is encouraged.

Development


Development that enhances the existing character of the precinct through well-articulated, human-scaled, built form is encouraged.

5.4 Precinct 4 – Albion Station

29/11/2018
C188Pt1

5.4-1 Precinct map

Diagram 6: Precinct 4 – Albion Station precinct map



5.4-2 Precinct objectives

Use

- To provide for a range of residential and commercial uses that will capitalise on the proximity to the Albion Railway Station.
- To encourage the conservation and adaptive reuse of the Darling Flour Mill site, the Albion substation and other heritage buildings.
- To encourage land uses that promote after-hours activity adjacent to the Albion Railway Station to support a safer and more vibrant transport hub.

Development

- To facilitate the longer term integration of large scale strategically important sites between Hampshire Road and Albion Railway Station along an extension of St Albans Road to the intersection of Anderson Road and Foundry Road and the introduction of a finer grain street and block pattern.
- To facilitate the extension of St Albans Road as a high quality, cycling and pedestrian-friendly street supported by quality built form frontages between Albion Station and Foundry Road.
- To ensure new development interfaces well with the extension of St Albans Road.
- To ensure that the significant heritage elements of the Darling Flour Mill are maintained.
- To preserve existing view corridors to the Darling Flour Mill from Ballarat Road in accordance with the Darling Flour Mill View Line Assessment, Tract, June 2014.
- To retain significant trees and landscape character, and provide high quality buildings with active interfaces in Talmage Street.
- To improve the amenity, safety and connectivity around the Albion Railway Station.
- To create a recreation and pedestrian link along the Stony Creek corridor.
- To ensure future development has an active frontage to McIntyre and Anderson Roads.
- To encourage the provision of street tree planting along McIntyre Road.

5.4-3 Precinct requirements

Use

Land in a Development Plan Area is subject to clause 4.4 to this schedule, as applicable.

The leasable floor area of retail premises should be less than 1000 square metres per occupancy.

The adaptive reuse of the Darling Flour Mill buildings should include active uses at ground floor level fronting Albion Railway Station.

Development

On lots adjoining Ballarat Road to which a landscape setback applies, the setback area between a building and the boundary with Ballarat Road should be five metres and landscaped to reinforce a boulevard theme.

Where possible, vehicle access is to be provided to streets other than McIntyre Road or Anderson Road, to minimise vehicle conflict along these roads.

Development on lots adjoining the Stony Creek corridor should be setback from the corridor to enable the provision of a substantial open space and recreation corridor along the alignment of Stony Creek.

Buildings located between Talmage Street and the railway corridor should:

- Be similar in form and massing to the Albion substation.

- Face Talmage Street.

5.4-4 Precinct guidelines

Use

Small-scaled industrial uses may be permitted on the Darling Flour Mill site where it can be demonstrated that the industrial use is compatible with and will not have inappropriate amenity impacts on adjacent or nearby residential uses.

The provision of higher density housing within and adjacent to Ferguson Street and along the rail corridor is encouraged.

Local convenience retailers, such as cafes and other uses that service the surrounding residential community, and activate street frontages and promote a village feel are encouraged.

Community and cultural uses, such as art studios, theatres and galleries, are encouraged.

Development

The setback of buildings located on the east side of Talmage Street should have regard to the location of the existing trees and the setback of the Albion substation.

5.4-5 Any other requirements

Development Plan Area C: Darling Flour Mill site

In addition to any other requirements for a development plan specified in clause 4.4 to this schedule, the development plan for the Darling Flour Mill site must:

- Be consistent with the relevant permits or exemptions issued by Heritage Victoria or any Conservation Management Plan endorsed by the Executive Director, Heritage Victoria, for heritage places on the land.
- Show the retention and re-use of the heritage buildings in the precinct.
- Include the provision of public access in the form of a pedestrian pathway along the northeast boundary of the precinct, adjacent to the railway corridor, and connections through to the Albion Railway Station.
- Include the provision of a new street along the north-eastern boundary of the precinct connecting Sydney Road with Ferguson Street.
- Ensure the development maintains views to the Darling Flour Mills.

Development Plan Area D: Albion Triangle site

In addition to any other requirements for a development plan specified in clause 4.4 to this schedule, the development plan for the Albion Triangle site must:

- Show the location of and arrangements for the extension of St Albans Road through to Anderson Road at its intersection with Foundry Road (in alignment with PAO5).
- Design the site layout and internal road configuration having regard to the existing subdivision pattern and capacity to stage the development across independent lots. Internal roads are to be Council standards.
- Include the provision of public access along the south-west boundary of the precinct, adjacent to the railway corridor, and the proposed connections through to the Albion Railway Station.
- Ensure development has an address to and includes the provision of a pedestrian and bicycle path along the Stony Creek Corridor.
- Provide for a new north/south road connection located to the east of Stony Creek.

6.0 Application requirements

10/12/2015
C105

In addition to the requirements at clause 37.08-7, an application must be accompanied by the following information, as appropriate:

- For an application to construct a building or to construct or carry out works on land adjacent to the southern side of Ballarat Road and within the existing view corridors to the Darling Flour Mill as viewed from Ballarat Road:
  - a plan, diagram or other technique, drawn to scale and dimensioned, showing the proposed building or works within the context of the view corridors of the Darling Flour Mill.
- For an application to construct a building or construct or carry out works:
  - an environmental site assessment and report prepared by an appropriately qualified person demonstrating that the environmental conditions are suitable for the construction and use of a basement or setting out conditions to be met to ensure that the environmental conditions are suitable for construction and use of a basement.
- For an application to use or develop land for a sensitive use (residential use, child care centre, pre-school centre or primary school):
  - the location and details of uses with adverse amenity potential to which a threshold distance applies under clause 52.10 of this scheme where the land to which the application applies is within the specified threshold distance.
- For an application for subdivision associated with an existing or proposed use or development that will create a lot that does not contain any part of that use or development:
  - demonstration that a building may be constructed on that lot in accordance with the relevant objectives and provisions of this schedule.
- For an application for subdivision of land located in an area designated as a Residential Growth Area in clause 1.0 to this schedule for residential purposes:
  - an assessment detailing how the proposal meets the objectives and/or standards of Clause 56, as relevant.

If in the opinion of the responsible authority an application requirement specified in this clause is not relevant to the assessment of an application, the responsible authority may waive or reduce the requirement.

7.0 Notice and review

20/01/2022
VC205

An application that exceeds the preferred building height as specified in clause 5 of this schedule is not exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act. This does not apply to an application for land to which a development plan approved in accordance with this schedule applies.

Notice of plans

Before deciding to approve a development plan, the responsible authority must seek the views of:

- The owners and occupiers of land located within the relevant development plan area.
- The owners and occupiers of land adjoining and opposite the relevant development plan area.
- Where the precinct adjoins a Transport Zone 2 or Transport Zone 3, the relevant road authority.
- Where the precinct adjoins a Public Use Zone, the relevant public land manager.
- Where the precinct includes a heritage place that is included on the Victorian Heritage Register, the Secretary to the department administering the *Heritage Act 1995*.

8.0 Decision guidelines

10/12/2015
C105

Before deciding on an application or approval of a development plan, in addition to the decision guidelines in clause 37.08-9 and clause 65 of this scheme, the responsible authority must consider, as appropriate:

General

- The precinct objectives set out in this schedule.
- The site context and how the proposal responds to its context.
- Whether the proposal will be an under-utilisation or under-development of the site having regard to the objectives and provisions of this schedule.
- Whether the proposal will prevent or limit the development or use of the land in accordance with this schedule.
- The views of the relevant road authority, as applicable.

Use of land

- The extent to which the proposal supports the consolidation of retail, commercial, community and entertainment uses within the Main Street Precinct.
- The impacts of uses with adverse amenity potential on a proposed use or development for a sensitive use (residential use, child care centre, pre-school centre or primary school) where the land to which the application applies is within the threshold distance specified under clause 52.10 of this scheme.

Subdivision

- Whether the subdivision will result in a lot layout or lot sizes that limit the potential for the intensification of and development within the activity centre in accordance with the objectives and provisions of this schedule.

Design and development

- Whether the building heights and setbacks provide for a consistent/continuous street edge at ground level where commercial uses are proposed.
- The extent to which the proposal maintains the significance or visual prominence of known heritage places, including view lines to the Darling Flour Mill.
- The extent to which the design, including the building setbacks, provides for privacy where residential uses are located at ground and upper levels.
- Whether the design of a building provides flexible floor spaces that can be adapted for a range of potential future uses.

Building height

Where a building or works exceeds the preferred maximum building height specified in clause 5.0 to this schedule the responsible authority must consider, as appropriate:

- The extent to which the building or works have regard to the transition of building heights from one precinct to another and/or land outside of the Activity Centre Zone.
- The extent to which the buildings or works avoid detrimental impacts on the street, public realm, adjoining properties and the surrounding area through visual appearance, overshadowing or wind effects.
- Whether a net community benefit results from the building and works having regard to:
  - the environmentally sustainable design performance of the building and works
  - the extent of community space provided within the development

- the extent of public open space provided within the development
- the extent to which 'business incubator' spaces or similarly subsidised spaces for start-up business, not-for-profit organisations, artists, education facilities and health facilities are provided within the development.

9.0 Advertising signs

10/12/2015
C105

Advertising sign requirements are at clause 52.05. All land located in a Mixed Use Area or Residential Growth Area, as identified in clause 1.0 to this schedule is in Category 2. All other land is in Category 1.

10.0 Other provisions of the scheme

10/12/2015
C105

An application under an overlay in clause 42.01, 43.01, 44.01 or 45.01 of this scheme is exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act.

11.0 Reference documents

10/12/2015
C105

Sunshine Town Centre Structure Plan (Brimbank City Council 2014)

Darling Flour Mill View Line Assessment (Tract 2014)

40 OVERLAYS

19/01/2006
VC37

This section sets out the overlays which apply in this scheme.

41 [NO CONTENT]

31/07/2018
VC148

42 ENVIRONMENTAL AND LANDSCAPE OVERLAYS

19/01/2006
VC37

42.01 ENVIRONMENTAL SIGNIFICANCE OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **ESO** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify areas where the development of land may be affected by environmental constraints.

To ensure that development is compatible with identified environmental values.

42.01-1 Environmental significance and objectives

31/07/2018
VC148

A schedule to this overlay must contain:

- A statement of environmental significance.
- The environmental objectives to be achieved.

42.01-2 Permit requirement

14/12/2023
VC253

A permit is required to:

- Construct a building or construct or carry out works. This does not apply if a schedule to this overlay specifically states that a permit is not required.
- Construct a fence if specified in a schedule to this overlay.
- Construct bicycle pathways and trails.
- Subdivide land. This does not apply if a schedule to this overlay specifically states that a permit is not required.
- Remove, destroy or lop any vegetation, including dead vegetation. This does not apply:
  - If a schedule to this overlay specifically states that a permit is not required.
  - If the table to Clause 42.01-3 specifically states that a permit is not required.
  - To the removal, destruction or lopping of native vegetation in accordance with a native vegetation precinct plan specified in the schedule to Clause 52.16.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where:	Clause 59.02

Class of application	Information requirements and decision guidelines
▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. ▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02
Construct a fence.	Clause 59.05
Remove, destroy or lop one tree provided: ▪ A permit has not been granted for a VicSmart application to remove, destroy or lop a tree on the same land within the last 12 months. ▪ There is no other current VicSmart application to remove, destroy or lop a tree on the same land.	Clause 59.06
Construct a building or construct or carry out works for: ▪ A carport, garage, pergola, verandah, deck, shed or similar structure. ▪ A rainwater tank. The buildings and works must be associated with a dwelling or a small second dwelling.	Clause 59.05

42.01-3 Table of exemptions

16/08/2024
VC262

The requirement to obtain a permit does not apply to:	
Emergency works	Vegetation that is to be removed, destroyed or lopped: ▪ in an emergency by, or on behalf of, a public authority or municipal council to create an emergency access or to enable emergency works; or ▪ where it presents an immediate risk of personal injury or damage to property. Only that part of the vegetation that presents the immediate risk may be removed, destroyed or lopped under this exemption.
Extractive industry	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of extractive industry in accordance with a work plan approved under the *Mineral Resources (Sustainable Development) Act 1990* and authorised by a work authority granted under that Act.
Fire protection	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of any of the following fire protection activities: ▪ fire fighting; ▪ planned burning;

The requirement to obtain a permit does not apply to:	
	▪ making or maintenance of a fuelbreak or fire fighting access track (or any combination thereof) that does not exceed a combined width of 6 metres; ▪ making of a strategic fuelbreak up to 40 metres wide by, or on behalf of, a public authority in accordance with a strategic fuelbreak plan approved by the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*); ▪ is ground fuel within 30 metres of a building and is vegetation other than native vegetation; ▪ in accordance with a fire prevention notice issued under either: – section 87 of the *Fire Rescue Victoria Act 1958*; – section 65 of the *Forests Act 1958*; or – section 41 of the *Country Fire Authority Act 1958*. ▪ keeping vegetation clear of, or minimising the risk of bushfire ignition from, an electric line in accordance with a code of practice prepared under Part 8 of the *Electricity Safety Act 1998*; ▪ minimising the risk to life and property from bushfire on a roadside of a public road managed by the relevant responsible road authority, and carried out by, or on behalf of that authority in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*). In this exemption, roadside, public road and responsible road authority have the same meanings as in section 3 of the *Road Management Act 2004*. *Note: Additional permit exemptions for bushfire protection are provided at Clause 52.12.*
Geothermal energy exploration and extraction	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary in accordance with an operation plan approved under the *Geothermal Energy Resources Act 2005*.
Greenhouse gas sequestration and exploration	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary in accordance with an operation plan approved under the *Greenhouse Gas Geological Sequestration Act 2008*.
Land management or directions notice	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to comply with a land management notice or directions notice served under the *Catchment and Land Protection Act 1994*.
Land use conditions	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to comply with a land use condition served under the *Catchment and Land Protection Act 1994*.
Mineral exploration and mining	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by the holder of an exploration, mining, prospecting, or retention licence issued under the *Mineral Resources (Sustainable Development) Act 1990*: ▪ that is low impact exploration within the meaning of Schedule 4A of the *Mineral Resources (Sustainable Development) Act 1990*; or ▪ in accordance with a work plan approved under Part 3 of the *Mineral Resources (Sustainable Development) Act 1990*. *Note: Schedule 4A of the Mineral Resources (Sustainable Development) Act 1990 specifies limits on the extent of native vegetation that may be removed as part of low impact exploration.*
Noxious weeds	Vegetation that is a noxious weed subject of a declaration under section 58 or section 58A of the *Catchment and Land Protection Act 1994*. This exemption does not apply to Australian Dodder (*Cuscuta australis*).
Pest animal burrows	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the removal of pest animal burrows. In the case of native vegetation the written agreement of an officer of the department responsible for administering the *Flora and Fauna Guarantee Act 1988* is required before the vegetation can be removed, destroyed or lopped.

The requirement to obtain a permit does not apply to:	
Planted vegetation	Vegetation that is to be removed, destroyed or lopped that was either planted or grown as a result of direct seeding for Crop raising or Grazing animal production.
Railways	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to maintain the safe and efficient function of an existing railway, or railway access road, in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Regrowth	Vegetation that is to be removed, destroyed or lopped that has naturally established or regenerated on land lawfully cleared of naturally established vegetation, and is: ▪ bracken (Pteridium esculentum); or ▪ within the boundary of a timber production plantation, as indicated on a Plantation Development Notice or other documented record, and has established after the plantation. This exemption does not apply to land on which vegetation has been destroyed or otherwise damaged as a result of flood, fire or other natural disaster.
Road safety	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by or on behalf of a public authority or municipal council to maintain the safe and efficient function of an existing public road in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Stone exploration	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of Stone exploration. The maximum extent of vegetation removed, destroyed or lopped under this exemption on contiguous land in the same ownership in a five year period must not exceed any of the following: ▪ 1 hectare of vegetation which does not include a tree. ▪ 15 trees with a trunk diameter of less than 40 centimetres at a height of 1.3 metres above ground level. ▪ 5 trees with a trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level. This exemption does not apply to costeaning and bulk sampling activities.
Surveying	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by, or on behalf of, a licenced surveyor (within the meaning of section 3 of the *Surveying Act 2004*) using hand-held tools to establish a sightline for the measurement of land.
Traditional owners	Vegetation that is to be removed, destroyed or lopped by a person acting under, and in accordance with: ▪ a natural resources agreement under Part 6 of the *Traditional Owners Settlement Act 2010*; or ▪ an authorisation order made under sections 82 or 84 of the *Traditional Owner Settlement Act 2010* as those sections were in force immediately before the commencement of section 24 of the *Traditional owners Settlement Amendment Act* in 2016 (1 May 2017).
Tram stops	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by or on behalf of the Head, Transport for Victoria to construct a tram stop, including a tram stop shelter.
Transport land	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by or on behalf of the Head, Transport for Victoria on land in a Transport Zone, or in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority, to construct or maintain transport system infrastructure.

42.01-4 Application requirements

31/07/2018
VC148

An application must be accompanied by any information specified in a schedule to this overlay.

42.01-5 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and Planning Policy Framework.
- The statement of environmental significance and the environmental objective contained in a schedule to this overlay.
- The need to remove, destroy or lop vegetation to create a defendable space to reduce the risk of bushfire to life and property.
- Any other matters specified in a schedule to this overlay.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 42.01 ENVIRONMENTAL SIGNIFICANCE OVERLAY

Shown on the planning scheme map as **ESO1**.

SYDENHAM RADIO TRANSMISSION ENVIRONMENTAL SIGNIFICANCE AREA

1.0 Statement of environmental significance

08/07/2021
C211brim

The 90 hectare site contains large expanses of Wallaby grass (Danthonia spp.) and Wallaby grass – Spear grass (Stipa spp) grassland of regional botanical significance. It represents a basalt plains grassland flora enhanced by transplanting from other sites with numerous rare and threatened flora species.

2.0 Environmental objective to be achieved

08/07/2021
C211brim

To protect populations or communities of native plants and fauna of national, state or regional significance consistent with the principles and requirements of the Commonwealth Endangered Species Protection Act 1992 and the Victoria Flora and Fauna Guarantee Act 1988.

3.0 Permit requirement

08/07/2021
C211brim

None specified.

4.0 Application requirements

08/07/2021
C211brim

The following application requirements apply to an application to use land to construct a building or construct or carry out works, to remove, destroy or lop any vegetation, or to subdivide land; in addition to those specified elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- The results of a detailed flora and fauna survey and assessment of the land which is undertaken by qualified and experienced personnel using methods acceptable to the Department administering the Flora and Fauna Guarantee Act 1988 and which documents:
  - Any significant populations or communities of native plants.
  - Any significant populations of native fauna.
  - Any concentrations of environmental weeds.
- An independent review of the flora and fauna survey and assessment undertaken by appropriately qualified and experienced personnel.
- Information that demonstrates that development impacts on the sites of national, state or regional significance for flora and fauna would be minimised and that the integrity of the site will be maintained or enhanced.
- A Land Management Plan prepared in accordance with the guidelines contained in the Brimbank Natural Heritage Strategy which presents details of proposed arrangements for the effective and ongoing management of the land consistent with the environmental objectives to this schedule.
- A demonstration that adequate safeguards would be put in place to ensure that activities in any developed portions of the land do not detrimentally affect significant communities or populations of native plants or native fauna or their habitats.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit to use land to construct a building or construct or carry out works, to remove destroy or lop vegetation, or to subdivide land under Clause 42.01, in addition to those specified in Clause 42.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The State Planning Policy Framework.
- The comments of the Department of Environment, Land, Water and Planning.

The responsible authority must be satisfied that:

- The flora and fauna survey and assessment of the land has been adequately completed under appropriate seasonal conditions.
- The flora and fauna survey and assessment has been independently reviewed in an appropriate manner.
- Any development plans for the land clearly take into consideration the environmental objectives of this schedule.

Implementation of the land management plan will prevent detrimental impacts on significant communities or populations of native plants and fauna.

08/07/2021
C211brim

SCHEDULE 2 TO CLAUSE 42.01 ENVIRONMENTAL SIGNIFICANCE OVERLAY

Shown on the planning scheme map as **ESO2**.

SYDENHAM RADIO TRANSMISSION ENVIRONMENTAL SIGNIFICANCE AREA – ROUND HILL

1.0 Statement of environmental significance

08/07/2021
C211brim

As one of the two eruption points of Newer Volcanics in the City of Brimbank, Round Hill is of local geomorphological significance.

2.0 Environmental objective to be achieved

08/07/2021
C211brim

To protect sites containing geological and geomorphological features that are unique or important examples in the local context.

3.0 Permit requirement

08/07/2021
C211brim

None specified.

4.0 Application requirements

08/07/2021
C211brim

The following application requirements apply to an application for a permit to use land to construct a building or construct or carry out works, or to subdivide land under Clause 42.01, in addition to those specified elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- a report which demonstrates that consideration has been given to the management principles for geological and geomorphological sites contained in the Brimbank Natural Heritage Strategy Background Papers.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit to use land to construct a building or construct or carry out works, or to subdivide land under Clause 42.01, in addition to those specified in Clause 42.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The Planning Policy Framework.
- The Brimbank Natural Heritage Strategy.

The responsible authority must be satisfied that:

- All reasonable means of effectively protecting the significant qualities of the site have been considered.
- The management principles for geological and geomorphological sites contained in the Brimbank Natural Heritage Strategy Background Papers have been followed.

08/07/2021
C211brim

SCHEDULE 3 TO CLAUSE 42.01 ENVIRONMENTAL SIGNIFICANCE OVERLAY

Shown on the planning scheme map as **ESO3**.

BALDWIN AVE/SOLOMON HEIGHTS ENVIRONMENTAL SIGNIFICANCE AREA

1.0 Statement of environmental significance

08/07/2021
C211brim

The Solomon Heights area contains 14.4 ha of indigenous vegetation cover, of which 14.2 ha is Plains Grassland and 0.2 ha of which is Basalt Escarpment Shrub land. The site supports Nationally, State and Regionally significant flora. All indigenous flora at the site is considered locally significant. The Solomon Heights Grasslands are Nationally Significant as 75 plants, or an estimated 2.1 to 3 percent of all wild individuals, of *Pimelea spinescens* are found within the study area. The Plains Grassland vegetation type is vital habitat for this species, as it does not occur in any other. The study area contains an estimated 0.6 to 0.8 percent of all remaining Basalt Plains Grassland.

2.0 Environmental objective to be achieved

08/07/2021
C211brim

To protect population or communities of native plants and fauna of national, State or regional (ie: within the Greater Melbourne Region) significance, consistent with the principles and requirements of the *Environment Protection Biodiversity Conservation Act 1999* and the *Victoria Flora and Fauna Guarantee Act 1988*.

3.0 Permit requirement

08/07/2021
C211brim

A permit is not required to remove, destroy or lop vegetation where:

- The vegetation is an environmental weed as specified in Table 1 to this overlay.
- The vegetation is dead.

4.0 Application requirements

08/07/2021
C211brim

The following application requirements apply to an application for a permit to rezone land or use land to construct a building or construct or carry out works, to remove, destroy or lop any vegetation, or to subdivide land under Clause 42.01, in addition to those specified elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- The results of a detailed flora and fauna survey and assessment of the land which is undertaken by qualified and experienced personnel using methods acceptable to the Department administering the Flora and Fauna Guarantee Act 1988 and which documents:
  - Any significant populations or communities of native plants
  - Any significant species or populations of native fauna
- An independent review of the flora and fauna survey and assessment undertaken by appropriately qualified and experienced personnel
- Information which demonstrates that development impacts on sites of national, State or regional significance for flora and fauna would be minimised and that the integrity of the site will be maintained or enhanced
- A Land Management Plan prepared in accordance with the guidelines contained in the Brimbank Natural Heritage Strategy which presents details of proposed arrangements for the effective and ongoing management of the land consistent with the environmental objectives to this schedule
- A demonstration that adequate safeguards would be put in place to ensure that activities in any developed portions of the land do not detrimentally affect significant communities or populations of native plants or native fauna or their habitats.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit to rezone land or use land to construct a building or construct or carry out works, to remove, destroy or lop vegetation, or to subdivide land under Clause 42.01, in addition to those specified in Clause 42.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The Planning Policy Framework.
- The local policy, Natural Heritage Policy and the Brimbank Natural Heritage Strategy (March 1997).
- The comments of the Department of Environment, Land, Water and Planning.

The responsible authority must be satisfied that:

- Any flora and fauna survey and assessment of the land has been adequately completed under appropriate seasonal conditions.
- Any flora and fauna survey and assessment of the land has been independently reviewed in an appropriate manner.
- Any development plans for the land clearly take into consideration the environmental objectives of this schedule.
- Implementation of the land management plan will prevent detrimental impacts on significant communities or populations of native plants and fauna.

Background documents

Flora and Fauna report on Baldwin Avenue/Solomon Heights Grassland, Abzeco P/L August 2005.

Natural Heritage Strategy – guidelines for protecting, enhancing and managing significant natural assets, 1997.

Sites of Botanical Significance in the Western Region of Melbourne, Department of Geography, University of Melbourne, 1987.

Table 1 Environmental Weeds

Species	Common Name
Cynara cardunculus	Spanish Artichoke
Helminthotheca echioides	Ox-tongue
Hypochoeris radicata	Cats Ear
Lycium ferocissimum	African Box-thorn
Nassella hyalina	Fine Needle-grass
Nassella leucotricha	Pale Needle-grass
Nassella neesiana	Chilean Needle-grass
Nassella trichotoma	Serrated Tussock
Palntago lanceolata	Ribwort
Allium vineale	Crow Carlic
Asphodelus fistulousus	Onion Weed
Aster subulatus	Aster Weed

Species	Common Name
Berkheya rigida	African Thistle
Brassica fruticulosa	Twiggy Turnip
Chrysanthermoides monilifera ssp. Monilifera	Boneseed
Cirsium vulgare	Spear Thistle
Conium maculatum	Hemlock
Convolvulus arvensis	Common Bindweed
Echium plantagineum	Paterson’s Curse
Foeniculum vulgare	Fennel
Fraxinus angustifolia ssp. Anustifolia	Desert Ash
Galenia pubescens	Galenia
Genista monspessulana	Montpellier Broom
Juncus acutus ssp. Acutus	Sharp Rush
Lavatera cretica	Cretan Hollyhock
Leontodon taraxacoides	Hairy Hawkbit
Marrubium vulgare	Horehound
Myrsiphyllum asparagoides	Simlax Asparagus
Olea europaea ssp. Europaea	African Olive
Opuntia vulgaris	Drooping Prickly Pear
Opuntia sp.	Prickly Pear
Oxalis pes-caprae	Soursob
Plantago coronopus	Buck's-horn Plantain
Prunus cerasifera	Cherry Plum
Populus sp.	Poplar
Ricinus communis	Castor Oil Plant
Rosa rubiginosa	Sweet Briar
Rubus discolour	Balckberry
Rumex conglomerates	Clustered Dock
Rumex crispus	Curled Dock
Salix spp.	Willows
Schinus molle var. areira	Pepper Tree

Species	Common Name
Silybum marianum	Variegated Thistle
Sonchus spp.	Sow-thistles
Tradescantia albiflora	Wandering Jew
Tragopogon porrifolius	Salsify
Ulex europaeus	Furze

08/07/2021
C211brim

SCHEDULE 4 TO CLAUSE 42.01 ENVIRONMENTAL SIGNIFICANCE OVERLAY

Shown on the planning scheme map as **ESO4**.

KORORROIT CREEK CORRIDOR PROTECTION

1.0 Statement of environmental significance

08/07/2021
C211brim

Kororoit Creek is a major environmental and recreational asset within Melbourne's western region winding its way from its headwaters at Mount Aitken, Deverall Hill and Beattie Hill to enter Port Philip Bay at Altona 8.1 kilometres downstream.

Kororoit Creek is significant for its geomorphological, landscape, biodiversity and recreational values, particularly within the 30 metre habitat corridor along the waterway.

Kororoit Creek is part of the extensive western basalt plains, which formed by volcanic activity at least two million years ago. The natural escarpments and deep pools of Kororoit Creek are a distinguished characteristic and make the creek a significant waterway within Melbourne's west and north. Kororoit Creek is an outstanding example of a Victorian basalt plains stream. In an urban Melbourne context it is one of the most valuable streams in Melbourne, with its natural pools and escarpments rivalling and surpassing most others.

Kororoit Creek passes through a diverse range of landscapes and land-uses. The characteristics of the creek alter from flat, open rural land to established and developing urban suburbs industrial land with significantly altered creek profiles and into flood plains passing through rich mangrove and saltmarsh habitats.

The creek corridor provides a habitat for endangered species such as the Growling Grass Frog and the Striped Legless Lizard, as well as internationally recognised migratory birds at the saltmarshes of the creek mouth. The creek also features significant remnant native vegetation, including the River Red Gum and White Mangroves. In addition, the creek banks and land at the top of the banks, while somewhat degraded contain a number of sites supporting remnant vegetation, providing valuable habitat.

Kororoit Creek corridor is regarded as an important and valuable asset by local communities of the western suburbs and visitors. The creek is used extensively for walking, cycling, open space, recreation and picnics.

As such, the protection and restoration of sites and features of geomorphological, biodiversity and recreational values are of a high importance.

Local Context

Brimbank City Council

The Kororoit Creek traverses through the established area of Deer Park, the new residential area of Cairnlea, the industrial area of Orica and the residential areas of Ardeer and Sunshine into the industrial area of Brooklyn.

The northern sections of the Creek are a more natural corridor containing significant species of flora and fauna and extensive areas of Aboriginal archaeological material and places of importance.

Significant areas of the Creek are highly modified and vegetation degraded. There is opportunity to protect those areas of high environmental quality from further loss, encourage the revegetation of degraded areas and the restoration of the natural creek corridor and provide a continuous publically managed and accessible waterway.

2.0 Environmental objectives to be achieved

08/07/2021
C211brim

2.1 Ecological systems

08/07/2021
C211brim

Objective 1

To protect and improve waterway health and biodiversity values of Kororoit Creek and its environs, including native vegetation, fauna habitat, flora and fauna species.

Guidelines

- Minimise degradation of environmental value by avoiding the removal or damage to existing native vegetation and habitat areas.
- Landscape design, groundwater/stormwater design and earthworks should prevent any adverse impacts by water run-off, weed invasion, exotic species introduction and land erosion.
- Limit public access to areas identified as high value biodiversity areas with appropriate fencing, access ways and signage.
- Protect or enhance water quality in the Creek, through the use of water sensitive urban design and the construction of stormwater treatment ponds adjacent to the Creek corridor.
- Locate passive and active recreational open spaces to minimise disruption to environmentally significant areas, with appropriate fencing, screening and/or landscape buffer areas.

2.2 Landscape character

16/08/2012
C131

Objective 2

To protect and enhance the natural geological form of the creek, particularly rock escarpments and associated pools of the Kororoit Creek

Guidelines

- Encourage rehabilitation works to return the creek banks to a natural state, particularly where it has been significantly altered or channelled.
- Protect natural river profile, geomorphology and geological formations by avoiding major earthworks, minimising cut and fill of embankments and managing access.

Objective 3

To improve the landscape character of the creek corridor

Guidelines

- Ensure that elements of the original landscape are retained particularly through the planting of indigenous vegetation.
- New landscaping and vegetation should be located and designed to reinforce the legibility of the local waterway landform and re-establish the Creek's original natural setting.

2.3 Open space and access objectives

08/07/2021
C211brim

Objective 4

To create and maintain a continuous open space corridor and access trail with links to an open space network of local parks, linear green spaces, regional parks and trail connections.

Guidelines

- Maintain opportunities for integration and connection of the Kororoit Creek trails and pathways with other existing and proposed trails.

- Retain existing connections and protect potential connections from the creek corridor to community facilities, other open space trails and the regional open space network.
- Construct access paths and trails in accordance with the AusRoads Trail Standards and the Melbourne Water Shared Pathways Guidelines (Jan 2009).
- Locate passive and active recreational open spaces to minimise disruption to environmentally significant areas, with appropriate fencing, screening and/or landscape buffer areas.

2.4 Views and visual features

16/08/2012 C131

Objective 5

To protect and enhance the natural and visually attractive creek corridor and landscape views along the creek corridor.

Guidelines

- Development and works (buildings, fences or other structures) should be designed and located so as not to be visually prominent or intrusive when viewed from the Creek corridor and pathways/trails.
- Landscape enhancement and revegetation works should seek to restore the natural environment and reduce the visual prominence of urban forms, for example landscape screening with indigenous vegetation to obscure the visibility of the built form.
- Ensure works adjoining the creek are sensitively placed and designed to minimise the visual impact on the creek corridor

2.5 Built form objectives

16/08/2012 C131

Objective 6

To avoid or minimise impacts of buildings and works on the creek corridor.

Guidelines

- Ensure careful and responsive subdivision and building design reflects the landform and geomorphology of the creek valley
- Ensure that the earthworks, built form and fencing retain and enhance the local natural landform and bank profile of the creek corridor, through appropriate setback and landscaping.
- Ensure development and works are sensitively placed and designed to provide a positive interface to the Creek corridor.
- Locate and design new buildings to not be visually prominent or intrusive when viewed from the creek corridor or pathways/trails.
- Ensure development provide opportunities for passive surveillance of the Creek corridor.
- Minimise hard paving surfaces on lots adjacent to the Creek.
- Encourage the provision of a continuous publically accessible open space corridor adjacent to the waterway.
- Fence transparency must be a minimum of 50%. Fence design, materials and transparency should be appropriate to the landscape setting of the Creek and provide opportunities for visual interaction along the Creek corridor.
- Built form should not be visually obtrusive within the Creek corridor. Visual bulk should be avoided through building form, materials, articulation, setbacks and with landscape screening where no design alternative exists.

- Building facades should be highly articulated in response to the landscape context, avoiding large, stark expanses of wall materials. External wall and roof materials should be appropriate to the natural, landscape setting of the creek corridor. Highly reflective or metallic materials should be avoided.
- Ensure the use of consistent built landscape elements, such as signage, pathways and furniture.

3.0 Permit requirement

08/07/2021
C211brim

In addition to the permit requirements of Clause 42.01-2, a permit is required to:

- construct a building or fence

A permit is not required for:

- Undertaking routine maintenance and repairs to existing buildings and works which are undertaken to the same details, specifications and materials.
- Works undertaken by or on behalf of a public authority or waterway management agency for:
  - ongoing management and operation of effluent treatment
  - ongoing management, operation and maintenance of a minor utility
  - ongoing management of fire breaks
  - regulation of the flow of water in a watercourse.
  - environmental protection and enhancement of the creek corridor.
  - regulation or mitigation of flooding from the creek.

The requirement for a permit to remove, destroy, prune or lop vegetation does not apply to:

- Removing environmental weeds identified in Table 1 to this Schedule or as proclaimed as a weed under the *Catchment and Land Protection Act (1994)*.
- Pruning or lopping of vegetation to maintain access to open space and pedestrian trails/paths, public safety or to maintain a plant's horticultural health.
- The removal of non-indigenous plants in the preparation for revegetation or native vegetation management works by / on behalf of a municipal council or public authority or water management agency.

4.0 Application requirements

08/07/2021
C211brim

The following application requirements apply to an application for a permit to subdivide land, construct a building or construct or carry out works under Clause 42.01, in addition to those specified elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A site plan to scale showing lot boundaries, setbacks of existing and proposed buildings and works, driveways and vehicle parking and loading areas, external storage and site service areas, proposed landscape areas and the location of any easements, native and exotic vegetation and the vegetation to be removed.
- An application for buildings and works must include an Environmental Construction Management Plan that will provide, but not be limited to the following information:
  - The location, species and value of existing native vegetation on site.
  - How buildings or works will not compromise remnant native vegetation.
  - How buildings or works will not compromise the creek corridor landscape or natural landform.

  - How the development will protect the existing ecological values of the creek corridor.
  - How buildings or works will not threaten stream processes or water quality.
  - Proposed measures to minimise the extent of stream bank disturbance and runoff.
  - The need to stabilise disturbed areas by engineering works or vegetation.
  - Construction vehicle access.
- Location of fuel tanks, water storage or other storage facilities so as to not inhibit the ability to carry out ecological burning of adjacent vegetation
- All hardstand areas to direct surface water away from native vegetation and into approved drainage points
- Building elevations drawn to scale.
- Existing and proposed finished site levels.
- The gradient and location of the top and toe of all cut and fill batters.
- The location, height and materials of construction of existing and proposed retaining walls.
- Floor plan layouts and finished floor levels.
- A landscape plan showing existing and new vegetation, retaining walls and fencing.The proposed external building materials, finishes and colours.
- Details of the location of the proposed method of sewage, stormwater, sullage and effluent disposal.
- An application to remove, destroy or lop vegetation must be accompanied by the following information:
  - A description of the vegetation to be removed, including the extent and type of vegetation and the number and size of any vegetation to be removed.
  - A written explanation justifying the removal of the vegetation.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 42.01, in addition to those specified in Clause 42.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The guidelines for each objective.
- The Municipal Planning Strategy and Planning Policy Framework.
- The *Kororoit Creek Regional Strategy 2005-2030* and any relevant adopted waterway management plan or waterway master plan.
- The views of Melbourne Water.

Background documents

Kororoit Creek Regional Strategy 2005-2030.

Brimbank Open Space Strategy.

Kororoit Creek Masterplan 2006

Port Phillip and Westernport Regional River Health Strategy (June 2007)

Table 1 to Schedule 4 Environmental Weeds

Species name	Common name
Agapanthus orientalis	Agapanthus
Agave sp	Agave
Aloe sp	Aloe
Anredera cordifolia	Madeira Vine
Berkheya rigida	African thistle
Beta vulgaris	wild beet
Carduus spp.	Slender Thistle
Chamecytisus proliterus	Tree lucern
Crataegus monogyna	Hawthorn
Cynadon dacctylon	Couch
Diptatherum miliaceam	Rice Millet
Lagunaria patersonii	Norfolk Island Hibiscus
Melaleuca armillaris	Bracelet Honey Myrtle
Opuntia sp.	Cactus/prickly pear
Polygala myrtifolia	Myrtle leaf milkwort
Prunus sp.	Cherry
Stenotaphrum secundatum	Buffalo grass
Thinopryum ponticum	Tall Wheat grass
Acacia baileyana	Cootamundra Wattle
Acer pseudoplatanus	Sycamore Maple
Allium triquetrum	Angled Onion
Anredera cordifolia	Madeira Vine
Asparagus asparagoides	Bridal Creeper
Carduus spp.	Slender Thistle
Carduus tenuiflorus	Winged Slender-thistle
Centaurea calcitrapa	Star Thistle
Chrysanthemoides monilifera	Boneseed
Cirsium arvense	Perennial Thistle
Cirsium vulgare	Spear Thistle
Clematis vitalba	Old Man's Beard
Convolvulus arvensis	Common Bindweed
Coprosma repens	Mirror Bush
Cortaderia selloana	Pampas Grass
Crataegus monogyna	Hawthorn
Cotoneaster glaucophyllus	Large-leaf Cotoneaster
Cotoneaster pannosus	Silver-leaf Cotoneaster

Species name	Common name
Cotoneaster franchetti	Grey Cotoneaster
Cuscuta planiflora	Small-seed Alfalfa-dodder
Cynara cardunculus	Artichoke Thistle
Cytisus scoparius	English Broom
Datura stramonium	Common Thorn-apple
Diplotaxis tenuifolia	Sand Rocket
Dipsacus fullonum subsp. fullonum	Wild Teasel
Dittrichia graveolens	Stinkwort
Echium plantagineum	Paterson's Curse
Eichhornia crassipes	Water Hyacinth
Emex australis	Spiny Emex
Eragrostis curvula	African Love-grass
Foeniculum vulgare	Fennel
Fraxinus angustifolia	Desert Ash
Genista linifolia	Flax Leaf Broom
Genista monspessulana	Montpellier Broom
Hedera helix	English Ivy
Hypericum perforatum subsp. veronense	St John's Wort
Ipomoea ssp.	Morning Glory
Juncus acutus subsp. acutus	Spiny Rush
Lepidium draba	Hoary Cress
Leucanthemum vulgare	Ox-eye Daisy
Ligustrum spp.	Privets
Lycium ferocissimum	African Box-thorn
Marrubium vulgare	Horehound
Moraea miniata	Two-leaf Cape-tulip
Nassella trichotoma	Serrated Tussock
Nassella neesiana	Chilean Needle-grass
Olea europaea	Olive
Onopordum acanthium subsp. acanthium	Scotch Thistle
Opuntia robusta	Wheel Cactus
Oxalis pes-caprae	Soursob
Paraserianthes lophantha	Cape Wattle
Paspalum dilatatum	Paspalum
Phalaris aquatica	Phalaris
Physalis viscosa	Sticky Ground-cherry
Pinus radiata	Radiata Pine

Species name	Common name
Pittosporum undulatum	Sweet Pittosporum
Reseda luteola	Weld
Ricinus communis	Castor Oil Plant
Rosa rubiginosa	Sweet Briar
Rubus fruticosus spp. agg.	Blackberry
Salix babylonica s.l.	Weeping Willow
Salix cinerea	Grey Sallow
Salix fragilis	Crack Willow
Salix spp.	Willow
Salix X rubens	Basket Willow
Schinus molle	Peppercorn
Scolymus hispanicus	Golden Thistle
Silybum marianum	Variegated Thistle
Solanum linnaeanum	Apple of Sodom
Solanum nigrum	Blackberry nightshade
Ulex europaeus	Gorse
Vinca major	Blue Periwinkle
Xanthium spinosum	Bathurst Burr
Zantedeschia aethiopica	White Arum Lily

08/07/2021
C211brim

SCHEDULE 5 TO CLAUSE 42.01 ENVIRONMENTAL SIGNIFICANCE OVERLAY

Shown on the planning scheme map as **ESO5.**

MARIBYRNONG RIVER VALLEY AND ENVIRONS

1.0 Statement of environmental significance

17/10/2013
C146

The Maribyrnong River extends from its source above the Organ Pipes National Park through Keilor, Essendon, Footscray and Yarraville to where it meets the Yarra River near the West Gate Bridge.

The character of the river as it flows through the municipality of Brimbank is of a natural river with a remote and natural non urban character.

The upper river valley, including Sydenham Park supports and connects significant areas of a range of native grasslands, escarpment shrublands and woodlands and provides a habitat for a range of mammals, reptiles and bird species. This section of the river also supports a small agricultural section, market gardens. As the river moves through the township of Keilor, it becomes a major feature of the regionally significant Brimbank Park and the adjoining Council owned park, recreation and trail network. Further south, through the steep valleys of the Sunshine North, the river becomes more urbanised with new residential development occurring in the River Valley Estate.

Maribyrnong River Valley Design Guidelines, May 2010 focuses on the characteristics of the river valley that need to be conserved, repaired or enhanced. To help guide future development, the river has been divided into seven 'lengths', each with a preferred character type.

The *Brimbank Green Wedge Management Plan 2010* identifies the environmental and cultural heritage assets of the river environs and the impacts of the adjoining horticultural and recreational uses abutting the river.

2.0 Environmental objective to be achieved

08/07/2021
C211brim

Ecological Objectives

Objective 1

To protect the ecological values of the Maribyrnong River and its environs, from loss and degradation.

Strategies

1.1 Avoid earth works and minimise cut and fill of embankments adjoining the river.
1.2 Landscape design, revegetation works, groundwater/stormwater design and earthworks should limit any adverse impacts on water run-off, weed invasion, exotic species introduction and land erosion.
1.3 Ensure the replanting of native/indigenous vegetation of the river environs.

Objective 2

To improve the health and quality of the waterway

Strategies

2.1 Ensure there is no loss of floodplain storage as a result of buildings and works.
2.2 Support low water consumption activities adjacent to the river and discourage uses with high water needs.
2.3 For new agricultural use require a water assessment/water plan to identify consumption and discharge needs, without compromising the health of the waterway.
2.4 Support storm water and irrigation run-off harvesting and treatment.
2.5 Ensure new development and works minimises runoff into the waterway and any runoff is adequately treated prior to entering the waterway to ensure water quality of the river is not affected in accordance with best practice environmental management.

Open Space and Access

Objective 3

To provide a publically managed vegetation and habitat corridor along the length of the river.

Strategies

3.1 Subdivision and development should provide for a vegetated corridor along the length of the River that reflects the relevant Ecological Vegetation Class.

Objective 4

To provide and improve existing open space links and connections to and from the river with adjoining community facilities, open space trails and the regional open space network.

Strategies

4.1 Ensure opportunities for integration and connections of the Maribyrnong River trails and pathways with other existing and proposed trails are maintained.
4.2 Construction of access paths and trails should be in accordance with the AusRoads Trail Standards and the Melbourne Water Shared Pathways Guidelines (Jan 2009) or equivalent local documents.
4.3 Ensure passive and active recreational open space areas are located to minimise disturbance to environmentally significant areas, with transparent/open style fencing and/or appropriate landscape buffers.

Objective 5

To provide for public access from surrounding areas to the waterway and open space corridor.

Strategies

5.1 Ensure public access provides clear visual links between the river and the hinterland.
5.2 Ensure the siting of public access avoids removal and disturbance of biodiversity and culturally significant areas.
5.3 Limit public and livestock access to areas identified as high value biodiversity areas defined with appropriate fencing, access ways and signage.
5.4 Access along the river side should be safe, visually clear and provide access for all abilities.

Vegetation, Landscape Character and Views

Objective 6

To protect the long term survival and viability of remnant native vegetation.

Strategies

6.1 Conserve significant vegetation and discourage the removal and damage of remnant vegetation.
6.2 Ensure suitable fencing is provided to protect remnant vegetation from pest and weed infestation.
6.3 Provide suitable buffers for fire protection works and site access.

Objective 7

To ensure planting and revegetation reinforces the preferred character of the river.

Strategies

7.1 Landscaping and revegetation works adjacent to the river should consist of the use of appropriate local native species and provide habitat for local fauna.
7.2 Plants used for landscaping and revegetation should be of local provenance, plants germinated from seed or cutting sourced from a local, remnant population and be reflective of the relevant Ecological Vegetation Class in accordance with the Department of Environment and Primary Industry benchmarks.
7.3 Planting should not include any environmental weeds as specified in Table 1 to this Schedule or as proclaimed as weeds under the Catchment and Land Protection Act 1994.
7.4 Within the Melbourne Airport Environs Overlay area, planting should not include any bird attracting species.

Objective 8

To maintain and protect views along the river corridor, including escarpments and other highly visible areas from visually intrusive development.

Strategies

8.1 Landscaping and revegetation works should not obscure, but enhance visual corridors to and from the hinterland to the river.
8.2 Landscape and revegetation works should visually reinforce clear access ways to and from the river.
8.3 Ensure buildings and works do not impinge on views along the waterway corridor.
8.4 Fencing must be a minimum of 50% transparency. Fence design, materials and transparency should be appropriate to the landscape setting of the river corridor and provide opportunities for visual interaction and views along the waterway.

Objective 9

To protect natural landforms and geological features along the waterway.

Strategies

9.1 All development and works should avoid disturbance to any natural features, landforms or sites of geological significance.
9.2 Ensure buildings and works do not contribute to erosion and disturbance to the river.
9.3 Ensure the protection of the natural gradient and landform of the river banks, avoid earth works and prevent cut and full embankments adjoining the top of escarpments.

Built form

Objective 10

To minimise the visual impact of buildings and works on the river corridor.

Strategies

10.1 Ensure buildings and works adjoining the river are sited and designed and utilise muted building materials and colours, to minimise visibility on the river corridor and trails.
10.2 Require landscaping to screen buildings and works and assist in the creation of a continuous band of planted landscape adjacent to the river.
10.3 Building materials and colours should reflect the natural setting of the river.

Objective 11

To ensure building development provides a positive frontage with the river corridor.

Strategies

11.1 Buildings should be oriented to front the open space along the waterway corridor.
11.2 Buildings should be designed to increase natural surveillance of the waterway corridor.
11.3 Development should retain and enhance the local natural landforms and the bank profile of the river.

3.0 Permit requirement

17/10/2013
C146

A permit is required to construct a building or to construct or display a sign.

Buildings and works

The requirement for a permit to construct a building or to construct or carry out works does not apply to the following:

- Undertaking routine maintenance and repairs to existing buildings and works.
- Construction of a building or carrying out works by a public authority (or agent for a public authority) for:
  - ongoing management, operation and maintenance of a minor utility

- ongoing management of fire breaks
- ongoing management and operation of effluent treatment
- regulation of the flow of water in a watercourse
- environmental protection and enhancement of the creek corridor
- regulation or mitigation of flooding from the creek
- the purpose of access pathways and trails

Vegetation

A permit is not required to remove, destroy, prune or lop:

- Environmental weeds identified in Table 1 to this Schedule or as proclaimed as weeds under the Catchment and Land Protection Act 1994.
- Vegetation to maintain existing access or to open space, access tracks, pedestrian trail/paths, public safety, to maintain a plant's horticultural health, to maintain fire breaks or to construct or maintain a property boundary fence for protection of a minor utility installation.
- The removal of non-indigenous plants in preparation for revegetation or native vegetation management works by or on behalf of a municipal council or public authority or water management agency.

4.0 Application requirements

08/07/2021
C211brim

The following application requirements apply to an application for a permit to subdivide land, construct a building or construct or carry out works under Clause 42.01, in addition to those specified elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A site plan to scale showing lot boundaries, setbacks of existing and proposed buildings and works, driveways and vehicle parking and loading areas, external storage and site service areas, proposed landscape areas and the location of any easements, native and exotic vegetation and the vegetation to be removed.
- Applications for buildings and works should include an Environmental Construction Management Plan that will provide, but not be limited to the following information:
  - The location, species and value of existing native vegetation on site.
  - How buildings or works will not compromise remnant native vegetation.
  - How buildings or works will not compromise the creek corridor landscape or natural landform.
  - How the development will protect the existing ecological values of the creek corridor.
  - How buildings or works will not threaten stream processes or water quality.
  - Proposed measures to minimise the extent of stream bank disturbance and runoff.
  - The need to stabilise disturbed areas by engineering works or vegetation.
  - Construction vehicle access.
- Building elevations drawn to scale.
- Existing and proposed finished site levels.
- The gradient and location of the top and toe of all cut and fill batters
- The location, height and materials of construction of existing and proposed retaining walls.

- Floor plan layouts and finished floor levels.
- A landscape plan showing existing and new vegetation, retaining walls and fencing
- The proposed external building materials, finishes and colours.
- Details of the location of the proposed method of sewage, stormwater, sullage and effluent disposal.
- For buildings and works associated with an agricultural or horticultural use, a Land Management Plan detailing how stormwater and land use runoff is to be collected, treated and/or reused.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit to construct a building or fence or carry out works or subdivide land, or remove, destroy or lop native vegetation under Clause 42.01, in addition to those specified in Clause 42.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The strategies for each objective.
- The Municipal Planning Strategy and Planning Policy Framework.
- The *Maribyrnong River Valley Design Guidelines April 2010*.
- *Brimbank Green Wedge Management Plan August 2010.*
- The views of the water authority or Melbourne Water.

Background documents

Maribyrnong River Valley Design Guidelines(April 2010)

Brimbank Green Wedge Management Plan August 2010.

Table 1 to Schedule 5 to Clause 42.01 - Environmental Weeds

Species name	Common Name
Agapanthus orientalis	Agapanthus
Agave sp	Agave
Aloe sp	Aloe
Anredera cordifolia	Madeira Vine
Berkheya rigida	African thistle
Beta vulgaris	wild beet
Carduus spp.	Slender Thistle
Chamecytisus proliterus	Tree lucern
Crataegus monogyna	Hawthorn
Cynadon dacctylon	Couch
Diptatherum miliaceam	Rice Millet
Lagunaria patersonii	Norfolk Island Hibiscus
Melaleuca armillaris	Bracelet Honey Myrtle
Opuntia sp.	Cactus/prickly pear
Polygala myrtifolia	Myrtle leaf milkwort
Prunus sp.	Cherry

Species name	Common Name
Stenotaphrum secundatum	Buffalo grass
Thinopryum ponticum	Tall Wheat grass

08/07/2021
C211brim

SCHEDULE 6 TO CLAUSE 42.01 ENVIRONMENTAL SIGNIFICANCE OVERLAY

Shown on the planning scheme map as **ESO6**.

SITES OF KNOWN BIOLOGICAL SIGNIFICANCE

1.0 Statement of environmental significance

08/07/2021
C211brim

Brimbank City Council supports some of the most threatened ecosystems in Australia. Sites of biological significance in the municipality play an important role in contributing to the ecological processes and biodiversity of the region.

Located in the Victorian Volcanic Plains Bioregion, the municipality supports four broad vegetation communities: Plains Grassland, Escarpment Shrubland, Riparian Complex and Plains Grassy Wetland.

Plains Grassland and Plains Grassy Wetland are listed as "endangered" vegetation communities under the *Victorian Flora and Fauna Guarantee Act 1988*. Plains Grassland (Natural Temperate Grasslands of the Victorian Volcanic Plains) is also listed as "critically endangered" under the Australian Government's *Environment Protection and Biodiversity Conservation Act 1999*, (EPBC Act). All ecological vegetation classes (evc) found in Brimbank are listed as "endangered" by the Department of Environment, Land, Water and Planning.

These vegetation communities provide critical habitat for several species of threatened fauna and flora including the Striped Legless Lizard (*Delmar impar*) which is listed as "vulnerable" under the EPBC Act, the Spiny Rice Flower (*Pimelea Spinescens subs spinecens*) and Golden Sun Moth (*Synemon* plana) which are both listed as "critically endangered".

Preserving the biodiversity of the region depends on retaining and enhancing existing native vegetation, sensitive land management, revegetating land with indigenous species and strengthening habitat corridors.

The sites covered by this schedule have been identified as sites of biological significance in the *Brimbank City Council Natural Heritage Strategy 1997*, the Department of Sustainability and Environment's Biodiversity Database and / or the *Brimbank Native Vegetation Review: Site Assessment 2007* and targeted flora and fauna reports. The ecological vegetation class of each site is listed in Table 2.

2.0 Environmental objective to be achieved

08/07/2021
C211brim

To protect and enhance the viability and connectivity of ecosystems, species and genetic diversity in areas of identified biological significance.

To ensure that any use, development or management of land within and adjacent to areas of biological significance are compatible with their long-term maintenance and conservation and will not have detrimental impacts on biodiversity values.

To maintain the integrity of sites of biological significance through protection from:

- pest plant and animal invasion;
- reduction or fragmentation of habitat;
- increases in nutrient and sediment input from fill batters and earthworks;
- inappropriate location of vehicle access;
- inappropriate fire regimes; and
- distortion of the natural hydrological regime.

To protect and enhance the landscape character and heritage values of identified grasslands, valleys and wetlands.

3.0 Permit requirement

08/07/2021
C211brim

A permit is not required:

- To remove vegetation not indigenous to the region or proclaimed as a weed under the *Catchment and Land Protection Act 1994*, or listed in Table 1 to this Schedule.
- For works undertaken by or on behalf of a public authority or waterway management agency involving revegetation, including preparatory works associated with revegetation.

4.0 Application requirements

08/07/2021
C211brim

The following application requirements apply to an application for a permit to construct a building or carry out works, to remove or lop any vegetation, or to subdivide land under Clause 42.01, in addition to those specified elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A report prepared by an appropriately qualified ecologist, biologist, botanist or zoologist. The report should include the following information:
  - A flora and fauna survey of the whole site, identifying the type, significance and fauna values or other habitat components of the vegetation on the site. The flora and fauna survey should provide the following information with reference to the *Port Phillip and Western Port Native Vegetation Plan or Victoria's Native Vegetation Management: A Framework for Action*:
    - The Bioregional Conservation Status of the Ecological Vegetation Classes found on the site.
    - The conservation significance of the site.
  - An explanation of how the proposal addresses the "three step approach" to avoid, minimise and offset native vegetation losses as specified in *Victoria's Native Vegetation Management: A Framework for Action* and the *Port Phillip and Western Port Native Vegetation Plan*.
  - Identification of any native vegetation or other habitat components to be removed, destroyed, damaged or otherwise disturbed.
  - The likely impact of the proposal on the biodiversity of the region.
  - The specific measures to be taken to ensure that any impacts on native flora and / or fauna are compensated for by rehabilitation or revegetation to achieve an environmental net gain in accordance with the requirements of the *Port Phillip and Western Port Native Vegetation Plan*. If the proposal involves clearing areas of native vegetation, the report should specify:
    - The quality and quantity of native vegetation to be removed (expressed in habitat hectares).
    - The native vegetation offset required (expressed in habitat hectares) to achieve a net gain in accordance with the requirements of the *Port Phillip and Western Port Native Vegetation Plan*.
    - An Offset Management Plan which outlines:
      - the location of the offset including fully dimensioned plans drawn to a scale of 1:200 or 1:500;
      - a habitat hectare assessment of the offset site;
      - the management actions required to achieve the specified net gain including revegetation, fencing, pest plant and animal control, burning regimes, methodology to be used for monitoring the site and signage;
      - the timing of the management actions including a schedule of works over a 10 year period;

- the land manager responsible for implementing the management plan;
- a schedule of costs for implementing the management plan including all administrative expenses;
- construction of and maintenance of management/access tracks or buffer areas required for the delivery of management activities; and
- the legal mechanism to be used to permanently secure the offset.

- Any statutory requirements under the Flora and Fauna Guarantee Act 1988 or the Environment Protection and Biodiversity Act 1999.

- A construction management plan showing how remnant patches of native vegetation will be protected during construction from vehicles, machinery and clean fill storage areas with appropriate fencing and / or buffer zones. All vehicle routes, machinery paths and clean fill storage areas should be located at least 3 metres from patches of native vegetation.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 42.01, in addition to those specified in Clause 42.01 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The Municipal Planning Strategy and Planning Policy Framework.
- The conservation status of the vegetation to be removed.
- The targets and policies specified in the *Port Phillip and Western Port Native Vegetation Plan* and *Victoria's Native Vegetation Management: A Framework for Action*.
- The reason for removing any vegetation and the viability of any alternative options which do not require removal of native vegetation or other habitat components. Where alternatives exist which do not require the loss of native vegetation or other habitat values, these alternatives should be favoured.
- The results of any flora and fauna survey and assessment of the land and consideration of whether the survey and assessment has been adequately completed under appropriate seasonal conditions and by suitably qualified personnel.
- If native vegetation is to be removed, whether suitable measures have been identified to achieve a net environmental gain in accordance with the requirements of the *Port Phillip and Western Port Native Vegetation Plan*.
- Any other statutory requirements related to native flora and fauna.
- If vegetation is to be removed and an offset is required, the preference is to locate offsets within Brimbank and connected to similar types of vegetation.

Table 1 to Schedule 6 to Clause 42.01 - Environmental Weeds

Species	Common Name
Cynara cardunculus	Spanish Artichoke
Helminthotheca echioides	Ox-tongue
Hypochoeris radicata	Cats Ear
Lycium ferocissimum	African Box-thorn
Nassella hyalina	Fine Needle-grass

Species	Common Name
Nassella leucotricha	Pale Needle-grass
Nassella neesiana	Chilean Needle-grass
Nassella trichotoma	Serrated Tussock
Palntago lanceolata	Ribwort
Allium vineale	Crow Carlic
Asphodelus fistulousus	Onion Weed
Aster subulatus	Aster Weed
Berkheya rigida	African Thistle
Brassica fruticulosa	Twiggy Turnip
Chrysanthermoides monilifera ssp. Monilifera	Boneseed
Cirsium vulgare	Spear Thistle
Conium maculatum	Hemlock
Convolvulus arvensis	Common Bindweed
Echium plantagineum	Paterson's Curse
Foeniculum vulgare	Fennel
Fraxinus angustifolia ssp. Anustifolia	Desert Ash
Galenia pubescens	Galenia
Genista monspessulana	Montpellier Broom
Juncus acutus ssp. Acutus	Sharp Rush
Lavatera cretica	Cretan Hollyhock
Leontodon taraxacoides	Hairy Hawkbit
Marrubium vulgare	Horehound
Myrsiphyllum asparagoides	Simlax Asparagus
Olea europaea ssp. Europaea	African Olive
Opuntia vulgaris	Drooping Prickly Pear
Opuntia sp.	Prickly Pear
Oxalis pes-caprae	Soursob
Plantago coronopus	Buck's-horn Plantain
Prunus cerasifera	Cherry Plum
Populus sp.	Poplar

Species	Common Name
Ricinus communis	Castor Oil Plant
Rosa rubiginosa	Sweet Briar
Rubus discolour	Balckberry
Rumex conglomerates	Clustered Dock
Rumex crispus	Curled Dock
Salix spp.	Willows
Schinus molle var. areira	Pepper Tree
Silybum marianum	Variegated Thistle
Sonchus spp.	Sow-thistles
Tradescantia albiflora	Wandering Jew
Tragopogon porrifolius	Salsify
Ulex europaeus	Furze

Table 2 to Schedule 6 to Clause 42.01

Site No.	Site Name	Ecological Vegetation Class
ESO4-7A	Calder Park Rail Reserve	Plains Grassland
ESO4-8A	Cyril Clements Reserve	Derived Grassy Woodland
ESO4-12A	Deer Park Rail Reserve - Railway Parade	Plains Grassland
ESO4-13A	Deer Park Urban Forest Grassland	Plains Grassland
ESO4-14A	Denton Grassland	Plains Grassland
ESO4-15A	Derrimut Grassland	Plains Grassland, Plains Grassy Wetland
ESO4-18A	Gilbertsons Drainage Easement Grasslands	Plains Grassland, Plains Grassy Wetland
ESO4-19A	Gilbertsons Estate Grasslands - Melbourne Water Retarding Basin	Plains Grassland
ESO6-19B	Gilbertsons Estate Grassland Patches	
ESO6-19M	Gilbertsons Estate Grassland Patches	
ESO4-20C	Ginifer Rail Reserve Grassland Patches	Plains Grassland
ESO4-20D	Ginifer Rail Reserve Grassland Patches	Plains Grassland
ESO4-23A	Iramoo Grassland	Plains Grassland
ESO4-25A	Jones Creek Grassland	Plains Grassland
ESO4-27A	Kayes Drain Grassland	Plains Grassland, Plains Grassy Wetland
ESO4-51A	Matthews Hill Grassland (O'Brien Park)	Plains Grassland
ESO4-55A	Mt Derrimut Grassland	Plains Grassland

Site No.	Site Name	Ecological Vegetation Class
ESO4-57A	Pimelea Terrace Grassland	Plains Grassland
ESO4-58A	Pioneer Park East	Plains Grassland
ESO4-59A	Pioneer Park West	Plains Grassland
ESO4-60A	Ptilotus Grassland	Plains Grassland
ESO4-61A	Reid Street Grassland	Plains Grassland
ESO4-62A	Lot 3 Robinsons Road	Plains Grassland
ESO4-63A	Oakwood Road - Eaton Court Grassland	Plains Grassland
ESO4-67A	St Albans Rail Reserve Grassland Patches - (north west)	Plains Grassland
ESO4-67B	St Albans Rail Reserve Grassland Patches - (south west)	Plains Grassland
ESO4-67C	St Albans Rail Reserve Grassland Patches - (south east)	Plains Grassland
ESO4-68A	St. Albans Transmission Line Grasslands	Plains Grassland
ESO4-69A	Stoney Creek Grassland	Plains Grassland
ESO4-70A	Sunshine Rail Reserve - Wright St	Plains Grassland
ESO4-73A	Sydenham Rail Reserve Grassland Patches	Plains Grassland
ESO4-74A	Taylors Creek Escarpment Shrubland - Green Gully	Plains Grassland, Escarpment Shrubland
ESO4-75D	Taylors Creek Grassland ? Wanaka Drive	Plains Grassland
ESO4-77A	Taylors Creek ? (Kings Road)	Plains Grassland, Plains Grassy Wetland
ESO4-78A	Taylors Creek - (Green Gully Road to Sunshine Avenue)	Riparian, Escarpment Shrubland, Plains Grassland, Plains Grassy Wetland
ESO4-79A	Calder Park Industrial Estate Grassland	Modified Plains Grassland
ESO5-80C	Kings Road Interchange	
ESO4-82A	Keilor Downs Plaza Grassland - (west)	Plains Grassland
ESO4-82B	Keilor Downs Plaza Grassland (east)	Plains Grassland
ESO4-83A	Bunnings Grassland	Plains Grassland
ESO4-84A	Investa Grassland	Plains Grassland
ESO4-86B	Ballarat Road Grassland (north)	Plains Grassland
ESO4-87A	Mobil Service Station Grassland	Plains Grassland
ESO5-88A	Cairnlea Drive, north of the Ring Road	
ESO4-91A	Steele Creek Grasslands	Plains Grassland

42.03 SIGNIFICANT LANDSCAPE OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **SLO** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify significant landscapes.

To conserve and enhance the character of significant landscapes.

42.03-1 Landscape character and objectives

31/07/2018
VC148

A schedule to this overlay must contain:

- A statement of the nature and key elements of the landscape.
- The landscape character objectives to be achieved.

42.03-2 Permit requirement

14/12/2023
VC253

A permit is required to:

- Construct a building or construct or carry out works. This does not apply:
  - If a schedule to this overlay specifically states that a permit is not required.
  - To the conduct of agricultural activities including ploughing and fencing (but not the construction of dams) unless a specific requirement for that activity is specified in a schedule to this overlay.
- Construct a fence if specified in the schedule to this overlay.
- Remove, destroy or lop any vegetation specified in a schedule to this overlay. This does not apply:
  - If the table to Clause 42.03-3 specifically states that a permit is not required.
  - To the removal, destruction or lopping of native vegetation in accordance with a native vegetation precinct plan specified in the schedule to Clause 52.16.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a fence.	Clause 59.05
Remove, destroy or lop one tree provided: ▪ A permit has not been granted for a VicSmart application to remove, destroy or lop a tree on the same land within the last 12 months. ▪ There is no other current VicSmart application to remove, destroy or lop a tree on the same land.	Clause 59.06
Construct a building or construct or carry out works for: ▪ A carport, garage, pergola, verandah, deck, shed or similar structure. ▪ A rainwater tank.	Clause 59.05

Class of application	Information requirements and decision guidelines
The buildings and works must be associated with a dwelling.	
Construct a building or construct or carry out works for a small second dwelling.	Clause 59.05

42.03-3 Table of exemptions

16/08/2024
VC262

The requirement to obtain a permit does not apply to:	
Emergency works	Vegetation that is to be removed, destroyed or lopped: ▪ in an emergency by, or on behalf of, a public authority or municipal council to create an emergency access or to enable emergency works; or ▪ where it presents an immediate risk of personal injury or damage to property. Only that part of the vegetation that presents the immediate risk may be removed, destroyed or lopped under this exemption.
Extractive industry	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of extractive industry in accordance with a work plan approved under the *Mineral Resources (Sustainable Development) Act 1990* and authorised by a work authority granted under that Act.
Fire protection	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of any of the following fire protection activities: ▪ fire fighting; ▪ planned burning; ▪ making or maintaining of a fuelbreak or fire fighting access track (or any combination thereof) that does not exceed a combined width of 6 metres; ▪ making of strategic fuelbreak up to 40 metres wide by, or on behalf of, a public authority in accordance with a strategic fuelbreak plan approved by the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*); ▪ is ground fuel within 30 metres of a building and is vegetation other than native vegetation; ▪ in accordance with a fire prevention notice issued under either: – section 87 of the *Fire Rescue Victoria Act 1958*; – section 65 of the *Forests Act 1958*; or – section 41 of the *Country Fire Authority Act 1958*. ▪ keeping vegetation clear of, or minimising the risk of bushfire ignition from, an electric line in accordance with a code of practice prepared under Part 8 of the *Electricity Safety Act 1998*; ▪ minimising the risk to life and property from bushfire of a roadside of a public road managed by the relevant responsible road authority, and carried out by or on behalf of that authority, in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*). In this exemption, roadside, public road and responsible road authority have the same meanings as in section 3 of the *Road Management Act 2004*. *Note: Additional permit exemptions for bushfire protection are provided at Clause 52.12.*
Geothermal energy exploration and extraction	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary in accordance with operation plan approved under the *Geothermal Energy Resources Act 2005*.

The requirement to obtain a permit does not apply to:	
Greenhouse gas sequestration and exploration	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary in accordance with an operation plan approved under the *Greenhouse Gas Geological Sequestration Act 2008*.
Land management or directions notice	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to comply with a land management notice or directions notice served under the *Catchment and Land Protection Act 1994*.
Land use conditions	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to comply with a land use condition served under the *Catchment and Land Protection Act 1994*.
Mineral exploration and extraction	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by the holder of an exploration, mining, prospecting, or retention licence issued under the *Mineral Resources (Sustainable Development) Act 1990*: ▪ that is low impact exploration within the meaning of Schedule 4A of the *Mineral Resources (Sustainable Development) Act 1990*; or ▪ in accordance with a work plan approved under Part 3 of the *Mineral Resources (Sustainable Development) Act 1990*. *Note: Schedule 4A of the Mineral Resources (Sustainable Development) Act 1990 specifies limits on the extent of native vegetation that may be removed as part of low impact exploration.*
Noxious weeds	Vegetation that is a noxious weed subject of a declaration under section 58 or section 58A of the *Catchment and Land Protection Act 1994*. This exemption does not apply to Australian Dodder (*Cuscuta australis*).
Pest animal burrows	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the removal of pest animal burrows. In the case of native vegetation the written agreement of an officer of the department responsible for administering the *Flora and Fauna Guarantee Act 1988* is required before the vegetation can be removed, destroyed or lopped.
Planted vegetation	Vegetation that is to be removed, destroyed or lopped that was either planted or grown as a result of direct seeding for Crop raising or Grazing animal production.
Railways	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to maintain the safe and efficient function of an existing railway, or railway access road, in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Regrowth	Vegetation that is to be removed, destroyed or lopped that has naturally established or regenerated on land lawfully cleared of naturally established vegetation, and is ▪ bracken (*Pteridium esculentum*); or ▪ within the boundary of a timber production plantation, as indicated on a Plantation Development Notice or other documented record, and has established after the plantation. This exemption does not apply to land on which vegetation has been destroyed or otherwise damaged as a result of flood, fire or other natural disaster.
Road safety	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by and on behalf of a public authority or municipal council to maintain the safe and efficient function of an existing public road in accordance with written agreement of the Secretary of the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Stone exploration	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of Stone exploration. The maximum extent of vegetation removed, destroyed or lopped under this exemption on contiguous land in the same ownership in a five year period must not exceed any of the following: ▪ 1 hectare of vegetation which does not include a tree.

The requirement to obtain a permit does not apply to:	
	▪ 15 trees with a trunk diameter of less than 40 centimetres at a height of 1.3 metres above ground level. ▪ 5 trees with a trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level. This exemption does not apply to costeaning and bulk sampling activities.
Surveying	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by, or on behalf of, a licenced surveyor (within the meaning of section 3 of the *Surveying Act 2004*) using hand-held tools to establish a sightline for the measurement of land.
Traditional owners	Vegetation that is to be removed, destroyed or lopped by a person acting under, and in accordance with: ▪ a natural resources agreement under Part 6 of the *Traditional Owners Settlement Act 2010*; or ▪ an authorisation order made under sections 82 or 84 of the *Traditional Owner Settlement Act 2010* as those sections were in force immediately before the commencement of section 24 of the *Traditional owners Settlement Amendment Act* in 2016 (1 May 2017).
Tram stops	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by or on behalf of the Head, Transport for Victoria to construct a tram stop, including a tram stop shelter.
Transport land	Vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by or on behalf of the Head, Transport for Victoria on land in a Transport Zone, or in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority, to construct or maintain transport system infrastructure.

42.03-4 Application requirements

31/07/2018
VC148

An application must be accompanied by any information specified in a schedule to this overlay.

42.03-5 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The statement of the nature and key elements of the landscape and the landscape character objective contained in a schedule to this overlay.
- The conservation and enhancement of the landscape values of the area.
- The need to remove, destroy or lop vegetation to create a defendable space to reduce the risk of bushfire to life and property.
- The impact of the proposed buildings and works on the landscape due to height, bulk, colour, general appearance or the need to remove vegetation.
- The extent to which the buildings and works are designed to enhance or promote the landscape character objectives of the area.
- The impact of buildings and works on significant views.
- Any other matters specified in a schedule to this overlay.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 42.03 SIGNIFICANT LANDSCAPE OVERLAY

Shown on the planning scheme map as **SLO1**.

OLD CALDER HWY (BETWEEN GREEN GULLY ROAD AND MARIBYRNONG RIVER), KEILOR RECREATION RESERVE AND THE LAGOON RESERVE

1.0 Statement of nature and key elements of landscape

08/07/2021
C211brim

The trees along the Old Calder Highway, between Green Gully Road and the Maribyrnong River, served as landscape markers to guide travellers to the Maribyrnong River crossing and on to the gold fields to the north. The indigenous sugar gums (*Eucalyptus cladocalyx*), the large pine trees (*Pinus pinea, Pinus canariensis*) and the other tree species (such as *Ulmus x hollandica* and *Eucalyptus sideroxylon*) along the Old Calder Highway have been a unique feature of the streetscape ever since. The plants and trees that were favoured for roadside reserves were predominantly hardy, drought tolerant species. Within Brimbank, there is generally a lack of mature trees along road reserves which makes this streetscape significant due to it rarity and uniqueness.

The trees in the Lagoon Reserve date back to the 1860s and are in the form of mature tree rows primarily located around the site perimeter. The species include elms (Ulmus procera and Ulmus x hollandica), pepper trees (Schinus molle var. areira), pines (*Pinus canariensis*), poplar (*Populus nigra*), Cyprus (*Cupressus macrocarpa*) and eucalypts (*Eucalyptus camaldulensis*).

The Keilor Recreation Reserve trees date back to the 1880s and border the sports fields. Species are largely pines (*Pinus canariensis, Pinus radiata*) and eucalypts (*Eucalyptus cladocalyx*).

The trees make a substantial contribution to the attractive and treed urban character of Keilor Village. The mature trees create a continuous and visually powerful landscape corridor along this section of the Old Calder Highway. This generates a landscape setting that is well-loved and valued by the community and defines the character of Keilor Village.

These trees are significant in terms of their size, number and high landscape contribution. The continuity of the canopy cover and the connectivity with surrounding open space also provides a valuable habitat for local fauna. All of these attributes speak to the high environmental value of the trees.

2.0 Landscape character objectives to be achieved

08/07/2021
C211brim

To retain the feature of trees within the streetscape.

To encourage the retention of the historic character of the area through the replanting program.

To ensure that vegetation is properly managed to reduce negative impacts on the landscape.

To ensure that development is located and designed to avoid inappropriate visual intrusion or other detrimental effects on the character of the area.

To encourage development in keeping with the character of the area.

3.0 Permit requirement

20/01/2022
VC205

Vegetation

A permit is required to remove, destroy or lop vegetation.

This does not apply to:

- Works undertaken by the road authority within the Transport Zone 2 that are required to ensure the safe and efficient operation of the road.
- The removal, destruction or lopping of a tree with a trunk circumference of 0.35 metres or less at a height of 1 metre above ground level.

- The removal, destruction or lopping of a tree with a height of one metre or less above ground level.
- The pruning or partial removal of branches directly overhanging dwellings, garages and outbuildings.
- The pruning or removal of vegetation to prevent damage, or further damage, to a pipeline, electricity or telephone transmission line, cable or other service and all other measures to prevent damage have been exhausted.
- The removal, destruction or lopping of vegetation if, in the opinion of the responsibility authority, the vegetation is dead, dying or dangerous.
- The sanitation or remedial pruning of vegetation which is required to prolong its life.
- The removal, destruction or lopping of vegetation identified as environmental weeds. Table 1 to this Schedule provides a list of environmental weeds.

Buildings and works

A permit is not required to construct a building or construct or carry out works provided:

- The height of the building does not exceed 2 storeys or 8 metres, whichever is the greater.
- The site coverage of all buildings, including any existing buildings, does not exceed 40 per cent of the site area.
- The natural surface level of the ground is not altered by more than 0.5 metres of cut or fill.
- The works involve routine repair or maintenance to existing buildings or works.
- The works are required to establish a drop zone around high risk trees, including mulching and planting of vegetation within the drop zone and reinforcement of the zone with a chained bollard.
- The works are set back a minimum of 4 metres from any vegetation that requires a permit under the provisions of this schedule.

An application for works within 4 metres of any vegetation that requires a permit under the provisions of this schedule should be accompanied by an arborist report that specifies a Tree Protection Zone (TPZ) for the vegetation.

4.0 Application requirements

08/07/2021
C211brim

None specified.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 42.03, in addition to those specified in Clause 42.03 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The effect of the removal of vegetation on the character of the area.
- The location of vegetation and its contribution to the landscape character of the area.
- The species of vegetation, its age, health, growth characteristics and structure.
- The impact of building or works on the landscape character of the area.
- Whether the tree will be replaced with a tree of the same species.
- Whether the tree will be converted into a habitat stump.
- Whether the works alter the existing ground level or topography of the land.

Background documents

Brimbank Post-contact Cultural Heritage Study, Vines et al, Volume 3 Place Report-Heritage Areas and Individual Places 2008

Independent Arborist Assessment for Brimbank (Older Calder Hwy near the Keilor Shopping Precinct), Homewood Consulting Pty Ltd, August 2008

Table 1 Environmental Weeds

Species	Common Name
Cynara cardunculus	Spanish Artichoke
Helminthotheca echioides	Ox-tongue
Hypochoeris radicata	Cats Ear
Lycium ferocissimum	African Box-thorn
Nassella hyalina	Fine Needle-grass
Nassella leucotricha	Pale Needle-grass
Nassella neesiana	Chilean Needle-grass
Nassella trichotoma	Serrated Tussock
Palntago lanceolata	Ribwort
Allium vineale	Crow Carlic
Asphodelus fistulousus	Onion Weed
Aster subulatus	Aster Weed
Berkheya rigida	African Thistle
Brassica fruticulosa	Twiggy Turnip
Chrysanthermoides monilifera ssp. Monilifera	Boneseed
Cirsium vulgare	Spear Thistle
Conium maculatum	Hemlock
Convolvulus arvensis	Common Bindweed
Echium plantagineum	Paterson's Curse
Foeniculum vulgare	Fennel
Fraxinus angustifolia ssp. Anustifolia	Desert Ash
Galenia pubescens	Galenia
Genista monspessulana	Montpellier Broom
Juncus acutus ssp. Acutus	Sharp Rush
Lavatera cretica	Cretan Hollyhock

Species	Common Name
Leontodon taraxacoides	Hairy Hawkbit
Marrubium vulgare	Horehound
Myrsiphyllum asparagoides	Simlax Asparagus
Olea europaea ssp. Europaea	African Olive
Opuntia vulgaris	Drooping Prickly Pear
Opuntia sp.	Prickly Pear
Oxalis pes-caprae	Soursob
Plantago coronopus	Buck’s-horn Plantain
Prunus cerasifera	Cherry Plum
Ricinus communis	Castor Oil Plant
Rosa rubiginosa	Sweet Briar
Rubus discolour	Blackberry
Rumex conglomerates	Clustered Dock
Rumex crispus	Curled Dock
Salix spp.	Willows
Silybum marianum	Variegated Thistle
Sonchus spp.	Sow-thistles
Tradescantia albiflora	Wandering Jew
Tragopogon porrifolius	Salsify
Ulex europaeus	Furze

08/07/2021
C211brim

SCHEDULE 2 TO CLAUSE 42.03 SIGNIFICANT LANDSCAPE OVERLAY

Shown on the planning scheme map as **SLO2**.

SUNSHINE MUNICIPAL OFFICE GARDEN

1.0 Statement of nature and key elements of landscape

08/07/2021
C211brim

The Municipal Office garden located at the intersection of Wilkinson Street and Alexandra Avenue is the intact remains of the once extensive landscape laid out in conjunction with the construction of the Sunshine Municipal Offices in 1967. The architect, G. Stuart Warmington was responsible for the design of the building, the surrounding landscape and car park.

The Municipal Office gardens are considered to be significant as the setting to the Offices, and for the collection of trees, shrubs and garden beds which survive from Warmington's original design. Historically, the building and landscape represent the economic and political maturation of the City of Sunshine as it grew to become one of Victoria's largest municipal populations as a consequence of post-World War Two migration and the increasing desire for suburban housing.

The garden includes mature specimens of Silky Oak (*Grevillia robusta),* River She Oak (*Casuarina cunninghamiana*), Norfolk Island Hibiscus (*Lagunaria pattersonii*), Willow Myrtle (*Agonis flexuosa*), Lemon Scented Gum (*Corymbia citriodora*), White Cedar (*Melia azederach*), Blue Cedar (*Cedrus atlantica* forma *glauca*), Brush Box (*Lophostemon confertus*) set into lawn. The choice of predominately Australian native trees is deliberate, and a strong statement regarding the emerging popularity of native trees in public design projects during the 1960s and 1970s. Immediate to the southern and western walls of the Municipal Offices are narrow garden beds, with small trees and shrubs, including but not limited to the following species: Cotoneaster (*Cotoneaster glaucophylla*), Viburnum (*Viburnum tinus*), Magnolia (*Magnolia x soulangeana*), Rhododendron (*Rhododendron c*v.), Azalea (*Azalea cv*.), Japanese Maple (*Acer japonicum*), Sacred Bamboo (*Nadina domestica*), Mahonia (*Mahonia c*v.). The juxtaposition of the exotic collection of shrubs and small trees and the collection of Australian native trees is a deliberate design. A number of mature Norfolk Island Hibiscus (*Lagunaria pattersonii*) are planted as street trees which enhance the garden.

The garden, including the mature trees, lawn and garden beds provides a important aesthetic frame and setting for the building and softens its impact on the largely residential streetscapes. It also represents a deliberate attempt to provide an attractive setting for the new (c1967) building, while providing a social function in the provision of an attractive recreational space for the public and municipal office employees.

Protection of the area is important to maintain the original intended landscape setting for the building, as well as conserving the historic, aesthetic and social values the landscape expresses.

2.0 Landscape character objectives to be achieved

08/07/2021
C211brim

To protect the landscape character of the Sunshine Municipal Office garden area from adverse impacts resulting from the inappropriate design and siting of new development and the loss of vegetation.

3.0 Permit requirement

08/07/2021
C211brim

Vegetation

A permit is required to remove, destroy or lop vegetation.

This does not apply to:

- The pruning or removal of vegetation to prevent damage, or further damage, to a pipeline, electricity or telephone transmission line, cable or other service and all other measures to prevent damage have been exhausted.

- The removal, destruction or lopping of vegetation if, in the opinion of the responsibility authority, the vegetation is dead, dying or dangerous.
- The sanitation or remedial pruning of vegetation which is required to prolong its life.
- The removal, destruction or lopping of vegetation identified as environmental weeds listed in Table 1 to this Schedule.

Buildings and works

A permit is not required to construct a building or construct or carry out works provided:

- The natural surface level of the ground is not altered by more than 0.5 metres of cut or fill.
- The works involve routine repair or maintenance to existing buildings or works.
- The works are required to establish a drop zone around high risk trees, including mulching and planting of vegetation within the drop zone and reinforcement of the zone with a chained bollard.
- The works are set back a minimum of 4 metres from any vegetation which requires a permit under the provisions of this schedule.

An application for buildings and works within 4 metres of any vegetation which requires a permit under the provisions of this schedule should be accompanied by an arborist report that specifies a Tree Protection Zone (TPZ) for the vegetation.

4.0 Application requirements

08/07/2021
C211brim

None specified.

5.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 42.03, in addition to those specified in Clause 42.03 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The effect of the removal of vegetation on the landscape character of the Municipal Office Garden area.
- The location of vegetation and its contribution to the landscape character of the area.
- The species of vegetation, its age, health, growth characteristics and structure.
- Whether the tree will be replaced with a tree of the same species.
- The impact of building or works on the landscape character of the Municipal Office garden area.
- The siting and design of building and works.
- Whether the works alter the existing ground level or topography of the land.

Background Documents

Brimbank Post-contact Cultural Heritage Study, Volume 3: Place Report-Heritage Areas and Individual Places, Vines et al, 2008.

Independent Landscape Assessment for Brimbank,Context Pty Ltd, 2015.

Table 1 to Schedule 2 to Clause 42.03 - Environmental Weeds

Species	Common Name
Cynara cardunculus	Spanish Artichoke
Helminthotheca echioides	Ox-tongue

Species	Common Name
Hypochoeris radicata	Cats Ear
Lycium ferocissimum	African Box-thorn
Nassella hyalina	Fine Needle-grass
Nassella leucotricha	Pale Needle-grass
Nassella neesiana	Chilean Needle-grass
Nassella trichotoma	Serrated Tussock
Palntago lanceolata	Ribwort
Allium vineale	Crow Carlic
Asphodelus fistulousus	Onion Weed
Aster subulatus	Aster Weed
Berkheya rigida	African Thistle
Brassica fruticulosa	Twiggy Turnip
Chrysanthermoides monilifera ssp. Monilifera	Boneseed
Cirsium vulgare	Spear Thistle
Conium maculatum	Hemlock
Convolvulus arvensis	Common Bindweed
Echium plantagineum	Paterson’s Curse
Foeniculum vulgare	Fennel
Fraxinus angustifolia ssp. Anustifolia	Desert Ash
Galenia pubescens	Galenia
Genista monspessulana	Montpellier Broom
Juncus acutus ssp. Acutus	Sharp Rush
Lavatera cretica	Cretan Hollyhock
Leontodon taraxacoides	Hairy Hawkbit
Marrubium vulgare	Horehound
Myrsiphyllum asparagoides	Simlax Asparagus
Olea europaea ssp. Europaea	African Olive
Opuntia vulgaris	Drooping Prickly Pear
Opuntia sp.	Prickly Pear
Oxalis pes-caprae	Soursob

Species	Common Name
Plantago coronopus	Buck’s-horn Plantain
Prunus cerasifera	Cherry Plum
Populus sp.	Poplar
Ricinus communis	Castor Oil Plant
Rosa rubiginosa	Sweet Briar
Rubus discolour	Blackberry
Rumex conglomerates	Clustered Dock
Rumex crispus	Curled Dock
Salix spp.	Willows
Schinus molle var. areira	Pepper Tree
Silybum marianum	Variegated Thistle
Sonchus spp.	Sow-thistles
Tradescantia albiflora	Wandering Jew
Tragopogon porrifolius	Salsify
Ulex europaeus	Furze

16/12/2022
VC201

SCHEDULE 3 TO CLAUSE 42.03 SIGNIFICANT LANDSCAPE OVERLAY

Shown on the planning scheme map as **SLO3**.

WATERWAYS OF THE WEST: MARIBYRNONG RIVER (MIRRANGBAMURN) CORRIDOR ENVIRONS:

REACH 3 – AFTON STREET CONSERVATION RESERVE, ESSENDON WEST TO URBAN GROWTH BOUNDARY, KEILOR PARK

1.0 Statement of nature and key elements of landscape

16/12/2022
VC201

The Maribyrnong River (Mirrangbamurn) forms part of the connected system of rivers, wetlands, and creeks within the Maribyrnong catchment. While the river has been modified in places and adapted to respond to urbanisation, it is still a significant and valued natural system in the urban landscape and there are opportunities to repair and enhance the river and its interfaces through careful management of future development.

Due to the topography and landscape of the river bushfire is a present risk in some locations along the corridor.

The Maribyrnong River supports a range of ecological, recreational, and cultural heritage values and is highly significant to Traditional Owners. The Maribyrnong River valley was once an environmentally rich area, containing a diversity of fauna and flora, and silcrete which made it an important resource base for Aboriginal people. Many of the stone working sites and quarries remain today, even in developed areas.

Reach 3 of the Maribyrnong River is characterised by steeply rising riverbanks with flat plateaus above creating a wider waterway corridor overall, particularly at Brimbank Park.

Reach 3 is predominately a deeply incised waterway corridor, broadly characterised by one to two storey residential development on large allotments, and open parkland areas located adjacent to the waterway corridor. Riparian vegetation and the sloping riverbank create a winding green corridor through the urban environs.

Reach 3 accommodates extensive parklands with recreation roles including Canning Reserve and Brimbank Park. Parklands also serve as conservation areas, providing protection to remnant vegetation like River Red Gums at Afton Street Conservation Reserve. The parklands accommodate substantial established native vegetation, and the wetlands within them are critical to ecological and hydrological systems that provide habitat for threatened species such as the Growling Grass Frog.

The Maribyrnong River Trail shared pedestrians and cyclists path extends for most of the length of the river. It provides access and connection between the major parkland areas and series of small reserves and parklands located along the waterway.

Remnant billabongs, wetlands and water crossings have cultural significance to Traditional Owners. These areas, including Solomon's Ford and Brimbank Park, have high cultural, scientific, and archaeological significance, and Aboriginal heritage values.

2.0 Landscape character objectives to be achieved

16/12/2022
VC201

To enhance the continuous riparian corridor landscape.

To retain indigenous riparian vegetation and canopy trees as a dominant landscape feature.

To encourage the revegetation of the waterway, ensuring it responds to the bushfire risk of a location, including planting of new indigenous vegetation throughout and adjacent to waterway corridor.

To ensure buildings and works are not visually dominant when viewed from the waterway corridor.

To ensure rear boundary fencing facing the waterway corridor is visually transparent.

3.0 Permit requirement

16/12/2022
VC201

A permit is required to:

- Construct a building or construct or carry out works. This does not apply if the buildings and works are:
  - sited more than 30 metres from the bank of the waterway,
  - with a height less than 6 metres above ground level, and
  - changing the ground level less than 600mm; or
  - carried out by, or on behalf of, a public land manager to:
    - sustain the form and stability of stream beds and banks, regulate or control the flow of water in a watercourse;
    - construct stream habitat works;
    - maintain the landscape quality, health or bank stability of areas that have been restored or revegetated; or
    - maintain or repair a pathway or trail.
- Construct a fence within 30 metres of a waterway. This does not apply if all the following requirements are met:
  - The fence is not higher than 1.8 metres above ground level.
  - The fence allows for some visual transparency.
  - The fence design, materials and colour are appropriate to the landscape setting.
- Remove, destroy, or lop native vegetation. This does not apply to:
  - Maintenance works carried out by, or on behalf of, a public land manager to remove, destroy, or lop native vegetation that has the capacity to adversely affect stream flow.
  - The creation of defendable space to reduce the risk of bushfire to life and property in bushfire prone areas.

The requirements of this schedule ceases to have effect after 31 December 2026.

4.0 Application requirements

16/12/2022
VC201

The following application requirements apply to an application for a permit under Clause 42.03, in addition to those specified elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- For an application to remove, destroy or lop native vegetation:
  - An assessment and justification of the proposed removal of the vegetation against the landscape character objectives of this schedule prepared by a suitably qualified person.
  - A description and accurate site plan denoting the position, height, number, trunk circumference, branch spread, slope of land and species of any vegetation to be removed.
  - A plan detailing the location of any new and replacement planting and proposed maintenance plan to reduce bushfire risk.
- For any other application:
  - A site survey plan certified by a qualified surveyor clearly showing the location and the distance of all buildings and works from the top of the banks of the waterway.
  - A site context plan and elevations showing:

    - Building heights using Australian Height Datum measured from ground level.
    - Areas of cut and fill.
    - Site coverage and permeability.
    - Location and proposed material for fences.
  - A schedule of materials and finishes.
  - A visual impact assessment of proposed buildings and works from public viewing points along the waterway.
- A landscape plan which includes:
  - The type, location, quantity, height at maturity and botanical names of any proposed plants and details of any proposed tree protection zones.
  - A maintenance/weed/erosion control plan for all proposed revegetated areas for areas immediately adjacent to the banks of the Maribyrnong River. The maintenance plan is to include proposed measures to reduce the risk of bushfire.
- Measures for how natural landforms will be protected, including appropriate approaches to vegetation retention and planting, ground preparation and minimising ground disturbance.
- The rate and quantity of stormwater leaving a property and measures to control and filter pollutants.
- A report that identifies values, threats and undertakes a risk assessment for the river corridor.

5.0 Decision guidelines

16/12/2022
VC201

The following decision guidelines apply to an application for a permit under Clause 42.03, in addition to those specified in Clause 42.03 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the buildings or works have considered bushfire risk.
- Whether the proposed replacement planting will increase bushfire risk to life and property.

43 HERITAGE AND BUILT FORM OVERLAYS

19/01/2006
VC37

43.01 HERITAGE OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **HO** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To conserve and enhance heritage places of natural or cultural significance.

To conserve and enhance those elements which contribute to the significance of heritage places.

To ensure that development does not adversely affect the significance of heritage places.

To conserve specified heritage places by allowing a use that would otherwise be prohibited if this will demonstrably assist with the conservation of the significance of the heritage place.

Scope

The requirements of this overlay apply to heritage places specified in the schedule to this overlay. A heritage place includes both the listed heritage item and its associated land. Heritage places may also be shown on the planning scheme map.

43.01-1 Permit requirement

14/01/2025
VC237

A permit is required to:

- Subdivide land.
- Demolish or remove a building.
- Construct a building or construct or carry out works, including:
  - Domestic services normal to a dwelling if the services are visible from a street (other than a lane) or public park.
  - A solar energy system attached to a building that primarily services the land on which it is situated if the system is visible from a street (other than a lane) or public park and if the schedule to this overlay specifies the heritage place as one where solar energy system controls apply.
  - A rainwater tank if the rainwater tank is visible from a street (other than a lane) or public park.
  - A fence, if the fence is visible from a street (other than a lane) or public park.
  - Roadworks which change the appearance of a heritage place or which are not generally undertaken to the same details, specifications and materials.
  - Buildings or works associated with a railway, railway station or tramway constructed or carried out by or on behalf of the Head, Transport for Victoria.
  - Street furniture other than:
    - Traffic signals, traffic signs, bus shelters, fire hydrants, parking meters, post boxes and seating.
    - Speed humps, pedestrian refuges and splitter islands.
  - A domestic swimming pool or spa and associated mechanical and safety equipment, if the swimming pool or spa and associated equipment are visible from a street (other than a lane) or public park.
  - A pergola or verandah, including an open-sided pergola or verandah to a dwelling with a finished floor level not more than 800mm above ground level and a maximum building height of 3 metres above ground level.

  - A deck, including a deck to a dwelling with a finished floor level not more than 800mm above ground level, if the deck is visible from a street (other than a lane) or public park
  - Non-domestic disabled access, excluding a non-domestic disabled access ramp if the ramp is not visible from a street (other than a lane) or public park.
  - An electric vehicle charging station if the charging station is visible from a street (other than a lane) or public park.
  - Services normal to a building other than a dwelling or small second dwelling, including chimneys, flues, skylights, heating and cooling systems, hot water systems, security systems and cameras, downpipes, window shading devices, or similar, if the works are visible from a street (other than a lane) or public park.
- Externally alter a building by structural work, rendering, sandblasting or in any other way.
- Construct or display a sign.
- Externally paint a building if the schedule to this overlay specifies the heritage place as one where external paint controls apply.
- Externally paint an unpainted surface.
- Externally paint a building if the painting constitutes an advertisement.
- Internally alter a building if the schedule to this overlay specifies the heritage place as one where internal alteration controls apply.
- Carry out works, repairs and routine maintenance which change the appearance of a heritage place or which are not undertaken to the same details, specifications and materials.
- Remove, destroy or lop a tree if the schedule to this overlay specifies the heritage place as one where tree controls apply. This does not apply:
  - To any action which is necessary to keep the whole or any part of a tree clear of an electric line provided the action is carried out in accordance with a code of practice prepared under Section 86 of the *Electricity Safety Act 1998*.
  - If the tree presents an immediate risk of personal injury or damage to property.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
▪ Subdivide land to realign the common boundary between 2 lots where the area of either lot is reduced by less than 15 percent and the general direction of the common boundary does not change. ▪ Subdivide land into lots each containing an existing building or car parking space where: – The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. – An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	Clause 59.07

Class of application	Information requirements and decision guidelines
▪ Subdivide land into 2 lots if: – The construction of a building or the construction or carrying out of works on the land is approved under this scheme or by a permit issued under this scheme and the permit has not expired. – The construction or carrying out of the approved building or works on the land has started lawfully. – The subdivision does not create a vacant lot. ▪ Demolish or remove an outbuilding (including a carport, garage, pergola, verandah, deck, shed or similar structure) unless the outbuilding is specified in the schedule to the Heritage Overlay. ▪ Demolish or remove a fence unless the fence is specified in the schedule to the Heritage Overlay. ▪ Externally alter a non-contributory building. ▪ External painting. ▪ Construct a fence. ▪ Construct a carport, garage, pergola, verandah, deck, shed or similar structure. ▪ Construct and install domestic services normal to a dwelling. ▪ Construct and install a non-domestic disabled access ramp. ▪ Construct a vehicle crossover. ▪ Construct a domestic swimming pool or spa and associated mechanical equipment and safety fencing. ▪ Construct a rainwater tank. ▪ Construct or display a sign. ▪ Lop a tree. ▪ Construct or install a solar energy system attached to a dwelling or small second dwelling. ▪ Construct and install an electric vehicle charging station. ▪ Construct and install services normal to a building other than a dwelling or small second dwelling, including chimneys, flues, skylights, heating and cooling systems, hot water systems, security systems and cameras, downpipes, window shading devices, or similar.	

43.01-2 Places in the Victorian Heritage Register

21/11/2017
VC141

A heritage place which is included in the Victorian Heritage Register is subject to the requirements of the *Heritage Act 2017*.

Permit requirement

A permit is required under this overlay to subdivide a heritage place which is included in the Victorian Heritage Register. This includes the subdivision or consolidation of land including any building or airspace.

Referral of applications

An application to subdivide a heritage place which is included in the Victorian Heritage Register must be referred to the relevant referral authority under Section 55 of the Act in accordance with Clause 66 of this scheme.

43.01-3 No permit required

14/12/2023
VC253

No permit is required under this overlay:

- For anything done in accordance with an incorporated plan specified in a schedule to this overlay.
- To internally alter a church for liturgical purposes if the responsible authority is satisfied that the alterations are required for liturgical purposes.
- For interments, burials and erection of monuments, re-use of graves, burial of cremated remains and exhumation of remains in accordance with the *Cemeteries and Crematoria Act 2003*.
- To develop a heritage place which is included in the Victorian Heritage Register, other than an application to subdivide a heritage place of which all or part is included in the Victorian Heritage Register.
- To construct a building or construct or carry out works for a small second dwelling if all the following requirements are met:
  - The building height must not exceed 5 metres.
  - The building must be finished using muted tones and colours.

43.01-4 Exemption from notice and review

14/01/2025
VC237

An application under this overlay for any of the following classes of development is exempt from the notice requirements of section 52(1) (a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act:

- Demolition or removal of an outbuilding (including a carport, garage, pergola, verandah, deck, shed or similar structure) unless the outbuilding is specified in the schedule to this overlay.
- Demolition or removal of a fence unless the fence is specified in the schedule to this overlay.
- External alteration of a building.
- External painting.
- Construction of a fence.
- Construction of a carport, garage, pergola, verandah, deck, shed or similar structure.
- Domestic services normal to a dwelling.
- Carry out works, repairs and routine maintenance.
- Internally alter a building.
- Non-domestic disabled access ramp.
- Construction of a vehicle crossover.
- Construction of a domestic swimming pool or spa and associated mechanical equipment and safety fencing.
- Construction of a tennis court.
- Construction of a rainwater tank.
- Construction or display of a sign.
- Lopping of a tree.

- Construction of seating, picnic tables, drinking taps, barbeques, rubbish bins, security lighting, irrigation, drainage or underground infrastructure, bollards, telephone boxes.
- Roadworks.
- An electric vehicle charging station.
- Services normal to a building other than a dwelling or a small second dwelling, including chimneys, flues, skylights, heating and cooling systems, hot water systems, security systems and cameras, downpipes, window shading devices, or similar.

43.01-5 Statements of significance

24/01/2020
VC160

The schedule to this overlay must specify a statement of significance for each heritage place included in the schedule after the commencement of Amendment VC148. This does not apply to:

- A heritage place included in the schedule to this overlay by an amendment prepared or authorised by the Minister under section 8(1)(b) or section 8A(4) of the Act before or within three months after the commencement of Amendment VC148.
- A registered heritage place included in the Victorian Heritage Register established under Part 3 of the *Heritage Act 2017*.
- A heritage place included in the schedule to this overlay on an interim basis.

43.01-6 Heritage design guidelines

31/07/2018
VC148

The schedule to this overlay may specify heritage design guidelines for any heritage place included in the schedule. A heritage design guideline must not contain any mandatory requirements.

43.01-7 Application requirements

31/07/2018
VC148

An application must be accompanied by any information specified in the schedule to this overlay.

43.01-8 Decision guidelines

24/01/2020
VC160

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The significance of the heritage place and whether the proposal will adversely affect the natural or cultural significance of the place.
- Any applicable statement of significance (whether or not specified in the schedule to this overlay), heritage study and any applicable conservation policy.
- Any applicable heritage design guideline specified in the schedule to this overlay.
- Whether the location, bulk, form or appearance of the proposed building will adversely affect the significance of the heritage place.
- Whether the location, bulk, form and appearance of the proposed building is in keeping with the character and appearance of adjacent buildings and the heritage place.
- Whether the demolition, removal or external alteration will adversely affect the significance of the heritage place.
- Whether the proposed works will adversely affect the significance, character or appearance of the heritage place.
- Whether the proposed subdivision will adversely affect the significance of the heritage place.
- Whether the proposed subdivision may result in development which will adversely affect the significance, character or appearance of the heritage place.

- Whether the proposed sign will adversely affect the significance, character or appearance of the heritage place.
- Whether the lopping or development will adversely affect the health, appearance or significance of the tree.
- Whether the location, style, size, colour and materials of the proposed solar energy system will adversely affect the significance, character or appearance of the heritage place.

43.01-9 Use of a heritage place

31/07/2018
VC148

A permit may be granted to use a heritage place (including a heritage place which is included in the Victorian Heritage Register) for a use which would otherwise be prohibited if all of the following apply:

- The schedule to this overlay specifies the heritage place as one where prohibited uses may be permitted.
- The use will not adversely affect the significance of the heritage place.
- The benefits obtained from the use can be demonstrably applied towards the conservation of the heritage place.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider the effect of the use on the amenity of the area.

43.01-10 Aboriginal heritage places

31/07/2018
VC148

A heritage place specified in the schedule to this overlay as an Aboriginal heritage place is also subject to the requirements of the *Aboriginal Heritage Act 2006*.

07/02/2019
C203

SCHEDULE TO CLAUSE 43.01 HERITAGE OVERLAY

1.0 Application requirements

27/06/2024
C225brim

The following application requirements apply to an application for a permit under Clause 43.01, in addition to those specified in Clause 43.01 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- Require all applications for the demolition of a contributory heritage place to be accompanied by a report from a suitably qualified structural engineer with experience in the conservation of heritage buildings that assesses the structural condition of the building and whether or not the defects can be repaired and the place restored.

2.0 Heritage places

08/05/2025
C243brim

The requirements of this overlay apply to both the heritage place and its associated land.

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
HO1	*Overnewton* 51 Overnewton Road, Keilor	-	-	-	-	-	Yes Ref No H200	Yes	No
HO2	*Bridge over Maribyrnong River* Melton-Keilor Road, Keilor and Keilor East	-	-	-	-	-	Yes Ref No H1427	No	No
HO3	*Former Massey Ferguson Complex* Devonshire and Hampshire and Harvester Roads, Sunshine.	-	-	-	-	-	Yes Ref No H0667	Yes	No
HO4	*John Darling and Son Flour Mill* 74 Sydney Street, Albion	-	-	-	-	-	Yes Ref No H829	Yes	No
HO5	*Rail Bridge (Albion Viaduct)*	-	-	-	-	-	Yes	No	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
	Over Maribyrnong River between Jacana and Albion Stations, Keilor East and Sunshine North						Ref No H1197		
HO6	*Black Powder Mill* Parklea Avenue and Grassy Point Road, Cairnlea	-	-	-	-	-	Yes Ref No H2029	Yes	No
HO7	*Harricks Homestead* 152 Harrick Road, Keilor Park	No	No	Yes	Yes	No	No	Yes	No
HO8	Foxley Lodge Farm and its drystone walls 472A Boundary Road, Derrimut	Yes	No	Yes	Yes	Yes, drystone walls	No	Yes	No
HO9	*1 Corio Street, Sunshine*	No	No	No	Yes	No	No	Yes	No
HO10	*H V McKay Memorial Gardens and Church* *118-122 Anderson Road, Sunshine*	-	-	-	-	-	Yes Ref No H1953	Yes	No
HO11	*H V McKay Offices* 2 Devonshire Road, Sunshine	-	-	-	-	-	Yes Ref No H1966	Yes	No
HO12	*Keilor Hotel* 670-674 Old Calder Highway, Keilor	-	-	-	-	-	Yes Ref No H1974	Yes	No
HO13	*Main Outfall Sewer* Brooklyn	-	-	-	-	-	Yes Ref No H1932	No	No
HO14	*Prefabricated Building*	-	-	-	-	-	Yes	Yes	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
	152 Harrick Road , Keilor Park						Ref No H1971		
HO15	*Trestle Bridge* Arundel Road, Keilor	-	-	-	-	-	Yes Ref No H1952	No	No
HO16	*Overnewton Gatehouse* 804-804A Old Calder Highway, Keilor	-	-	-	-	-	Yes Ref No H1947	Yes	No
HO17	Mt Derrimut Homestead, its drystone walls and associated buildings including the meteorological centre Mt Derrimut Road, Derrimut	No	No	Yes	Yes	No	No	Yes	No
HO18	*H V McKay Offices* (eastern portion of the office complex) 2 Devonshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO19	Commonwealth Munitions Housing Estate Sunshine	No	No	No	Yes	No	No	No	No
HO20	Concrete Housing Estate Leith Avenue, Sunshine	No	No	No	Yes	No	No	No	No
HO21	ICI Residential Heritage Area Deer Park	No	No	No	Yes	No	No	No	No
HO22	Sunshine Commercial Heritage Area Sunshine	No	No	No	Yes	No	No	No	No
HO23	McKay Housing Estate	No	No	No	Yes	No	No	No	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
	Durham Road, Sunshine								
HO24	McKay Housing Estate King Edward Avenue, Sunshine	No	No	No	Yes	No	No	Yes, for 19-21 Sydney Street, Albion	No
HO25	Railway Station Estate Sunshine	No	No	No	Yes	No	No	No	No
HO26	War Service Homes Heritage Area Albion	No	No	No	Yes	No	No	No	No
HO27	Former Keilor Police Station (the original bluestone building and adjoining front and west side setback) 779 Old Calder Highway, Keilor	No	No	No	Yes	No	No	Yes	No
HO28	Albion VR, D.C. sub station Talmage Street, Albion	No	No	No	Yes	No	No	Yes	No
HO29	*Pig and Calf Market (WMMT)* 55 Market Road, Brooklyn	No	No	No	Yes	No	No	Yes	No
HO30	*Monsanto Chemicals, Huntsman Chemical Co.* 454 Somerville Road, Brooklyn	No	No	No	Yes	No	No	Yes	No
HO34	*Hume and Hovell Cairn* cnr Station and Ballarat Roads, Deer Park	No	No	No	Yes	No	No	No	No
HO35	*Milburn's Weir* near Arundel Road across Maribyrnong River, Keilor	No	No	No	Yes	No	No	No	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
HO36	Anderson Farm House 100 Taylors Road, St Albans	No	No	No	Yes	No	No	No	No
HO37	*Steel Creek Rail Embankment* off Roberts Road, Keilor	No	No	No	Yes	No	No	No	No
HO38	*Hume and Hovell Cairn* cnr East Esplanade and Power Street, St Albans	No	No	No	Yes	No	No	No	No
HO39	*Sunshine Railway Signal Box* off Hampshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO40	*Black Arch rail bridge* Sunshine Road, Sunshine	No	No	No	Yes	No	No	No	No
HO41	*Railway Culvert* off Victoria Road, Sydenham	No	No	No	Yes	No	No	No	No
HO42	*Sugar Gum row* Talmage Street, Albion	No	No	Yes	Yes	No	No	No	No
HO43	*Railway Culvert* Sydenham Road, St Albans	No	No	No	Yes	No	No	No	No
HO44	*Hazelwood – John Milburn's farmhouse* 136 Arundel Road, Keilor	No	No	No	Yes	No	No	No	No
HO46	*Robertson's Homestead* off Calder Highway, Keilor	No	No	No	Yes	No	No	Yes	No
HO47	*Dodds homestead ruins*	No	No	No	Yes	No	No	No	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
	end Dodds Road, Brimbank Park (Western Ring Road, Keilor East), Keilor								
HO48	*St Augustine's Catholic Church* 100 Harrick Road, Keilor Park	No	No	No	Yes	No	No	Yes	No
HO49	*Former Shire Hall and Courthouse* 777 Old Calder Highway, Keilor	No	No	No	Yes	No	No	Yes	No
HO50	*Keilor Cemetery* cnr Cemetery Road and Ely Street, Keilor East **Incorporated plan:** Keilor Cemetery Incorporated Plan	No	No	Yes	Yes	No	No	No	No
HO51	*Sunshine Advocate Office* 11-15 Sun Crescent, Sunshine	No	No	No	Yes	No	No	Yes	No
HO52	Keiglo, now Sacred Heart Presbytery 4 Winifred Street, St Albans	No	No	No	Yes	No	No	Yes	No
HO53	*H V McKay Memorial Gates* Anderson Road, Sunshine	No	No	No	Yes	No	No	No	No
HO55	*Sam McKay house and garden* 147 Anderson Road, Sunshine	No	No	No	Yes	No	No	No	No
HO56	*Former Sunshine Technical School* 111 and 129-133 Derby Road, Sunshine	-	-	-	-	-	Yes Ref No H2458	Yes	No
HO60	Sydenham Railway Station Melton Highway, Sydenham	No	No	No	Yes	No	No	Yes	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
HO61	*House* 48 Station Place, Sunshine	No	No	No	Yes	No	No	No	No
HO63	*ANZ Bank, former ES&A Bank* 115 Durham Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO64	*Sunshine Metropolitan Fire Station and Flats* 330 Hampshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO65	*Derrimut Hotel* 132 Durham Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO67	*Robinson House* 33 Sun Crescent, Sunshine	No	No	No	Yes	No	No	No	No
HO70	*St Theresa's Catholic Church and School* 26 Adelaide Street, Albion	No	No	No	Yes	No	No	Yes	No
HO73	*Former Wunderlich, now West End Market* 47-49 McIntryre Road, Sunshine	No	No	No	Yes	No	No	No	No
HO74	*Selwyn Park* *61A Selwyn Street, Albion*	No	No	Yes	Yes	No	No	No	No
HO75	*Sunshine Baptist Church* *42 Ridley Street and 16 Sydney Street, Sunshine*	No	No	No	Yes	No	No	Yes	No
HO76	*Cameron house and dairy* 49 Sydney Street, Albion	No	No	No	Yes	No	No	No	No
HO77	*House and trees* 22-24 Talmage Street, Ardeer	No	No	Yes	Yes	No	No	No	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
HO79	*Ford* Burke Road to Canning Street, Avondale Heights	No	No	No	Yes	No	No	No	No
HO80	*Lions House of Sunshine* 8 Watt Street, Sunshine	No	No	No	Yes	No	No	Yes	No
HO81	*Guiding Star Hotel* 700 Geelong Road, Brooklyn	No	No	No	Yes	No	No	Yes	No
HO82	*Hunt Club Hotel* 775 Ballarat Road, Deer Park	No	No	No	Yes	No	No	Yes	No
HO83	*Deer Park Hotel* 760 Ballarat Road, Deer Park	No	No	No	Yes	No	No	Yes	No
HO84	*Deer Park Primary School No.1434* *812 Ballarat Road, Deer Park*	No	No	No	Yes	No	No	No	No
HO86	*Opie's Dairy* 2-4 Egan Street, Deer Park	No	No	No	Yes	No	No	No	No
HO88	*Neale Road Ford* 192 Neale Road, Deer Park	No	No	No	Yes	No	No	No	No
HO89	*Deer Park Hall* 50 Station Road, Deer Park	No	No	No	Yes	No	No	Yes	No
HO91	*Sunshine Market* 13-19 City Place, Sunshine	No	No	No	Yes	No	No	Yes	No
HO92	*Frank Milburn's House* off Arundel Road, Keilor	No	No	No	Yes	No	No	No	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
HO93	*Christ Church Keilor (Anglican Church)* *36 Church Street, Keilor*	No	No	No	Yes	No	No	Yes	No
HO94	*McFarlane gates, Keilor Recreation Reserve* 704A Old Calder Highway, Keilor	No	No	No	Yes	No	No	No	No
HO95	*Keilor Reserve* 704A Old Calder Highway, Keilor **Incorporated plan:** Keilor Reserve Incorporated Plan	No	No	Yes	Yes	No	No	No	No
HO96	*Cenotaph war memorial* 704B Old Calder Highway, Keilor	No	No	No	Yes	No	No	No	No
HO97	*Borrell's Farm ruins and site of market garden* 745 Old Calder Highway, Keilor	No	No	No	Yes	No	No	No	No
HO98	*House, St Albans Estate* 16 Arthur Street, St Albans	No	No	No	Yes	No	No	No	No
HO99	*St Albans Uniting Church (formerly Presbyterian)* *24-26 East Esplanade, St Albans*	No	No	No	Yes	No	No	Yes	No
HO101	*St George's Free Serbian Orthodox Church* 6 Kate Street, St Albans	No	No	No	Yes	No	No	Yes	No
HO102	*Errington Reserve & Memorial Gardens* *309A Main Road East, St Albans*	No	No	No	Yes	No	No	No	No
HO103	*St Albans Community Hall Youth Club/ Tin Shed*	No	No	No	Yes	No	No	Yes	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
	309A Main Road East, St Albans								
HO105	*Methodist church and hall* 32 Devonshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO106	*Macedonian Community Centre* 45 Fourth Avenue, Sunshine	No	No	No	Yes	No	No	Yes	No
HO107	*Hannah McKay House* 145 Anderson Road, Sunshine	No	No	No	Yes	No	No	No	No
HO108	*Chemist Shop* 234 Hampshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO109	*Sunshine Municipal Offices* 6-18 Alexandra Avenue, Sunshine	No	No	No	Yes	No	No	Yes	No
HO110	*Sunshine State Primary School 3113* *111 Derby Road, Sunshine*	No	No	No	Yes	No	No	No	No
HO111	*Standard Steel* 12-16 Market Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO113	Our Lady of the Immaculate Conception Catholic Church 93 Monash Street, Sunshine	No	No	No	Yes	No	No	Yes	No
HO114	*Parsons House* 114 Morris Street, Sunshine	No	No	No	Yes	No	No	No	No
HO115	*Our Lady's School* Station Place/Monash Street, Sunshine	No	No	No	Yes	No	No	Yes	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
HO116	*Palmas* 2 Tyler Street, Sunshine	No	No	No	Yes	No	No	No	No
HO117	*Sheep dip* Burrowye Crescent near Taylors Creek, Taylors Lakes	No	No	No	Yes	No	No	No	No
HO119	*St Andrews Greek Orthodox Church (Greek Cypriot)* 14 Simmie Street, West Sunshine	No	No	No	Yes	No	No	Yes	No
HO120	*Presbyterian Manse/Kirby House* 127 Durham Road, Sunshine	No	No	No	Yes	No	No	No	No
HO121	*William McKay House* 150 Durham Road, Sunshine	No	No	No	Yes	No	No	No	No
HO122	Albion Primary School No.4265 61-81 Adelaide Street, Albion	No	No	No	Yes	No	No	No	No
HO123	*Ralph's meatworks* 690 Geelong Road, Brooklyn	No	No	No	Yes	No	No	Yes	No
HO124	*Brimbank Farm* Brimbank Road, Keilor	No	No	No	Yes	No	No	No	No
HO125	*Former Church of Christ* *81-83 Hampshire Road, Sunshine*	No	No	No	Yes	No	No	Yes	No
HO126	*Former Masonic Lodge No. 226* 93 Hampshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
HO127	*Sunshine Picture Theatre* 126-128 Hampshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO129	*Chisholm Shelter Shed (archaeological site)* 658A Old Calder Highway, Keilor	No	No	No	Yes	No	No	No	No
HO130	*Shops* 193-197 Hampshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO131	*Lagoon Reserve, trees* 755 Old Calder Highway, Keilor	No	No	Yes	Yes	No	No	No	No
HO132	*Ukranian Catholic Church* 2 Holmes Street, Ardeer	No	No	No	Yes	No	No	Yes	No
HO133	*Shops* 207-219 Hampshire Road, Sunshine	No	No	No	Yes	No	No	Yes	No
HO134	*Victorian Row House* 25 Benjamin Street, Sunshine	No	No	No	Yes	No	No	No	No
HO135	*Victorian Row House* 29 Benjamin Street, Sunshine	No	No	No	Yes	No	No	No	No
HO136	*Victorian Row House* 31 Benjamin Street, Sunshine	No	No	No	Yes	No	No	No	No
HO137	*Victorian Row House* 33 Benjamin Street, Sunshine	No	No	No	Yes	No	No	No	No
HO138	*Victorian Row House* 35 Benjamin Street, Sunshine	No	No	No	Yes	No	No	No	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
HO139	*House* 50 Forrest Street, Sunshine	No	No	No	Yes	No	No	No	No
HO140	*Former ICI Leathercloth Factory* *Orica, Deer Park*	No	No	No	Yes	No	No	No	No
HO141	*Former ICI Administration Buildings* *Orica, Deer Park*	No	No	No	Yes	No	No	No	No
HO142	*Former ICI Explosives Manufacturing Complex* *Orica, Deer Park*	No	No	No	Yes	No	No	No	No
HO143	*Former ICI Entry Gates, Nobel Building and White House* *Orica, Deer Park*	No	No	Yes	Yes	No	No	No	No
HO144	*Hampshire House* 233-241 Hampshire Road, Sunshine	No	No	No	Yes	No	No	No	No
HO145	*Richard's Dairy* 44 Hampshire Road, Sunshine	No	No	No	Yes	No	No	No	No
HO147	17-27 Maxweld Street, Ardeer	No	No	No	Yes	No	No	No	No
HO149	*Former City West Water administrative building* St Albans Road, Sunshine North	No	No	Yes	Yes	No	No	No	No
HO150	*Moderne House* 86 Monash Street, Sunshine	No	No	No	Yes	No	No	No	No
HO151	*Grand Junction Estate and Matthew's Hill Precinct, Sunshine*	No	No	Yes –	Yes	No	No	No	No

PS map ref	Heritage place	External paint controls Apply?	Internal alteration controls Apply?	Tree controls apply?	Solar energy system controls apply?	Outbuildings or fences not exempt under Clause 43.01-4	Included on the Victorian Heritage Register under the Heritage Act 2017?	Prohibited uses permitted?	Aboriginal heritage place?
	Statement of significance: Grand Junction Estate and Matthew's Hill Precinct Statement of Significance, 2021			Canary Island Palms in Victoria and Robinson Street reserves and the street tree planting at the junction of Hill, Drayton and Matthews Streets.					
HO152	*Sunshine Barley Terminal Silos* 2 Wright Street, Sunshine **Statement of Significance:** Sunshine Barley Terminal Silos Statement of Significance October 2022	No	No	No	Yes	No	No	Yes	No

43.02 DESIGN AND DEVELOPMENT OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **DDO** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify areas which are affected by specific requirements relating to the design and built form of new development.

43.02-1 Design objectives

19/01/2006
VC37

A schedule to this overlay must contain a statement of the design objectives to be achieved for the area affected by the schedule.

43.02-2 Buildings and works

28/02/2025
VC274

Permit requirement

A permit is required to:

- Construct a building or construct or carry out works. This does not apply:
  - If a schedule to this overlay specifically states that a permit is not required.
  - To the construction of an outdoor swimming pool associated with a dwelling unless a specific requirement for this matter is specified in a schedule to this overlay.
  - To the construction of a building or construction or carrying out of works for a small second dwelling if all the following requirements are met:
    - The building height must not exceed 5 metres.
    - The building must be finished using muted tones and colours.
- Construct a fence if specified in a schedule to this overlay.

Buildings and works must be constructed in accordance with any requirements in a schedule to this overlay. A schedule may include requirements relating to:

- Building setbacks.
- Building height.
- Plot ratio.
- Landscaping.
- Any other requirements relating to the design or built form of new development.

A permit may be granted to construct a building or construct or carry out works which are not in accordance with any requirement in a schedule to this overlay, unless the schedule specifies otherwise.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a fence.	Clause 59.05

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works for: ▪ A carport, garage, pergola, verandah, deck, shed or similar structure. ▪ An outdoor swimming pool. The buildings and works must be associated with a dwelling.	Clause 59.05
Construct a building or construct or carry out works with an estimated cost of up to $1,000,000 where the land is in an industrial zone.	Clause 59.05
Construct a building or construct or carry out works with an estimated cost of up to $500,000 where the land is in a commercial zone or a Special Use Zone, Comprehensive Development Zone, Capital City Zone, Docklands Zone, Priority Development Zone, Activity Centre Zone or Precinct Zone.	Clause 59.05

Exemption from notice and review

A schedule to this overlay may specify that an application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

43.02-3 Subdivision

31/07/2018
VC148

Permit requirement

A permit is required to subdivide land.

This does not apply if a schedule to this overlay specifically states that a permit is not required.

Subdivision must occur in accordance with any lot size or other requirement specified in a schedule to this overlay.

A permit may be granted to subdivide land which is not in accordance with any lot size or other requirement in a schedule to this overlay, unless the schedule specifies otherwise.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Subdivide land to realign the common boundary between 2 lots where: ▪ The area of either lot is reduced by less than 15 percent. ▪ The general direction of the common boundary does not change.	Clause 59.01
Subdivide land into lots each containing an existing building or car parking space where: ▪ The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme.	Clause 59.02

Class of application	Information requirements and decision guidelines
▪ An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision.	
Subdivide land into 2 lots if: ▪ The construction of a building or the construction or carrying out of works on the land: – Has been approved under this scheme or by a permit issued under this scheme and the permit has not expired. – Has started lawfully. ▪ The subdivision does not create a vacant lot.	Clause 59.02

Exemption from notice and review

A schedule to this overlay may specify that an application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

43.02-4 Signs

31/07/2018
VC148

Sign requirements are at Clause 52.05 unless otherwise specified in a schedule to this overlay.

43.02-5 Application requirements

31/07/2018
VC148

An application must be accompanied by any information specified in a schedule to this overlay.

43.02-6 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The design objectives of the relevant schedule to this overlay.
- The provisions of any relevant policies and urban design guidelines.
- Whether the bulk, location and appearance of any proposed buildings and works will be in keeping with the character and appearance of adjacent buildings, the streetscape or the area.
- Whether the design, form, layout, proportion and scale of any proposed buildings and works is compatible with the period, style, form, proportion, and scale of any identified heritage places surrounding the site.
- Whether any proposed landscaping or removal of vegetation will be in keeping with the character and appearance of adjacent buildings, the streetscape or the area.
- The layout and appearance of areas set aside for car parking, access and egress, loading and unloading and the location of any proposed off street car parking
- Whether subdivision will result in development which is not in keeping with the character and appearance of adjacent buildings, the streetscape or the area.
- Any other matters specified in a schedule to this overlay.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 43.02 DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO1**.

SKYLINE AREAS

1.0 Design objectives

08/07/2021
C211brim

Generally to protect areas along the Maribyrnong River from visual intrusion caused by the inappropriate siting or appearance of buildings and works

To encourage development in keeping with the character and appearance of the area

To protect and enhance the skyline when viewed from the river or its banks

To encourage development consistent with the Maribyrnong River Valley Design Guidelines, April 2010.

2.0 Buildings and works

08/07/2021
C211brim

A permit is not required for:

- Buildings and works in a residential zone or on public land if they are no more than 6 metres above ground level.
- Repairs and routine maintenance to buildings and works.

A permit is required to construct a fence.

3.0 Subdivision

08/07/2021
C211brim

None specified.

4.0 Signs

08/07/2021
C211brim

A permit is required to display a Section 1 sign specified in any category of advertising control specified in Clause 52.05.

This does not apply to a Home based business sign, provided only one is displayed on the premises and the display area does not exceed 0.2 square metres.

5.0 Application requirements

08/07/2021
C211brim

None specified.

6.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 43.02, in addition to those specified in Clause 43.02 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the location bulk, outline and appearance of the building or works will be in keeping with the character and appearance of the area.
- Whether the location, bulk, outline and appearance of the building or works will be in keeping with or enhance the skyline when viewed from the river.
- The Maribyrnong River Valley Design Guidelines, April 2010.

08/07/2021
C211brim

SCHEDULE 4 TO CLAUSE 43.02 DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO4**.

LAND REFERRED TO AS LOTS 6 & 7, FITZGERALD ROAD, SUNSHINE WEST ADJACENT TO THE WESTERN RING ROAD

1.0 Design objectives

08/07/2021
C211brim

To ensure that the development of land adjacent to the alignment of the Western Ring Road is undertaken with appropriate noise attenuation measures to minimise the impact of traffic noise on noise sensitive activities.

2.0 Buildings and works

15/03/2024
VC256

Any development within the area defined on Maps 8DDO and 11DDO which is associated with a use listed below must include noise attenuation measures to the satisfaction of the Roads Corporation. In considering whether any measures proposed are to its satisfaction, the Roads Corporation will consider any appropriate Australian Standard in relation to road traffic noise intrusion.

- Accommodation
- Child care centre
- Education centre
- Indoor recreation facility
- Office
- Place of assembly
- Retail premises
- Warehouse
- Art and craft centre
- Display home
- Funeral parlour
- Hospital
- Research centre
- Veterinary centre
- Winery

3.0 Subdivision

08/07/2021
C211brim

None specified.

4.0 Signs

08/07/2021
C211brim

None specified.

5.0 Application requirements

08/07/2021
C211brim

None specified.

6.0 Decision guidelines

08/07/2021
C211brim

None specified.

08/07/2021
C211brim

SCHEDULE 5 TO CLAUSE 43.02 DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO5**.

LAND LOCATED BETWEEN TAYLORS CREEK AND PROPERTIES FRONTING PATTERSON AVENUE & CAMPASPE CRESCENT

1.0 Design objectives

08/07/2021
C211brim

To protect the areas along Taylors Creek from visual intrusion caused by inappropriate development, with the scale of development to be generally limited to single storey with low pitched roof forms.

To encourage development that would not adversely impact on local amenity and is in keeping with the character and appearance of the area.

To protect the skyline when viewed from the creek and its banks.

To ensure adequate geotechnical investigations are carried out prior to the construction or carrying out of any buildings and works.

To encourage landscaping consistent with Taylors Creek Landscape Master Plan, May 2004.

2.0 Buildings and works

08/07/2021
C211brim

A permit is required to construct or carry out buildings and works, including a fence.

A permit is not required for fencing constructed of a plastic coated chain wire to a maximum height of 1.5 metres and of a green or black colour.

3.0 Subdivision

08/07/2021
C211brim

None specified.

4.0 Signs

08/07/2021
C211brim

None specified.

5.0 Application requirements

08/07/2021
C211brim

An application to develop land under this overlay must be accompanied by the following information:

- A geotechnical report that details the existing site condition and the suitability of the land for the development proposed.
- A detailed landscape plan showing details of the existing vegetation on site, whether any vegetation is to be removed and proposed landscape layout which includes the description of vegetation to be planted, the surfaces to be constructed, a site works specification and the method of preparing, draining, watering and maintaining the landscape area.

6.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 43.02, in addition to those specified in Clause 43.02 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the location, scale, siting, roof form, bulk and appearance of any proposed buildings and works will be in keeping with the character and appearance of adjacent buildings, the creek environment and the existing open space adjacent to Taylors Creek.
- Whether any proposed landscaping or removal of vegetation will be in accordance with Taylors Creek Landscape Master Plan May 2004.

- Whether the design of any proposed buildings and works and access to the site would have a detrimental impact on the amenity of the area.
- Whether the layout allows for safe access and egress from the site and location of any proposed car parking.
- Whether the location, bulk, outline and appearance of the building or works will be in keeping with or enhance view from the creek and the character of Taylors Creek.
- Whether geotechnical report submitted with the application indicate that the site condition is appropriate for the development proposed.

08/07/2021
C211brim

SCHEDULE 6 TO CLAUSE 43.02 DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO6.**

LAND ADJOINING MCINTYRE ROAD BETWEEN WESTERN HIGHWAY AND THE WESTERN RING ROAD, NORTH SUNSHINE

1.0 Design objectives

15/05/2008
C102

General

General design objectives for McIntyre Road, North Sunshine are:

- To improve the visual appearance, accessibility and safety of, and reduce the congestion of McIntyre Road and surrounding area.
- To achieve a consistent and uniform built edge along McIntyre Road.
- To ensure all future development has an active frontage to McIntyre Road.
- To encourage the provision of street tree planting along McIntyre Road.

Industrial and Commercial

Industrial and Commercial design objectives for McIntyre Road, North Sunshine are:

- To improve the visual appearance of industrial and commercial areas.
- To ensure that signage and fencing in industrial areas is appropriate and sympathetic to the surrounding environment.
- To encourage innovative new development to use contemporary design and diverse forms, colours and materials.
- To encourage the provision of landscaping, including mature tree planting where possible, within building setbacks.
- To facilitate the efficient and safe operation of McIntyre Road and the integration of visitor car parking.
- All loading and unloading should occur within the site.
- To avoid the presence of roller shutter doors and similar in commercial areas.

Residential

Residential design objectives for McIntyre Road, North Sunshine are:

- To provide for a high quality and contemporary design responses
- To minimise traffic conflicts on McIntyre Road between local residential traffic and through traffic.

North Sunshine Industrial Area

Design objectives for the North Sunshine Industrial Area are:

- To provide a uniform built edge along McIntyre Road consistent with the prevailing setbacks.
- To encourage design that presents a positive and interactive edge to McIntyre Road.
- To minimise blank walls along street frontages.
- To encourage landscaping, including mature tree planting where possible, to be incorporated within car parks.
- To encourage landscape setbacks of a minimum of 3 metres across the frontage of sites.

- To encourage landscape setbacks of a minimum of 1.5 metres along the side boundary when adjacent to a road.
- To limit signage to the name, purpose and location of the business on the land.
- To encourage the provision of visitor car parking on adjoining and nearby land.
- To encourage the use of front building setbacks for visitor car parking.
- To encourage development that creates a range of lot sizes through the consolidation of lots.

McIntyre Road Shopping Centre

Design objectives for the McIntyre Road Shopping Centre are:

- To avoid front setbacks to retain a consistent and uniform edge to McIntyre Road.
- To encourage development on corner blocks to address both street frontages with interactive interfaces and no setbacks.
- To encourage the provision of verandahs or similar to create a positive pedestrian building environment along the building edges.
- To encourage a high degree of glazing that avoids blank frontages.
- To encourage the clear identification of building entries.
- To encourage the use of a range of building materials and colour to create an interesting building mass.
- To encourage a mix of uses such as use of upper floors for office/ residential. Commercial/ retail uses to occur at ground level where appropriate.
- To avoid development above a three storey wall height.
- To provide buffer treatments to residential interfaces.
- To avoid roller shutter doors and similar.

2.0 Buildings and works

08/07/2021
C211brim

A permit is required to construct a fence fronting McIntyre Road unless it is:

- Less than 1.2 metres in height; or
- Between 1.2 metres and 1.8 metres in height and at least 50% transparent.

An application must be accompanied by a statement which demonstrates how the proposed development achieves each of the general and residential or industrial and commercial Design Objectives of this schedule.

3.0 Sustainability

15/05/2008
C102

Residential and commercial buildings should exhibit environmental sustainable design principles including maximising opportunities for northern orientation and natural lighting.

Shading devices should be used at eastern and western façades where appropriate to minimise heat loss and gain.

Drought resistant landscaping should be applied with the inclusion of water tanks for irrigation purposes where appropriate.

4.0 Vehicle crossovers to McIntyre Road

08/07/2021
C211brim

Not more than one vehicle crossing to McIntyre Road may be provided for each residential property. Where possible, vehicle access is to be provided to streets other than McIntyre Road, to minimise vehicle conflict along McIntyre Road.

If greater than one vehicle crossing is required for a new development, the application must be supported by a Traffic Report by a suitably qualified professional.

5.0 Signs

08/07/2021
C211brim

In addition to the requirements at Clause 52.05, signs should also comply with the signage principles of the *McIntyre Road Sunshine North Urban Design Framework 2006* and the *North Sunshine Industrial Estate Guidelines 2006.*

6.0 Exemption from notice and review

15/05/2008
C102

An application which complies with the building and works requirements in this schedule is exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act.

7.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 43.02, in addition to those specified in Clause 43.02 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the development is consistent with preferred character and positively contributes to a contemporary, innovative, positive and 'interactive' built form edge to McIntyre Road.
- Whether the building setbacks and heights are generally consistent with the desired built form outcomes.
- Whether proposed landscaping positively enhances the character of McIntyre Road.
- Whether the proposed development reduces or minimises the number of crossovers to McIntyre Road.
- Whether adequate off-site visitor car parking has been provided.
- Whether the proposed signage and fencing is appropriate and sympathetic to the surrounding environment.
- Whether the proposed development incorporates sustainable design principles.

Industrial and Commercial Development:

Before deciding on an application for Industrial or Commercial Development, the responsible authority must also consider, as appropriate:

- Matters raised in sections 1.0 and 2.0 of this Schedule.
- Whether a high degree of glazing and minimal blank frontages to the McIntyre Road frontage has been included.
- Whether the articulation and range of building materials and colours used creates an interesting building mass.
- Whether identified building entries satisfactorily address the streetscape.
- The clarity of pedestrian connections from McIntyre Road to building entry points.
- Whether landscaping, including mature tree planting where possible, has been satisfactorily incorporated within car parks.
- Whether all loading and unloading is incorporated into the design to occur within the site.
- Whether appropriate buffer treatments to residential interfaces and incorporating noise attenuation have been included where applicable.

North Sunshine Industrial Area:

Before deciding on an application for the North Sunshine Industrial Area, the responsible authority must also consider, as appropriate:

- Matters raised in sections 1.0 and 2.0 of this Schedule.
- Whether a uniform built edge along McIntyre Road consistent with the prevailing setbacks has been applied.
- Whether the design presents a positive and interactive edge to McIntyre Road.
- Whether blank walls along the street frontages have been avoided.
- Whether landscaping, including mature tree planting where possible, has been satisfactorily incorporated within car parks.
- Whether a landscape setback of a minimum of 3 metres wide has been provided across the frontage of the site.
- Whether a landscape setback of a minimum of 1.5 metres wide has been provided along the side boundary when adjacent to a road.
- Whether signage has been limited to the name, purpose and location of the business on the land.
- Whether visitor car parking has been provided for on adjoining and nearby land.
- Whether the development encourages the use of front building setback for visitor car parking.
- Whether the development creates a range of lot sizes through the consolidation of lots.

Residential Development:

Before deciding on an application for residential development, the responsible authority must also consider, as appropriate:

- Matters raised in sections 1.0 and 2.0 of this Schedule.
- Whether an innovative, contemporary design and a diverse built form has been provided.
- Whether development along McIntyre Road avoids blank walls to the street frontage.
- Whether an appropriate height has been applied. Development should not exceed above a three storey wall height.
- Whether vehicle access is made from adjoining side streets in preference to McIntyre Road.
- Whether building setbacks along McIntyre Road utilise landscape treatments.

McIntyre Road Shopping Centre:

Before deciding on an application relating to the McIntyre Road Shopping Centre, the responsible authority must also consider, as appropriate:

- Matters raised in sections 1.0 and 2.0 of this Schedule.
- Whether setbacks have been avoided to retain a consistent and uniform edge to McIntyre Road.
- Whether corner blocks address both street frontages with interactive interfaces and zero setbacks.
- Whether verandahs or similar have been used to create a positive pedestrian building environment along the building edges.
- Whether development incorporated a high degree of glazing and avoids blank frontages.
- Whether building entries are clearly identified.
- Whether a range of building materials and colour has been used to create an interesting building mass.

- Whether upper floors have been used for the purposes of office/ residential with commercial/ retail uses at ground level where appropriate.
- Whether an appropriate height has been applied. Development should not exceed above a three storey wall height.
- Whether appropriate buffer treatments to residential interfaces have been provided.
- Whether roller shutter doors and similar have been avoided.

08/07/2021
C211brim

SCHEDULE 7 TO CLAUSE 43.02 DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO7**.

LAND LOCATED AT 79 WRIGHT STREET SUNSHINE

1.0 Design objectives

08/07/2021
C211brim

To ensure that the residential subdivision and development of the land provides for environmentally sustainable development.

To ensure that development is site responsive and provides for an appropriate mix of lot sizes and dwelling types.

To ensure that the built form enhances neighbourhood character and that the height, setbacks and bulk respects the environs of Kororoit Creek and the adjoining residential area.

To ensure that the development of the land addresses traffic issues.

To ensure that flora and fauna and Aboriginal issues are identified and addressed prior to the development of the site.

To ensure that the development of the land is consistent with the Kororoit Creek Regional Strategy 2005-2030.

2.0 Buildings and works

08/07/2021
C211brim

A permit is required to construct a fence facing the creek that exceeds 1.2 metres in height and is not a minimum of 50% transparent.

A permit is not required for:

- Front fences facing the creek not exceeding 1.2 metres in height and having a minimum of 50% transparency.
- Road works and associated street furniture and lighting.
- Buildings and works associated with the provision of public open space.
- Repairs and routine maintenance to buildings and works.

Buildings and works should be constructed in accordance with the following objectives:

Building design

- The rear elevation of all buildings must be articulated at all levels.
- Any wall on a boundary should be articulated to provide visual relief to the satisfaction of the responsible authority.

Building height

- The height of buildings fronting the creek environment should be limited to 2 storeys or 7.0 metres. A third level may be considered if the building is well articulated and the upper level is setback from the lower levels to minimise the appearance of visual bulk when viewed from the creek environment.

Building setbacks

- Separation must be provided between groups of buildings fronting the Kororoit Creek environs to reduce the visual bulk fronting the creek. The area between the groups of buildings must be landscaped to reduce visual bulk fronting the creek.
- Buildings adjacent to the western boundary of the site should be setback at ground level to provide an area of private open space. The upper level of these buildings must be setback from

the lower ground floor level to reduce bulk, potential overlooking and overshadowing to dwellings to the west.

Landscaping

- Landscaping of the site adjacent to and between buildings fronting the Creek Corridor should reflect the existing indigenous landscaping and landform / topography of the Creek Corridor valley.
- The role of Kororoit Creek as a connecting element within the diverse urban form should be reinforced through the creation of an integrated and unified landscape character, based on the use of planting materials and consistent built-landscape elements, such as signage, pathways, furniture.
- Landscaping of internal street networks and the general development should contain a consistent theme and mirror the indigenous flora and fauna of the area to reduce the risk of weeds and erosion of the creek environs.

3.0 Subdivision

08/07/2021
C211brim

None specified.

4.0 Signs

08/07/2021
C211brim

None specified.

5.0 Application requirements

08/07/2021
C211brim

None specified.

6.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 43.02, in addition to those specified in Clause 43.02 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the development provides for an appropriate mix of lot sizes, dwelling types and built form to provide a range of housing choices.
- The residential subdivision and development of the land should appropriately address the Kororoit Creek, provide useable and accessible public open space adjacent to the creek and maintain the values of the creek environs.
- Buildings adjacent to the creek environs must have a frontage onto the creek, with setbacks maximised and fences that are permeable to protect the appearance and surveillance of the Creek Corridor.
- The residential subdivision must provide a road and associated landscaping adjoining the Kororoit Creek to maintain the openness of the area.
- The development must be consistent with the Kororoit Creek Regional Strategy 2005-2030.
- Whether water sensitive urban design principles are used to minimise potential impact on receiving waters.
- Whether the development is designed to address flooding issues associated with the Kororoit Creek to the satisfaction of Melbourne Water.
- The application should provide an aboriginal cultural heritage plan in accordance with the Aboriginal Heritage Act 2006 and a flora and fauna assessment.
- Whether the design of any proposed buildings and works would have a detrimental impact on the amenity of the area.

- Whether the layout provides for the safe access/egress to and from the site and that the layout provides for the separation of vehicle and pedestrian traffic, efficient vehicle and pedestrian movement through the site and does not impact on the amenity of the surrounding area.
- Whether sufficient car parking is provided on site.
- Whether the development provides for adequate access to each dwelling for emergency vehicles, mail delivery and the pick up of garbage.
- Whether clear physical links are provided between the Kororoit Creek corridor, Activity Centres, Schools and other Community facilities.
- Urban infrastructure, such as powerlines, drains, car parks etc. must be dealt with sensitively to minimise the visual and physical impact on the Kororoit Creek Corridor.
- Whether the development minimises environmental impact and degradation, including:
  - ensuring water quality is protected
  - the control and management of sediment and stormwater run off.

Background documents

Kororoit Creek Regional Strategy 2005-2030.

08/07/2021
C211brim

SCHEDULE 8 TO CLAUSE 43.02 DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO8.**

SUNSHINE HOSPITAL MEDICAL SERVICES PRECINCT

1.0 General design objectives

15/12/2011
C124

- To facilitate the development of a medical services precinct that complements the redevelopment of Sunshine Hospital.
- To ensure development achieves the design objectives and requirements for each area within the medical services precinct.
- To ensure development within the proposed medical services precinct is of a high quality, well designed and of a contemporary style that will create an attractive new built form character.
- To ensure new development is of a scale, height and built form, including setbacks that respects the amenity of the public realm and neighbouring residential areas and the existing industrial land in Furlong Road and limits adverse effects.
- To ensure the amenity impacts of existing industrial uses are considered in the location and design of new use and development adjacent to existing industrial use.
- To ensure that the development of land is consistent with the Sunshine Hospital Medical Services Precinct, Design and Development Principles, June 2009.

General design guidelines

- Building facades (including front, rear and side) should be well articulated, through variations in form, material and colours to include vertical design elements and incorporate upper level setbacks.
- On corner sites buildings should address both street frontages with either openings or street level windows.
- New development should not significantly overshadow existing secluded private open space of adjoining residential properties.
- Views into existing secluded private open space and habitable room windows should be minimised.
- Obscure glazing in any part of the window below 1.7 metres may be openable provided that there are no direct views as specified above.
- The design of new buildings should promote visual interaction between ground floor activity and pedestrians on the street. A minimum of 25% of the ground floor building facade should have transparent elements such as doors and windows to promote the surveillance of abutting streets and any abutting public open spaces.
- The layout of new development should be integrated with the street. Buildings should be oriented to front existing streets.
- High fencing in front of medical buildings and dwellings should be avoided.
- Proposed development should be accompanied by a schedule of colours, finishes and materials.

Traffic and car parking objectives

- To improve the public realm by minimising the impact of vehicles, both visually and physically.
- To ensure that the development of land avoids adverse impacts from potential traffic increases.

Traffic and car parking guidelines

- Pedestrian routes within car parks should be connected to key destinations and not impeded by vehicular movement.
- The design of buildings should minimise the visual intrusion of car parking facilities through methods such as landscaping to reduce visibility from the public realm, adjoining residential properties and create an attractive appearance.
- Car parking should be located to the side or rear of properties or in a basement.
- The use of barbed wire in car parking facilities is discouraged.
- Acoustic fencing should be provided to adjoining residential properties and land with an interface with an industrial zone.
- Access and egress to car parking areas should be located from pedestrian access to ensure pedestrian safety.

2.0 Sunshine Medical Services Precincts

08/07/2021
C211brim

Area 1 - Furlong Road and Majorca Street Area (Map 1)

Preferred character

- A new built form character incorporating taller structures of 3 storeys to complement the scale of the hospital.
- Well designed and quality new development of a contemporary architectural character.
- A pedestrian friendly public realm to maximise the permeability and surveillance of adjoining streets.
- Consolidated car parking facilities that are integrated with the development, surrounding hospital and medical services precinct.

Building design objectives

- To encourage the development of a new higher scale built form character associated with medical services that does not adversely impact upon the amenity of neighbouring properties.
- To ensure a positive public-private interface is achieved where development relates to the adjacent street and public spaces.

Building design guidelines

- The height of buildings fronting the street should be limited to a maximum of three (3) storeys or 10.5 metres. An increase in building height may be considered if the building is well articulated and the upper levels are setback from the lower levels to minimise the appearance of visual bulk when viewed from the footpath directly opposite the site.
- The scale of any new development that has a rear abuttal to Gillon Court and Ironbark Street should be of a scale which is respectful of the existing character of the area.
- Development proposals must include a plan showing the proposed viewline (1.6m above ground) to demonstrate the building is not visually dominant from the footpath on the opposite side of the street of the proposed development.
- All buildings should be setback a minimum of 2.0 metres from Furlong Road and Majorca Street to allow for landscaping within the setback area.
- The height and setback of a building from a boundary adjoining a residential property should be designed to respect the existing and preferred neighbourhood character and limit the impact on the adjoining dwellings.

Area 2 – St Albans Road/St Albans South Area (Map 1)

Preferred character

- A predominantly residential built form character with a consistent built form scale of 1-2 storeys.
- Provision of adequate front, side and rear setbacks to allow for landscaping to respect the predominately residential character.

Building design objectives

- To ensure the built form of new development respects the existing residential character in terms of scale, height, massing, front, side and rear setbacks, limits the impact on the amenity of existing dwellings and makes efficient use of the site.
- The layout of new development should be integrated with the street.
- Buildings should be designed to promote the surveillance of abutting streets and any abutting public open spaces.

Building design guidelines

- The height of buildings fronting the street should be limited to a maximum of two (2) storeys or 7.0 metres. An increase in building height may be considered if the building is well articulated and the upper levels are setback from the lower levels to minimise the appearance of visual bulk when viewed from the footpath directly opposite the site.
- The setbacks of buildings from a street should respect the existing or preferred neighbourhood character and make efficient use of the site.
- The height and setback of a new building from side and rear boundaries should respect the existing and preferred neighbourhood character and limit the impact on the amenity of existing dwellings.
- Buildings should be oriented to front existing and proposed streets.
- High fencing in front of buildings should be avoided to ensure active streetscapes and maintain surveillance of the public realm.

3.0 Buildings and works

15/12/2011
C124

The permit requirement for buildings and works includes the construction of a front fence facing the street that exceeds 1.2 metres in height and is not a minimum of 50% transparent.

A permit is not required for:

- Buildings and works associated with the provision of public open space.
- Repairs and routine maintenance to buildings and works.
- Road works and associated street furniture and lighting.

4.0 Signs

08/07/2021
C211brim

Sign requirements are at Clause 52.05.

Signage should be provided within the architecture of the building to ensure a consistent and uncluttered approach.

5.0 Decision guidelines

08/07/2021
C211brim


The following decision guidelines apply to an application for a permit under Clause 43.02, in addition to those specified in Clause 43.02 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- How the design, height and visual bulk of new development responds to the existing and preferred character and amenity of the Furlong Road/Majorca Street character area (Area 1) and the St Albans Road/St Albans South character area (Area 2).
- The impact of traffic generated by non-residential development and its impact on the adjoining main roads.
- How the development improves the street environment for pedestrians along street frontages.
- Whether the design of any proposed buildings and works would have a detrimental impact on the amenity of the area.
- Whether the layout provides for the safe access/egress to and from the site and that the layout provides for the separation of vehicle and pedestrian traffic, efficient vehicle and pedestrian movement and does not impact on the amenity of the surrounding area.
- The impact of car parking facilities on the public realm and amenity of the existing streetscape.
- Whether the development provides for adequate access to each building for emergency vehicles, mail delivery and the pick up of garbage.
- The objectives and preferred character guidelines.

Background documents

Sunshine Hospital Medical Services Precinct, Design and Development Principles, June 2009.

Map 1 to Schedule 8 to Clause 43.02 - Land affected by Design and Development Overlay - Schedule 8



LEGEND

Area 1 - Furlong Road/Majorca Street

Area 2 - St Albans Road/St Albans South

08/07/2021
C211brim

SCHEDULE 9 TO CLAUSE 43.02 DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO9**.

ST ALBANS ACTIVITY CENTRE

1.0 Design objectives

08/07/2021
C211brim

General

To ensure development contributes to the preferred character of the precinct and where appropriate has regard to the preferred character of adjoining precincts.

To ensure buildings are designed and sited to maximise pedestrian access, weather protection, provide landscaping opportunities, promote surveillance of adjoining streets, public spaces and create a pedestrian friendly public realm and minimise conflict between vehicle and pedestrian movement.

To encourage the consolidation of lots to accommodate larger scale development.

Residential Precincts

To ensure built form of development is designed to minimise impact on the amenity of existing dwellings.

To ensure fencing in front of buildings does not dominate street frontages and restrict surveillance of the public realm.

To protect adjoining sites, streets and public open spaces from development that causes undue overshadowing during the winter solstice at 22 June.

Commercial/Retail/Mixed Use Precincts

To encourage the development of a higher scale built form character that does not adversely impact on the amenity of adjoining lots or the public realm, including access to sunlight, loss of light, overlooking and the performance of ESD infrastructure.

To ensure a consistent street edge is provided at ground level for commercial uses.

To ensure residential uses within mixed-use developments have access to daylight and usable private open space.

Access from laneways and local streets should be encouraged for car parking, waste removal and loading.

Precinct 1 – Residential Areas 1A, 1B and 1C

To ensure the west side of Collins Street, St Albans is developed as a mixed use precinct and provides a direct pedestrian connection to Alfrieda Street.

To encourage consolidation of public car parking assets on Collins Street, St Albans.

To encourage the development of mid-block pedestrian connection between Collins Street and Alfrieda Street, St Albans.

To ensure development provides for the widening and improved access and loading within Alfrieda Lane, St Albans.

Precinct 2 – Main Road

To ensure that Main Road, St Albans provides links to major land uses such as Errington Reserve, McKechnie Street Reserve and Victoria University, St Albans.

To achieve and retain the appearance of a fine grain subdivision pattern and narrow frontages at ground floor level along Main Road, St Albans.

To ensure the St Albans Railway Station is integrated into the Activity Centre through public realm improvements.

To encourage good east-west accessibility for pedestrians across the rail corridor.

To ensure solar access is maintained to existing and new public spaces for pedestrian amenity, in particular along the southern footpath of Main Road and St Albans Square and any new public spaces resulting from the redevelopment of the area.

To ensure that development does not encroach on the existing car parking spaces at the frontage of sites at 340-342 Main Road West, St Albans.

Precinct 3 – McKechnie/Kruger

To ensure development on the east side of McKechnie Street, St Albans and on land fronting open space provides passive surveillance and an active street edge.

To ensure landscaped front setbacks reinforce the predominately residential character of the area.

To ensure built form provides passive surveillance, an active street edge and promotes walking and cycling between Victoria University, St Albans Campus and the St Albans Activity Centre.

Precinct 4 – Errington

To ensure good pedestrian accessibility and linkages to the Errington Reserve, St Albans, the community centre and throughout the precinct.

To encourage the redevelopment of underutilised sites for a mix of uses.

To ensure buildings with a frontage to Errington Reserve, St Albans provide passive surveillance and an active street edge to the Reserve.

To ensure solar access is maintained to existing and new public spaces for pedestrian amenity, in particular along the southern footpath of Main Road and Princes Street, St Albans and any new public spaces resulting from the redevelopment of the area.

To ensure land use, development and connections are consistent with the Errington Precinct Master Plan 2014.

Precinct 5 – Alfrieda Street/Victoria Crescent

To ensure east west pedestrian and bicycle connectivity across Alfrieda Street, between Alfrieda Street and Collins Street, St Albans and to the St Albans Railway Station.

To ensure car parking areas are landscaped and located in well-lit and safe locations.

To encourage retention of the fine grain subdivision pattern and narrow frontages at ground floor level along Alfrieda Street, St Albans.

To ensure solar access is maintained to existing and new public spaces for pedestrian amenity, in particular along the southern footpath of Alfrieda Street, Victoria Crescent, St Albans and open space areas adjoining the St Albans rail corridor.

To ensure development provides for the widening and improved access and loading within Alfrieda Lane, St Albans.

2.0 Buildings and works

08/07/2021
C211brim

Permit requirements

A permit is not required for the following:

- buildings and works associated with the provision of public open space.

A permit is required for the following:

- the construction of a front fence exceeding 1.2 metres in height and which is less than 50% transparent facing a street.

Buildings and works requirements

General

- The height of buildings and street wall heights should be limited to the preferred maximum height shown in Map 1.
- Buildings higher than the preferred maximum height shown on Map 1 may be considered if the design of the building reduces visual bulk through setbacks, building articulation and high quality building materials.
- Buildings should incorporate sustainable design features to address water and waste management, solar access and energy saving techniques.
- Pedestrian access through the precinct should be well lit and provide access for people with disabilities.
- Development must not prejudice the future provision of pedestrian and bicycle links as shown in the St Albans Activity Centre Precinct Structure Plan 2011 (Revised July 2015).

Residential Precincts

- Buildings should be oriented to front existing streets and where applicable, front onto public open space areas.
- The height of buildings fronting the street should be limited to a maximum of two (2) storeys. Upper levels should be articulated and set back from the street frontage by 2-4 metres to ensure building bulk is reduced and access to daylight/sunlight to adjoining uses and public spaces is maximised.
- Fencing to building frontages should be limited to a maximum height of 1.5 metres with 50% transparency.
- Buildings should be set back to provide for sufficient landscaping.

Commercial/Retail/Mixed Use Precincts

- Upper levels should be set back from podiums/streetwalls to ensure building bulk is reduced and access to sunlight to public spaces is maximised.
- New development should provide for loading areas to the rear of sites, avoiding key pedestrian routes.

Precinct 1 – Residential Areas 1A, 1B and 1C

- Mixed use development on Collins Street, St Albans should provide car parking on site or as part of a consolidated public carpark in Collins Street.
- Development on the west side of Collins Street, St Albans should consider opportunities for pedestrian connection between Collins Street and Alfrieda Street.
- Development must be set back from rear property boundaries on Alfrieda Lane, to improve vehicle access and loading.

Precinct 2 – Main Road

- Development on the north side of Main Road, St Albans should demonstrate that the southern footpath of Main Road, St Albans will receive solar access on 22 June.
- On Main Road West, St Albans where existing car parking is located within the site frontage, development should adopt a building setback in line with the predominant setback to ensure the car parking area is retained.

Precinct 3 – McKechnie/Kruger

- The layout of large redevelopment sites should optimise sunlight access to internal streets, windows and communal spaces and provide front setbacks that provide opportunities for landscaping, including at least one canopy tree.

Precinct 4 - Errington

- Development should provide linkages around and through buildings and spaces to provide good pedestrian connections through the precinct, particularly between St Albans Train Station and Errington Reserve, St Albans.
- Developments should demonstrate that the southern footpath of Princess Street, St Albans will receive solar access on 22 June.

Precinct 5 – Alfrieda/Victoria Crescent

- Development should provide safe and convenient/accessible pedestrian access between the development site, St Albans Railway Station and the existing retail area.
- Developments on the north side Victoria Crescent, St Albans should demonstrate that the southern footpaths of Victoria Crescent, St Albans will receive solar access on 22 June.
- To ensure development on the west side of Collins Street provides for the widening and improved access and loading within Alfrieda Lane, St Albans.

3.0 Subdivision

08/07/2021
C211brim

None specified.

4.0 Signs

08/07/2021
C211brim

None specified.

5.0 Application requirements

08/07/2021
C211brim

None specified.

6.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 43.02, in addition to those specified in Clause 43.02 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:


- Whether the proposed development achieves the design objectives and buildings and works requirements specified in this schedule.
- The subdivision of land should support development in accordance with the preferred character and objectives of the relevant precinct.
- Whether the design of any new development effectively integrates with the existing area.
- How the design, height and visual bulk of new development responds to the preferred character and amenity of the precincts.
- The contribution the development makes to public spaces, future pedestrian and bicycle networks and car parking in the St Albans Activity Centre.
- How the development improves the street environment for pedestrians along street frontages.
- The architectural quality of the building design, robustness and quality of building materials to ensure reduced maintenance of the building over time.

Background Documents

St Albans Activity Centre Precinct Structure Plan 2011 (Revised July 2015)

Errington Precinct Master Plan 2014


Map 1 to Schedule 9 to Clause 43.02 - St Albans Activity Centre and Precincts



LEGEND

- 2 storey preferred street wall height with variable street setback
- 3 storey preferred street wall height with 0m street setback
- Precinct boundary
- Open green space
- 4 Preferred Number of Storeys
- St Albans Railway Station
- SP01: Residential Precinct
- SP02: Main Road/Station Precinct
- SP03: McKechnie/Kruger Precinct
- SP04: Errington Precinct
- SP05: Alfreida/Victoria Crescent Precinct

Map 2 to Schedule 9 to Clause 43.02 - Proposed Pedestrian and Bicycle Connections



LEGEND

- SP01: Residential Precinct
- SP02: MainRoad/Station Precinct
- SP03: McKechine/Kruger Precinct
- SP04: Errington Precinct
- SP05: Alfreida/Victoria Crescent Precinct
- Open green space
- potential future bicycle path
- proposed new pedestrian path
- proposed off-road bicycle path
- proposed on-road bicycle path
- St Albans railway station

24/03/2016
C162

SCHEDULE 10 TO THE DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO10.**

KEILOR VILLAGE ACTIVITY CENTRE

1.0 Design objectives

24/03/2016
C162

- To improve the appearance of the Keilor Village Activity Centre (as shown in Figure 1) by facilitating development that is respectful of the area's character and history.
- To ensure that the development of land, shopfronts and signage are consistent with the *Keilor Village Vision Document, November 2015.*
- To ensure development is of a high quality, sustainable and well designed so as to create an attractive built form.
- To ensure development is of a scale and height (including setbacks) that respects the amenity of the public realm and neighbouring properties.
- To ensure that development of land provides an attractive setting to car parking areas.
- To ensure changes to the public realm improve the appearance and connectivity of the village and are respectful of Keilor's physical character and landscape setting and are complementary to private works that are undertaken.
- To ensure new development provides active frontages, natural surveillance, interest to the streetscape and are well lit and attractive.
- To encourage urban design initiatives which discourage criminal activity.

2.0 Design guidelines

24/03/2016
C162

General

- Heights and setbacks should be consistent with those in Figure 1.
- Front and side setbacks should be consistent with the existing built form of the area.
- Any upper storey development proposed in the west 'main' group of shops should be setback from the Old Calder Highway frontage, so the existing low scale streetscape is retained (see Figure 1).
- Development of up to three storeys may be considered behind the Keilor Hotel and in the 'east group of shops (see Figure 1).
- Where developments of three storeys are proposed, varied articulation and upper level setbacks are encouraged to reduce the potential impact of the scale and bulk of the development.
- Residential development on the upper levels of existing or proposed retail development should integrate with the street and be designed to promote the surveillance of the public realm.
- Commercial development abutting residential uses should respect the neighbouring property's scale and privacy.
- A simple and uncluttered approach to design is encouraged.
- Development should provide active frontages, natural surveillance and interest to the streetscape. On corner sites development should address both street frontages with either opening or street level windows.
- High fencing in front of buildings is discouraged to ensure active streetscapes and maintain surveillance of the public realm.
- Development should incorporate environmentally sustainable design principles, including the selection of materials and building performance.

- Roof forms should be generally flat or have a low pitch.
- Traditional building materials (such as brick, local stone, timber and corrugated iron) should be utilised. Modern lightweight materials can be considered on the upper levels and exterior building colours should be subtle.
- Existing trees should be maintained where possible.
- Additional landscaping is encouraged to strengthen the vegetated setting of the village.
- Planting should complement the significant historical landscape elements of the village which includes a mix of exotic and native species.
- Car parking should be located to the side and rear of properties.
- New development should minimise the visual intrusion of car parking facilities through the use of landscaping.
- Water Sensitive Urban Design (WSUD) should be incorporated in the design of car parking areas to improve the sustainability of the village centre and support additional planting.
- Lighting within car parking areas or other public spaces should be well-designed, contemporary, simple and functional.
- Loading areas should be integrated into the design of new developments.

Shopfront design

- 80% of new / altered shopfronts should comprise of clear glazing and / or entries.
- The obscuring / painting out of windows and glass doors is discouraged.
- The use of openable windows in shopfronts is encouraged to assist in activating the public realm, if they do not pose an obstruction to pedestrians.
- The incorporation of a cantilevered canopy or verandah that is consistent with those existing in the areas is encouraged.
- Where parapets are incorporated into the design, they should be simple in style and form.
- Where security grilles are proposed, the use of open and transparent grilles in encouraged. Roller shutters on building frontages are discouraged.
- Rooftop plant and equipment should be located away from sensitive adjoining uses and be appropriately screened so that it is not visible from the street and does not detrimentally affect the amenity of adjoining residents through noise or emissions.

Public realm

- Any change to the public realm proposed as part of a development, should be respectful of Keilor's physical character and landscape setting.
- The creation of new public spaces, in a variety of sizes, is encouraged as part of new development proposals. New public spaces should be overlooked by active frontages.
- Development should facilitate a shared-space approach in the laneway at the rear of the west 'main' group of shops fronting the Old Calder Hwy so that vehicles do not dominate this space and it can operate as a pedestrian friendly, appealing environment (see Figure 1).
- Encourage connectivity from the west 'main' group of shops fronting the Old Calder Hwy, to the rear laneway, through the provision of walk through facilities (see Figure 1).
- Ensure new development which adjoins the public realm applies a consistent range of materials and colour palette to infrastructure including paving.

3.0 Buildings and works

24/03/2016
C162

Application requirements

An application must be accompanied by the following information, plans and reports to the satisfaction of the responsible authority:

- A comprehensive statement which demonstrates how the proposed development addresses the relevant design objectives and guidelines of this schedule.
- Streetscape elevations.
- A schedule of materials and finishes which specifies high quality materials and finishes.

Applications for development which exceed the preferred heights in Figure 1 must be accompanied by:

- A set of 'as constructed' perspective diagrams, accurately showing the proposal as viewed from the streetscape and public spaces.

4.0 Decision guidelines

24/03/2016
C162

Before deciding on an application, the Responsible Authority must consider, where appropriate:

- Whether the development complies with the design guidelines under Clause 2.0 of this schedule.

Reference documents

Keilor Village Vision Document, November 2015.

Brimbank Activity Centre Strategy, 2008.

Figure 1 – Keilor Village Precincts and Preferred Building Heights



08/07/2021
C211brim

SCHEDULE 11 TO CLAUSE 43.02 DESIGN AND DEVELOPMENT OVERLAY

Shown on the planning scheme map as **DDO11**.

BROOKLYN INDUSTRIAL AND COMMERCIAL PRECINCT

1.0 Design objectives

08/07/2021
C211brim

To maintain and strengthen the economic role of the precinct as a key employment node.

To improve the amenity and appearance of the Brooklyn Industrial and Commercial Precinct.

To create an attractive environment to work and visit.

To ensure that development incorporates appropriate design measures that will protect surrounding residents and businesses from adverse visual, noise, odour or dust impacts.

To ensure new development provides suitable internal access and connectivity throughout the precinct.

To ensure best practice environmental design, operation and storm water reuse is used for new development and business operations.

To improve water quality and discharge rates into Kororoit Creek and other drainage outlets.

To improve the image and create a sense of identity for the precinct.

To ensure high quality landscape treatments contribute positively to the street edges and to the setting of buildings.

To minimise visual clutter, including excess signage and external storage.

2.0 Buildings and works

08/07/2021
C211brim

A permit is required to construct a front fence facing a street frontage that exceeds:

- 1.2 metres in height in the Commercial 2 Zone.
- 2 metres in height in the Industrial 1 Zone.

A permit is not required for:

- Buildings and works associated with the provision of public open space.

Buildings and works should be constructed in accordance with the following requirements:

Access and connection

- Vehicle crossovers, driveways, access lands and car spaces must be treated with an all-weather seal or other durable surface. This requirement cannot be varied with a permit.
- Access to the site should be designed so that vehicles enter and exit the site in a forward direction.
- Access to the site should contribute to a safe, legible and attractive frontage.
- Visitor car parking spaces should be clearly defined and signed and located towards the primary street frontage.
- Loading facilities should not be located between any building on the land and the landscape buffer to the frontage of the site.
- Staff car parking is encouraged to be located to the side or rear of the development.
- Access for loading and deliveries should be separated from pedestrian accessways.
- Car parking areas within the site frontage should be designed to incorporate landscaping.
- Internal vehicle access lanes should be arranged to maximise truck-queuing opportunities on-site and avoid truck-queuing off-site.

For land within a Commercial Zone:

- Site frontages should be designed to allow for the future provision of on street bicycle paths.

Environmental conditions

- All external areas including storage areas, should be sealed and landscaped to prevent dust generation.
- Development should incorporate Water Sensitive Urban Design, stormwater treatment, detention and reuse initiatives.

For land within an Industrial Zone:

- Prior to the approval of new development on disused landfill sites, a 'land fill gas' assessment should be undertaken in accordance with the Best Practice Environmental Management – Siting, Design, Operation and Rehabilitation of Landfills (EPA publication 788.3, 2015).
- The stockpiling and storage of materials should accord with best practice.
- Facilities to remove dirt and mud from wheels should be provided where vehicles traverse unsealed areas.

For land used for shipping container storage:

- Areas used to stack shipping containers should be constructed and provided with an all- weather surface to withstand shipping container loads and lifting equipment.

Landscape

- Landscape areas should have a minimum width of 5 metres along street frontages and a minimum width of 2 metres for side streets.
- Boundaries to the Kororoit Creek or the Federation Trail should have a landscape area of a minimum 3 metres and be landscaped with indigenous species of local providence.

For land within a Commercial Zone:

- Development should contribute to the boulevard character of Geelong Road.

For land within an Industrial Zone:

- Mature trees should be retained where possible and incorporated into new development design.
- Landscape bunds that screen stockpiles must be landscaped and be constructed no more than 2 metres higher than the approved stockpile height. This requirement cannot be varied with a permit. The bunds should be engineered to support long term landscaping and irrigation.
- Development should provide outdoor breakout spaces and amenity areas for staff. These areas should be landscaped with shade trees and located away from adverse amenity impacts.

For land used for shipping container storage:

- Landscape areas used to screen or soften the appearance of shipping container stacks or waste storage areas should be of sufficient dimensions to accommodate effective screen planting, such as combinations of dense shrubs and high branching taller trees.
- Landscaping should be provided along road boundaries of land used for shipping container storage and should be of a sufficient width to fulfil the purpose of the landscaping (for example, to screen storage areas from view).

Image and identity

- Heritage buildings should be conserved and adaptively reused.
- Development should be of a contemporary architectural style.
- Building facades should provide visual interest.

- Blank walls should be avoided.
- Building plant equipment and building services should be screened, through the use of architectural features or building design and not be visible from the street frontage.
- Development along the Federation Trail or Kororoit Creek should provide an articulated frontage and provide passive surveillance.
- Rubbish storage facilities and enclosures, manufactured goods, raw product or other equipment associated with the use of the site should be located within a building or screened from view from the frontage of the site.
- Utilities and services should be located in underground conduits.
- Energy efficient lighting should be provided for security and navigation through the site.

For land within a Commercial Zone:

- A robust palette of materials and strong colours are encouraged, to reinforce the location of entrances and corners of the precinct along Geelong Road.
- Integrated art, identifiable architecture and/or landscaping are encouraged to mark the entrances and corners of the precinct along Geelong Road.
- Long walls constructed on a single plane should be avoided or softened through the use of varied building treatments and finishes and the location of feature entrances.

For land within an Industrial Zone:

- Buildings should be setback a minimum of 9 metres from the site frontage and 4 metres on a side street. Only set back landscaping and car parking will be permitted within this setback.
- Building materials should reflect the industrial nature of the precinct and include the use of corrugated iron, timber and textured concrete.

For land used for shipping container storage:

- The location, scale and height of container stacking should have regard to the scale and height of buildings on site, or buildings on adjoining land.
- Shipping containers stacked adjacent to landscape areas or property boundaries should be stacked in a tier or pyramid formation to reduce visual bulk.

Fences

For land within a Commercial Zone:

A front fence should:

- Not be higher than 2 metres.
- Be transparent.
- Be black or green plastic coated, if chain mesh.
- Not include barbed wire.

For land within an Industrial Zone:

A front fence should:

- If transparent, be black or green plastic coated.

3.0 Subdivision

08/07/2021
C211brim

Road access to the new lots should be at least 18 metres wide.

New roads should provide footpaths and landscaping in road reserves.

Provide sufficient off-street car parking, vehicle turning and standing areas.

4.0 Signs

08/07/2021
C211brim

Signage should be integrated into the built form of the building.

Free standing signage should be low and integrated into the front landscape treatment.

Signage should be limited to avoid visual clutter and repetition.

Shared signage is encouraged for multiple business sites.

5.0 Application requirements

08/07/2021
C211brim

None specified.

6.0 Decision guidelines

08/07/2021
C211brim

The following decision guidelines apply to an application for a permit under Clause 43.02, in addition to those specified in Clause 43.02 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the development has any adverse visual impact on adjacent areas of public open space.
- Whether new driveways and vehicle crossings have been located to avoid street trees.
- Whether the development will make a positive streetscape contribution.
- Whether any steps have been taken to minimise visual clutter caused by overhead services.
- Whether carparking vehicle access and service areas visually impinge on front setbacks and/or landscape buffers.
- Whether the landscape treatment in the front and side setbacks contribute to the enhancement and improved appearance of the precinct.
- For land within the Commercial 2 Zone, seek the views of the agency with the management and operation controls of the gas transmission infrastructure (APA Gasnet).
- For land with a frontage to Geelong Road, seek the views of VicRoads.
- For proposed land use and development that includes the emission of dust, particles, smoke or gas, above a height of 240m AHD, seek the views of Melbourne Airport.
- The design objectives of this Schedule.

Background documents

The Brooklyn Evolution, February 2016

Greening the West – A Regional approach, Strategic Plan, 2013

43.04 DEVELOPMENT PLAN OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **DPO** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify areas which require the form and conditions of future use and development to be shown on a development plan before a permit can be granted to use or develop the land.

To exempt an application from notice and review if a development plan has been prepared to the satisfaction of the responsible authority.

43.04-1 Objectives

31/07/2018
VC148

A schedule to this overlay may specify objectives to be achieved for the area affected by the overlay.

43.04-2 Requirement before a permit is granted

31/07/2018
VC148

A permit must not be granted to use or subdivide land, construct a building or construct or carry out works until a development plan has been prepared to the satisfaction of the responsible authority.

This does not apply if a schedule to this overlay specifically states that a permit may be granted before a development plan has been prepared to the satisfaction of the responsible authority.

A permit granted must:

- Be generally in accordance with the development plan.
- Include any conditions or requirements specified in a schedule to this overlay.

43.04-3 Exemption from notice and review

31/07/2018
VC148

If a development plan has been prepared to the satisfaction of the responsible authority, an application under any provision of this planning scheme is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

43.04-4 Preparation of the development plan

25/02/2025
VC257

The development plan may consist of plans or other documents and may, with the agreement of the responsible authority, be prepared and implemented in stages.

A development plan that provides for residential subdivision in the Neighbourhood Residential Zone, General Residential Zone, Housing Choice and Transport Zone, Residential Growth Zone, Mixed Use Zone, Township Zone, Comprehensive Development Zone and Priority Development Zone must meet the requirements of Clause 56 as specified in the zone.

The development plan must describe:

- The land to which the plan applies.
- The proposed use and development of each part of the land.
- Any other requirements specified for the plan in a schedule to this overlay.

The development plan may be amended to the satisfaction of the responsible authority.

08/07/2021
C211brim

SCHEDULE 2 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO2**.

KEILOR DOWNS PLAZA SHOPPING CENTRE

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

None specified.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

None specified.

4.0 Requirements for development plan

08/07/2021
C211brim

In preparing a Development Plan or amending a Development Plan, the following matters must be considered:

- The extent to which the proposed development integrates with the existing development
- The effect of any proposed development on adjoining land uses, including residential properties.
- Any strategic plan or policy adopted by the Responsible Authority.

The development plan must show:

- Appropriate landscape buffers around the proposed development including adjacent to surrounding residential development
- Timing and staging (if appropriate) of development.
- Restriction of access to the site to the existing accessway off Copernicus Way.
- The location, height and dimensions of all buildings and works.
- The external design and finishes of all buildings to be constructed on the land.
- The number, location and layout of all car parks and accessways (including pedestrian access)
- The location and layout of any loading facilities and rubbish storage facilities.
- Proposed lighting facilities.

08/07/2021
C211brim

SCHEDULE 3 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO3**.

RIVER VALLEY ESTATE

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

A permit may be granted before a development plan has been prepared to the satisfaction of the Responsible Authority only for a golf course development generally in accordance with the plan entitled "Conceptual Masterplan, No. TW-PC", dated May 1998 prepared by Thomson, Wolveridge and Perrett.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

None specified.

4.0 Requirements for development plan

08/07/2021
C211brim

The development plan must:

- Describe the land to which the plan applies.
- Show or make provision for:
  - The proposed use of each part of the land.
  - The relationship of the land to the existing or proposed uses on adjoining land.
- Population targets for component areas of the Plan.
- Appropriate buffer distances between land used for industrial purposes and residential or other sensitive uses.
- A road layout pattern and design which is ecologically sustainable, enhances the residential character of the area and establishes a movement network which:
  - Provides good internal and external access for residents.
  - Maximises safety.
  - Encourages use of public transport
  - Minimises through-traffic.
  - Provides for connection between the proposed urban area and adjoining areas.
- A traffic assessment which addresses the impact of the development on the arterial and local road networks and identifies mitigating works on those networks including funding responsibilities.
- Public transport facilities.
- The means by which employment will be created or opportunities for employment facilitated.
- Commercial and community centres and facilities in a sustainable hierarchy.
- A range of housing and lot types and densities, including medium-density and other special housing areas.
- Water, sewerage, drainage, electricity and gas services.

- Major drainage lines, water features, proposed retarding basins and floodways and the means by which they will be managed and water quality maintained.
- Open space and recreation facilities and major pedestrian and cycle networks.
- An overall scheme for landscape planting and the preservation of stands of indigenous vegetation and individual trees where possible and any areas for regeneration.
- Sites of conservation, heritage and archaeological signification and the means by which they will be managed (in particular, the identified area of significant native grassland).
- The staging and anticipated timing of development.
- Arrangements for the provision and funding of social and physical infrastructure.
- Arrangements for the rehabilitation of excavated and filled areas of the site including the following:
  - the processing of rock, stone, gravel, sand, clay, soil, concrete, asphalt, bricks or similar materials for use at the site in reclamation, landscaping or the construction of buildings, roads or other works;
  - the filling of the land with non-putrescible waste material imported to the site;
  - the making safe of any hazardous rock faces;
  - the landscaping of the rehabilitated areas and any areas to be used for open space;
  - filling and battering of quarried areas;
  - the proper control of excavation and filling to ensure that there is no loss of amenity to the area or detrimental impact on the environment;
  - impacts on the surrounding road network from truck movements to and from the site during filling and rehabilitation works;
  - the completion of a site assessment to ensure that the land to be used for public open space is environmentally suitable for the use;
  - type of fill which may include clean fill, waste material or contaminated fill and the like;
  - trucking routes and access arrangements;
  - operating hours;
  - control of dust and other emissions;
  - noise management;
  - a program for filling including staging in a manner and in a time designed to minimise any adverse impact on the amenity of nearby areas;
  - security measures to ensure public safety including details of fencing, gates and monitoring of the site;
  - measures to ensure that materials do not spill onto public roadways;
  - measures for the protection of the Maribyrnong River, native grasslands and riverside linear open space during rehabilitation works; and
  - proposals to ensure that rehabilitation works are completed.
- Arrangements for public access along the west side of the Maribyrnong River.
- The preparation of a stormwater management plan to the satisfaction of Melbourne Water and the responsible authority.
- Access to the road network to be to the satisfaction of, and at no cost to, the responsible authority and VicRoads.

- The areas that will be available as open space at the completion of each stage of the development.
- The construction of a pedestrian/bike path across Maribyrnong River.

Archaeological Survey

The development plan must take into account the recommendations of an archaeological survey of the site to the satisfaction of the responsible authority.

River Valley Estate Building Design Guidelines

The development plan must include guidelines that provide for, amongst other matters, the scale, form, height and colour of buildings and the landscaping of sites.

08/07/2021
C211brim

SCHEDULE 4 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO4**.

26S GLENBROOK AVENUE AND 147A CAIRNLEA DRIVE, CAIRNLEA

This schedule applies to the land known as the "Cairnlea Mixed Use Precinct".

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

A permit may be granted before a development plan has been approved for:

- Any works, associated with the remediation of the land in accordance with or for the purpose of obtaining a Certificate or Statement of Environmental Audit under the *Environment Protection Act 1970*.
- Vegetation removal.
- Subdivision of the land into superlots or to realign property boundaries, or create a road, or create or remove easements.

Before granting a permit, the responsible authority must be satisfied that the works will not prejudice the ability of future use and development to meet the vision for the site.

Cultural Heritage Management Plan

Before any permit is granted for works defined as a 'high impact activity' within the definition of the *Aboriginal Heritage Regulations 2007*, for any part of the land which is within an area of Cultural Heritage Sensitivity, a Cultural Heritage Management Plan (CHMP) must be produced and approved by the Registered Aboriginal Party and Aboriginal Affairs Victoria, as required.

The above requirement does not apply if the proponent can demonstrate to the satisfaction of the responsible authority that a CHMP is not required in accordance with the provisions of the *Aboriginal Heritage Regulations 2007*.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

Except for a permit issued under Clause 2.0 of this Schedule, a permit must contain the following conditions, as appropriate, which give effect to the provisions and requirements of an approved development plan:

Construction Management Plan

Prior to the commencement of works, a construction management plan must be submitted to and approved by the responsible authority which demonstrates the following:

- Measures to be implemented to minimise adverse impacts during development on environmental values such as threatened species, habitat, water quality, and sites of biological and cultural significance.
- Measures to be implemented to minimise generation of sediment on site, the transportation of sediment onto public roads into drains and waterways, and the generation of dust.
- Measures to be taken to avoid any impacts on the operation of public transport and access to bus stops.
- Location of the site offices, off-street vehicle parking for construction workers and employees on the site.

- Methods to be used for the collection and disposal of construction waste and storage of construction materials.
- Hours of operation on the construction site.

All works conducted on the land must be in accordance with the approved construction management plan.

Landscaping Plan

Prior to the commencement of works, a detailed landscaping plan consistent with the landscaping masterplan must be submitted and approved by the responsible authority that includes:

- A planting scheme with predominantly indigenous and native landscape species that are suitable for planting in a residential area.
- Details of street trees to be provided within the site, and how they integrate with the surrounding and adjoining street networks.
- A landscape boulevard and entry treatment along Cairnlea Drive, immediately north of Ballarat Road.
- Details of landscaping associated with the proposed open space areas.
- Details of the shared path network.

4.0 Requirements for development plan

08/07/2021
C211brim

A development plan must include the following requirements:

- A siting and design plan showing:
  - An indicative development schedule including the number, type and density of dwellings and the floor area of any proposed non-residential uses.
  - A transition in lot size between the adjoining and new residential areas along the northern boundary.
  - Provide a lot layout that ensures there are opportunities for active and passive surveillance in the area.
  - The location of up to four storey medium density housing abutting the common boundary with the M80 road reserve.
  - The location of up to four storey medium density housing in proximity to 'Gateway Hill', Cairnlea Drive, Ballarat Road, Kororoit Creek and the commercial area.
  - The location of landscaped wall treatments on medium density housing where abutting the common boundary with the M80 road reserve or commercial area.
  - The details of billboard signage to be located within the 'Gateway Hill' area fronting the M80 and Ballarat Road.
- A traffic and access plan which includes an assessment addressing the potential impact of the proposed development on the arterial and local road networks and identifies mitigating works on those, including:
  - The intersection of Glenbrook Avenue and Cairnlea Drive.
  - Potential loading requirements for the commercial land that clearly avoid heavy vehicles using residential streets.
  - Road reserves and road widths that comply with council requirements and the Public Transport Guidelines for Land Use and Development.
  - The location of internal road, cycle and pedestrian networks and their connection to existing networks, including public transport.

- Traffic calming methods such as road humps and/or chicanes to be provided within the residential development.
- A reservation for the creation of an access point into the adjoining property located at 18A Jonesfield Corner, Cairnlea.
- A cycling and walking plan to be produced, having regard to the Brimbank Walking and Cycling Strategy 2008 (as amended), including details of the location and reservation for shared paths and how pedestrian connectivity is to be provided to the surrounding Principal Bicycle Network (PBN) and public transport.
- An interface along the existing water ways including pedestrian and bicycle paths.
- Pedestrian links to and from the site across Cairnlea Drive and Ballarat Road.
- Access to the commercial land, including left in only access from Ballarat Road and left in access and left out egress from Cairnlea Drive.

The traffic and access plan must incorporate the views of the Roads Corporation, relevant floodplain management authority and the Public Transport Development Authority.

- A landscaping master plan, including:
  - The location of trees to be removed in accordance with a tree assessment.
  - The general location of street trees.
  - A concept plan for the proposed active open space and 'Gateway Hill' areas.
  - A concept plan for all areas that interface with adjoining road or waterway reserves.
  - The location and design of entry treatments, signage and landscaping along Cairnlea Drive and the existing waterways to create a legible entry to the site.
- A development contributions plan showing the developer contribution 'works in kind' that are to be provided within the designated active open space reserve.
- A stormwater management plan that addresses the control of flows in and around the site for discharges up to and including the 1 in 100 year flows and addresses the need for retention storage to control flows and water quality treatments to a best practice standard.
- A services plan including:
  - Details of the physical infrastructure to accommodate the development including the provision of water, sewerage, drainage, electricity, gas and telecommunication services to be provided underground.
  - The location of existing and proposed easements.
- An Adverse Amenity Impact Assessment (AAIA) prepared by a suitably qualified person(s). The results of the AAIA must provide guidance for any further staging and development of the site. The report must identify all potential adverse amenity impacts from nearby uses and consider:
  - Whether the proposed use and development is likely to be affected by odour, noise or dust from any surrounding industrial activities and/or Major Hazard Facility (MHF).
  - The mitigation or remedial measures that could be taken to minimise or avoid adverse impacts identified in the report.
- A Noise Impact Assessment (NIA) prepared by a suitably qualified person(s). The results of the NIA must provide guidance for any future staging and development of the site and should include:

  - An assessment of potential noise impacts between residential and commercial development on the land including recommendations for mitigation.
  - Recommendations for appropriate mitigation measures to minimise noise impacts on the land from the M80 and potential future western freight alignment.
- A plan showing the indicative staging and timing of key infrastructure and facilities.

Before deciding whether a development plan, or amendment to a development plan is satisfactory, the responsible authority must consider, as appropriate:

- The views of the relevant floodplain management authority, with respect to the integration of proposed pedestrian and bike path locations.
- The views of the Public Transport Development Authority.

The views of the relevant referral authorities (including but not limited to the Roads Corporation) must be sought prior to approval of the development plan for:

- The proposed access arrangements from Ballarat Road to the site.
- The required noise impact assessment and potential noise mitigation measures required.

08/07/2021
C211brim

SCHEDULE 5 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO5**.

LAND AT THE NORTH WEST CORNER OF KINGS ROAD AND TAYLORS ROAD, DELAHEY

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

None specified.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

Any permit granted must include conditions or requirements for:

- The funding of infrastructure to the satisfaction of the responsible authority; or
- An agreement between the owner of the land and the responsible authority under Section 173 of the Planning and Environment Act before the commencement of the development covering the arrangements for the provision of funding for infrastructure.

4.0 Requirements for development plan

08/07/2021
C211brim

The development plan must include the following:

- The boundaries and dimensions of the site.
- The layout and setbacks of proposed buildings and works.
- Elevations of all buildings.
- Details of materials and finishes to all buildings and surfaces.
- The number of car parking spaces and car parking layout including loading and unloading facilities.
- Design details of all proposed public vehicle and pedestrian access ways.
- Pedestrian and vehicular management.
- A flora and fauna survey documenting any significant populations or communities of native vegetation and native fauna.
- An overall plan for landscape planting, the preservation of native vegetation and fauna and the means by which they will be managed and in particular, the identified areas of native vegetation and native fauna.
- Lighting of all common areas.
- The staging and anticipated timing of development.
- Fencing to all common boundaries with adjoining land in a residential zone and buffer areas between the residential zone and the site.

In considering the development plan, the responsible authority must consider:

- Whether the location, bulk, height and appearance of any proposed buildings or works are in keeping with the neighbourhood character of the area.
- Whether any proposed landscaping will be in keeping with the character and appearance of adjacent land.
- The layout and appearance of areas set aside for car parking, access and egress, loading and unloading and the location of any proposed car parking.

- The preservation of significant communities of native vegetation or native fauna.
- The Brimbank Natural Heritage Strategy (1997).

08/07/2021
C211brim

SCHEDULE 6 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO6**.

CAIRNLEA ESTATE - FORMER ALBION EXPLOSIVES FACTORY SITE

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

None specified.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

Any permit granted must include conditions or requirements for an agreement with the responsible authority under Section 173 under the Planning and Environment Act 1987 covering the arrangements for the provision and funding of infrastructure.

4.0 Requirements for development plan

08/07/2021
C211brim

The development plan must show:

- The proposed use of each part of the land.
- A range of lot types and densities.
- Provision for water, drainage, electricity, sewerage and gas.
- The pattern and location of a road system based on an ecologically sustainable and practical hierarchy of roads and connections between the proposed urban area and adjoining land.
- Waterways, proposed retarding basins and floodways and the means by which these will be managed and the water quality maintained.
- Site of conservation, heritage and archaeological significance and the means by which they will be managed.
- The staging and anticipated timing of development.
- The provision of educational, civic and community facilities.
- Open space facilities including pedestrian and cycle networks.
- A range of lot sizes within the residential areas.
- The design, building setbacks, building height and building materials on areas along the Western Highway and the Western Ring Road.
- Any landmark proposed for the site.
- An overall landscaping plan, particularly in public open spaces areas highlighting the preservation of indigenous vegetation where possible.

In considering the development plan, the responsible authority must consider:

- The impact on the significant environmental historic and archaeological features on the site.
- Accessibility to and from the site.
- Buffer distances between any industrial and residential uses.
- Whether the location, bulk, outline and appearance of the building and works will be in keeping with the future character and appearance of the overall subject site.
- Whether the location, bulk, outline and appearance of the building or works will be in keeping with or enhance the site when viewed from the Western Highway and Western Ring Road.

- The manner in which the Development Plan can proceed in the event that the owner of any land is not able or intending to develop.
- The Cairnlea Development Plan submission 1998 prepared by Hassell Pty Ltd.

Cairnlea Retail Centre

In considering the development of the Cairnlea retail centre, the responsible Authority must consider:

- The Cairnlea Retail Centre Urban Design Guidelines, 2002 prepared by HASSELL Pty. Ltd.

08/07/2021
C211brim

SCHEDULE 7 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO7**.

10 MCKECHNIE STREET, ST ALBANS

The Overlay applies to the land known as 10 McKechnie Street, St Albans.

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

A permit may be granted to use or subdivide land, construct a building or construct or carry out works (including demolition and other works related to the environmental audit and remediation) before a Development Plan has been approved, provided the responsible authority is satisfied that the subdivision, use or buildings or works will not prejudice the future use or development of the land in an integrated manner as contemplated by this Overlay and that land contamination and adverse amenity impacts have been addressed.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

None specified.

4.0 Requirements for development plan

08/07/2021
C211brim

A development plan must be prepared that meets the following criteria to the satisfaction of the Responsible Authority:

- A **Concept Plan** which shows or provides the following information:
  - The proposed land use and development of each part of the land, having regard to the purpose of the Residential 1 Zone;
  - A range of lot sizes, densities and housing typologies to achieve at least 200 dwellings on the land;
  - Indicative building heights and setbacks;
  - Staging Plan for development;
  - A north-south link along McKechnie Street adjacent to the western boundary of the site that will be available at all times for pedestrian and cycle access, to the satisfaction of the responsible authority;
  - Locations for vehicle egress and ingress, road layout and the location of car parking areas;
  - Treatments for key interface areas (e.g. between open space areas and proposed development, within existing streetscapes, and buffer treatment between residential and non-residential land uses and the proposed development);
  - Passive surveillance of public spaces;
  - Pedestrian and cycle paths;
  - Traffic management treatments on Gratz and Gooding Streets as recommended by the Integrated Traffic Management Plan to the satisfaction of the responsible authority; and
  - Areas of public open space.
- A **Town Planning Report** that includes:

  - How the proposed development plan will meet the planning policy framework on urban design, adopted Urban Design Guidelines for Victoria and the requirements of Clause 56 (as appropriate) of the Scheme; and
  - The proposed arrangement of land uses across the site.

- A **Landscape Plan** including:
  - A consistent landscape theme across the site that complements any proposed future development;
  - The location and species of vegetation to be retained;
  - The inclusion of any Water Sensitive Urban Design including locations of retarding basins (if required) and means by which these will be managed; and
  - Proposed Street cross-sections.
- An **Integrated Traffic Management Plan** including the following:
  - An existing conditions assessment;
  - The likely traffic generation of the proposed development and measures to mitigate impacts;
  - The road layout and design including the preferred road reserve widths and cross-sections;
  - The means of vehicle ingress and egress to and from the site;
  - Location and access points for on-site car parking;
  - A pedestrian and bicycle network plan;
  - Public transport arrangements and access routes; and
  - A description as to how the plan responds to State Government objectives.
- A **Service Infrastructure Assessment** detailing:
  - The servicing requirements of the proposed development;
  - The availability of existing services to connect to the site to support the proposed development;
  - Any upgrades required to existing infrastructure; and
  - Any new infrastructure required to be provided.
- An **Adverse Amenity Impacts Report** prepared by a suitably qualified person(s) to the satisfaction of the Responsible Authority. The report must identify all potential adverse amenity impacts from the industrial property to the south-east and consider:
  - Whether the proposed use and development is likely to be affected by any odour, noise and dust sources from the industrial property to the south-east;
  - What ameliorative or remedial measures can and will be taken to minimise or avoid the adverse impacts identified in the report.
- An **Acoustic Assessment** prepared by a suitably qualified consultant that addresses the following:
  - The potential impacts of the rail line to the east of the site; and
  - Recommendations to address the potential impacts identified.
- A **Flora and Fauna Assessment** to be undertaken to inform the preparation of the development plan and identify areas of remnant indigenous vegetation and threatened species habitat for retention including:

- Whether there is any native or indigenous vegetation;
- A plan identifying the location, type, condition and size and existing vegetation on-site;
- Recommendations as to the retention value of the existing vegetation; and
- Suggested management of any native or indigenous vegetation.

At the request or with the consent of the owner of the land affected, the Development Plan may be amended to the satisfaction of the Responsible Authority. The Responsible Authority may waive the need to provide any of the information detailed above that is not relevant to a particular Development Plan or part thereof.

15/02/2018
C148

SCHEDULE 8 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO8.**

110V AND 112 – 116 ANDERSON ROAD, SUNSHINE

1.0 Requirement before a permit is granted

15/02/2018
C148

A permit may be granted to use, subdivide or construct or carry out works before a development plan has been prepared to the satisfaction of the Responsible Authority.

The Responsible Authority must be satisfied that the permit will not predjudice the future use or development of the land in an integrated manner, and will contribute to the implementation of the *Sunshine Town Centre Structure Plan (2014)*.

2.0 Conditions and requirements for permits

15/02/2018
C148

The following conditions and/or requirements apply to permits:

- A **Construction Management Plan** which details measures to manage and minimise the impact of any excavation, demolition, building or works on the environment and surrounding area.
- A **Landscaping Plan** which details new and existing vegetation, any proposed retention and removal of vegetation, a planting schedule, any fencing and details of surface finishes.
- An **Aviation Fuel Pipeline Mitigation Report** which demonstrates that:
  - Buildings and works satisfy the requirement contained in the *Somerton Aviation Fuel Pipeline Safety Management Study 112 – 116 Anderson Road, Sunshine, Victoria (2015)*.
  - Buildings and works are carried out in accordance with Australian Standard 2885.1 Pipelines – Gas & liquid petroleum standard, Part 1 (AS-2885.1), Section 4.7.4.

3.0 Requirements for development plan

08/07/2021
C211brim

The Development Plan should be generally in accordance with the concept plan shown at Map 1 and should be consistent with the following objectives:

- To achieve a high quality, integrated residential development which is responsive to the site's sensitive interfaces.
- To minimise the impact of development on the adjoining H.V. McKay Memorial Gardens through appropriate setbacks, built form transition and planting.
- To provide safe vehicle and pedestrian access to and from the site.

The Development Plan must include the following:

- A **Site Context Analysis** that includes, but is not limited, to the following:
  - The identification of physical and environmental issues associated with the land and surrounding area including adjacent road and rail infrastructure.
  - The location of any existing easements and restrictions.
  - The location of existing points of access to the site and adjoining sites.
  - The identification of sensitive interface areas such as HV McKay Memorial Gardens (north), the Bendigo rail corridor (east), the Ballarat rail corridor (south) and Anderson Road (west).
  - An arboricultural assessment of any significant heritage and landscape trees on the land, and on land adjacent to the northern boundary within the H.V McKay Memorial Gardens. The assessment should include advice on the long-term health and retention value of any significant trees.
- An **Overall Layout Plan** that includes, but is not limited, to the following:

- Proposed lot layout, building orientation, location of private and public open space.
- Three dimensional building envelope plans including indicative building heights to show the following:
  - Building heights generally not exceeding 11 metres (3 storeys) along the interface with the HV McKay Memorial Gardens.
  - Building heights generally not exceeding 13.5 metres (4 storeys) along the interface with Anderson Road.
  - Building heights generally not exceeding 30 metres (9 storeys) for the remainder of the site.
  - A minimum building setback of 5 metres along the interface with the HV McKay Memorial Gardens.
- Shadow diagrams of proposed building envelope conditions between 9am and 3pm on 22 September.
- An indicative development schedule including the number, type and density of dwellings and the floor area of any proposed non-residential uses.
- The location and details of internal road, bicycle and pedestrian networks and connections with existing road, bicycle and pedestrian networks external to the land, ensuring pedestrian access to the H.V McKay Memorial Gardens (including the existing north south path) and the Devonshire Road footbridge.


- An **Traffic Management Plan** that includes, but is not limited, to the following:
  - An assessment which considers safety and vehicle movements within the development, the location of proposed vehicle access to and egress from the land, streetscape improvements and the location of traffic signals to Anderson Road.
  - Details proposed access routes to public transport, how these will be integrated into the future development and measures to maintain pedestrian access to the Devonshire Road footbridge and rail corridor.
  - The location of visitor car parking.

The views of the Roads Corporation (VicRoads) must be sought prior to the approval of the Traffic Management Plan.

- An **Open Space and Landscape Plan** that includes, but is not limited, to the following:
  - A clear delineation between the H.V. McKay Memorial Gardens and the site with the provision of a linear landscape area which details:
    - Additional tree planting along the interface.
    - A public path along the eastern boundary of the site and connections to existing paths.
    - Front fences should be no greater than 1.2 metres in height and visually permeable.
  - The size and location of public open space.
  - The designation of tree protection zones for trees identified in the arboricultural assessment to be retained.
  - Public areas and private areas, including areas for street tree planting that will provide an overall tree canopy cover of 30 percent, tree species selection and maturity at planting.
  - The choice of tree species that allows for tree canopy height generally greater than 12 metres at maturity.

  - The proposed interface treatment which outlines boundary materials and heights between the development and the H.V McKay Memorial Gardens, the Bendigo rail corridor, the Ballarat rail corridor and Anderson Road.
  - The number of driveways and crossovers should be minimised to ensure appropriate tree numbers and canopy cover.
- An **Environmental Sustainability Plan** that outlines initatives to be included in the future development.
- A **Stormwater Management Plan** that addresses the control of flows in and around the land for discharges up to and including the 1 in 100 year flows and addresses the need for retention storage to control flows and water quality treatments to a best practice standard.
- An **Infrastructure Plan** that identifies all existing and proposed infrastructure requirements and easements (water, sewerage, drainage, electricity, gas and telecommunication services) to service the development. The report must also address the need for the relocation of any services and whether services will be provided above or below ground.
- A **Noise and Vibration Impact Analysis** that includes an assessment of the existing and future noise and vibration impacts from the adjoining rail corridors and Anderson Road on the land, with recommendations for suitable mitigation measures that will not detract from the amenity of the residential development.

Map 1 to Schedule 8 to Clause 43.04: Concept Plan



LEGEND

- Site boundary
- Heritage interface (5 metres)
- Other interface conditions
- Local park
- Vehicle access to site
- Fully directional signalised vehicle access to site
- Pedestrian link
- Railway
- Rail maintenance vehicle access

BUILDING HEIGHTS

- 11 metres (3 storeys)
- 13.5 metres (4 storeys)

08/07/2021
C211brim

SCHEDULE 9 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO9**.

51 & 63A REGAN STREET, ST ALBANS

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

A permit may be granted before a development plan has been approved for the following:

- Any buildings or works, including the demolition or construction of part of any building, associated with the remediation of the land in accordance with or for the purpose of obtaining a Certificate or Statement of Environmental Audit under the *Environment Protection Act 1970*.
- Subdivision; and
- Removal or creation of easements or restrictions.

Provided the responsible authority is satisfied that the subdivision, buildings or works will not prejudice the preparation of the development plan.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

None specified.

4.0 Requirements for development plan

08/07/2021
C211brim

A development plan must be prepared that includes the following elements to the satisfaction of the responsible authority.

- A **Concept Plan** which shows or provides the following information:
  - The proposed land use and development of each part of the land, having regard to the purpose of the General Residential Zone and Urban Floodway Zone;
  - A range of lot sizes, densities and housing typologies to achieve at least 200 dwellings on the land;
  - Indicative building heights and setbacks;
  - Staging Plan for development;
  - The continuation of Regan Street adjacent to the eastern boundary of the site, to the satisfaction of the responsible authority;
  - Locations for vehicle egress and ingress, road layout and the location of car parking areas;
  - Treatments for key interface areas (e.g. between open space, existing residential development, and the proposed development including identifying development that will front the proposed retarding basin);
  - How mature trees have been incorporated into the concept plan;
  - The reuse of the unique street lights within the development; and
  - Public open space.
- A **Town Planning Report** that includes:

  - How the proposed development plan will meet the planning policy framework on urban design, adopted Urban Design Guidelines for Victoria and the requirements of Clause 56 (as appropriate) of the Scheme.
  - Indicative housing designs that will incorporate the use of environmentally sustainable design initiatives, such as the use of eaves, shading devices, noise attenuation and the orientation of windows and open space.

- A **Landscape Plan** including:
  - A consistent landscape theme across the site that complements any proposed future development and incorporates eucalypts planting;
  - The location and species of vegetation to be retained and Tree Protection Zones as per AS 4970 Protection of Trees on Development Sites;
  - The inclusion of any water sensitive urban design including locations and designs of retarding basins and means by which these will be managed; and
  - Proposed street cross-sections.
- An **Integrated Traffic Management Plan** including the following:
  - An existing conditions assessment;
  - The likely traffic generation of the proposed development and measures to mitigate impacts;
  - The road layout and design including the preferred road reserve widths and cross-sections;
  - The means of vehicle ingress and egress to and from the site;
  - Location and access points for on-site car parking; and
  - A pedestrian and bicycle network plan.
- A **Service Infrastructure Assessment** detailing:
  - The servicing requirements of the proposed development;
  - The availability of existing services to connect to the site to support the proposed development;
  - The management of stormwater on the land;
  - Any upgrades required to existing infrastructure; and
  - Any new infrastructure required to be provided.
- An **Adverse Amenity Impacts Report** prepared by a suitably qualified person(s) to the satisfaction of the responsible authority. The report must identify all potential adverse amenity impacts from the industrial property to the south-east and the Sunbury Rail line to the east and consider:
  - Whether the proposed use and development is likely to be affected by any odour, noise and dust sources from the industrial property to the east and south-east;
  - What ameliorative or remedial measures can and will be taken to minimise or avoid the adverse impacts identified in the report.
  - Whether the proposed use and development is likely to be affected by the Sunbury Railway line to the east having consideration of the Victorian Freight and Logistics Plan (2013) or similar.
- A **Flora and Fauna Assessment** that identifies areas of remnant indigenous vegetation and threatened species habitat for retention including:

- Whether there is any native or indigenous vegetation in suitable conditions between October and November and following a 4 week period of no disturbance;
- A plan identifying the location, type, condition and size and existing vegetation on-site;
- Recommendations as to the retention value of the existing vegetation; and
- Suggested management of any native or indigenous vegetation.

At the request of or with the consent of the owner of the land affected, the development plan may be amended to the satisfaction of the responsible authority. The responsible authority may waive the need to provide any of the information detailed above that is not relevant to a particular development plan or part thereof.

08/07/2021
C211brim

SCHEDULE 13 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO13.**

SUNSHINE GOLF COURSE (130 FITZGERALD STREET) AND THE MASONIC CENTRE (1A RALPH STREET), SUNSHINE WEST

1.0 Conditions and requirements for permits

19/01/2006
VC37

Any permit granted must include conditions or requirements for the owner to enter into an agreement with the Responsible Authority under Section 173 of the Planning and Environment Act 1987 to provide for the following matters:

- A contribution towards physical and social infrastructure to the satisfaction of the Responsible Authority.
- The establishment of the following controls on all lots adjoining the common boundary of land abutting any existing residential land to the north, south or east (such boundaries to be referred to in this clause as the "residential common boundaries") except for the lots identified separately in this Schedule:
  - A 3 metre wide landscape buffer adjoining the residential common boundaries.
  - A setback of 5 metres for any single storey part of a building from the residential common boundaries.
  - A setback of 9 metres for any part of a building of two or more storeys from the residential common boundaries, provided that if such building is located on a lot which shares a boundary with the residential common boundaries, the maximum height of such building shall not be more than 9 metres.
  - A setback of 5 metres for any outbuilding from the common residential boundaries unless such outbuilding is 1.8 metres or less in height and covers a building footprint of no greater than 5 square metres.

The establishment of the following controls on the lots described below:

- Any new lot to the north of Lot 2511 PS422889 (10 Magenta Court) is to have the following:
  - North-south orientation.
  - A minimum 3 metre wide landscape strip with native tree plantings from the common residential boundary.
  - A minimum distance of 19 metres between the southern wall of any new dwelling and the northern wall of the dwelling at 10 Magenta Court.
  - A minimum setback of 5 metres for any outbuildings from the common residential boundary.

Any new lot to the north of Lot 2312 PS422888 (9 Eucalyptus Court) is to have the following:

- A minimum 3 metre wide landscape strip with native plantings from the common residential boundary.
- A minimum setback of 5 metres for any outbuildings from the common residential boundary.
- Any dwelling to be single storey only.
- A minimum distance of 20 metres between the southern wall of the new dwelling and the northern wall of the existing dwelling at 9 Eucalyptus Court.

Any new lot to the north of Lot 102 LP323006M (16 Noble Court) to be separated by a 5 metre landscape buffer and road (no less than 6 metres in width) from the northern boundary of 16 Noble Court. Any dwelling on such (new) lots must be no closer than 22.5 metres from the nearest 1st storey window of the dwelling on 16 Noble Court.

2.0 Requirements for development plan

19/01/2006
VC37

A Development Plan must include a report detailing how the plan achieves the following objectives:

- To provide certainty about the future scale and character of the development on the land.
- To create a high quality living environment.
- To provide a principal access onto Fitzgerald Road and to explore the possibility of a secondary access onto Ralph Street.
- To provide for integration of the development with the character of the area.
- To provide for different housing opportunities on the land.
- To limit development generally to two storeys but provide opportunities for townhouse and/or apartment style development at the centre of the land that may rise for four storeys above ground.
- To ensure that new development does not have a detrimental visual impact on abutting residential land in terms of height or bulk.
- To provide effective design buffers between the land and abutting residential land through the use of planting and setback of buildings.
- To protect the amenity of abutting residential land from unreasonable overlooking and overshadowing.
- To contribute to the improvement of on site stormwater drainage systems.

A Development Plan must show:

- The numbers, approximate lot distribution and the layout of lots and approximate size of lots provided that the number of lots is in the vicinity of 660.
- The roads to and from the land and how they connect with the existing road network.
- The pedestrian and bicycle network and linkages with surrounding land.
- Dimensions and typical cross sections of the road network.
- The retention of significant vegetation and enhancement with native and indigenous planting.
- Details of house types and proposed siting and detailed design at the interface with adjoining residential lots including planting, fencing and indicative house types.
- The identification of parts of the land to be used for different densities of housing and the height of the buildings proposed for these areas.
- The location and area of public open spaces.
- The proposed landscape themes for the roads and pedestrian network and other public spaces.
- The provision of on-street visitor car parking.
- The location, extent and principal features of the drainage system and a methodology to mitigate and contain flood flows to a reduced area on the land.
- The proposed staging of development.
- The incorporation of ecologically sustainable development approaches encompassing:
  - Site planning.
  - Landscaping.
  - Biodiversity and ecosystem improvements.
  - The promotion of sustainable forms of transport.
  - Building design, materials and construction methods.

- Methods to promote energy efficiency and minimise waste.
- Methods to promote a water sensitive urban design solution to the development of the land including stormwater management.

08/07/2021
C211brim

SCHEDULE 14 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO14**.

SOUTH WEST INDUSTRIAL PARK (AREA 2)

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

A permit may be granted to construct or carry out minor works before a Development Plan has been prepared to the satisfaction of the responsible authority.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

Any application for minor works (before a development plan has been approved) must be accompanied by a report demonstrating that they will not prejudice the future development of the land in accordance with the Concept Plan (Map 1) that forms part of this schedule.

4.0 Requirements for development plan

08/07/2021
C211brim

The development plan must describe the land to which the plan applies, generally be in accordance with the Concept Plan (Map 1) that forms part of this schedule and show or make provision for:

- The proposed use of each part of the land, having regard to the purpose of the Industrial 1 Zone.
- The relationship with the existing or proposed uses on adjoining land.
- A road layout pattern and design which is ecologically sustainable, enhances the character of the area and establishes a movement network which:
  - Implements the Concept Plan.
  - Provides good internal and external access.
  - Encourages use of public transport.
  - Provides connection between the proposed urban area and adjoining areas.
- A traffic assessment which addresses the impact of the development on the arterial and local road network and identifies mitigating works on those networks including funding responsibilities.
- A proposed lot layout that has regard to the types of uses which are proposed or likely to be developed.
- Water, sewerage, drainage, electricity and gas services.
- Major drainage lines, water features, proposed retarding basins and floodways and the means by which they will be managed and the water quality maintained.
- An overall scheme for landscape planting and the preservation of stands of indigenous vegetation and individual trees, together with any areas for regeneration.
- Sites of conservation, heritage and archaeological significance and the means by which they will be managed or any impacts minimised (including the location and management of the basalt stone walls referred to as BH2 - H7822-0214 in the Victorian Heritage Inventory).
- The arrangements for providing and funding physical infrastructure.
- The preparation of a stormwater management plan to the satisfaction of Melbourne Water and the Responsible Authority.

- Access to the road network to the satisfaction of, and at no cost to, the Responsible Authority and VicRoads.
- Appropriate noise attenuation from freeways and arterial roads.
- Addressing the impact of storm water drainage on downstream grasslands.
- The Brimbank City Council, Urban Design Strategy, December 1997.
- Bus routes and associated infrastructure such as bus shelters.
- The staging and anticipated timing of development.

Any development plan may be amended with the approval of the responsible authority.

Archaeological Survey

An archaeological survey must be carried out prior to the approval of the development plan. The development plan must take into account the recommendations of the archaeological survey to the satisfaction of the responsible authority.

Flora and Fauna Survey

A flora and fauna survey must be carried out prior to the approval of the development plan. The development plan must take into account the recommendations of the flora and fauna survey to the satisfaction of the responsible authority and the Department of Environment, Land, Water and Planning.

Building Design Guidelines

The development plan must include guidelines that provide for, amongst other matters, the scale, form, height and colour of buildings and fences, landscaping of sites and impacts on views from arterial roads and surrounding areas.


Agreement

The responsible authority may require land owners to enter into an Agreement pursuant to section 173 of the Act.

The Agreement may make provision for:

- A sharing of the costs of the development plan preparation and any studies required.
- Contributions to be made by the owners towards the provision of on-site and off-site road, traffic and bridge infrastructure, drainage and stormwater retention works (including the provision of land and/or payment of financial levies) required as a consequence of the intended use and development of the land.
- Contributions to be made by the owners toward the provision and maintenance of a linear park in association with Laverton Creek, including facilities for pedestrians and cyclists.

Map 1 to Schedule 14 to Clause 43.04 – Concept Plan



08/07/2021
C211brim

SCHEDULE 15 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO15.**

247-251 ST ALBANS ROAD, SUNSHINE NORTH

This schedule applies to the land known as 'Former City West Water Site', at the corner of St Albans Road and the Western Ring Road, Sunshine North.

1.0 Requirement before a permit is granted

16/07/2015
C134

A permit may be granted before a development plan has been approved for the following:

- Any buildings or works, including the demolition or construction of part of any building, associated with the remediation of the land in accordance with or for the purpose of obtaining a Certificate or Statement of Environmental Audit under the Environment Protection Act 1970 provided the works are carried out in accordance with a Construction Management Plan prepared in accordance with this Schedule.
- Subdivision.
- Removal or creation of easements or restrictions.
- Any buildings or works associated with the maintenance, repair or preparation of the identified heritage building for re-use.

Provided the responsible authority is satisfied that the subdivision, buildings or works will not prejudice the preparation of the Development Plan or Conservation Management Plan.

Cultural Heritage Management Plan

Before any permit is granted for works defined as 'high impact activity' within the definition of the *Aboriginal Heritage Regulations 2007*, for any part of the land which is within an area of Cultural Heritage Sensitivity, a Cultural Heritage Management Plan (CHMP) must be produced and approved by the Registered Aboriginal Party and Aboriginal Affairs Victoria as relevant.

The above requirement does not apply if the proponent can demonstrate to the satisfaction of the Responsible Authority that a CHMP is not required in accordance with the provisions of the *Aboriginal Heritage Regulations 2007*.

2.0 Conditions and requirements for permits

08/07/2021
C211brim

Except for a permit issued under Clause 1.0, a permit must contain the following conditions as appropriate, which give effect to the provisions and requirements of an approved Development Plan:

Construction Management Plan

Prior to the commencement of works, a Construction Management Plan must be submitted to and approved by the responsible authority which:

- Details the measures to be implemented to minimise adverse impacts during development on environmental values including habitat, water quality, sites of biological and cultural significance and vegetation to be retained on the site.
- Details the measures to be implemented to minimise:
  - the generation of sediment on site
  - the transport of sediment onto public roads and into drains and waterways
  - the generation of dust.
- Shows the location of site offices, off-street vehicle parking for construction vehicles and employees.

- Details the methods to be used for the collection and disposal of construction waste and the storage of construction materials.
- Details the hours of operation on site.

All works conducted on the land must be in accordance with the approved Construction Management Plan.

Conservation Management Plan

Prior to the commencement of any development on the land affected by a Heritage Overlay, plans and/or any necessary reports demonstrating how the development will implement the recommendations set out in the Conservation Management Plan forming part of the approved Development Plan must be submitted to the satisfaction of the responsible authority. Once approved, the plans and/or reports will form part of the permit.

Historic Archaeological Site Assessment

Prior to any works occurring on site an Historic Archaeological Site Assessment must be undertaken to the satisfaction of Council and Heritage Victoria which includes but is not limited to:

- A ground survey of Lot 2 on the plan of subdivision PS411165A.
- Completion of a Heritage Inventory Site Card, which notes the basic details (description location and extent) of any historical archaeological site located in the subject area.

Landscaping Plan

Prior to the commencement of works, a Landscaping Plan must be submitted to and approved by the responsible authority which details:

- A scheme for indigenous landscape planting and the preservation of existing vegetation and individual trees on the land, which encourages the preservation of areas of remnant vegetation and habitat on the land.
- The protection and integration of mature trees which are to be retained on the site.
- The designation of tree protection zones for mature trees on land to be retained adjacent to the western boundary of the site and the Western Ring Road and within the Melbourne Water Stony Creek proposed linear park.
- The details of street trees to be provided within the site, integrating existing trees within an appropriate development and open space context.
- Planting in public areas to soften the appearance of telecommunications and other services facilities and built form.
- Details on how public open space areas are to be developed and managed.

Except for a permit issued under Clause 1.0, a permit application must provide the following as appropriate, which give effect to the provisions and requirements of an approved Development Plan:

Environmentally Sustainable Development Plan

The Environmentally Sustainable Development Plan must include, but is not limited to:

- Information on Environmentally Sustainable Development principles to be incorporated into the development.
- Design principles to improve the energy efficiency of buildings and works.
- Design principles to integrate the site with the Principle Public Transport Network.

Acoustic Requirement

Where dwellings or other sensitive uses are proposed, a permit condition shall be imposed which requires the installation and implementation of any mitigation measures necessary to achieve the relevant acoustic performance standards identified in the acoustic assessment required by Clause 3.0 of this Schedule, to the satisfaction of the responsible authority.

3.0 Requirements for a Development Plan

16/07/2015
C134

Any development plan should be generally in accordance with the concept plan dated August 2014 prepared by Brimbank City Council, and must be informed by a detailed site analysis of the natural, cultural and strategic context of the site and the immediately adjoining land.

The development plan may be prepared and approved in stages and a permit issued for that stage may be issued prior to the approval of a development plan for any other stage of the development, provided that the future subdivision, use and development of the land in an integrated manner will not be prejudiced.

An approved development plan may be amended with the approval of the responsible authority.

A development plan must show the following matters (as applicable if the development plan is approved in stages) to the satisfaction of the responsible authority:

Site Analysis Plan

The Site Analysis Plan must include, but is not limited to, the following:

- The identification of physical and environmental issues associated with the land and surrounding area such as surface water hydraulics and areas of potential contamination.
- The location of existing and planned points of access to the site.
- The location of the existing heritage buildings on site.
- Identify sensitive interface areas such as the land adjacent to the Melbourne Water Stony Creek proposed linear park, the area between the mixed use and residential areas and any abutting or nearby industrial land.

Conservation Management Plan

For land affected by the Heritage Overlay, a Conservation Management Plan must be prepared by a suitably qualified person(s). The Conservation Management Plan shall be prepared in accordance with the Information Guide *Conservation Management Plans: Managing Heritage Places* (Heritage Council of Victoria 2010) to the satisfaction of the Responsible Authority. The Conservation Management Plan must address:

- The conservation and management of the heritage building.
- How the future development of the land will enhance and compliment the identified heritage values of the heritage place.
- The scope of works proposed for the heritage place to facilitate its reuse and how it will be integrated with the surrounding development.

Overall Layout, Traffic and Access Plan

The Overall Layout, Traffic and Access Plan must include, but is not limited to, the following:

- The location and details of internal road, cycle and pedestrian networks.
- A traffic assessment which addresses the impact of the proposed subdivision, use and development on the arterial and local road networks and identifies mitigating works, including potential road treatments/improvements, on those networks to the satisfaction of the Responsible Authority and VicRoads.
- An indicative storm water and drainage management plan.

- The indicative future uses within the Mixed Use zoned land for employment uses, including retirement accommodation and aged care facilities.
- The location of the Melbourne Water Stony Creek proposed linear park.
- The location of any heritage buildings to be retained on site for adaptive re-use.
- Key interface areas between the site and adjoining land.
- Key interface areas between residential and non-residential uses within the site.
- The provision of a road along a minimum of 80 per cent of the length of the eastern boundary adjoining the Melbourne Water Stony Creek proposed linear park.
- The location and detail of two separate road access points to the land from St Albans Road.
- The provision of at least one through road connection from St Albans Road into the residential zoned land.
- The location and details for the connecting vehicle and pedestrian bridge to Metherall Street.
- Bicycle and pedestrian connections to Furlong Road and St Albans Road for the provision of sustainable transport outcomes.
- A footpath for the length of the St Albans Road frontage of the land.

Open Space, Environment and Landscape Plan

The Open Space, Environment and Landscape Plan must include, but is not limited to:

- The location of any wetlands, retarding basin or public open space required for the management of stormwater within the site.
- Pedestrian connections to and the interface treatment between development and the Melbourne Water Stony Creek proposed linear park.
- The provision of a minimum three metre wide landscape buffer between the road and the Melbourne Water Stony Creek proposed linear park along the eastern boundary of the site.
- The indicative size and location of Public Open Space.
- A road running along the southern land boundary to provide an appropriate interface with the adjoining grasslands.
- The provision of a treed landscape buffer between the Mixed Use and Residential Zones, to be located at the rear of business allotments as appropriate.
- The location of individual mature trees to be retained and those proposed to be removed.
- The location and extent of remnant indigenous vegetation on the site.
- Details of existing vegetation proposed for removal.

Flora and Fauna Assessment

A Flora and Fauna Assessment must be prepared by a suitably qualified person(s) to the satisfaction of the responsible authority to identify areas of remnant indigenous vegetation and threatened species habitat. The Assessment must include, but is not limited to:

- The identification of any native or indigenous vegetation on site.
- A plan identifying the location, type, condition and size of existing vegetation on-site, including recommendations as to the retention value of the vegetation.
- Suggest a management plan for any native or indigenous vegetation to be retained.

Acoustic Assessment

An acoustic assessment shall be prepared by a suitably qualified person and be to the satisfaction of the responsible authority. The report shall consider potential acoustic amenity impacts from the Western Ring Road, St Albans Road, the Bendigo/Swan Hill and Albion/Jacana rail lines and the proposed Western Goods line. It is to include any recommended mitigation measures and confirm that development on the site is capable of compliance with:

- VicRoads Traffic Noise Policy external noise limit of 63dB LA10(18h).
- Australian Standards 2107 and 3671.
- Victorian Government Passenger Rail Infrastructure Noise Policy, April 2013.


4.0 Decision guidelines

08/07/2021
C211brim

In assessing a Development Plan for each stage of the development the Responsible Authority will consider, as appropriate:

- The views of Melbourne Water, as the relevant floodplain management authority. In particular, with respect to the integration of the proposed road and public open space network with the drainage capacity and surface water hydrology of the development.
- The views of VicRoads.

Map 1 to Schedule 15 to Clause 43.04 - Concept Plan (August 2014)



08/07/2021
C211brim

SCHEDULE 16 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO16**.

ORICA DEER PARK DEVELOPMENT PLAN

1.0 Objectives

08/07/2021
C211brim

None specified.

2.0 Requirement before a permit is granted

08/07/2021
C211brim

A permit may be granted before a development plan has been approved for the following:

- Any buildings or works, including the demolition or construction of part of any building, associated with the remediation of the land in accordance with or for the purpose of obtaining a Certificate or Statement of Environmental Audit under the *Environment Protection Act 1970*.
- Any buildings or works associated with an existing use being carried out on the site.
- Alterations or additions to existing site infrastructure such as car parking and internal access roads.
- Subdivision of land.
- Removal, variation or creation of easements, restrictions or reserves.
- Removal of vegetation.
- Site offices or display suites.
- Signs.

A planning report must be submitted as part of any application for a planning permit and should demonstrate that the buildings and works and/or subdivision of land will not prejudice or conflict with:

- The long term future use and development of the land;
- The preparation of a Development Plan; or
- The provisions and requirements of any approved Development Plan.

3.0 Conditions and requirements for permits

08/07/2021
C211brim

Economic Impact Assessment Requirements

If required by the Responsible Authority considering the proposed scale, use and extent of shop floorspace proposed and already permitted on the land subject to this Development Plan Overlay, applications for permits for the use of the land as "shop" should be accompanied by an economic impact assessment. The economic impact assessment should (as appropriate) demonstrate how the proposed use:

- may impact existing or proposed activity centres in the area; and
- responds to the state and local planning policy framework.

Health and Safety Assessments

The following requirements apply to use and building and works applications for permits on land subject to the Development Plan Overlay which fall within the 'Health and Safety' area:

- The application must demonstrate that the proposal is appropriately designed and located having regard to any health and safety risks associated with the location of the Major Hazard Facility.
- The application must consider (as appropriate) risk management requirements, including emergency evacuation procedures, any open space to the east, robust building materials, air

ventilation systems capable of isolation and building orientation with ingress and egress orientated to the east.

Before granting a planning permit (or amendment to a planning permit) for a use, building or works application within the 'Health and Safety' area the Responsible Authority must give notice of the application to WorkSafe Victoria in accordance with Clause 66.06.

Odour Assessment

All applications for the following uses, or buildings and works associated with the following uses, within 300 metres of the nearest lease boundary of the Gate 3 Precinct industries (765 Ballarat Road, Deer Park) must be accompanied by an air emissions report to determine the impacts (if any) of air emissions from the Gate 3 Precinct on the proposed use:

- Accommodation
- Agriculture
- Child care centre
- Cinema-based entertainment.
- Education centre.
- Leisure and recreation.
- Office.
- Place of assembly.
- Retail premises.

Before granting a permit (or an amendment to a planning permit) for a use or buildings and works associated with a use of the type listed above within 300 metres of the nearest lease boundary of the Gate 3 Precinct industries (765 Ballarat Road Deer Park) the Responsible Authority must give notice of the application to the Environment Protection Authority in accordance with Clause 66.06.

4.0 Requirements for development plan

08/07/2021
C211brim

The Development Plan must include the following matters (as relevant if the Development Plan is approved in stages):

Health and Safety

The identification of any area of the land subject to the Development Plan Overlay which falls within a planning advisory area published by WorkSafe Victoria in accordance with the *Advisory Note Major Hazard Facilities: Land use planning near a major hazard facility*.

If no advisory area has been published, and unless otherwise advised by WorkSafe Victoria, the inner advisory area is 100 metres, and the outer advisory area is 300 metres both measured from the hazard source.

Odour Assessment

An odour assessment for the area of the land subject to the Development Plan Overlay which falls within 300 metres of the nearest lease of the Gate 3 Precinct industries (765 Ballarat Road, Deer Park).

The odour assessment requirements must be developed in consultation with the Environment Protection Authority and the occupiers of nearby industries.

Infrastructure

An Infrastructure Analysis Report which addresses the following, as appropriate:

- Location of existing infrastructure on the site.

- Drainage.
- Pedestrian/ shared paths, including Kororoit Creek and Ballarat Road.
- Public open space.
- Traffic management.
- Details of how the need or otherwise for infrastructure relates to the proposed use and development of the land and, where need is identified, how the necessary infrastructure will be provided for, including works-in-kind, and payments towards new infrastructure.

Siting and Staging Plan

A site context plan and an indicative staging plan.

The site plan should identify:

- The indicative future use of land within each precinct.
- Indicative lot sizes, building heights and setbacks.
- The interface treatments within the site and the interface and address to Ballarat Road, and the Western Ring Road (M80).
- Infrastructure assets.
- Adjoining and nearby land uses, including open space, community facilities and existing industries.
- Transport networks, including vehicular, pedestrian and bicycle, as well as emergency evacuation routes and access for emergency services.
- If required by the Department of Transport Planning and Local Infrastructure (Freight Logistics and Marine Division), identification of a railway corridor generally along the eastern boundary of the site to connect to a Western Interstate Freight Terminal Facility.

The indicative staging plan should identify:

- The proposed sequencing of development, the timing of the provision of infrastructure and services and overall integration with other development stages, and
- Vehicular access points, road infrastructure works and traffic management for each stage of development.

Services

A Stormwater Management Plan, prepared by a suitably qualified person(s) that addresses:

- The control of flows in and around the site for discharges up to and including the 1 in 100 year flows and addresses the need for retention storage to control flows and water quality treatments to a best practice standard. Details of the physical infrastructure required to accommodate the subdivision, use and/or development including the provision of water, sewerage, drainage, electricity, gas and telecommunication services and whether services will be provided above or below ground.
- The location of existing and proposed easements.

Traffic

A Traffic Management Plan prepared by a suitably qualified person(s). The Plan must include the following:

- The location of existing roads into, within and around the site.
- A traffic assessment which addresses the impact of the proposed subdivision, use and development on the arterial and local road networks and identifies mitigating works, including

potential road widening, other road treatments/improvements on those networks to the satisfaction of the responsible authority and VicRoads.

- A new centralised north – south access route with a secondary road network which creates an active and attractive public realm with amenity provided for vehicles, cyclists and pedestrians.
- Potential for connections to the west, towards Station Street and the Deer Park activity area and railway station, having regard to the Heritage Overlay.
- The incorporation of a grid street pattern for the internal road network, that will accommodate public transport facilities and pedestrian and cyclist infrastructure. Required future road improvements and signalisation of intersections based on the outcomes of Road Safety Audits at ingress and egress points along Ballarat Road.
- Emergency evacuation routes and access for emergency services.
- Indicative cross-sections of the street network, including provision for footpaths, bicycle paths and other infrastructure as appropriate.

The views of the Department of Transport Planning and Local Infrastructure (Freight Logistics and Marine Division), Public Transport Victoria, VicRoads, the Metropolitan Fire Brigade and State Emergency Services, must be sought prior to the approval of the Traffic Management Plan.

Access

An Access Plan, prepared by a suitably qualified person(s) which must include the following:

- Convenient and safe access to and from the site to facilitate staged and/or final site access arrangements.
- Linkages to the pedestrian and bicycle corridor along Kororoit Creek in appropriate locations having regard to flooding and safety issues.
- A Cycling and Walking Plan, having regard to the Brimbank Walking and Cycling Strategy 2008 (as amended), including existing vehicle, pedestrian and bicycle routes into, within and around the site, details of how pedestrian and bicycle connectivity is to be provided (including future links to Deer Park Station and Deer Park Activity Centre) and connections provided to the surrounding Principal Bicycle Network (BPN) and including a pedestrian path along the Ballarat Road frontage of the site.
- A cycle link from the existing off and on-road lanes along the northern side of Ballarat Road through the site.

The views of the Department of Transport Planning and Local Infrastructure (Freight Logistics and Marine Division), Public Transport Victoria and VicRoads, must be sought prior to the approval of the Access Plan.

Flora and Fauna

- Information that responds to the recommendations of the Summary of Ecological Values, Orica Deer Park Site, Deer Park, Victoria Ecology and Heritage Partners, December 2012.
- A plan showing the indicative removal and or retention of vegetation to the satisfaction of the Responsible Authority.
- Information that addresses the interface between any proposed development of the site and the Kororoit Creek corridor including the protection and enhancement of riparian vegetation.

Open Space and Landscaping

A landscaping and open space plan prepared by a suitably qualified person(s) to the satisfaction of the Responsible Authority that includes:

- The location and species of existing trees over 3 metres in height.
- A landscape concept plan for the land.

- The preferred species of street trees, including concepts for roadway and kerbside planting based on Council's preferred planting lists, including native vegetation where appropriate, and
- The location and indicative design of landscape treatments of the connecting roadways to create legible entries/exits to the site.

Heritage

- Information that responds to the recommendations of the Interpretation Plan, Orica Explosives Factories Complex, Ballarat Road, Deer Park prepared by Lovell Chen, dated December 2012 including the Orica Explosives Factories Complex, Landscape Conservation Analysis, John Patrick Pty Ltd, August 2012. This represents the Heritage Interpretation Plan defined in an Agreement between Brimbank City Council and Orica Australia Pty Ltd made on 3 April 2012 further to Section 173 of the Planning and Environment Act 1987 and is registered on title to the land.
- Details of how development will incorporate, interpret, retain and/or reuse identified heritage elements into the development of the site, and
- Information that responds to the recommendations of the Environmental Contamination Works, Commercial/Industrial Subdivision & Development, Orica Site, Deer Park: Voluntary Cultural Heritage Management Plan – 10825 of 9 March 2010 prepared by Golder Associates for Orica Australia Pty Ltd.

Design, Layout and Built Form

Information that shows how the development of the site or a stage will achieve the integrated development of the site as a whole, by the preparation of Design Guidelines. The Design Guidelines should address the following as appropriate and be implemented as part of the Development Plan:

- Provision of high-quality, site-responsive design outcomes and architectural styles.
- Orientation of buildings to face the primary street frontage and building entry points to have a relationship with the public realm.
- Avoidance of blank walls or large loading docks facing Kororoit Creek or other areas of public open space and the primary road network.
- Principles of Crime Prevention Through Environmental Design (CPTED).
- Indicative building height.
- Preferred front, side and rear building setbacks, including landscaping.
- Indicative cross-sections of the street network, including concepts for roadway and kerbside planting.
- Preferred fencing styles which are appropriate to the various land uses and locations within the site, taking into account the need for security.
- Screening of plant and equipment areas and waste storage.
- Ensuring new buildings and works are sited to maximise solar access.
- Providing for a diversity of lot sizes to accommodate a range of building types and land uses.
- A preference for below-ground services.
- Providing safe, well lit and convenient pedestrian and vehicular access throughout the site.
- A preferred landscaping theme and incorporation of new canopy trees and reference to Council's preferred planting lists including native vegetation where appropriate, and
- An avoidance of visual clutter and signage to consider the requirements of Clause 52.05 of the Planning Scheme.
- The interface with nearby existing industrial uses.

If a rail corridor is identified on the site, the Design Guidelines should require an appropriate response to any proposed adjacent sensitive land uses. The response should ensure development is designed to address potential amenity impacts from unrestricted freight use of the railway and include an Adverse Amenity Impacts Report by a suitably qualified person(s).

Decision guidelines

Before approving a Development Plan (or amendment to the plan) the responsible authority must consider the following, as appropriate:

- The Municipal Planning Strategy and Planning Policy Framework.
- The purpose of the applicable Zone.
- The need for safe and attractive pedestrian linkages within the site and to the surrounding residential and public open space areas.
- Whether the proposed development responds appropriately to the context of the site in terms of the use of land and the form of development.
- Whether the location of proposed uses within the 'Health and Safety' area are appropriate having regard to the intensity of the use (i.e. number of people), the vulnerability of the proposed population and the ability of the proposed population to respond to an emergency if required.
- The findings and recommendations of the Odour Assessment.

Before approving a Development Plan (or amendment to the plan) the responsible authority must seek the views of:

- Melbourne Water.
- VicRoads.
- Department of Transport, Planning and Local Infrastructure, Freight Logistics and Marine Division.
- The Metropolitan Fire Brigade and State Emergency Services.
- WorkSafe Victoria, and
- Environment Protection Authority.

08/07/2021
C211brim

SCHEDULE 17 TO CLAUSE 43.04 DEVELOPMENT PLAN OVERLAY

Shown on the planning scheme map as **DPO17.**

This schedule applies to land generally known as:

- 95 Station Road and 814 Ballarat Road, Deer Park
- 27 Driscolls Road, Kealba
- 32A Green Gully Road, Keilor
- 18-24 Robertsons Road and 16-28 McCubbin Drive, Taylors Lakes

1.0 Requirement before a permit is granted

04/05/2017
GC46

A permit may be granted before a development plan has been approved for:

- Any buildings or works associated with the remediation of land in accordance with or for the purpose of obtaining a Certificate or Statement of Environmental Audit under the *Environment Protection Act 1970*.
- Subdivision.
- Creation, variation or removal of easements or restrictions.

Before granting a permit the responsible authority must be satisfied that the permit will not prejudice the preparation of a Development Plan and future use and development of the land in an integrated manner.

2.0 Conditions and requirements for permits

04/05/2017
GC46

Except for a permit granted before a development plan has been approved in accordance with Clause 1.0 of this Schedule, a permit must contain the following conditions:

- A construction management strategy must be submitted to and approved by the Responsible Authority which
  - Details measures to be implemented to minimise adverse impacts during the development on environmental values including habitat, water quality, sites of biological and cultural significance and vegetation to be retained on site.
  - Details the measures to be implemented to minimise the generation of sediment on the site, the transport of sediment onto public roads and into drains and waterways and the generation of dust.
  - Shows the designation of tree protection zones for canopy trees to be retained on the land.
  - Shows the location of site offices, off-street vehicle parking for construction vehicles and employees.
  - Details the methods to be used for the collection and disposal of construction waste and the storage of construction materials.
  - Details of the hours of construction on the site.
- All works conducted on the land must be in accordance with the approved construction management strategy.

3.0 Requirements for development plan

04/05/2017
GC46

In preparing a development plan or an amendment to a development plan, the following should be achieved:

- Where residential uses are proposed, a range of dwelling types, as appropriate, to cater for a variety of housing needs.

- Sustainable design features to address water management, solar access and energy saving initiatives, to deliver lower living costs for future residents.
- Variation to building forms across the site.
- Internal amenity for future residents.
- Protection of the amenity of adjoining sites by providing for a maximum of 2 storey built form adjacent to or opposite any existing single or double storey residential development.
- Graduation of taller buildings across the balance of the site with reference to analysis of shadow, visual amenity impacts and the character of the area.
- Appropriate buffer treatments at the interface with any non-residential uses on adjoining properties.
- A positive interface to adjacent public open space giving appropriate consideration to issues of safety and surveillance.
- Improved local permeability through provision of new pedestrian/cycle pathways or new local street networks where appropriate that link to the existing networks.
- Where provided, locate open space adjacent to existing or proposed pedestrian/cycle pathways.
- Retention of vegetation where appropriate.

Development plan components

The development plan must be prepared in consultation with the Roads Corporation and include the following information:

- Existing conditions plan, showing surrounding land uses and development, adjoining roads and pedestrian links, public transport routes, topography, existing canopy trees, vegetation and development and social infrastructure.
- Concept plans for the layout of the site which show:
  - Identification of sensitive interface areas.
  - The type and location of proposed uses on the site.
  - Proposed lot and road layout, new building orientation and location, indicative uses for each building, car parking areas, public roads, vehicle access locations, pedestrian and bike paths and areas and locations of private and public open space.
  - Stormwater and drainage management treatments including any water sensitive design, or integrated water management elements.
  - Three dimensional building envelope plans including indicative building heights and setbacks.
  - The design philosophy for the site and indicative architectural themes.
  - Shadow diagrams of proposed building envelope conditions at 10.00am, 1.00pm and 3.00pm at 22 September.
  - An indicative development schedule including the number, type and density of dwellings and the floor area of any proposed non-residential uses.
  - Where non-residential uses are proposed, details of the nature of the proposed use.
- A traffic management report and car parking plan, which identifies:
  - Roads, pedestrian, cyclist and vehicle access locations, including parking areas, both internal and external to the site.
  - Any traffic management measures.
  - Location of and linkages to public transport.

  - Car parking rates for all uses, including visitor parking.
  - Provision for bicycle facilities.
  - Proposed staging plan (if relevant).
- An arboricultural assessment of any significant vegetation on the land, including advice on the long-term health and retention value of such vegetation.
- A landscape plan for the site, including principles and guidelines.
- For 95 Station Street and 814 Ballarat Road, Deer Park, how any off-site environmental risks from the Orica site will be managed.
- For 32A Green Gully Road, Keilor, the views of the airport lessee company of Melbourne Airport.

The development plan for any part of the development area or for any stage of development may be amended from time to time to the satisfaction of the responsible authority.

The responsible authority may waive the need to provide any of the information detailed above that is not relevant to a particular Development Plan or part of a Development Plan.

44 LAND MANAGEMENT OVERLAYS

19/01/2006
VC37

44.04 LAND SUBJECT TO INUNDATION OVERLAY

06/09/2021
VC171

Shown on the planning scheme map as **LSIO** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify flood prone land in a riverine or coastal area affected by the 1 in 100 (1 per cent Annual Exceedance Probability) year flood or any other area determined by the floodplain management authority.

To ensure that development maintains the free passage and temporary storage of floodwaters, minimises flood damage, responds to the flood hazard and local drainage conditions and will not cause any significant rise in flood level or flow velocity.

To minimise the potential flood risk to life, health and safety associated with development.

To reflect a declaration under Division 4 of Part 10 of the *Water Act, 1989*.

To protect water quality and waterways as natural resources by managing urban stormwater, protecting water supply catchment areas, and managing saline discharges to minimise the risks to the environmental quality of water and groundwater.

To ensure that development maintains or improves river, marine, coastal and wetland health, waterway protection and floodplain health.

44.04-1 Land subject to inundation objectives and statement of risk

24/01/2020
VC160

A schedule to this overlay may contain:

- Land subject to inundation management objectives to be achieved.
- A statement of risk.

44.04-2 Buildings and works

14/12/2023
VC253

A permit is required to construct a building or to construct or carry out works, including:

- A fence.
- Roadworks, if the water flow path is redirected or obstructed.
- Bicycle pathways and trails.
- Public toilets.
- A domestic swimming pool or spa and associated mechanical and safety equipment if associated with one dwelling on a lot.
- Rainwater tank with a capacity of not more than 10,000 litres.
- A pergola or verandah, including an open-sided pergola or verandah to a dwelling or a small second dwelling with a finished floor level not more than 800mm above ground level and a maximum building height of 3 metres above ground level.
- A deck, including a deck to a dwelling or a small second dwelling with a finished floor level not more than 800mm above ground level.
- A disabled access ramp.

This does not apply:

- If a schedule to this overlay specifically states that a permit is not required.
- To roadworks or bicycle paths and trails constructed or carried out by or on behalf of the Head, Transport for Victoria, to the satisfaction of the relevant floodplain management authority.

- To flood mitigation works carried out by the responsible authority or floodplain management authority.
- To the following works in accordance with plans prepared to the satisfaction of the responsible authority:
  - The laying of underground sewerage, water and gas mains, oil pipelines, underground telephone lines and underground power lines provided they do not alter the topography of the land.
  - The erection of telephone or power lines provided they do not involve the construction of towers or poles.
- To post and wire and post and rail fencing.

44.04-3 Subdivision

31/07/2018
VC148

A permit is required to subdivide land.

44.04-4 Application requirements

31/07/2018
VC148

An application must be accompanied by any information specified in a schedule to this overlay.

44.04-5 Local floodplain development plan

31/07/2018
VC148

If a local floodplain development plan has been developed for the area and has been incorporated into this scheme, an application must be consistent with the plan.

44.04-6 Exemption from notice and review

31/07/2018
VC148

An application under this overlay is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

44.04-7 Referral of applications

31/07/2018
VC148

An application must be referred to the relevant floodplain management authority under Section 55 of the Act unless in the opinion of the responsible authority, the proposal satisfies requirements or conditions previously agreed in writing between the responsible authority and the floodplain management authority.

44.04-8 Decision guidelines

06/09/2021
VC171

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any local floodplain development plan.
- Any comments from the relevant floodplain management authority.
- The existing use and development of the land.
- Whether the proposed use or development could be located on flood-free land or land with a lesser flood hazard outside this overlay.
- Alternative design or flood proofing responses.
- The susceptibility of the development to flooding and flood damage.
- The potential flood risk to life, health and safety associated with the development. Flood risk factors to consider include:

  - The frequency, duration, extent, depth and velocity of flooding of the site and accessway.
  - The flood warning time available.
  - Tidal patterns.
  - Coastal inundation and erosion.
  - The danger to the occupants of the development, other floodplain residents and emergency personnel if the site or accessway is flooded.
- The effect of the development on redirecting or obstructing floodwater, stormwater or drainage water and the effect of the development on reducing flood storage and increasing flood levels and flow velocities.
- The effect of the development on river, marine and coastal health values including wetlands, natural habitat, stream stability, erosion, environmental flows, water quality, estuaries and sites of scientific significance.
- Any other matters specified in a schedule to this overlay.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 44.04 LAND SUBJECT TO INUNDATION OVERLAY

Shown on the planning scheme map as **LSIO**.

1.0 Land subject to inundation objectives to be achieved

08/07/2021
C211brim

None specified.

2.0 Statement of risk

08/07/2021
C211brim

None specified.

3.0 Permit requirement

08/07/2021
C211brim

None specified.

4.0 Application requirements

08/07/2021
C211brim

None specified.

5.0 Decision guidelines

08/07/2021
C211brim

None specified.

44.05 SPECIAL BUILDING OVERLAY

01/07/2021
VC203

Shown on the planning scheme map as **SBO** with a number (if shown).

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify land in urban areas liable to inundation by overland flows from the urban drainage system as determined by, or in consultation with, the floodplain management authority.

To ensure that development maintains the free passage and temporary storage of floodwaters, minimises flood damage, is compatible with the flood hazard and local drainage conditions and will not cause any significant rise in flood level or flow velocity.

To protect water quality and waterways as natural resources by managing urban stormwater, protecting water supply catchment areas, and managing saline discharges to minimise the risks to the environmental quality of water and groundwater.

44.05-1 Flooding management objectives and statement of risk

31/07/2018
VC148

A schedule to this overlay may contain:

- Flooding management objectives to be achieved.
- A statement of risk.

44.05-2 Buildings and works

14/12/2023
VC253

A permit is required to construct a building or to construct or carry out works, including:

- A fence.
- Roadworks, if the water flow path is redirected or obstructed.
- Bicycle pathways and trails.
- Public toilets.
- A domestic swimming pool or spa and associated mechanical and safety equipment if associated with one dwelling on a lot.
- A rainwater tank with a capacity of not more than 10,000 litres.
- A pergola or verandah, including an open-sided pergola or verandah to a dwelling or small second dwelling with a finished floor level not more than 800mm above ground level and a maximum building height of 3 metres above ground level.
- A deck, including a deck to a dwelling or small second dwelling with a finished floor level not more than 800mm above ground level.
- A disabled access ramp.

This does not apply:

- If a schedule to this overlay specifically states that a permit is not required.
- To roadworks or bicycle paths and trails constructed or carried out by or on behalf of the Head, Transport for Victoria, to the satisfaction of the relevant floodplain management authority.
- To flood mitigation works carried out by the responsible authority or floodplain management authority.
- To the following works in accordance with plans prepared to the satisfaction of the responsible authority:

  - The laying of underground sewerage, water and gas mains, oil pipelines, underground telephone lines and underground power lines provided they do not alter the topography of the land.
  - The erection of telephone or power lines provided they do not involve the construction of towers or poles designed to operate at more than 66,000 volts.

- To landscaping, driveways, vehicle cross overs, footpaths or bicycle paths if there is no significant change to existing surface levels, or if the relevant floodplain management authority has agreed in writing that the flowpath is not obstructed.
- To an extension of less than 20 square metres in floor area to an existing building (not including an out-building), where the floor levels are constructed to at least 300mm above the flood level or if the relevant floodplain management authority has agreed in writing that the flowpath is not obstructed.
- To an upper storey extension to an existing building.
- To an alteration to an existing building where the original building footprint remains the same and floor levels are constructed to at least 300mm above flood level.
- To an out-building (including replacement of an existing building) if the out-building is less than 10 square metres in floor area and constructed to at least 150mm above the flood level or the relevant floodplain management authority has agreed in writing that the flowpath is not obstructed.
- To a replacement building (not including an out-building) if it is constructed to at least 300mm above the flood level and the original building footprint remains the same. The responsible authority may require evidence of the existing building envelope.
- To fencing with at least 25% openings and with the plinth at least 300mm above the flood level.
- To a replacement fence in the same location and of the same type and materials as the existing fence.
- To a pergola or an open deck area with unenclosed foundations.
- To a carport constructed over an existing carspace.
- To an in-ground swimming pool and associated security fencing, where the perimeter edging of the pool is constructed at natural surface levels and excavated material is removed from the flowpath.
- To a tennis court at existing surface level with fencing designed to minimise obstruction to flows.
- To an aviary or other enclosure for a domestic animal if it is less than 10 square metres in floor area at ground level.
- To open sided verandahs, open sided picnic shelters, barbeques and park furniture (excluding playground equipment) if there is less than 30mm change to existing surface levels.
- To radio masts, light poles or signs on posts or attached to buildings.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct a building or construct or carry out works.	Clause 59.08

44.05-3 Subdivision

31/07/2018
VC148

A permit is required to subdivide land.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Any of the following classes of subdivision: ▪ Subdivide land to realign the common boundary between 2 lots where the area of either lot is reduced by less than 15 percent and the general direction of the common boundary does not change. ▪ Subdivide land into lots each containing an existing building or car parking space where: – The buildings or car parking spaces have been constructed in accordance with the provisions of this scheme or a permit issued under this scheme. – An occupancy permit or a certificate of final inspection has been issued under the Building Regulations in relation to the buildings within 5 years prior to the application for a permit for subdivision. ▪ Subdivide land into 2 lots if: – The construction of a building or the construction or carrying out of works on the land is approved under this scheme or by a permit issued under this scheme and the permit has not expired. – The construction or carrying out of the approved building or works on the land has started lawfully. – The subdivision does not create a vacant lot.	Clause 59.08

44.05-4 Application requirements

31/07/2018
VC148

Unless otherwise agreed in writing by the relevant floodplain management authority, an application to construct a building or construct or carry out works must be accompanied by a site plan which shows, as appropriate:

- The boundaries and dimensions of the site.
- Relevant existing and proposed ground levels, to Australian Height Datum, taken by or under the direction or supervision of a licensed land surveyor.
- The layout, size and use of existing and proposed buildings and works, including vehicle parking areas.
- Floor levels of any existing and proposed buildings to Australian Height Datum.
- Cross sectional details of any basement entry ramps and other basement entries to Australian Height Datum, showing floor levels of entry and exit areas and drainage details.
- Any other application requirements specified in a schedule to this overlay.

Local floodplain development plan

If a local floodplain development plan has been developed for the area and has been incorporated into this scheme, an application must be consistent with the plan.

44.05-5 Exemption from notice and review

31/07/2018
VC148

An application under this overlay is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

44.05-6 Referral of applications

31/07/2018
VC148

An application must be referred to the relevant floodplain management authority under Section 55 of the Act unless in the opinion of the responsible authority, the proposal satisfies requirements or conditions previously agreed to in writing between the responsible authority and the floodplain management authority.

44.05-7 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Any local floodplain development plan.
- Any comments from the relevant floodplain management authority.
- The existing use and development of the land.
- Whether the proposed use or development could be located on flood-free land or land with a lesser flood hazard outside this overlay.
- The susceptibility of the development to flooding and flood damage.
- Flood risk factors to consider include:
  - The frequency, duration, extent, depth and velocity of flooding of the site and accessway.
  - The flood warning time available.
  - The danger to the occupants of the development, other floodplain residents and emergency personnel if the site or accessway is flooded.
- The effect of the development on redirecting or obstructing floodwater, stormwater or drainage water and the effect of the development on reducing flood storage and increasing flood levels and flow velocities.
- Any other matters specified in a schedule to this overlay.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 44.05 SPECIAL BUILDING OVERLAY

Shown on the planning scheme map as **SBO.**

1.0 Flooding management objectives to be achieved

08/07/2021
C211brim

None specified.

2.0 Statement of risk

08/07/2021
C211brim

None specified.

3.0 Permit requirement

25/11/2022
GC207

None specified.

4.0 Application requirements

08/07/2021
C211brim

None specified.

5.0 Decision guidelines

08/07/2021
C211brim

None specified.

45 OTHER OVERLAYS

19/01/2006
VC37

45.01 PUBLIC ACQUISITION OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **PAO** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify land which is proposed to be acquired by a Minister, public authority or municipal council.

To reserve land for a public purpose and to ensure that changes to the use or development of the land do not prejudice the purpose for which the land is to be acquired.

To designate a Minister, public authority or municipal council as an acquiring authority for land reserved for a public purpose.

45.01-1 Permit required

14/12/2023
VC253

A permit is required to:

- Use land for any Section 1 or Section 2 use in the zone.
- Construct a building or construct or carry out works, including:
  - A domestic swimming pool or spa and associated mechanical and safety equipment if associated with one dwelling on a lot.
  - A pergola or verandah, including an open-sided pergola or verandah to a dwelling or a small second dwelling with a finished floor level not more than 800mm above ground level and a maximum building height of 3 metres above ground level.
  - A deck, including a deck to a dwelling or a small second dwelling with a finished floor level not more than 800mm above ground level.
- Damage, demolish or remove a building or works.
- Damage, remove, destroy or lop any vegetation. This does not apply:
  - If the vegetation has been planted for pasture, timber production or any other crop.
  - To any action which is necessary to keep the whole or any part of a tree clear of an electric line provided the action is carried out in accordance with a code of practice prepared under Section 86 of the *Electricity Safety Act 1998*.
  - If the vegetation presents an immediate risk of personal injury or damage to property.
- Subdivide land.

This does not apply:

- To the acquiring authority for the land if the land has been acquired and any of the above matters for which a permit is required is consistent with the purpose for which the land was acquired.
- To an authority or a municipal council if the responsible authority, after consulting with the acquiring authority for the land, is satisfied that any of the above matters for which a permit is required is consistent with the purpose for which the land is to be acquired.

45.01-2 Exemption from notice and review

31/07/2018
VC148

An application under this overlay is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

45.01-3 Referral of applications

28/10/2013
VC102

An application must be referred under Section 55 of the Act to the acquiring authority for the land.

45.01-4 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The effect of the proposed use or development on the purpose for which the land is to be acquired as specified in the schedule to this overlay.

A permit granted under this clause may be conditional on:

- The extent of alterations and extensions to an existing building and works, and the materials that may be used.
- The location, dimensions, design and material or a new building or works.
- The demolition, removal or alteration of any buildings or works.
- The demolition or removal of buildings or works constructed or carried out in accordance with a permit under this clause.
- No compensation being payable for the demolition or removal of any buildings or works constructed under the permit.

45.01-5 Land not to be spoiled or wasted

19/01/2006
VC37

Land must not be spoiled or wasted so as to adversely affect the use of the land for the purpose for which it is to be acquired.

45.01-6 Reservation for public purpose

19/01/2006
VC37

Any land included in a Public Acquisition Overlay is reserved for a public purpose within the meaning of the *Planning and Environment Act 1987*, the *Land Acquisition and Compensation Act 1986* or any other act.

45.01-7 Acquiring authority

28/10/2013
VC102

An acquiring authority is the Minister, public authority or municipal council specified in the schedule to this overlay as the acquiring authority for the land.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 45.01 PUBLIC ACQUISITION OVERLAY

1.0
25/11/2022
GC207

Public acquisition

PS map ref	Acquiring Authority	Purpose of acquisition
PAO1	Brimbank City Council	Park
PAO2	Brimbank City Council	Car park
PAO3	Brimbank City Council	Road
PAO4	Department of Infrastructure	Road
PAO5	Vic Roads	Road
PAO6	Department of Education	Education centre
PAO8	Brimbank City Council	Drainage Infrastructure
PAO9	Brimbank City Council	Sewerage & Road Infrastructure
PAO10	Melbourne Water Corporation	Retarding Basin
PAO11	Brimbank City Council	Sewerage & Water Infrastructure
PAO12	Roads Corporation	Outer Metropolitan Ring / E6 Transport Corridor
PAO13	Vic Roads	Transport

45.03 ENVIRONMENTAL AUDIT OVERLAY

01/07/2021
VC203

Shown on the planning scheme map as **EAO.**

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To ensure that potentially contaminated land is suitable for a use which could be significantly adversely affected by any contamination.

Application

This provision applies to land in an Environmental Audit Overlay and applies whether or not a permit is required.

45.03-1 Requirement

04/05/2022
VC210

Before a sensitive use (residential use, child care centre, kindergarten, pre-school centre, primary school, even if ancillary to another use), children's playground or secondary school commences or before the construction or carrying out of buildings and works in association with these uses commences:

- A preliminary risk screen assessment statement in accordance with the *Environment Protection Act 2017* must be issued stating that an environmental audit is not required for the use or the proposed use; or
- An environmental audit statement under Part 8.3 of the *Environment Protection Act 2017* must be issued stating that the land is suitable for the use or proposed use; or
- A certificate of environmental audit must be issued for the land in accordance with Part IXD of the Environment Protection Act 1970; or
- A statement of environmental audit must be issued for the land in accordance with Part IXD of the Environment Protection Act 1970 stating that the environmental conditions of the land are suitable for the use or proposed use.

Exemption from requirement

The requirement for a preliminary risk screen assessment statement, an environmental audit statement, a certificate of environmental audit or a statement of environmental audit in this provision does not apply to the construction or carrying out of buildings and works if:

- The buildings and works are associated with an existing sensitive use, secondary school or children’s playground, included in Clause 62.02-1 or 62.02-2, and the soil is not disturbed;
- The buildings and works are required by the Environment Protection Authority or an environmental auditor appointed under the *Environment Protection Act 2017* to make the site suitable for use; or
- The buildings and works are reasonably required by environmental auditor appointed under the *Environment Protection Act 2017* or the *Environment Protection Act 1970* to undertake a preliminary risk screen assessment or environmental audit.

45.04 ROAD CLOSURE OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **RXO**.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify a road that is closed by an amendment to this planning scheme.

45.04-1 Road closure

19/01/2006
VC37

A road included in this overlay is closed on the date notice of approval of the amendment is published in the Government Gazette.

45.04-2 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- That the road is closed.

45.06 DEVELOPMENT CONTRIBUTIONS PLAN OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **DCPO** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To identify areas which require the preparation of a development contributions plan for the purpose of levying contributions for the provision of works, services and facilities before development can commence.

45.06-1 Development contributions plan

19/01/2006
VC37

A permit must not be granted to subdivide land, construct a building or construct or carry out works until a development contributions plan has been incorporated into this scheme.

This does not apply to the construction of a building, the construction or carrying out of works or a subdivision specifically excluded by a schedule to this overlay.

A permit granted must:

- Be consistent with the provisions of the relevant development contributions plan.
- Include any conditions required to give effect to any contributions or levies imposed, conditions or requirements set out in the relevant schedule to this overlay.

45.06-2 Preparation of a development contributions plan

19/01/2006
VC37

The development contributions plan may consist of plans or other documents and may, with the agreement of the planning authority, be prepared and implemented in stages.

The development contributions plan must:

- Specify the area to which the plan applies.
- Set out the works, services and facilities to be funded through the plan, including the staging of the provision of those works, services and facilities.
- Relate the need for the works, services or facilities to the proposed development of land in the area.
- Specify the estimated costs of each of the works, services and facilities.
- Specify the proportion of the total estimated costs of the works, services and facilities which is to be funded by a development infrastructure levy or community infrastructure levy or both.
- Specify the land in the area and the types of development in respect of which a levy is payable and the method for determining the levy payable in respect of any development of land.
- Provide for the procedures for the collection of a development infrastructure levy in respect to any development for which a permit is not required.

The development contributions plan may:

- Exempt certain land or certain types of development from payment of a development infrastructure levy or community infrastructure levy or both.
- Provide for different rates or amounts of levy to be payable in respect of different types of development of land or different parts of the area.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 45.06 DEVELOPMENT CONTRIBUTIONS PLAN OVERLAY

Shown on the planning scheme map as **DCPO1.**

SUNSHINE DEVELOPMENT CONTRIBUTIONS PLAN

1.0 Area covered by this development contributions plan

10/12/2015
C105

This development contributions plan applies to all new development within the Sunshine Town Centre Structure Plan area as shown on the planning scheme maps as DCPO1.

2.0 Summary of costs

10/12/2015
C105

Facility	Total cost $	Time of provision	Actual cost contribution attributable to development $	Proportion of cost attributable to development %
Open space	1,183,564	2019	1,082,249	91.4
Kindergarten	3,762,800	2016	607,041	16.1
Road	3,009,499	2015-2034	1,686,743	56.1
Urban design	29,316,778	2015-2034	18,710,378	63.8
TOTAL	**37,272,641**		**22,086,412**	**59.3**

3.0 Summary of contributions

08/07/2021
C211brim

Facility	Levies Payable By The Development ($)				
	Development infrastructure		Community infrastructure	All infrastructure	
	residential per dwelling	non-residential per sqm		residential per dwelling	non-residential per sqm
Open space	370	Retail 0 Commercial 0	-	370	Retail 0 Commercial 0
Kindergarten	207	Retail 0 Commercial 0	-	207	Retail 0 Commercial 0
Road	159	Retail 8 Commercial 1	-	159	Retail 8 Commercial 1
Urban design	1831	Retail 26 Commercial 26	-	1831	Retail 26 Commercial 26
TOTAL	**2567**	**Retail 35 Commercial 27**	**-**	**2567**	**Retail 35 Commercial 27**

Notes: *Square metres of floorspace (sqm) refers to leaseable floorspace.*

The above listed contribution amounts are current as at 30 June 2013. They will be adjusted on 1 July each year to cover inflation, by applying the Consumer Price Index for Melbourne (All Groups) as published by the Australian Bureau of Statistics.

Payment of development contributions is to be made in cash. Council, at its discretion, may consider accepting works in lieu of cash contributions, provided the value of the works / land in question does not exceed the cash liability of the proponent under this development contributions plan (unless the proponent agrees).

Generally the permit condition will state that the contribution must be paid before any buildings or works authorised by the planning permit can commence. This accommodates situations whereby a planning permit might be issued but is not acted upon.

Where no planning permit is required for a development, the contribution must be made on the date of issue of a building permit under the Building Act 1993.

Payment of a development contribution required under this development contributions plan must be made for all development of the land that results in net additional demand units. New development is taken to include construction of a new building or an extension to an existing building.

For land uses not included within the planning scheme definition of the above uses, the development contribution that is required for 'commercial' will be applied unless council agrees to vary that rate, on submission by a permit applicant on the basis of information provided that justifies the application of an alternative rate.

Brimbank City Council is Collection Agency and Development Agency for this development contributions plan.

4.0 Land or development excluded from development contributions plan

15/01/2024
VC249

No land is exempt from this development contributions plan unless exempt by legislation or Ministerial Direction or legal agreement with Brimbank City Council.

Developments excluded from contributions under this plan are:

- The development of land for a small second dwelling.
- Development of social housing undertaken by a registered housing association or government agency.
- Construction of a building or construction or carrying out of works or subdivision by or on behalf of Brimbank City Council on council land.
- Construction of a building or construction or carrying out of works or subdivision by or on behalf of VicTrack on VicTrack land where the purpose of the works is for transport in accordance with Clause 36.04 Transport Zone.
- Construction of a building or construction or carrying out of works or a subdivision that does not result in the creation of net additional demand units, such as:
  - construction or display of a sign
  - construction of outbuilding, car port or garage associated with an existing dwelling
  - construction of an awning
  - installation of automatic teller machine, flue, grease trap or other similar equipment
  - external alterations, additions and restorations requiring approval under the Heritage Overlay
  - building and works associated with the refurbishment of an existing property that does not increase the number of dwellings or net leasable floor area of the premises
  - construction of a building or construction or carrying out of works to reinstate the pre-existing standard of buildings damaged or destroyed.

Note: *This schedule sets out a summary of the costs, timing of provision and contributions prescribed in the development contributions plan. Refer to the incorporated development contributions plan for full details.*

25/01/2018
C187

SCHEDULE 2 TO CLAUSE 45.06 DEVELOPMENT CONTRIBUTIONS PLAN OVERLAY

Shown on the planning scheme map as **DCPO2.**


BRIMBANK DEVELOPMENT CONTRIBUTIONS PLAN

1.0 Area covered by this development contributions plan

15/01/2024
VC249

The Brimbank Development Contributions Plan (*December 2023*) applies to all new development within the 19 Charge Areas as shown below in Map 1.

Map 1 to Schedule 2 to Clause 45.06 – DCP area and charging areas



2.0 Summary of costs

25/01/2018
C187

Facility	Total cost $	Time of provision	Actual cost contribution attributable to development $	Proportion of cost attributable to development %
Community Facility CFCI	$71,293,993	2016-2036	$8,414,388	11.8%
Community Facility CFDI	$8,800,000	2016-2036	$1,122,994	12.8%
Path PADI	$25,763,200	2016-2036	$4,220,166	16.4%
Road RDDI	$4,573,500	2016-2036	$849,365	18.6%
TOTAL	**$110,430,693**		**$14,606,913**	**13.2%**

Notes: *This table sets out a summary of the costs prescribed in the Development Contributions Plan. Refer to the incorporated document for full details.*

Brimbank City Council is Collection Agency and Development Agency for this DCP.

Brimbank City Council commits to delivering the DCP projects by December 31 2036, but may deliver projects earlier. It is likely that projects will be progressively delivered over the DCP period.

3.0 Summary of contributions

25/01/2018
C187

AREA		LEVIES PAYABLE BY RESIDENTAIL DEVELOPMENT		
Charge Area Number and Name		Development Infrastructure	Community infrastructure	All infrastructure
		Per Dwelling	Per Dwelling	Per Dwelling
Area 01	Sydenham - Hillside	$184.63	$722.71	$907.34
Area 02	Taylors Lakes (West) & District	$172.71	$722.71	$895.42
Area 03	Keilor - Taylors Lakes (East)	$121.18	$714.21	$835.39
Area 04	Delahey	$254.85	$864.88	$1,119.72
Area 05	Keilor Downs	$204.26	$847.94	$1,052.20
Area 06	Keilor Park & District	$92.52	$714.21	$806.73
Area 07	Kings Park	$170.96	$864.88	$1,035.84
Area 08	St Albans (West)	$527.74	$1,092.88	$1,620.61
Area 09	St Albans (East)	$495.26	$1,075.94	$1,571.20
Area 10	Kealba	$154.14	$847.94	$1,002.08
Area 11	Albanvale	$424.68	$864.88	$1,289.56
Area 12	Cairnlea	$453.06	$950.47	$1,403.54
Area 13	Deer Park	$552.91	$950.47	$1,503.38
Area 14	Ardeer	$254.66	$675.06	$929.72
Area 15	Albion	$232.64	$675.06	$907.70
Area 16	Sunshine North	$218.74	$653.88	$872.63
Area 17	Derrimut	$129.74	$714.21	$843.96
Area 18	Sunshine West	$362.10	$737.97	$1,100.07
Area 19	Sunshine	$341.39	$737.97	$1,079.36

AREA		LEVIES PAYABLE BY RETAIL DEVELOPMENT		
Charge Area Number and Name		Development Infrastructure Per Square Metre (SQM) of Floorspace	Community infrastructure Per Square Metre (SQM) of Floorspace	All infrastructure Per Square Metre (SQM) of Floorspace
Area 01	Sydenham - Hillside	$5.43	-	$5.43
Area 02	Taylors Lakes (West) & District	$4.53	-	$4.53
Area 03	Keilor - Taylors Lakes (East)	$2.23	-	$2.23
Area 04	Delahey	$5.20	-	$5.20
Area 05	Keilor Downs	$3.55	-	$3.55
Area 06	Keilor Park & District	$1.77	-	$1.77
Area 07	Kings Park	$1.93	-	$1.93
Area 08	St Albans (West)	$4.92	-	$4.92
Area 09	St Albans (East)	$4.83	-	$4.83
Area 10	Kealba	$2.72	-	$2.72
Area 11	Albanvale	$5.87	-	$5.87
Area 12	Cairnlea	$4.40	-	$4.40
Area 13	Deer Park	$6.17	-	$6.17
Area 14	Ardeer	$1.97	-	$1.97
Area 15	Albion	$1.84	-	$1.84
Area 16	Sunshine North	$4.78	-	$4.78
Area 17	Derrimut	$1.90	-	$1.90
Area 18	Sunshine West	$4.04	-	$4.04
Area 19	Sunshine	$3.98	-	$3.98

AREA		LEVIES PAYABLE BY COMMERCIAL DEVELOPMENT		
Charge Area Number and Name		Development Infrastructure Per Square Metre (SQM) of Floorspace	Community infrastructure Per Square Metre (SQM) of Floorspace	All infrastructure Per Square Metre (SQM) of Floorspace
Area 01	Sydenham - Hillside	$2.00	-	$2.00
Area 02	Taylors Lakes (West) & District	$1.99	-	$1.99
Area 03	Keilor - Taylors Lakes (East)	$1.95	-	$1.95
Area 04	Delahey	$3.75	-	$3.75
Area 05	Keilor Downs	$3.02	-	$3.02
Area 06	Keilor Park & District	$1.39	-	$1.39
Area 07	Kings Park	$2.71	-	$2.71
Area 08	St Albans (West)	$5.49	-	$5.49
Area 09	St Albans (East)	$5.03	-	$5.03
Area 10	Kealba	$2.60	-	$2.60
Area 11	Albanvale	$7.70	-	$7.70
Area 12	Cairnlea	$5.67	-	$5.67
Area 13	Deer Park	$8.11	-	$8.11
Area 14	Ardeer	$2.34	-	$2.34
Area 15	Albion	$1.84	-	$1.84
Area 16	Sunshine North	$3.77	-	$3.77
Area 17	Derrimut	$2.58	-	$2.58
Area 18	Sunshine West	$4.61	-	$4.61
Area 19	Sunshine	$4.13	-	$4.13

AREA		LEVIES PAYABLE BY INDUSTRIAL DEVELOPMENT		
Charge Area Number and Name		Development Infrastructure Per Square Metre (SQM) of Floorspace	Community infrastructure Per Square Metre (SQM) of Floorspace	All infrastructure Per Square Metre (SQM) of Floorspace
Area 01	Sydenham - Hillside	$0.48	-	$0.48
Area 02	Taylors Lakes (West) & District	$0.42	-	$0.42
Area 03	Keilor - Taylors Lakes (East)	$0.25	-	$0.25
Area 04	Delahey	$0.55	-	$0.55
Area 05	Keilor Downs	$0.40	-	$0.40
Area 06	Keilor Park & District	$0.19	-	$0.19
Area 07	Kings Park	$0.27	-	$0.27
Area 08	St Albans (West)	$0.62	-	$0.62
Area 09	St Albans (East)	$0.59	-	$0.59
Area 10	Kealba	$0.32	-	$0.32
Area 11	Albanvale	$0.80	-	$0.80
Area 12	Cairnlea	$0.59	-	$0.59
Area 13	Deer Park	$0.84	-	$0.84
Area 14	Ardeer	$0.25	-	$0.25
Area 15	Albion	$0.22	-	$0.22
Area 16	Sunshine North	$0.52	-	$0.52
Area 17	Derrimut	$0.26	-	$0.26
Area 18	Sunshine West	$0.51	-	$0.51
Area 19	Sunshine	$0.49	-	$0.49

Notes: *Square metres of floorspace (SQM) refers to gross floorspace.*

The above listed contribution amounts are current as at 30 June 2016. They will be adjusted annually on July 1 each year to cover inflation, by applying the Consumer Price Index for Melbourne (All Groups) as published by the Australian Bureau of Statistics. A list showing the current contribution amounts will be held at Council's Planning Department.

Payment of development contributions is to be made in cash. Council, at its discretion, may consider accepting works in lieu of cash contributions, provided the value of the works / land in question does not exceed the cash liability of the proponent under this DCP (unless the proponent agrees).

Payment of the Development Infrastructure Levy at Subdivision Stage is to be made prior to the issue of a statement of compliance for the approved subdivision. At Council's discretion, payment of the levy may be deferred to a later date, subject to the developer/land owner entering into an agreement under section 173 of the Planning and Environment Act 1987 to pay the levy at an alternative date agreed upon.

Payment of the Development Infrastructure Levy at Planning Permit Stage where there is no subdivision is to be made prior to the commencement of any development or works.

Payment of the Community Infrastructure Levy is to be made at the building permit stage, no later than the date of issue of a building permit under the Building Act 1993.

Where no permit is required for a development, the contribution must be made no later than the date of issue of a building permit under the Building Act 1993.

Payment of a development contribution required under this DCP must be made for all development of the land. New development is taken to include construction of a new dwelling or building or an extension to an existing retail building or commercial office building or industrial building, unless exempt from this DCP.

For land uses not included within the planning scheme definition of the above uses, the development contribution that is required for "commercial office" will be applied unless Council agrees to vary that rate, on submission by a permit applicant on the basis of information provided that justifies the application of an alternative rate.

4.0 Land or development excluded from development contributions plan

15/01/2024
VC249

No land or development is exempt from this development contributions plan unless exempt by legislation or Ministerial Direction or legal agreement with Brimbank City Council, or stated below:

- The development of land for a small second dwelling.

- Land developed for a non-government school as defined in Part 3 of the *Ministerial Direction on Development Contributions Plans* of 11 October 2016.
- Land developed for housing by or for the Department of Health and Human Services, as defined in *Ministerial Direction on Development Contributions Plans* of 11 October 2016.
- Land which has an existing section 173 Agreement under the *Planning and Environment Act 1987* and/or a Deed of Agreement which requires the payment of a contributions levy and/or construction of a community and/or physical infrastructure.
- Construction of a building or carrying out of works or a subdivision that does not result in the creation of new additional demand units, such as:
  - renovations or alterations to an existing dwelling.
  - construction of outbuildings normal to an existing dwelling.
  - construction of a fence.
  - demolition of a dwelling followed by construction of a replacement dwelling on the same land. This exemption applies to a single dwelling but not to a second or subsequent dwellings on the same land.
  - construction of a building or construction or carrying out of works to reinstate the pre-existing standard of a building other than a dwelling unintentionally damaged or destroyed. This exemption applies only to the extent that the floor area of the new building is not greater than that of the damaged or destroyed building.

Note: This schedule sets out a summary of the costs and contributions prescribed in the Brimbank Development Contributions Plan. Refer to the incorporated Brimbank Development Contributions Plan (December 2023) for full details.

45.08 MELBOURNE AIRPORT ENVIRONS OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **MAEO** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To ensure that land use and development are compatible with the operation of Melbourne Airport in accordance with the relevant airport strategy or master plan and with safe air navigation for aircraft approaching and departing the airfield.

To assist in shielding people from the impact of aircraft noise by requiring appropriate noise attenuation measures in dwellings and other noise sensitive buildings.

To provide for appropriate levels of noise attenuation depending on the level of forecasted noise exposure.

45.08-1 Use of land

14/05/2007
VC30

Any requirement in a schedule to this overlay must be met.

45.08-2 Buildings and works

26/11/2015
VC107

Any requirement in a schedule to this overlay must be met.

Any building for which a permit is required under this overlay must be constructed so as to comply with any noise attenuation measures required by Section 3 of Australian Standard AS 2021-2015, Acoustics - Aircraft Noise Intrusion - Building Siting and Construction, issued by Standards Australia Limited.

Note: In Section 3 of Australian Standard AS 2021-2015, Table 3.3 refers to both building types and activities within those buildings. Each building type listed has its ordinary meaning and should not be interpreted as defined in this scheme.

45.08-3 Subdivision

14/05/2007
VC30

A permit is required to subdivide land.

Subdivision must occur in accordance with any lot size or other requirement specified in a schedule to this overlay.

45.08-4 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- Whether the proposal will result in an increase in the number of dwellings and people affected by aircraft noise.
- Whether the proposal is compatible with the present and future operation of the airport in accordance with the current Melbourne Airport Master Plan approved in accordance with the *Airports Act 1996*.
- Location of the development in relation to the criteria set out in Table 2.1 Building Site Acceptability Based on ANEF Zones in Australian Standard AS 2021-2015.

45.08-5 Exemption from notice

31/07/2018
VC148

An application under this overlay is exempt from the notice requirements of section 52(1)(a), (b) and (d) of the Act.

45.08-6 Notification requirements

31/07/2018
VC148

In accordance with section 52(1)(c) of the Act, notice of an application under this overlay to use land, subdivide land or to construct a building or construct or carry out works must be given to the airport lessee company of Melbourne Airport in accordance with the Commonwealth *Airports Act 1996*, unless otherwise agreed in writing between the responsible authority and the airport lessee. The notice must be accompanied by a copy of the application, existing condition and development plans.

45.08-7 Transitional arrangements

26/10/2021
VC173

The requirements of Clause 45.08 do not apply to any development for which a building permit issued pursuant to the *Building Act 1993* prior to the date of commencement of Amendment VC173.

The requirements of the planning scheme as in force immediately before the date of commencement of Amendment VC173 continue to apply to a permit application made before that date.

This sub-clause does not apply 12 months after the date of commencement of Amendment VC173.

21/12/2023
C238brim

SCHEDULE 1 TO CLAUSE 45.08 MELBOURNE AIRPORT ENVIRONS OVERLAY

Shown on the planning scheme map as **MAEO1**.

Purpose

To identify areas that are or will be subject to high levels of aircraft noise based on the 25 Australian Noise Exposure Forecast (ANEF) contour and to restrict use and development to that which is appropriate to that level of exposure.

1.0 Use of land

21/12/2023
C238brim

Dwelling and Small second dwelling

A permit is required to use land for a:

- Dwelling.
- Small second dwelling

Land must not be used for:

- More than one Dwelling on a lot.
- More than one Small second dwelling on a lot. The Small second dwelling must be a moveable building and only used to provide accommodation for a person dependent on a resident of the existing dwelling.

Other use

A permit is required to use land for:

- Art and craft centre.
- Bar.
- Cinema based entertainment facility.
- Crematorium.
- Display home centre.
- Funeral parlour.
- Host farm.
- Hotel.
- Home based business.
- Indoor recreation facility.
- Office.
- Place of assembly (other than Drive-in theatre).
- Research and development centre.
- Research centre.
- Residential hotel.
- Restricted recreation facility.
- Retail premises.
- Veterinary centre.

Land must not be used for:

- Accommodation (other than Dwelling, Host farm, Residential hotel and Small second dwelling).

- Drive-in theatre.
- Education centre.
- Hospital.

2.0 Buildings and works

26/10/2021
VC173

A permit is required to construct a building or construct or carry out works for a use in Clause 1.0.

A permit is not required for the following:

- An open sided carport, verandah, pergola or other open sided structure.
- A non-habitable room or outbuilding.
- A swimming pool or tennis court.
- An alteration or extension to a dwelling which existed as at the date of commencement of Amendment VC173 provided:
  - The extension is less than 50 per cent of the floor area of the dwelling at that date.
  - The dwelling was not constructed between 14 May 2007 and the date of commencement of Amendment VC173 on land that was subject to this overlay during this period.

3.0 Subdivision

14/05/2007
VC30

Any subdivision of land which would increase the number of Dwellings which the land could be used for is prohibited. This does not apply to the subdivision of land to create a lot for a Dwelling in respect of which a permit has been granted.

21/12/2023
C238brim

SCHEDULE 2 TO CLAUSE 45.08 MELBOURNE AIRPORT ENVIRONS OVERLAY

Shown on the planning scheme map as **MAEO2**.

Purpose

To identify areas that are or will be subject to moderate levels of aircraft noise based on the 20-25 Australian Noise Exposure Forecast (ANEF) contours and to limit use and development to that which is appropriate to that level of exposure.

1.0 Use of land

21/12/2023
C238brim

Dwelling

A permit is required to use land for a Dwelling.

The development of a single lot for two or more Dwellings must not exceed a density of one Dwelling per 300 square metres.

Small second dwelling

A permit is required to use land for a Small second dwelling.

The development of a Dwelling and Small second dwelling on a single lot must be on a lot of at least 600 square metres.

Other use

A permit is required to use the land for:

- Accommodation.
- Arts and craft centre.
- Bar.
- Display home centre.
- Education centre.
- Hospital.
- Hotel.
- Office.
- Place of assembly.
- Research and development centre.
- Research centre.
- Restricted recreation facility.

2.0 Buildings and works

26/10/2021
VC173

A permit is required to construct a building or construct or carry out works for a use in Clause 1.0.

A permit is not required to construct the following:

- An open sided carport, verandah, pergola or other open sided structure.
- A non-habitable room or outbuilding.
- A swimming pool or tennis court.
- An alteration or extension to a dwelling which existed as at the date of commencement of Amendment VC173 provided:

- The extension is less than 50 per cent of the floor area of the dwelling at that date.
- The dwelling was not constructed between 14 May 2007 and the date of commencement of Amendment VC173 on land that was subject to this overlay during this period.

3.0 Subdivision

21/12/2023
C238brim

A permit is required to subdivide land.

Each lot must be at least 300 square metres.

A permit may be granted to create smaller lots:

- If the responsible authority is satisfied the lots will not be used for Accommodation; or
- Provided the average area of all lots is not less than 300 square metres. An agreement under Section 173 of the Act must be entered into with the owner of each lot created which ensures that the land may not be further subdivided.

The above lot size provisions do not apply to the subdivision of land in respect of which a permit was granted before the date of commencement of Amendment VC173 or in accordance with the transitional arrangements of VC173 in Clause 45.08-7 to allow the development of that land so long as the form of the subdivision is consistent with the permitted development.

45.09 PARKING OVERLAY

31/07/2018
VC148

Shown on the planning scheme map as **PO** with a number.

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To facilitate an appropriate provision of car parking spaces in an area.

To identify areas and uses where local car parking rates apply.

To identify areas where financial contributions are to be made for the provision of shared car parking.

45.09-1 Operation

19/04/2013
VC95

This overlay operates in conjunction with Clause 52.06.

A schedule to this overlay may:

- Vary the requirements of Clause 52.06 as allowed by this overlay.
- Specify additional requirements to the requirements of Clause 52.06 as allowed by this overlay.
- Specify requirements for the provision of a financial contribution as a way of meeting the car parking requirements of Clause 52.06 or this overlay.

45.09-2 Parking objectives

19/04/2013
VC95

A schedule to this overlay must specify the parking objectives to be achieved for the area affected by the schedule.

45.09-3 Permit requirement

25/05/2017
VC133

A schedule to this overlay may specify that:

- The exemption from the requirement for a permit in Clause 52.06-3 does not apply. If the exemption does not apply, a permit is required for any of the matters set out in Clause 52.06-3.
- A permit must not be granted to reduce (including reduce to zero) the number of car parking spaces required under Clause 52.06-5 or this overlay.
- A permit must not be granted to provide some or all of the car parking spaces required under Clause 52.06-5 or this overlay on another site.
- A permit must not be granted to provide more than the maximum parking provision specified in a schedule to this overlay.
- A permit is not required under Clause 52.06-3.

45.09-4 Number of car parking spaces required

19/04/2013
VC95

A schedule to this overlay may:

- Vary the car parking rate and measure for any use listed in Table 1 of Clause 52.06-5.
- Specify the car parking requirements for any use of land not listed in Table 1 of Clause 52.06-5.
- Specify maximum and minimum car parking requirements for any use of land.
- For any use listed in Table 1 of Clause 52.06-5, apply Column B in the Table to that use.

45.09-5 Application requirements and decision guidelines for permit applications

25/05/2017
VC133

Before deciding on an application under Clause 52.06-3, in addition to the relevant decision guidelines in Clause 52.06-7, the responsible authority must consider, as appropriate:

- The parking objectives of the relevant schedule to this overlay.
- Any application requirements and decision guidelines specified in a schedule to this overlay.

45.09-6 Financial contribution requirement

19/04/2013
VC95

A schedule to this overlay may allow a responsible authority to collect a financial contribution in accordance with the schedule as a way of meeting the car parking requirements that apply under this overlay or Clause 52.06.

A schedule must specify:

- The area to which the provisions allowing the collection of financial contributions applies.
- The amount of the contribution that may be collected in lieu of each car parking space that is not provided, including any indexation of that amount.
- When any contribution must be paid.
- The purposes for which the responsible authority must use the funds collected under the schedule. Such purposes must be consistent with the objectives in section 4 of the Act.

45.09-7 Requirements for a car parking plan

25/05/2017
VC133

A schedule to this overlay may specify additional matters that must be shown on plans prepared under Clause 52.06-8.

45.09-8 Design standards for car parking

25/05/2017
VC133

A schedule to this overlay may specify:

- Additional design standards.
- Other requirements for the design and management of car parking.

Plans prepared in accordance with Clause 52.06-8 must meet any design standards and requirements specified in a schedule to this overlay.

45.09-9 Decision guidelines for car parking plans

25/05/2017
VC133

Before deciding whether a plan prepared under Clause 52.06-8 is satisfactory, in addition to the decision guidelines in Clause 52.06-10, the responsible authority must consider, as appropriate, any other matter specified in a schedule to this overlay.

14/04/2023
C216brim

SCHEDULE 1 TO CLAUSE 45.09 PARKING OVERLAY

Shown on the planning scheme map as **PO1**.

SUNSHINE METROPOLITAN ACTIVITY CENTRE

1.0 Parking objectives to be achieved

14/04/2023
C216brim

To identify appropriate car parking rates for various land uses in the Sunshine Metropolitan Activity Centre which:

- support vehicle access for those who need it and prioritise the needs of people with special access requirements.
- support a shift to sustainable travel modes and minimise the environmental impact of cars and car parking facilities.
- discourage the oversupply of car parking by encouraging the use of existing supply before building more parking.

2.0 Permit requirement

14/04/2023
C216brim

A permit is required to reduce (including reduce to zero) the minimum number of car parking spaces required for a use as specified in this schedule.

3.0 Number of car parking spaces required

14/04/2023
C216brim

If a use is specified in the Table below, the number of car parking spaces required for the use is calculated by multiplying the *Rate* specified for the use by the accompanying *Measure*.

Table: Car parking spaces

Use	Rate	Measure
Dwelling	0.7 spaces	To each 1 bedroom dwelling
	0.9 spaces	To each 2 bedroom dwelling
	1.3 spaces	To each 3 bedroom dwelling
Office	2.0 spaces	To each 100 sqm of net floor area
Restricted retail	1.8 spaces	To each 100 sqm of leasable floor area
Restaurant	2.5 spaces	To each 100 sqm of leasable floor area
Shop (other than listed in this table)	2.5 spaces	To each 100 sqm of leasable floor area
Supermarket	3.5 spaces	To each 100 sqm of leasable floor area

For all other uses listed in Table 1 of Clause 52.06-5, the *Rate* in Column B of Table 1 in Clause 52.06-5 applies.

If in calculating the number of car parking spaces the result if not a whole number, the required number of car parking spaces is to be rounded down to the nearest whole number.

See 45.09-4 for relevant provisions.

4.0 Application requirements and decision guidelines for permit applications

14/04/2023
C216brim

The following application requirements apply to an application for a permit under Clause 45.09, in addition to those specified in Clause 45.09 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A transport assessment which considers the impacts of reducing parking below the minimum limit and the decision guidelines of this Schedule.
- A Green Travel Plan which includes a variety of transport demand management measures that reduces peoples' dependency on private vehicle trips.

The following decision guidelines apply to an application for a permit under Clause 45.09, in addition to those specified in Clause 45.09 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The transport assessment.
- Any empirical analysis which supports a variation in the number of car parking spaces that should be provided.
- The particular characteristics of the proposed use with regard to the likely car parking demands generated.
- For reductions in the rate of provision for commercial uses:
  - the availability of car parking in the locality and its suitability to accommodate parking generated by the development.
  - the likelihood of staff using active and public transport options rather than cars.
  - the parking restrictions in the area which remove opportunity for long-term parking for staff.
  - ensure land uses frequented by people with limited mobility, such as hospitals and medical centres, provide sufficient car parking spaces, including an appropriate proportion of disabled car spaces.
- For reductions in the rate of provision for residential uses:
  - the likelihood of residents using active and public transport options or car share rather than owning cars.
  - the parking restrictions in the area which remove opportunity for long-term on-street parking for new residents.
- Any effect on pedestrian, cycle and vehicle traffic in the area.
- The likely contribution of public transport and opportunities to walk and cycle in mitigating car parking demands, and whether appropriate provision can be made for use of sustainable transport to encourage mode shift from private vehicle travel.
- Whether a range of sustainable transport initiatives have been adopted including, but not limited to:
  - Provision of bicycle and 'end of trip' facilities in excess of those set out under Clause 52.34 and/or other clauses of the Brimbank Planning Scheme; and
  - Whether the development includes bicycle, electronic bicycle, cargo bicycle, motorcycle and car share parking
- Whether site size, access, design or other constraints warrant reducing the parking requirement.
- The impact on safety and convenience of pedestrians moving around the car parking facility.
- Whether a better urban design or heritage outcomes would be achieved through the lesser provision of parking.
- Whether the overall benefits of the development would outweigh the need to provide the full number of on-site parking spaces and make a more efficient use of the land.
- Whether historic contributions have been made towards the provision of car parking facilities.

See 45.09-5 for relevant provisions.

5.0 Financial contribution requirement

14/04/2023
C216brim

None specified.

6.0 Requirements for a car parking plan

14/04/2023
C216brim

The following requirements must be shown on a car parking plan, in addition to the matters that must be shown on plans prepared under Clause 52.06-8:

- Any spaces allocated to car share parking, motorcycle parking and bicycle parking.
- If a Green Travel Plan is provided under any provision of the Scheme, any relevant information specified in the Green Travel Plan.
- How car parking areas at the ground floor and above are designed to, or be capable of, facilitating the future adaptation to support alternate uses in the long term.
- How provisions have been made to allow for future vehicle charging.

7.0 Design standards for car parking

14/04/2023
C216brim

The following design standards for car parking and other requirements for the design and management of car parking must be met, in addition to the matters that must be shown on plans prepared under Clause 52.06-9:

- The design and provision of vehicle crossovers should:
  - Be limited to one per site frontage, other than on corner lots.
  - Avoid the removal of street trees.
  - Maximize pedestrian safety and site lines.
- The layout and design of car parking areas should make a positive contribution to the public realm, including maximising opportunities for active frontages and casual surveillance.

8.0 Decision guidelines for car parking plans

14/04/2023
C216brim

The following decision guidelines apply car parking plans under Clause 45.09, in addition to those specified in Clause 45.09 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the car parking plan encourages sustainable transport patterns that preference walking, cycling and public transport use (including adopting current design standards such as Australian Standard, Parking facilities Part 3: Bicycle parking facilities (AS2890.3-2015)).
- The extent to which the car parking areas are designed for future adaptation and repurposing.
- The extent to which car parking facilities (crossovers, accessways, garages and carports) are visible from the streetscape.

9.0 Background document

14/04/2023
C216brim

Sunshine Metropolitan Activity Centre Car Parking Plan (GTA now Stantec, July 2021)

14/04/2023
C216brim

SCHEDULE 2 TO CLAUSE 45.09 PARKING OVERLAY

Shown on the planning scheme map as **PO2**.

ST ALBANS MAJOR ACTIVITY CENTRE

1.0 Parking objectives to be achieved

14/04/2023
C216brim

To identify appropriate car parking rates for various land uses in the St Albans Major Activity Centre which:

- support vehicle access for those who need it and prioritise the needs of people with special access requirements.
- support a shift to sustainable travel modes and minimise the environmental impact of cars and car parking facilities.
- discourage the oversupply of car parking by encouraging the use of existing supply before building more parking.

2.0 Permit requirement

14/04/2023
C216brim

A permit is required to reduce (including reduce to zero) the minimum number of car parking spaces required for a use as specified in this schedule.

3.0 Number of car parking spaces required

14/04/2023
C216brim

If a use is specified in the Table below, the number of car parking spaces required for the use is calculated by multiplying the *Rate* specified for the use by the accompanying *Measure*.

Table: Car parking spaces

Use	Rate	Measure
Dwelling	0.7	To each 1 bedroom dwelling
	0.9	To each 2 bedroom dwelling
	1.3	To each 3 or more bedroom dwelling
Office	2.5	To each 100sqm of net floor area
Restricted retail	2.0	To each 100sqm of leasable floor area
Restaurant	3.0	To each 100sqm of leasable floor area
Shop (other than listed in this table)	3.0	To each 100sqm of leasable floor area
Supermarket	4.0	To each 100sqm of leasable floor area

For all other uses listed in Table 1 of Clause 52.06-5, the *Rate* in Column B of Table 1 in Clause 52.06-5 applies.

If in calculating the number of car parking spaces the result is not a whole number, the required number of car parking spaces is to be rounded down to the nearest whole number.

4.0 Application requirements and decision guidelines for permit applications

14/04/2023
C216brim

The following application requirements apply to an application for a permit under Clause 45.09, in addition to those specified in Clause 45.09 and elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- A transport assessment which considers the impacts of reducing parking below the minimum limit and the decision guidelines of this Schedule.
- A Green Travel Plan which includes a variety of transport demand management measures that reduces peoples' dependency on private vehicle trips.

The following decision guidelines apply to an application for a permit under Clause 45.09, in addition to those specified in Clause 45.09 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- The transport assessment.
- Any empirical analysis which supports a variation in the number of car parking spaces that should be provided.
- The particular characteristics of the proposed use with regard to the likely car parking demands generated.
- For reductions in the rate of provision for commercial uses:
  - the availability of car parking in the locality and its suitability to accommodate parking generated by the development.
  - the likelihood of staff using active and public transport options rather than cars.
  - the parking restrictions in the area which remove opportunity for long-term parking for staff.
  - ensure land uses frequented by people with limited mobility, such as hospitals and medical centres, provide sufficient car parking spaces, including an appropriate proportion of disabled car spaces.
- For reductions in the rate of provision for residential uses:
  - the likelihood of residents using active and public transport options or car share rather than owning cars.
  - the parking restrictions in the area which remove opportunity for long-term on-street parking for new residents.
- Any effect on pedestrian, cycle and vehicle traffic in the area.
- The likely contribution of public transport and opportunities to walk and cycle in mitigating car parking demands, and whether appropriate provision can be made for use of sustainable transport to encourage mode shift from private vehicle travel.
- Whether a range of sustainable transport initiatives have been adopted including, but not limited to:
  - Provision of bicycle and 'end of trip' facilities in excess of those set out under Clause 52.34 and/or other clauses of the Brimbank Planning Scheme; and
  - Whether the development includes bicycle, electronic bicycle, cargo bicycle, motorcycle and car share parking
- Whether site size, access, design or other constraints warrant reducing the parking requirement.
- The impact on safety and convenience of pedestrians moving around the car parking facility.
- Whether a better urban design or heritage outcomes would be achieved through the lesser provision of parking.
- Whether the overall benefits of the development would outweigh the need to provide the full number of on-site parking spaces and make a more efficient use of the land.
- Whether historic contributions have been made towards the provision of car parking facilities.

5.0 Financial contribution requirement

14/04/2023
C216brim

None specified.

6.0 Requirements for a car parking plan

14/04/2023
C216brim

The following requirements must be shown on a car parking plan, in addition to the matters that must be shown on plans prepared under Clause 52.06-8:

- Any spaces allocated to car share parking, motorcycle parking and bicycle parking.
- If a Green Travel Plan is provided under any provision of the Scheme, any relevant information specified in the Green Travel Plan.
- How car parking areas at the ground floor and above are designed to, or be capable of, facilitating the future adaptation to support alternate uses in the long term.
- How provisions have been made to allow for future vehicle charging.

7.0 Design standards for car parking

14/04/2023
C216brim

None specified.

8.0 Decision guidelines for car parking plans

14/04/2023
C216brim

The following decision guidelines apply car parking plans under Clause 45.09, in addition to those specified in Clause 45.09 and elsewhere in the scheme which must be considered, as appropriate, by the responsible authority:

- Whether the car parking plan encourages sustainable transport patterns that preference walking, cycling and public transport use (including adopting current design standards such as Australian Standard, Parking facilities Part 3: Bicycle parking facilities (AS2890.3-2015)).
- The extent to which the car parking areas are designed for future adaptation and repurposing.
- The extent to which car parking facilities (crossovers, accessways, garages and carports) are visible from the streetscape.

9.0 Background document

14/04/2023
C216brim

St Albans Major Activity Centre Car Parking Plan (GTA now Stantec, July 2021)

45.12 SPECIFIC CONTROLS OVERLAY

04/05/2022
VC210

Shown on the planning scheme map as **SCO** with a number.

Purpose

To apply specific controls designed to achieve a particular land use and development outcome in extraordinary circumstances.

45.12-1 Use or development

31/07/2018
VC148

Land affected by this overlay may be used or developed in accordance with a specific control contained in the incorporated document corresponding to the notation on the planning scheme map (as specified in the schedule to this overlay). The specific control may:

- Allow the land to be used or developed in a manner that would otherwise be prohibited or restricted.
- Prohibit or restrict the use or development of the land beyond the controls that may otherwise apply.
- Exclude any other control in this scheme.

45.12-2 Expiry of a specific control

31/07/2018
VC148

If a specific control contained in an incorporated document identified in the schedule to this clause allows a particular use or development, that control will expire if any of the following circumstances applies:

- The use and development is not started within two years of the approval date of the incorporated document or another date specified in the incorporated document.
- The development is not completed within one year of the date of commencement of works or another date specified in the incorporated document.

The responsible authority may extend the periods referred to if a request is made in writing before the expiry date or within three months afterwards.

Upon expiry of the specific control, the land may be used and developed only in accordance with the provisions of this scheme.

23/12/2020
GC176

SCHEDULE TO CLAUSE 45.12 SPECIFIC CONTROLS OVERLAY

1.0 Specific controls

23/12/2020
GC176

PS Map Ref	Name of incorporated document
SCO2	Mental Health Beds Expansion Program Incorporated Document, November 2020

50 PARTICULAR PROVISIONS

19/01/2006
VC37

This section sets out Particular Provisions which apply to the matters specified.

51 PROVISIONS THAT APPLY ONLY TO A SPECIFIED AREA

31/07/2018
VC148

51.01 SPECIFIC SITES AND EXCLUSIONS

31/07/2018
VC148

Purpose

To recognise specific controls designed to achieve a particular land use and development outcome existing on the approval date.

To provide in extraordinary circumstances specific controls designed to achieve a particular land use and development outcome.

51.01-1 Use or development

31/07/2018
VC148

Land identified in the schedule to this clause may be used or developed in accordance with the specific controls contained in the incorporated document corresponding to that land. The specific controls may:

- allow the land to be used or developed in a manner that would otherwise be prohibited or restricted;
- prohibit or restrict the use or development of the land beyond the controls that may otherwise apply;
- exclude any other control in this scheme.

51.01-2 Expiry of a specific control

31/07/2018
VC148

If a specific control contained in an incorporated document identified in the schedule to this clause allows a particular use or development, that control will expire if any of the following circumstances applies:

- The development and use is not started within two years of the approval date or another date specified in the incorporated document.
- The development is not completed within one year of the date of commencement of works or another date specified in the incorporated document.

The responsible authority may extend the periods referred to if a request is made in writing before the expiry date or within three months afterwards.

Upon expiry of the specific control, the land may be used and developed only in accordance with the provisions of this scheme.

11/10/2018
GC96

SCHEDULE TO CLAUSE 51.01 SPECIFIC SITES AND EXCLUSIONS

1.0

12/08/2021
C210brim

Specific sites and exclusions

Address of land	Title of incorporated document
Land on the south side of Stenson Road, Kealba, generally north of the 55 metre contour described as Crown Allotment 6 and 7, Section A, Parish of Maribyrnong and Part Lot 7, LP220103, Malcolm Court, Kealba.	Stenson Road Subdivision – 22 June 1999.
Land required for the Palmers Road and Robinsons Road upgrade as identified in clause 3 of the incorporated document.	Palmers Road and Robinsons Road Upgrade (Sayers Road to Western Freeway, Truganina) Incorporated Document, July 2012.
Land required for the Water for a Growing West Project as shown on the project plans included in the Incorporated Document.	Water for a Growing West Project Incorporated Document, July 2014.
Land required for the Main Road, St Albans Level Crossing Removal Project.	Main Road, St Albans Level Crossing Removal Project Incorporated Document, May 2014.
Land required for the Furlong Road, St Albans Level Crossing Removal Project as shown on the project area maps in the incorporated document.	Furlong Road, St Albans Level Crossing Removal Project Incorporated Document, August 2015.
Land required for the Melton Highway, Sydenham Level Crossing Removal Project as shown on the project area maps in the incorporated document.	Melton Highway, Sydenham Level Crossing Removal Project, Incorporated Document, October 2016.
Land identified in clause 3 of the Palmers Road Upgrade Project (Western Freeway to Calder Freeway) Incorporated Document, June 2017.	Palmers Road Upgrade Project (Western Freeway to Calder Freeway) Incorporated Document, June 2017.
Land required for the Outer Suburban Arterial Roads Program – Western Package as shown on the project area maps in the incorporated document.	Outer Suburban Arterial Roads - Western Package Incorporated Document, June 2017.
The land identified in clause 3 of the West Gate Tunnel Project Incorporated Document, December 2017.	West Gate Tunnel Project Incorporated Document, December 2017.
The land identified in Clause 3.0 of the Melbourne Metro Rail Project: Upgrades to the Rail Network Incorporated Document, May 2018.	Melbourne Metro Rail Project: Upgrades to the Rail Network Incorporated Document, May 2018.

51.02 METROPOLITAN GREEN WEDGE LAND: CORE PLANNING PROVISIONS

31/07/2018
VC148

Purpose

To protect metropolitan green wedge land from uses and development that would diminish its agricultural, environmental, cultural heritage, conservation, landscape natural resource or recreation values.

To protect productive agricultural land from incompatible uses and development.

To ensure that the scale of use is compatible with the non-urban character of metropolitan green wedge land.

To encourage the location of urban activities in urban areas.

To provide transitional arrangements for permit applications made to the responsible authority before 19 May 2004.

To provide deeming provisions for metropolitan green wedge land.

51.02-1 Application

25/02/2025
VC257

These provisions apply to land in Metropolitan Melbourne that is outside an Urban Growth Boundary as shown on a planning scheme map in this scheme, unless any of the following apply:

- The land is in a Neighbourhood Residential Zone, General Residential Zone, Residential Growth Zone, Housing Choice and Transport Zone, Low Density Residential Zone, Mixed Use Zone, Township Zone, Industrial 1 Zone, Industrial 2 Zone, Industrial 3 Zone, Commercial 1 Zone, Commercial 2 Zone, Commercial 3 Zone, Public Use Zone, Public Park and Recreation Zone, Public Conservation and Resource Zone, Transport Zone or Urban Floodway Zone.
- The land is identified in the schedule to this clause.

51.02-2 Use of land

01/01/2024
VC250

A use listed in the table to this clause is prohibited. This does not apply if a condition opposite the use is met.

Table to Clause 51.02-2

Use	Condition
Accommodation (other than Camping and caravan park, Dwelling, Group accommodation, Host farm, Residential building and Small second dwelling)	
Cinema based entertainment facility	
Display home centre	
Dwelling	Must be the only dwelling on the lot. This does not apply to the replacement of an existing dwelling if the existing dwelling is removed or altered (so it can no longer be used as a dwelling) within one month of the occupation of the replacement dwelling.
Education centre (other than Primary school and Secondary school)	
Freeway service centre	

Use	Condition
Freezing and cool storage	The goods stored must be agricultural produce, or products used in agriculture.
Function centre	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. No more than 150 patrons may be present at any time. If used in conjunction with Restaurant, the total number of patrons present at any time must not exceed 150.
Funeral parlour	
Group accommodation	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. Must be no more than 40 dwellings.
Hospital	
Indoor recreation facility	Must be for equestrian based leisure, recreation or sport.
Industry (other than Materials recycling, Refuse disposal, Transfer station, Research and development centre, and Rural industry)	
Major sports and recreation facility	Must be for outdoor leisure, recreation or sport.
Manufacturing sales	Must be an incidental part of Rural industry.
Materials recycling	Must be used in conjunction with Refuse disposal or Transfer station.
Motor racing track **Nightclub** **Office**	
Place of assembly (other than Carnival, Cinema based entertainment facility, Circus, Exhibition centre, Function centre, Hall, Nightclub, Place of worship and Restricted place of assembly)	Must not be used for more than 10 days in a calendar year.
Research and development centre	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery.
Research centre	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery.

Use	Condition
Residential building (other than Residential hotel)	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. Must be used to provide accommodation for persons away from their normal place of residence.
Residential hotel	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. Must be no more than 80 bedrooms.
Restaurant	Must be used in conjunction with Agriculture, Natural systems, Outdoor recreation facility, Rural industry or Winery. No more than 150 patrons may be present at any time. If used in conjunction with Function centre, the total number of patrons present at any time must not exceed 150.
Restricted place of assembly	Must not be used for more than 30 days in a calendar year.
Retail premises (other than Manufacturing sales, Market, Plant nursery, Primary produce sales and Restaurant) **Service station**	
Small second dwelling	Must be no more than one dwelling existing on the lot. Must be the only small second dwelling on the lot. Reticulated natural gas must not be supplied to the building, or part of a building, used for the small second dwelling.
Warehouse (other than Freezing and cool storage, Milk depot, Rural store, Solid fuel depot and Vehicle store)	
Wind energy facility	Must not be on land in a Rural Conservation Zone.

51.02-3 Subdivision

31/07/2018
VC148

The subdivision of land to create a lot that is smaller in area than the minimum area specified for the land in the zone is prohibited unless:

- The subdivision is the re-subdivision of existing lots, the number of lots is not increased, and the number of dwellings that the land could be used for does not increase.
- The subdivision is by a public authority or utility service provider to create a lot for a utility installation.

51.02-4 Existing uses

31/07/2018
VC148

If an existing use right is established by these provisions, Clauses 63.05 and 63.08 apply to the use as if the use were in Section 3 of a zone.

51.02-5 Transitional arrangements for permit applications

31/07/2018
VC148

The requirements of the planning scheme as in force immediately before 19 May 2004, continue to apply to a permit application made before that date to the extent that, but for this clause, Clauses 35.04, 35.05, 35.06 or this clause would apply to such an application. This does not apply to a permit application to subdivide land.

51.02-6 Deeming provisions for land outside an urban growth boundary

31/07/2018
VC148

Any reference in this planning scheme to a Rural Zone or a schedule to a Rural Zone as it applies to land outside an Urban Growth Boundary is deemed to be a reference to a Green Wedge Zone or a schedule to a Green Wedge Zone.

Any reference in this planning scheme to a Rural Living Zone or a schedule to a Rural Living Zone as it applies to land outside an Urban Growth Boundary is deemed to be a reference to a Green Wedge A Zone or a schedule to a Green Wedge A Zone.

Any reference in this planning scheme to an Environmental Rural Zone or a schedule to an Environmental Rural Zone as it applies to land outside an Urban Growth Boundary is deemed to be a reference to a Rural Conservation Zone or a schedule to a Rural Conservation Zone.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 51.02 METROPOLITAN GREEN WEDGE LAND: CORE PLANNING PROVISIONS

1.0 Land where core planning provisions apply

08/07/2021
C211brim

Land
Special Use Zone 1, Calder Raceway between Calder Freeway and the Melbourne to Bendigo Railway Line, Calder Park
Special Use Zone 5, Overnewton Anglican College Keilor Campus, 2 – 30 Overnewton Road, Keilor.
Special Use Zone 6, Lowther Hall Anglican Grammar School, Keilor Campus, 32-50 Overnewton Road, Keilor.

51.04 MELBOURNE AIRPORT ENVIRONS STRATEGY PLAN

31/07/2018
VC148

Scope

To ensure consistency between this planning scheme and the Melbourne Airport Environs Strategy Plan pursuant to the requirements of Part 3C of the *Planning and Environment Act 1987*.

52 PROVISIONS THAT REQUIRE, ENABLE OR EXEMPT A PERMIT

31/07/2018
VC148

52.01 COMBUSTIBLE CLADDING RECTIFICATION EXEMPTIONS

05/11/2020
VC191

Purpose

To facilitate the rectification of combustible cladding on buildings.

52.01-1 Permit exemption

05/11/2020
VC191

Any requirement of this planning scheme to obtain a permit does not apply to the rectification of combustible cladding on a building:

- In accordance with an emergency order, building notice or building order made under Part 8 of the *Building Act 1993*.
- Owned by the Crown, a Minister, municipal council or public authority, including a public authority established for a public purpose under a Commonwealth Act.

52.01-2 Exemption from notice and review

05/11/2020
VC191

An application to amend a permit to allow the rectification of combustible cladding on a building:

- In accordance with an emergency order, building notice or building order made under Part 8 of the *Building Act 1993*; or
- Owned by the Crown, a Minister, municipal council or public authority, including a public authority established for a public purpose under a Commonwealth Act,

is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

52.02 EASEMENTS, RESTRICTIONS AND RESERVES

20/09/2010
VC71

Purpose

To enable the removal and variation of an easement or restrictions to enable a use or development that complies with the planning scheme after the interests of affected people are considered.

Permit requirement

A permit is required before a person proceeds:

- Under Section 23 of the *Subdivision Act 1988* to create, vary or remove an easement or restriction or vary or remove a condition in the nature of an easement in a Crown grant.
- Under Section 24A of the *Subdivision Act 1988*.
- Under Section 36 of the *Subdivision Act 1988* to acquire or remove an easement or remove a right of way.

This does not apply:

- If the action is required or authorised by the schedule to this clause.
- In the circumstances set out in Section 6A(3) of the *Planning and Environment Act 1987*.
- If the person proceeds under Section 362A of the *Land Act 1958*.
- In the case of a person proceeding under Section 36 of the *Subdivision Act 1988*, if the council or a referral authority gives a written statement in accordance with Section 36(1)(a) or (b) of the *Subdivision Act 1988*.

In this clause, **restriction** has the same meaning as in the *Subdivision Act 1988*.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in clause 65, the responsible authority must consider the interests of affected people.

Note: Section 23 of the Subdivision Act 1988 provides that either the council or the person benefiting from the direction must lodge a certified plan at the Titles Office for registration.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 52.02 EASEMENTS, RESTRICTIONS AND RESERVES

1.0

09/11/2006
C91

Under Section 23 of the Subdivision Act 1988

Land	Easement or restriction	Requirement
20 Darlington Grove, Sydenham, previously described as Lot 40 on Plan of Subdivision 215996M but now described as part of the land in Plan of Consolidation 367994P.	Restrictive Covenant contained in Instrument of Transfer No. R316716N.	Vary the restrictive covenant by inserting the following after the covenant: '…except that Lot 40 on LP215996M may be developed and used for a nursing home generally in accordance with Permit No. P685/2005.

2.0

19/01/2017
GC51

Under Section 24A of the Subdivision Act 1988

Land	Person	Action
18-24 Robertsons Road and 16-28 McCubbin Drive, Taylors Lakes.	The person or body in whom or in which the land is vested.	Remove the reservations from the land on PS316588 and PS342427.

3.0

09/11/2006
C91

Under Section 36 of the Subdivision Act 1988

Land	Easement or right of way	Requirement
None specified.		

52.03 LEVEL CROSSING REMOVAL PROJECT

31/01/2020
VC170

Purpose

To facilitate the Level Crossing Removal Project.

52.03-1 Application

31/01/2020
VC170

This clause applies to the use and development of land (other than the subdivision of land) for projects undertaken by the Level Crossing Removal Project and declared under section 10(1)(b) of the *Major Transport Projects Facilitation Act 2009*.

This clause does not apply to a project for which a document has been incorporated into this planning scheme expressly for that project.

52.03-2 Exemption from planning scheme requirements

31/01/2020
VC170

Any requirement of this planning scheme to obtain a permit or any provision of this planning scheme that prohibits the use or development of land, requires the use or development of land to be carried out in a particular manner, or requires a specified thing to be done to the satisfaction of a specified person or body, does not apply to any use or development this Clause 52.03 applies to if the requirements of Clause 52.03 are met.

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

52.03-3 Use and development requirements

20/01/2022
VC205

The use and development of land must be undertaken in accordance with the plans and documents approved under this clause, to the satisfaction of the Minister for Planning.

The construction of a building or the construction or carrying out of works in a Floodway Overlay, Land Subject to Inundation Overlay, Special Building Overlay or Urban Floodway Zone must be undertaken to the satisfaction of the relevant floodplain management authority.

The creation or alteration of access to a road in a Transport Zone 2 or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority and the purpose of acquisition is for a road, must be undertaken to the satisfaction of the Head, Transport for Victoria.

The use and development of land in a Public Acquisition Overlay must be undertaken to the satisfaction of the relevant acquiring authority.

52.03-4 Consultation requirement

31/01/2020
VC170

Prior to the commencement of the use or development:

- Public consultation, and consultation with the relevant municipal council, must be undertaken to the satisfaction of the Minister for Planning.
- A report that summarises the feedback provided during consultation and explains how the feedback has been considered and responded to must be prepared to the satisfaction of the Minister for Planning.

52.03-5 Project boundary requirement

31/01/2020
VC170

Prior to the commencement of the use or development, a plan that shows the boundary of the land on which the use or development will be undertaken must be prepared to the satisfaction of the Minister for Planning.

52.03-6 Other pre-commencement requirements

04/05/2022
VC210

The following requirements may be satisfied for separate components or stages of a project but each requirement must be satisfied prior to the commencement of the use or development for that component or stage.

The following requirements may be varied or waived by the Minister for Planning.

Prior to the commencement of the use or development (other than a preparatory use or development), the following plans and documents must be prepared to the satisfaction of the Minister for Planning:

- An environmental management framework, prepared in consultation with each relevant municipal council, that includes:
  - A summary of key construction methodologies.
  - An overarching framework of measures to reduce and manage environmental and amenity effects during construction.
  - A summary of performance monitoring and reporting processes, including auditing, to ensure environmental and amenity effects are reduced and managed during construction.
  - A summary of how each relevant municipal council, the community and other stakeholders will be engaged during construction, including enquiries and complaints management.

  The environmental management framework must be accompanied by a summary of the consultation with each relevant municipal council that informed the preparation of the environmental management framework.
- If the land is in the Heritage Overlay and the development would require a permit under the overlay were it not for the exemption in Clause 52.03-2:
  - A report that addresses the impact of that development on the heritage significance of the heritage place.
  - Site plans and elevations showing the extent of that development on the land.
  - Photographs of any buildings or works to be demolished or removed, including photographs of the exterior and interior of the building and contextual images of the building's environs and setting.
- If the land is in an Environmental Significance Overlay, a Significant Landscape Overlay or a Vegetation Protection Overlay and the development would require a permit under the overlay were it not for the exemption in Clause 52.03-2, a report that addresses the impact of the development on any environmental, vegetation or landscape significance or objective specified in a schedule to the overlay.
- Any other information the Minister for Planning considers necessary to assist the Minister's assessment of the plans and documents required to be submitted under this clause.

Prior to the commencement of the use of any new open space, an environmental assessment (or similar) that demonstrates that the environmental conditions of the land are suitable for that use must be undertaken to the satisfaction of the Minister for Planning.

52.03-7 Native vegetation requirements

20/03/2023
VC229

In this clause:

- ***Guidelines*** *means the Guidelines for removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, December 2017);
- ***Secretary*** means the Secretary to the Department of Environment, Land, Water and Planning *(as constituted under Part 2 of the Conservation, Forests and Lands Act 1987)*.

The following requirements may be satisfied for separate components or stages of a project. However, each requirement must be satisfied prior to the removal, destruction or lopping of native vegetation for that component or stage.

Prior to the removal, destruction or lopping of native vegetation to enable a preparatory use or development, information about that native vegetation must be submitted to the Secretary. The information must include a description of, and maps showing, the native vegetation to be removed, destroyed or lopped in accordance with application requirement 1 in Table 4 of the Guidelines.

Prior to the removal, destruction or lopping of native vegetation (other than to enable a preparatory use or development):

- Information about that native vegetation in accordance with application requirements 1, 5 and 9 in Table 4 of the Guidelines must be provided to the satisfaction of the Secretary. The information provided to the Secretary must include information about any native vegetation that has been or is to be removed, destroyed or lopped to enable a preparatory use or development.
- The biodiversity impacts from the removal, destruction or lopping of that native vegetation must be offset in accordance with the Guidelines. The biodiversity impacts from the removal, destruction or lopping of native vegetation to enable a preparatory use or development must be included in the total biodiversity impacts when determining the offset.
- Evidence that the required offset has been secured must be provided to the satisfaction of the Secretary.

The Secretary may vary the timing of the above offset requirement if the Secretary considers there are exceptional circumstances to warrant the variation.

The secured offset for the project may be reconciled at the completion of a project in accordance with the *Assessor's handbook – Applications to remove, destroy or lop native vegetation* (Department of Environment, Land, Water and Planning, October 2018).

52.03-8 Preparatory use and development

31/01/2020
VC170

For the purposes of Clause 52.03, a preparatory use or development is a use or development required to prepare for the construction of a project. It is limited to the following:

- Use and development that would not require a permit under a provision of this planning scheme were it not for the exemption in Clause 52.03-2.
- Works associated with investigating, testing and surveying land.
- Creation and use of construction access points, accessways and working platforms.
- Site establishment works including construction of temporary site fencing and hoarding, site offices, and hardstand and laydown areas.
- Construction and use of temporary car parking.
- Construction or installation of environment and traffic controls.
- Construction, protection, modification, removal or relocation of utility services, rail signalling, and overhead and associated infrastructure.
- Salvage and relocation of cultural heritage material and other management actions required to be undertaken in compliance with:
  - a cultural heritage management plan approved under the *Aboriginal Heritage Act 2006* or otherwise in compliance with that Act; or
  - the conditions of any permit or consent granted under the *Heritage Act 2017* or otherwise in compliance with that Act.

- Demolition or removal of a building (other than a building in a Heritage Overlay) or works to the minimum extent necessary to enable another preparatory use or development.
- Removal, destruction or lopping of vegetation (other than a tree in the Heritage Overlay specified below) to the minimum extent necessary to enable another preparatory use or development.

For the purposes of Clause 52.03, preparatory development does not include:

- Demolition or removal of a building in a Heritage Overlay.
- Removal, destruction or lopping of a tree in a Heritage Overlay if the schedule to the overlay specifies the heritage place as one where tree controls apply.

52.04 TRANSITIONAL PROVISIONS FOR A DEPENDENT PERSONS UNIT

14/12/2023
VC253

52.04-1 Purpose

28/03/2024
VC259

To provide transitional provisions for the use or development of land for a dependent person's unit.

52.04-2 Application

28/03/2024
VC259

This clause applies to the use and development of land for a dependent person's unit.

For the purposes of clause 52.04 and any reference to a dependent person's unit in this planning scheme, a dependent person's unit means:

A movable building on the same lot as an existing dwelling and used to provide accommodation for a person dependent on a resident of the existing dwelling.

52.04-3 Exemption from planning scheme requirements

28/03/2024
VC259

Any requirement of this planning scheme to obtain a permit for the use of land or the construction or carrying out of buildings and works, or any provision of this planning scheme that prohibits the use of land or the construction or carrying out of buildings and works, requires the use of land or the construction or carrying out of buildings and works to be carried out in a particular manner, or requires a specified thing to be done to the satisfaction of a specified person or body, does not apply to a dependent person's unit, if the requirements of clause 52.04 are met.

The requirements of clause 52.04 are met if any of the following apply:

- No permit is required under this clause, and any requirement or condition of this clause is met.
- A permit is required under this clause, and a permit has been issued.

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

52.04-4 Operation of use of land requirements

03/03/2025
VC266

The following requirements apply to the use of land for a dependent person's unit, as specified in clause 52.04-5.

Table 1 zones

The use of land for a dependent person's unit in a zone listed in Table 1 does not require a permit. Any condition opposite the zone listed in Table 1 must be met. If the condition is not met, the use of land for a dependent person's unit requires a permit under this clause unless the zone is specifically included in Table 3 as a zone that does not meet the Table 1 condition.

Table 2 zones

The use of land for a dependent person's unit in a zone listed in Table 2 requires a permit under this clause. Any condition opposite the zone must be met. If the condition is not met, the use of land for a dependent person's unit is prohibited.

Table 3 zones

The use of land for a dependent person's unit in a zone listed in Table 3 is prohibited.

52.04-5 Use of land requirements

25/02/2025
VC257

Table 1 - Permit not required

Zone	Condition
Low Density Residential Zone	Must be the only dependent person's unit on the lot.
Township Zone	Must meet the requirements of clause 52.04-7.
Mixed Use Zone **Residential Growth Zone** **General Residential Zone** **Neighbourhood Residential Zone** **Housing Choice and Transport Zone**	Must be the only dependent person's unit on the lot.
Rural Living Zone	Must be the only dependent person's unit on the lot.
Rural Activity Zone	Must meet the requirements of clause 52.04-8. Must be located more than 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.
Farming Zone	Must be the only dependent person's unit on the lot. Must meet the requirements of clause 52.04-8. Must be located more than one kilometre from the nearest title boundary of land subject to: ▪ A permit for a wind energy facility; or ▪ An application for a permit for a wind energy facility; or ▪ An incorporated document approving a wind energy facility; or ▪ A proposed wind energy facility for which an action has been taken under section 8(1), 8(2), 8(3) or 8(4) of the *Environment Effects Act 1978*. Must be located more than 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.
Commercial 1 Zone	Any frontage at ground floor level must not exceed 2 metres
Public Use Zone	The use must be for the purpose described in the table to clause 36.01-6 which corresponds to the notation on the planning scheme map. The use must be carried out by or on behalf of the public land manager.
Public Park and Recreation Zone	Must be either of the following:

Zone	Condition
	▪ A use conducted by or on behalf of a public land manager, Parks Victoria or the Great Ocean Road Coast and Parks Authority, under the relevant provisions of the *Local Government Act 2020*, the *Reference Areas Act 1978*, the *National Parks Act 1975*, the *Fisheries Act 1995*, the *Wildlife Act 1975*, the *Forest Act 1958*, the *Water Industry Act 1994*, the *Water Act 1989*, the *Marine Safety Act 2010*, the *Port Management Act 1995*, or the *Crown Land (Reserves) Act 1978*. ▪ A use specified in an Incorporated plan in a schedule to clause 36.02.
Public Conservation and Resource Zone	Must be a use conducted by or on behalf of a public land manager, Parks Victoria or the Great Ocean Road Coast and Parks Authority, under the relevant provisions of the *Local Government Act 2020*, the *Reference Areas Act 1978*, the *National Parks Act 1975*, the *Fisheries Act 1995*, the *Wildlife Act 1975*, the *Forests Act 1958*, the *Water Industry Act 1994*, the *Water Act 1989*, the *Marine Safety Act 2010*, the *Port Management Act 1995* or the *Crown Land (Reserves) Act 1978*.
Urban Growth Zone	Must be the only dependent person's unit on the lot. Must meet the requirements of clause 52.04-8.

Table 2 - Permit required

Zone	Condition
Low Density Residential Zone **Township Zone**	Must meet the requirements of clause 52.04-7.
Green Wedge Zone **Green Wedge A Zone** **Rural Conservation Zone**	Must be the only dependent person's unit on the lot. Must meet the requirements of clause 52.04-8.
Rural Living Zone **Farming Zone** **Rural Activity Zone**	Must meet the requirements of clause 52.04-8.
Transport Zone	The use must be for a transport purpose and carried out by or on behalf of a relevant transport manager.
Urban Growth Zone	Must meet the requirements of clause 52.04-8.

Table 3 - Prohibited

Zone
Industrial 1 Zone
Industrial 2 Zone
Industrial 3 Zone
Commercial 2 Zone
Commercial 3 Zone
Port Zone
Public Conservation and Resource Zone – If the table 1 condition is not met
Urban Floodway Zone

52.04-6 Use of land requirements in a specified special purpose zone

28/02/2025
VC274

If land is in a Special Use Zone, Comprehensive Development Zone, Capital City Zone, Docklands Zone, Priority Development Zone, Activity Centre Zone or Precinct Zone, the permit requirement in that zone for use of land applies as specified in the schedule to the zone.

If dependent person's unit is not specified in a schedule to the zone, the use of land for a dependent person's unit is subject to the use of land requirements for 'Accommodation'.

52.04-7 Use of land requirements in a Low Density Residential Zone and a Township Zone

28/03/2024
VC259

A lot used for a dependent person's unit in a Low Density Residential Zone and a Township Zone must meet the following requirements:

- Each dependent person's unit must be connected to reticulated sewerage, if available. If reticulated sewerage is not available, all wastewater from each dependent person's unit must be treated and retained within the lot in accordance with the requirements in the Environment Protection Regulations under the *Environment Protection Act 2017* for an on-site wastewater management system.
- Each dependent person's unit must be connected to a reticulated potable water supply or have an alternative potable water supply, with appropriate storage capacity.
- Each dependent person's unit must be connected to a reticulated electricity supply or have an alternative energy supply.

52.04-8 Use of land requirements in a rural zone and an Urban Growth Zone

28/03/2024
VC259

A lot used for a dependent person's unit in a Rural Living Zone, Green Wedge Zone, Green Wedge A Zone, Rural Conservation Zone, Farming Zone, Rural Activity Zone and Urban Growth Zone must meet the following requirements:

- Access to the dependent person's unit must be provided via an all-weather road with dimensions adequate to accommodate emergency vehicles.
- Each dependent person's unit must be connected to reticulated sewerage, if available. If reticulated sewerage is not available, all wastewater from each dwelling must be treated and retained within the lot in in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017* for an on-site wastewater management system.

- The dependent person's unit must be connected to a reticulated potable water supply or have an alternative potable water supply with adequate storage for domestic use as well as for fire fighting purposes.
- The dependent person's unit must be connected to a reticulated electricity supply or have an alternative energy source.

52.04-9 Use of land requirements in an Airport Environs Overlay and Melbourne Airport Environs Overlay

28/03/2024
VC259

A permit is required under this clause to use land in an Airport Environs Overlay or a Melbourne Airport Environs Overlay for a dependent person's unit.

Land in an Airport Environs Overlay or a Melbourne Airport Environs Overlay must not be used for:

- More than one dependent person's unit.
- A dependent person's unit if there is an existing small second dwelling on the lot.
- A dependent person's unit if the size of the lot is less than 600 square metres.

52.04-10 Buildings and works requirements in a specified overlay

03/03/2025
VC266

A permit is required under the following overlays to construct a building or construct or carry out works for a dependent person's unit:

- Erosion Management Overlay. This does not apply if a schedule to the overlay specifically states that a permit is not required for a dependent person's unit.
- Floodway Overlay. This does not apply if a schedule to the overlay specifically states that a permit is not required for a dependent person's unit.
- Land Subject to Inundation Overlay. This does not apply if a schedule to the overlay specifically states that a permit is not required for a dependent person's unit.
- Special Building Overlay. This does not apply if a schedule to the overlay specifically states that a permit is not required for a dependent person's unit.
- Bushfire Management Overlay. This does not apply to any of the following:
  - If a schedule to the overlay specifically states that a permit is not required for a dependent person's unit.
  - An alteration or extension to an existing building used for a dependent person's unit that is less than 50 percent of the gross floor area of the existing building.

An application under a Bushfire Management Overlay must meet the requirements of clause 53.02-4, unless the application meets all of the requirements specified in a schedule to clause 44.06.

Any other requirement for a dependent person's unit specified in a schedule to an overlay applies.

52.04-11 Decision guidelines

28/03/2024
VC259

Before deciding on an application for a permit under clauses 52.04-5, 52.04-6, 52.04-9 or 52.04-10 the responsible authority must consider the decision guidelines of clause 65, including the decision guidelines of the zone or overlay, as appropriate.

52.04-12 Expiry

03/03/2025
VC266

The requirements of this clause do not have effect after 28 March 2026.

The requirements of the planning scheme that applied to the use or development of land (other than subdivision) for a dependent person's unit before the approval date of Amendment VC253 continue to apply:

- To a planning permit application for the use or development of land (other than subdivision) for a dependent person's unit lodged before the approval date of Amendment VC253.
- Where a planning permit was not required for the use or development of land (other than subdivision) for a dependent person's unit before the approval date of Amendment VC253 if one of the following applies:
  - A building permit was issued for the development of land (other than subdivision) for a dependent person's unit before the approval date of Amendment VC253.
  - A building surveyor has been appointed to issue a building permit for the development of land (other than subdivision) for a dependent person's unit before the approval date of Amendment VC253. A building permit must be issued within 3 months of the approval date of Amendment VC253.
  - A building surveyor is satisfied, and certifies in writing, that substantial progress was made on the design of the dependent person's unit before the approval date of Amendment VC253. A building permit must be issued within 3 months of the approval date of Amendment VC253.

52.05 SIGNS

31/07/2018
VC148

Purpose

To regulate the development of land for signs and associated structures.

To ensure signs are compatible with the amenity and visual appearance of an area, including the existing or desired future character.

To ensure signs do not contribute to excessive visual clutter or visual disorder.

To ensure that signs do not cause loss of amenity or adversely affect the natural or built environment or the safety, appearance or efficiency of a road.

52.05-1 Application

31/07/2018
VC148

This clause applies to the development of land for signs.

52.05-2 Requirements

28/02/2025
VC274

Sign categories

Clauses 52.05-11 to 52.05-14 specify categories of sign control. The zone provisions specify which category of sign control applies to the zone.

Each category is divided into three sections.

If a sign can be interpreted in more than one way, the most restrictive requirement must be met.

Section 1

A sign in Section 1 of the category may be constructed or put up for display without a permit, but all the conditions opposite the sign must be met. If the conditions are not met, the sign is in Section 2.

Some overlays require a permit for Section 1 signs.

Section 2

A permit is required to construct or put up for display a sign in Section 2.

This does not apply to a sign specified in Clause 52.05-10.

All the conditions opposite the sign must be met. If the conditions are not met, the sign is prohibited.

Section 3

A sign in Section 3 is prohibited and must not be constructed or put up for display.

VicSmart applications

Subject to Clause 71.06, an application under this clause for a development specified in Column 1 is a class of VicSmart application and must be assessed against the provision specified in Column 2.

Class of application	Information requirements and decision guidelines
Construct or put up for display a sign in an industrial zone, commercial zone, Special Use Zone, Comprehensive Development Zone, Docklands Zone, Priority Development Zone, Activity Centre Zone or Precinct Zone if: ▪ The sign is not within 30 metres of land (not a road) which is in a residential zone.	Clause 59.09

Class of application	Information requirements and decision guidelines
▪ The sign is not a pole sign, a sky sign, a reflective sign, internally illuminated sign, floodlit sign, electronic sign or animated sign. ▪ The display area of the sign does not exceed 10 square metres.	

52.05-3 Referral of applications

31/07/2018
VC148

An application to construct or put up for display an animated or electronic sign within 60 metres of a freeway or arterial road declared under the *Road Management Act 2004* must be referred in accordance with section 55 of the Act to the referral authority specified in Clause 66.03 or a schedule to that clause.

52.05-4 Expiry of permits

31/07/2018
VC148

A permit for a sign other than a major promotion sign expires on the date specified in the permit. If no date is specified, the expiry date is 15 years from the date of issue of the permit.

52.05-5 Existing signs

31/07/2018
VC148

A sign that was lawfully displayed on the approval date or that was being constructed or put up for display on that date may be displayed or continue to be displayed and may be repaired and maintained.

The content of a lawfully displayed sign may be renewed or replaced. However, a permit is required if:

- The display area is to be increased.
- The renewal or replacement would result in a different type of sign.

A sign that is reconstructed must meet the relevant sign requirements.

A major promotion sign displayed in accordance with a permit granted between 19 September 1995 and 18 September 1997 may continue to be displayed:

- until 31 December 2008; or
- where a permit application seeking permission to display the sign is lodged before 31 December 2008, until the permit application is finally determined.

52.05-6 Application requirements

20/01/2022
VC205

An application must be accompanied by the following information, as appropriate:

Site context

- A site context report, using a site plan, photographs or other methods to accurately describe:
  - The location of the proposed sign on the site or building and distance from property boundaries.
  - The location and size of existing signage on the site including details of any signs to be retained or removed.
  - The location and form of existing signage on abutting properties and in the locality.
  - The location of closest traffic control signs.
  - Identification of any view lines or vistas that could be affected by the proposed sign.

Sign details

- The location, dimensions, height above ground level and extent of projection of the proposed sign.
- The height, width, depth of the total sign structure including method of support and any associated structures such as safety devices and service platforms.
- Details of associated on-site works.
- Details of any form of illumination, including details of baffles and the times at which the sign would be illuminated.
- The colour, lettering style and materials of the proposed sign.
- The size of the display (total display area, including all sides of a multi-sided sign).
- The location of any logo box and proportion of display area occupied by such a logo box.
- For animated or electronic signs, a report addressing the decision guidelines at Clause 52.05-8 relating to road safety.
- Any landscaping details.

Signs with a display area of 18 square metres or more

- For a sign with a display area of 18 square metres or more:
  - A description of the existing character of the area including built form and landscapes.
  - The location of any other signs over 18 square metres, or scrolling, electronic or animated signs within 200 metres of the site.
  - Any existing identifiable advertising theme in the area.
  - Photo montages or a streetscape perspective of the proposed sign.
  - Level of illumination including:
    - Lux levels for any sign on or within 60 metres of a Transport Zone 2, Transport Zone 3, a residential zone or public land zone.
    - The dwell and change time for any non-static images.
  - The relationship to any significant or prominent views and vistas.

52.05-7 Exemption from notice and review

31/07/2018
VC148

An application for a sign is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act provided the sign:

- Is to be constructed or displayed on land specified in the schedule to this clause.
- Meets any condition specified in the schedule to this clause.

52.05-8 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

All signs

- The character of the area including:
  - The sensitivity of the area in terms of the natural environment, heritage values, waterways and open space, rural landscape or residential character.

  - The compatibility of the proposed sign with the existing or desired future character of the area in which it is proposed to be located.
  - The cumulative impact of signs on the character of an area or route, including the need to avoid visual disorder or clutter of signs.
  - The consistency with any identifiable outdoor advertising theme in the area.
- Impacts on views and vistas:
  - The potential to obscure or compromise important views from the public realm.
  - The potential to dominate the skyline.
  - The potential to impact on the quality of significant public views.
  - The potential to impede views to existing signs.
- The relationship to the streetscape, setting or landscape:
  - The proportion, scale and form of the proposed sign relative to the streetscape, setting or landscape.
  - The position of the sign, including the extent to which it protrudes above existing buildings or landscape and natural elements.
  - The ability to screen unsightly built or other elements.
  - The ability to reduce the number of signs by rationalising or simplifying signs.
  - The ability to include landscaping to reduce the visual impact of parts of the sign structure.
- The relationship to the site and building:
  - The scale and form of the sign relative to the scale, proportion and any other significant characteristics of the host site and host building.
  - The extent to which the sign displays innovation relative to the host site and host building.
  - The extent to which the sign requires the removal of vegetation or includes new landscaping.
- The impact of structures associated with the sign:
  - The extent to which associated structures integrate with the sign.
  - The potential of associated structures to impact any important or significant features of the building, site, streetscape, setting or landscape, views and vistas or area.
- The impact of any illumination:
  - The impact of glare and illumination on the safety of pedestrians and vehicles.
  - The impact of illumination on the amenity of nearby residents and the amenity of the area.
  - The potential to control illumination temporally or in terms of intensity.
- The impact of any logo box associated with the sign:
  - The extent to which the logo box forms an integral part of the sign through its position, lighting and any structures used to attach the logo box to the sign.
  - The suitability of the size of the logo box in relation to its identification purpose and the size of the sign.
- The need for identification and the opportunities for adequate identification on the site or locality.
- The impact on road safety. A sign is a safety hazard if the sign:

- Obstructs a driver's line of sight at an intersection, curve or point of egress from an adjacent property.
- Obstructs a driver's view of a traffic control device, or is likely to create a confusing or dominating background that may reduce the clarity or effectiveness of a traffic control device.
- Could dazzle or distract drivers due to its size, design or colouring, or it being illuminated, reflective, animated or flashing.
- Is at a location where particular concentration is required, such as a high pedestrian volume intersection.
- Is likely to be mistaken for a traffic control device, because it contains red, green or yellow lighting, or has red circles, octagons, crosses, triangles or arrows.
- Requires close study from a moving or stationary vehicle in a location where the vehicle would be unprotected from passing traffic.
- Invites drivers to turn where there is fast moving traffic or the sign is so close to the turning point that there is no time to signal and turn safely.
- Is within 100 metres of a rural railway crossing.
- Has insufficient clearance from vehicles on the carriageway.
- Could mislead drivers or be mistaken as an instruction to drivers.

Major promotion signs

- The effect of the proposed major promotion sign on:
  - Significant streetscapes, buildings and skylines.
  - The visual appearance of a significant view corridor, viewline, gateway location or landmark site identified in a framework plan or local policy.
  - Residential areas and heritage places.
  - Open space and waterways.
- When determining the effect of a proposed major promotion sign, the following locational principles must be taken into account:
  - Major promotion signs are encouraged in commercial and industrial locations in a manner that complements or enhances the character of the area.
  - Major promotion signs are discouraged along forest and tourist roads, scenic routes or landscaped sections of freeways.
  - Major promotion signs are discouraged within open space reserves or corridors and around waterways.
  - Major promotion signs are discouraged where they will form a dominant visual element from residential areas, within a heritage place or where they will obstruct significant viewlines.
  - In areas with a strong built form character, major promotion signs are encouraged only where they are not a dominant element in the streetscape and except for transparent feature signs (such as neon signs), are discouraged from being erected on the roof of a building.

52.05-9 Mandatory conditions

31/07/2018
VC148

All signs

A permit for a sign that includes an expiry date must include a condition that provides that on expiry of the permit the sign and structures built specifically to support and illuminate it must be removed.

Major promotion signs

A permit for a major promotion sign must include conditions that specify:

- That the sign must not:
  - Dazzle or distract drivers due to its colouring.
  - Be able to be mistaken for a traffic signal because it has, for example, red circles, octagons, crosses or triangles.
  - Be able to be mistaken as an instruction to drivers.
- An expiry date that is 15 years from the date the permit is issued unless otherwise specified in this clause. This does not apply to a permit for major promotion sign for a special event or temporary building shrouding.

A permit for a major promotion sign may specify an expiry date other than 15 years, but the date must not be less than 10 years or more than 25 years from the date the permit is issued. Before deciding to alter the specified expiry date of 15 years, the responsible authority must consider, as appropriate:

- The purpose of the sign.
- The existing or desired character of the area.
- The Municipal Planning Strategy and the Planning Policy Framework in terms of the extent to which the proposed sign is consistent with any relevant policy direction and the extent to which the area may be expected to change over time.
- The extent to which the signage is physically and visually integrated into the architecture of the building.

52.05-10 Signs not requiring a permit

26/09/2023
VC246

Despite any provision in a zone, overlay, or other particular provision of this scheme, a permit is not required to construct or put up for display any of the following signs:

- A sign identifying the functions or property of a government department, public authority or municipal council, but not a promotion sign displayed at the direction of any of these bodies.
- A sign controlling traffic on a public road, railway, tramway, water or in the air, provided it is displayed at the direction of a government department, public authority or municipal council.
- A sign at a hospital that gives direction to emergency facilities.
- A sign in a road reserve that gives direction or guidance about a tourist attraction, service or facility of interest to road users. The sign must be displayed to the satisfaction of the road authority.
- A sign required by statute or regulation, provided it is strictly in accordance with the requirement.
- A sign at a railway station or bus terminal that provides information or direction for people using the station or terminal.
- A sign on a showground, on a motor racing track or on a major sports and recreation facility, provided the sign's display cannot be seen from nearby land.

- A sign with a display area not exceeding 1 square metre to each premises that provides information about a place of worship. It must not be an animated or internally illuminated sign.
- A sign inside a building that cannot generally be seen outside.
- A sign with a display area not exceeding 2 square metres concerning construction work on the land. Only one sign may be displayed, it must not be an animated or internally illuminated sign and it must be removed when the work is completed.
- A sign with a display area not exceeding 5 square metres publicising a local educational, cultural, political, religious, social or recreational event not held for commercial purposes. Only one sign may be displayed on the land, it must not be an animated or internally illuminated sign and it must not be displayed longer than 14 days after the event is held or 3 months, whichever is sooner. A sign publicising a local political event may include information about a candidate for an election.
- A sign publicising a special event on the land or in the building on which it is displayed, provided no more than 8 signs are displayed in a calendar year and the total number of days the signs are displayed does not exceed 28 in that calendar year. The sign must be removed when the event is finished.
- A sign with a display area not exceeding 2 square metres publicising the sale of goods or livestock on the land or in the building on which it is displayed, provided the land or building is not normally used for that purpose. Only one sign may be displayed, it must not be an animated or internally illuminated sign and it must not be displayed longer than 3 months without a permit.
- A sign with an display area not exceeding 10 square metres publicising the sale or letting of the property on which it is displayed. Only one sign may be displayed, it must not be an animated sign and it must not be displayed longer than 7 days after the sale date. A permit may be granted for:
  - The display area to exceed 10 square metres if the sign concerns more than 20 lots.
  - The sign to be displayed on land excised from the subdivision and transferred to the municipal council.
  - The sign to be displayed longer than 7 days after the sale date.
- A sign publicising or providing information about Victoria's container deposit scheme under the *Circular Economy (Waste and Recycling) Act* 2021. The sign must be attached to an automated collection point, or a building used for a Container deposit scheme centre. The display area for the sign must not exceed 8 square metres. The sign must not be an animated, floodlit or internally illuminated sign.

No permit is required to fly the Australian flag or to display the flag on a building, painted or otherwise represented, provided it is correctly dimensioned and coloured in accordance with the *Flags Act 1953*.

52.05-11 Category 1 - Commercial areas

03/02/2022
VC199

Minimum limitation

Purpose

To provide for identification and promotion signs and signs that add vitality and colour to commercial areas.

Section 1 - Permit not required

Sign	Condition
Bed and breakfast sign **Business identification sign** **Home based business sign** **Promotion sign**	The total display area of all signs to each premises must not exceed 8 sqm. This does not include a sign with a display area not exceeding 1.5 sqm that is below a verandah or, if no verandah, that is less than 3.7 m above pavement level.
Direction sign	None specified
Internally illuminated sign	The total display area to each premises must not exceed 1.5 sqm. No part of the sign may be above a verandah or, if no verandah, more than 3.7 m above pavement level. The sign must be more than 30 m from a residential zone or pedestrian or traffic lights.

Section 2 - Permit required

Sign	Condition
Any sign not in Section 1	None specified

Section 3 - Prohibited

Sign
Nil

52.05-12 Category 2 - Office and industrial

03/02/2022
VC199

Low limitation

Purpose

To provide for adequate identification signs and signs that are appropriate to office and industrial areas.

Section 1 - Permit not required

Sign	Condition
Bed and breakfast sign **Business identification sign** **Home based business sign** **Pole sign**	The total display area of all signs to each premises must not exceed 8 sqm. This does not include a direction sign.
Direction sign	Only one to each premises.
Internally illuminated sign	The display area must not exceed 1.5 sqm. The sign must be more than 30 m from a residential zone or pedestrian or traffic lights.

Section 2 - Permit required

Sign	Condition
Any sign not in Section 1	None specified

Section 3 - Prohibited

Sign
Nil

52.05-13 Category 3 - High amenity areas

03/02/2022
VC199

Medium limitation

Purpose

To ensure that signs in high-amenity areas are orderly, of good design and do not detract from the appearance of the building on which a sign is displayed or the surrounding area.

Section 1 - Permit not required

Sign	Condition
Bed and breakfast sign	Only one to each premises.
Home based business sign	The display area must not exceed 0.2 sqm.
Direction sign	None specified

Section 2 - Permit required

Sign	Condition
Above-verandah sign	None specified
Business identification sign	
Electronic sign	The display area must not exceed 3 sqm.
Floodlit sign	None specified
High-wall sign	Must be a business logo or street number.
Internally illuminated sign	None specified
Pole sign	
Promotion sign	The display area must not exceed 3 sqm.
Reflective sign	None specified

Section 3 - Prohibited

Sign
Any sign not in Sections 1 or 2

52.05-14 Category 4 - Sensitive areas

17/10/2023
VC241

Maximum limitation

Purpose

To provide for unobtrusive signs in areas requiring strong amenity control.

Section 1 - Permit not required

Sign	Condition
Bed and breakfast sign	Only one to each premises.
Home based business sign	The display area must not exceed 0.2 sqm.
Direction sign	None specified

Section 2 - Permit required

Sign	Condition
Business identification sign	The total display area to each premises must not exceed 3 sqm. This does not apply to a Business identification sign on land used for a Freeway service centre or Service station.
Floodlit sign	Must not be a Promotion sign on land used for an Open sports ground.
Above-verandah sign **High-wall sign** **Internally illuminated sign** **Pole sign**	Must be on land used for a Freeway service centre or Service station.
Electronic sign	Must be on land used for a Freeway service centre or Service station. The display area must not exceed 3 sqm.
Promotion sign	Must be on land used for a Freeway service centre, Service station or Open sports ground. Must promote goods, services, events or matters provided, undertaken or sold on land used for a Freeway service centre or Service station.

Section 3 - Prohibited

Sign
Any sign not in Sections 1 or 2

08/07/2021
C211brim

SCHEDULE TO CLAUSE 52.05 SIGNS

1.0

08/07/2021
C211brim

Exemption from notice and review

Land	Condition
None specified	

52.06 CAR PARKING

31/07/2018
VC148

Purpose

To ensure that car parking is provided in accordance with the Municipal Planning Strategy and the Planning Policy Framework.

To ensure the provision of an appropriate number of car parking spaces having regard to the demand likely to be generated, the activities on the land and the nature of the locality.

To support sustainable transport alternatives to the motor car.

To promote the efficient use of car parking spaces through the consolidation of car parking facilities.

To ensure that car parking does not adversely affect the amenity of the locality.

To ensure that the design and location of car parking is of a high standard, creates a safe environment for users and enables easy and efficient use.

52.06-1 Scope

25/02/2025
VC257

Clause 52.06 applies to:

- a new use; or
- an increase in the floor area or site area of an existing use; or
- an increase to an existing use by the measure specified in Column C of Table 1 in Clause 52.06-5 for that use.

Clause 52.06 does not apply to:

- the extension of one dwelling on a lot in the Neighbourhood Residential Zone, General Residential Zone, Residential Growth Zone, Housing Choice and Transport Zone, Mixed Use Zone or Township Zone; or
- the construction and use of one dwelling on a lot in the Neighbourhood Residential Zone, General Residential Zone, Residential Growth Zone, Housing Choice and Transport Zone, Mixed Use Zone or Township Zone unless the zone or a schedule to the zone specifies that a permit is required to construct or extend one dwelling on a lot; or
- the construction and use of a small second dwelling.

52.06-2 Provision of car parking spaces

19/04/2013
VC95

Before:

- a new use commences; or
- the floor area or site area of an existing use is increased; or
- an existing use is increased by the measure specified in Column C of Table 1 in Clause 52.06-5 for that use,

the number of car parking spaces required under Clause 52.06-5 or in a schedule to the Parking Overlay must be provided to the satisfaction of the responsible authority in one or more of the following ways:

- on the land; or
- in accordance with a permit issued under Clause 52.06-3; or
- in accordance with a financial contribution requirement specified in a schedule to the Parking Overlay.

If a schedule to the Parking Overlay specifies a maximum parking provision, the maximum provision must not be exceeded except in accordance with a permit issued under Clause 52.06-3.

52.06-3 Permit requirement

28/02/2025
VC274

A permit is required to:

- Reduce (including reduce to zero) the number of car parking spaces required under Clause 52.06-5 or in a schedule to the Parking Overlay.
- Provide some or all of the car parking spaces required under Clause 52.06-5 or in a schedule to the Parking Overlay on another site.
- Provide more than the maximum parking provision specified in a schedule to the Parking Overlay.

A permit is not required if a schedule to the Parking Overlay specifies that a permit is not required under this clause.

A permit is not required to reduce the number of car parking spaces required for a new use of land if the following requirements are met:

- The number of car parking spaces required under Clause 52.06-5 or in a schedule to the Parking Overlay for the new use is less than or equal to the number of car parking spaces required under Clause 52.06-5 or in a schedule to the Parking Overlay for the existing use of the land.
- The number of car parking spaces currently provided in connection with the existing use is not reduced after the new use commences.

A permit is not required to reduce the required number of car parking spaces for a new use of an existing building if the following requirements are met:

- The building is in the Commercial 1 Zone, Commercial 2 Zone, Commercial 3 Zone, Activity Centre Zone or Precinct Zone.
- The gross floor area of the building is not increased.
- The reduction does not exceed 10 car parking spaces.
- The building is not in a Parking Overlay with a schedule that allows a financial contribution to be paid in lieu of the provision of the required car parking spaces for the use.

VicSmart applications

Subject to Clause 71.06, an application under this clause to reduce the required number of car parking spaces by no more than 10 car parking spaces is a class of VicSmart application and must be assessed against Clause 59.10.

52.06-4 Exemption from notice and review

31/07/2018
VC148

An application under Clause 52.06-3 is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if:

- the application is only for a permit under Clause 52.06-3; or
- the application is also for a permit under another provision of the planning scheme and in respect of all other permissions sought, the application is exempt from the notice requirements of Section 52(1)(a), (b) and (d), the decision requirements of Section 64(1), (2) and (3) and the review rights of Section 82(1) of the Act.

52.06-5 Number of car parking spaces required under Table 1

24/01/2020
VC160

Table 1 of this clause sets out the car parking requirement that applies to a use listed in the Table.

A car parking requirement in Table 1 may be calculated as either:

- a number of car parking spaces; or
- a percentage of the total site area that must be set aside for car parking.

A car parking requirement in Table 1 is calculated by multiplying the figure in Column A or Column B (whichever applies) by the measure (for example square metres, number of patrons or number of bedrooms) in Column C.

Column A applies unless Column B applies.

Column B applies if:

- any part of the land is identified as being within the Principal Public Transport Network Area as shown on the *Principal Public Transport Network Area Maps* (State Government of Victoria, August 2018); or
- a schedule to the Parking Overlay or another provision of the planning scheme specifies that Column B applies.

Where an existing use is increased by the measure specified in Column C of Table 1 for that use, the car parking requirement only applies to the increase, provided the existing number of car parking spaces currently being provided in connection with the existing use is not reduced.

If in calculating the number of car parking spaces the result is not a whole number, the required number of car parking spaces is to be rounded down to the nearest whole number.

Where the car parking requirement specified in Table 1 is calculated as a percentage of the total site area, the area to be provided for car parking includes an accessway that directly abuts any car parking spaces, but does not include any accessway or portion of an accessway that does not directly abut any car parking spaces.

The car parking requirement specified in Table 1 includes disabled car parking spaces. The proportion of spaces to be allocated as disabled spaces must be in accordance with Australian Standard AS2890.6-2009 (disabled) and the Building Code of Australia.

The car parking requirement specified for a use listed in Table 1 does not apply if:

- a car parking requirement for the use is specified under another provision of the planning scheme; or
- a schedule to the Parking Overlay specifies the number of car parking spaces required for the use.

Table 1: Car parking requirement

Use	Rate Column A	Rate Column B	Car Parking Measure Column C
Amusement parlour	4	3.5	To each 100 sq m of net floor area
Art & craft centre	4	3.5	To each 100 sq m of net floor area
Bar	0.4		To each patron permitted
		3.5	Space to each 100 sq m of leasable floor area
Betting agency	4	3.5	To each 100 sq m of leasable floor area
Bowling green	6	6	To each rink plus 50 per cent of the relevant requirement of any ancillary use
Child care centre	0.22	0.22	To each child
Cinema based entertainment facility	0.3	0.3	To each patron permitted
Convenience restaurant	0.3		To each patron permitted
		3.5	To each 100 sq m of leasable floor area

Use	Rate Column A	Rate Column B	Car Parking Measure Column C
Convenience shop if the leasable floor area exceeds 80 sq m	10		To each premises
		3.5	To each 100 sq m of leasable floor area
Display home centre	5		To each dwelling for five or fewer contiguous dwellings, plus
	2		To each additional contiguous dwelling
		3.5	To each 100 sq m of floor area
Dwelling	1	1	To each one or two bedroom dwelling, plus
	2	2	To each three or more bedroom dwelling (with studies or studios that are separate rooms counted as a bedrooms) plus
	1	0	For visitors to every 5 dwellings for developments of 5 or more dwellings
Education centre other than listed in this table	0.4	0.3	To each student that is part of the maximum number of students on the site at any time
Food and drink premises other than listed in this table	4	3.5	To each 100 sq m of leasable floor area
Freezing and cool storage,	1.5	1	To each 100 sq m of net floor area
Fuel depot	10	10	Per cent of site area
Funeral Parlour	0.3	0.3	To each patron permitted
Gambling premises other than listed in this table	0.4		To each patron permitted
		3.5	To each 100 sq m of leasable floor area
Golf course	4	4	To each hole plus 50 per cent of the relevant requirement of any ancillary uses.
Home based business	1	0	To each employee not a resident of the dwelling
Hotel	0.4		To each patron permitted
		3.5	To each 100 sq m of leasable floor area
Industry other than listed in this table	2.9	1	To each 100 sq m of net floor area
Landscape gardening supplies	10	10	Per cent of site area
Mail centre	3.5	3	To each 100 sq m of net floor area
Manufacturing sales	4	3.5	To each 100 sq m of leasable floor area
Market	8	3.5	To each 100 sq m of site area
Materials recycling	10	10	Per cent of site area
Medical centre	5		To the first person providing health services plus
	3		To every other person providing health services
		3.5	To each 100 sq m of leasable floor area
Milk depot	10	10	Per cent of site area

Use	Rate Column A	Rate Column B	Car Parking Measure Column C
Motel	1	1	To each unit, and one to each manager dwelling, plus 50 per cent of the relevant requirement of any ancillary use
Motor repairs	3	3	To each 100 sq m of net floor area plus
	1	1	for each vehicle being serviced, repaired or fitted with accessories, including vehicles waiting to be serviced, repaired, fitted with accessories or collected by owners
Office other than listed in this table	3.5	3	To each 100 sq m of net floor area
Place of assembly other than listed in this table	0.3	0.3	To each patron permitted
Postal agency	4	3.5	To each 100 sq m of leasable floor area
Primary produce sales	4	3.5	To each 100 sq m of leasable floor area
Primary school	1	1	To each employee that is part of the maximum number of employees on the site at any time
Research and development centre	3.5	3	To each 100 sq m of net floor area
Residential aged care facility	0.3	0.3	To each lodging room
Residential village	1	1	To each one or two bedroom dwelling plus
	2	2	To each three or more bedroom dwelling (with studies or studios that are separate rooms counted as a bedrooms) plus
	1	0	For visitors to every five dwellings for developments of five or more dwellings
Retirement village	1	1	To each one or two bedroom dwelling plus
	2	2	To each three or more bedroom dwelling (with studies or studios that are separate rooms counted as a bedrooms) plus
	1	0	For visitors to every five dwellings for developments of five or more dwellings
Restaurant	0.4		To each patron permitted
		3.5	To each 100 sq m of leasable floor area
Restricted retail premises	3	2.5	To each 100 sq m of leasable floor area
Rooming house	1	1	To each four bedrooms
Saleyard	10	10	Per cent of site area
Secondary school	1.2	1.2	To each employee that is part of the maximum number of employees on the site at any time
Shop other than listed in this table	4	3.5	To each 100 sq m of leasable floor area
Squash court – other than in conjunction with a dwelling	3	3	To each court plus 50 per cent of the relevant requirement of any ancillary use

Use	Rate Column A	Rate Column B	Car Parking Measure Column C
Store other than listed in this table	10	10	Per cent of site area
Supermarket	5	5	To each 100 sq m of leasable floor area
Swimming pool – other than in conjunction with a dwelling	5.6	5.6	To each 100 sq m of the site
Tennis court – other than in conjunction with a dwelling	4	4	To each court plus 50% of the requirement of any ancillary use
Trade supplies	10	10	Per cent of site area
Veterinary centre	5		To the first person providing animal health services plus
	3		To every other person providing animal health services
		3.5	To each 100 sq m of leasable floor area
Warehouse other than listed in this table	2	2	To each premises plus
	1.5	1	To each 100 sq m of net floor area
Winery	0.4		To each patron permitted
		3.5	To each 100 sq m of leasable floor area

52.06-6 Number of car parking spaces required for other uses

16/01/2018
VC142

Where a use of land is not specified in Table 1 or where a car parking requirement is not specified for the use in another provision of the planning scheme or in a schedule to the Parking Overlay, before a new use commences or the floor area or site area of an existing use is increased, car parking spaces must be provided to the satisfaction of the responsible authority. This does not apply to the use of land for a temporary portable land sales office located on the land for sale.

52.06-7 Application requirements and decision guidelines for permit applications

25/05/2017
VC133

For applications to reduce the car parking requirement

An application to reduce (including reduce to zero) the number of car parking spaces required under Clause 52.06-5 or in a schedule to the Parking Overlay must be accompanied by a Car Parking Demand Assessment.

The Car Parking Demand Assessment must assess the car parking demand likely to be generated by the proposed:

- new use; or
- increase in the floor areas or site area of the existing use; or
- increase to the existing use by the measure specified in Column C of Table 1 in Clause 52.06-5 for that use.

The Car Parking Demand Assessment must address the following matters, to the satisfaction of the responsible authority:

- The likelihood of multi-purpose trips within the locality which are likely to be combined with a trip to the land in connection with the proposed use.
- The variation of car parking demand likely to be generated by the proposed use over time.

- The short-stay and long-stay car parking demand likely to be generated by the proposed use.
- The availability of public transport in the locality of the land.
- The convenience of pedestrian and cyclist access to the land.
- The provision of bicycle parking and end of trip facilities for cyclists in the locality of the land.
- The anticipated car ownership rates of likely or proposed visitors to or occupants (residents or employees) of the land.
- Any empirical assessment or case study.

Before granting a permit to reduce the number of spaces, the responsible authority must consider the following, as appropriate:

- The Car Parking Demand Assessment.
- Any relevant local planning policy or incorporated plan.
- The availability of alternative car parking in the locality of the land, including:
  - Efficiencies gained from the consolidation of shared car parking spaces.
  - Public car parks intended to serve the land.
  - On street parking in non residential zones.
  - Streets in residential zones specifically managed for non-residential parking.
- On street parking in residential zones in the locality of the land that is intended to be for residential use.
- The practicality of providing car parking on the site, particularly for lots of less than 300 square metres.
- Any adverse economic impact a shortfall of parking may have on the economic viability of any nearby activity centre.
- The future growth and development of any nearby activity centre.
- Any car parking deficiency associated with the existing use of the land.
- Any credit that should be allowed for car parking spaces provided on common land or by a Special Charge Scheme or cash-in-lieu payment.
- Local traffic management in the locality of the land.
- The impact of fewer car parking spaces on local amenity, including pedestrian amenity and the amenity of nearby residential areas.
- The need to create safe, functional and attractive parking areas.
- Access to or provision of alternative transport modes to and from the land.
- The equity of reducing the car parking requirement having regard to any historic contributions by existing businesses.
- The character of the surrounding area and whether reducing the car parking provision would result in a quality/positive urban design outcome.
- Any other matter specified in a schedule to the Parking Overlay.
- Any other relevant consideration.

For applications to allow some or all of the required car parking spaces to be provided on another site

Before granting a permit to allow some or all of the car parking spaces required under Clause 52.06-5 or in a schedule to the Parking Overlay to be provided on another site, the responsible authority must consider the following, as appropriate:

- The proximity of the car parking on the alternate site to the subject site.
- The likelihood of the long term provision and availability of the car parking spaces.
- Whether the location of the car parking spaces is consistent with any relevant local policy or incorporated plan.
- Any other matter specified in a schedule to the Parking Overlay.

For applications to provide more than the maximum parking provision specified in a schedule to the Parking Overlay

An application to provide more than the maximum parking provision specified in a schedule to the Parking Overlay must be accompanied by a Car Parking Demand Assessment.

The Car Parking Demand Assessment must assess the car parking demand likely to be generated by the proposed use or increase to the existing use.

The Car Parking Demand Assessment must address the following matters, to the satisfaction of the responsible authority:

- The likelihood of multi-purpose trips within the locality which are likely to be combined with a trip to the land in connection with the proposed use.
- The variation of car parking demand likely to be generated by the proposed use over time.
- The short-stay and long-stay car parking demand likely to be generated by the proposed use.
- The availability of public transport in the locality of the land.
- The convenience of pedestrian and cyclist access to the land.
- The provision of bicycle parking and end of trip facilities for cyclists in the locality of the land.
- The anticipated car ownership rates of likely or proposed visitors to or occupants (residents or employees) of the land.
- Any empirical assessment or case study.

52.06-8 Requirement for a car parking plan

25/05/2017
VC133

Plans must be prepared to the satisfaction of the responsible authority before any of the following occurs:

- a new use commences; or
- the floor area or site area of an existing use is increased; or
- an existing use is increased by the measure specified in Column C of Table 1 in Clause 52.06-5 for that use.

The plans must show, as appropriate:

- All car parking spaces that are proposed to be provided (whether on the land or on other land).
- Access lanes, driveways and associated works.
- Allocation of car parking spaces to different uses or tenancies, if applicable.
- Any landscaping and water sensitive urban design treatments.
- Finished levels, if required by the responsible authority.

- Any other matter specified in a schedule to the Parking Overlay.

Plans must be provided to the responsible authority under Clause 52.06-8 wherever Clause 52.06 applies, whether or not a permit application is being made under Clause 52.06-3 or any other provision of the planning scheme.

Where an application is being made for a permit under Clause 52.06-3 or another provision of the planning scheme, the information required under Clause 52.06-8 may be included in other plans submitted with the application.

Clause 52.06-8 does not apply where no car parking spaces are proposed to be provided.

52.06-9 Design standards for car parking

03/02/2022
VC199

Plans prepared in accordance with Clause 52.06-8 must meet the design standards of Clause 52.06-9, unless the responsible authority agrees otherwise.

Design standards 1, 3, 6 and 7 do not apply to an application to construct one dwelling on a lot.

Design standard 1 – Accessways

Accessways must:

- Be at least 3 metres wide.
- Have an internal radius of at least 4 metres at changes of direction or intersection or be at least 4.2 metres wide.
- Allow vehicles parked in the last space of a dead-end accessway in public car parks to exit in a forward direction with one manoeuvre.
- Provide at least 2.1 metres headroom beneath overhead obstructions, calculated for a vehicle with a wheel base of 2.8 metres.
- If the accessway serves four or more car spaces or connects to a road in a Transport Zone 2 or Transport Zone 3, the accessway must be designed so that cars can exit the site in a forward direction.
- Provide a passing area at the entrance at least 6.1 metres wide and 7 metres long if the accessway serves ten or more car parking spaces and is either more than 50 metres long or connects to a road in a Transport Zone 2 or Transport Zone 3.
- Have a corner splay or area at least 50 per cent clear of visual obstructions extending at least 2 metres along the frontage road from the edge of an exit lane and 2.5 metres along the exit lane from the frontage, to provide a clear view of pedestrians on the footpath of the frontage road. The area clear of visual obstructions may include an adjacent entry or exit lane where more than one lane is provided, or adjacent landscaped areas, provided the landscaping in those areas is less than 900mm in height.

If an accessway to four or more car parking spaces is from land in a Transport Zone 2 or Transport Zone 3, the access to the car spaces must be at least 6 metres from the road carriageway.

If entry to the car space is from a road, the width of the accessway may include the road.

Design standard 2 – Car parking spaces

Car parking spaces and accessways must have the minimum dimensions as outlined in Table 2.

Table 2: Minimum dimensions of car parking spaces and accessways

Angle of car parking spaces to access way	Accessway width	Car space width	Car space length
Parallel	3.6 m	2.3 m	6.7 m


Angle of car parking spaces to access way	Accessway width	Car space width	Car space length
45º	3.5 m	2.6 m	4.9 m
60º	4.9 m	2.6 m	4.9 m
90º	6.4 m	2.6 m	4.9 m
	5.8 m	2.8 m	4.9 m
	5.2 m	3.0 m	4.9 m
	4.8 m	3.2 m	4.9 m

Note *Some dimensions in Table 2 vary from those shown in the Australian Standard AS2890.1-2004 (off street). The dimensions shown in Table 2 allocate more space to aisle widths and less to marked spaces to provide improved operation and access. The dimensions in Table 2 are to be used in preference to the Australian Standard AS2890.1-2004 (off street) except for disabled spaces which must achieve Australian Standard AS2890.6-2009 (disabled).*

A wall, fence, column, tree, tree guard or any other structure that abuts a car space must not encroach into the area marked 'clearance required' on Diagram 1, other than:

- A column, tree or tree guard, which may project into a space if it is within the area marked 'tree or column permitted' on Diagram 1.
- A structure, which may project into the space if it is at least 2.1 metres above the space.

Diagram 1 Clearance to car parking spaces



Car spaces in garages or carports must be at least 6 metres long and 3.5 metres wide for a single space and 5.5 metres wide for a double space measured inside the garage or carport.

Where parking spaces are provided in tandem (one space behind the other) an additional 500 mm in length must be provided between each space.

Where two or more car parking spaces are provided for a dwelling, at least one space must be under cover.

Disabled car parking spaces must be designed in accordance with Australian Standard AS2890.6-2009 (disabled) and the Building Code of Australia. Disabled car parking spaces may encroach into an accessway width specified in Table 2 by 500mm.

Design standard 3: Gradients

Accessway grades must not be steeper than 1:10 (10 per cent) within 5 metres of the frontage to ensure safety for pedestrians and vehicles. The design must have regard to the wheelbase of the vehicle being designed for; pedestrian and vehicular traffic volumes; the nature of the car park; and the slope and configuration of the vehicle crossover at the site frontage. This does not apply to accessways serving three dwellings or less.

Ramps (except within 5 metres of the frontage) must have the maximum grades as outlined in Table 3 and be designed for vehicles travelling in a forward direction.

Table 3: Ramp gradients

Type of car park	Length of ramp	Maximum grade
Public car parks	20 metres or less	1:5 (20%)
	longer than 20 metres	1:6 (16.7%)
Private or residential car parks	20 metres or less	1:4 (25%)
	longer than 20 metres	1:5 (20%)

Where the difference in grade between two sections of ramp or floor is greater that 1:8 (12.5 per cent) for a summit grade change, or greater than 1:6.7 (15 per cent) for a sag grade change, the ramp must include a transition section of at least 2 metres to prevent vehicles scraping or bottoming.

Plans must include an assessment of grade changes of greater than 1:5.6 (18 per cent) or less than 3 metres apart for clearances, to the satisfaction of the responsible authority.

Design standard 4: Mechanical parking

Mechanical parking may be used to meet the car parking requirement provided:

- At least 25 per cent of the mechanical car parking spaces can accommodate a vehicle height of at least 1.8 metres.
- Car parking spaces that require the operation of the system are not allocated to visitors unless used in a valet parking situation.
- The design and operation is to the satisfaction of the responsible authority.

Design standard 5: Urban design

Ground level car parking, garage doors and accessways must not visually dominate public space.

Car parking within buildings (including visible portions of partly submerged basements) must be screened or obscured where possible, including through the use of occupied tenancies, landscaping, architectural treatments and artworks.

Design of car parks must take into account their use as entry points to the site.

Design of new internal streets in developments must maximise on street parking opportunities.

Design standard 6: Safety

Car parking must be well lit and clearly signed.

The design of car parks must maximise natural surveillance and pedestrian visibility from adjacent buildings.

Pedestrian access to car parking areas from the street must be convenient.

Pedestrian routes through car parking areas and building entries and other destination points must be clearly marked and separated from traffic in high activity parking areas.

Design standard 7: Landscaping

The layout of car parking areas must provide for water sensitive urban design treatment and landscaping.

Landscaping and trees must be planted to provide shade and shelter, soften the appearance of ground level car parking and aid in the clear identification of pedestrian paths.

Ground level car parking spaces must include trees planted with flush grilles. Spacing of trees must be determined having regard to the expected size of the selected species at maturity.

52.06-10 Decision guidelines

25/05/2017
VC133

Before deciding that a plan prepared under Clause 52.06-8 is satisfactory the responsible authority must consider, as appropriate:

- The role and function of nearby roads and the ease and safety with which vehicles gain access to the site.
- The ease and safety with which vehicles access and circulate within the parking area.
- The provision for pedestrian movement within and around the parking area.
- The provision of parking facilities for cyclists and disabled people.
- The protection and enhancement of the streetscape.
- The provisions of landscaping for screening and shade.
- The measures proposed to enhance the security of people using the parking area particularly at night.
- The amenity of the locality and any increased noise or disturbance to dwellings and the amenity of pedestrians.
- The workability and allocation of spaces of any mechanical parking arrangement.
- The design and construction standards proposed for paving, drainage, line marking, signage, lighting and other relevant matters.
- The type and size of vehicle likely to use the parking area.
- Whether the layout of car parking spaces and access lanes is consistent with the specific standards or an appropriate variation.
- The need for the required car parking spaces to adjoin the premises used by the occupier/s, if the land is used by more than one occupier.
- Whether the layout of car spaces and accessways are consistent with Australian Standards AS2890.1-2004 (off street) and AS2890.6-2009 (disabled).
- The relevant standards of Clauses 56.06-2, 56.06-4, 56.06-5, 56.06-7 and 56.06-8 for residential developments with accessways longer than 60 metres or serving 16 or more dwellings.
- Any other matter specified in a schedule to the Parking Overlay.

52.06-11 Construction of car parking

25/05/2017
VC133

Where a plan is required under Clause 52.06-8, the car parking spaces, access lanes, driveways and associated works and landscaping shown on the plan must be:

- constructed and available for use in accordance with the plan approved by the responsible authority; and
- formed to such levels and drained so that they can be used in accordance with the plan; and
- treated with an all-weather seal or some other durable surface; and

- line-marked or provided with some other adequate means of showing the car parking spaces,

before any of the following occurs:

- the new use commences; or
- the floor area or site area of the existing use is increased; or
- the existing use is increased by the measure specified in Column C of Table 1 in Clause 52.06-5 for that use.

52.07 EMERGENCY RECOVERY

22/11/2022
VC228

Purpose

To facilitate and support recovery from emergencies.

To facilitate the construction and use of temporary accommodation following an emergency.

To enable businesses and services to continue operating following an emergency.

To support the provision of materials and infrastructure required for emergency recovery.

52.07-1 Exemption from planning scheme requirements

04/11/2022
VC226

Any requirement of this planning scheme to obtain a permit or any provision of this planning scheme that prohibits the use or development of land, requires the use or development of land to be carried out in a particular manner, or requires a specified thing to be done to the satisfaction of a specified person or body, does not apply to any of the following uses or developments if the requirements of clause 52.07 are met:

- The use of land or the construction of a building or the construction or carrying out of works:
  - Associated with recovery carried out by or on behalf of a municipal council or public authority; or
  - For accommodation; or
  - For a use (other than accommodation) that was lawfully carried out in a building immediately before that building was damaged or destroyed by an emergency.
- The removal, destruction or lopping of vegetation.

This exemption does not apply to:

- The requirement in clause 45.03-1.
- The use or development of land to which clause 52.14 applies.

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

52.07-2 Information to responsible authority

04/11/2022
VC226

The following requirement does not apply to the use or development of land associated with recovery carried out by or on behalf of a municipal council or public authority.

Before the commencement of a use or the construction of a building under clause 52.07, the following information must be given in writing to the responsible authority and to the satisfaction of the responsible authority:

- A description of the proposed use.
- A description of the proposed building.
- A description of the land on which the use will be carried out or the building will be constructed by:
  - Stating the address of the land; or
  - Stating the title particulars of the land; or
  - Including a plan showing the land; or
  - Any combination of these.

52.07-3 Temporary accommodation requirements

04/11/2022
VC226

The following requirements do not apply to the use or development of land associated with recovery carried out by or on behalf of a municipal council or public authority.

Land must only be used for accommodation under this clause to accommodate a person whose principal place of residence was damaged or destroyed by a bushfire on the same land or contiguous land in the same ownership.

Land used for accommodation under this clause must meet the following requirements:

- Access to the accommodation must be provided via an all-weather road with dimensions adequate to accommodate emergency vehicles.
- The accommodation must be connected to reticulated sewerage, if available. If reticulated sewerage is not available, all wastewater from the accommodation must be treated and retained within the lot in accordance with the requirements in the Environment Protection Regulations under the *Environment Protection Act 2017* for an on-site wastewater management system or treated and disposed of to the satisfaction of the responsible authority.
- The accommodation must be connected to a reticulated potable water supply or have an alternative potable water supply.
- The accommodation must be connected to a reticulated electricity supply or have an alternative energy source.

The use of land for accommodation under this clause must not continue after 3 years of the commencement of the use unless in accordance with the requirements of this planning scheme.

A building or works constructed or carried out under this clause for accommodation must be on the same land, or on contiguous land in the same ownership, as a building used for accommodation that was damaged or destroyed by a bushfire and must be completed within 18 months of the date that building was damaged or destroyed.

Unless in accordance with the written agreement of the responsible authority, the combined gross floor area of all buildings constructed for accommodation under this clause on contiguous land in the same ownership must not exceed 60 square metres.

52.07-4 Continuation of use requirements

04/11/2022
VC226

The following requirements do not apply to the use or development of land:

- For accommodation; or
- Associated with recovery carried out by or on behalf of a municipal council or public authority.

Unless in accordance with the written agreement of the responsible authority, the use of land under this clause for a use that was carried out in a building immediately before that building was damaged or destroyed by an emergency must be carried out on the same land, or on contiguous land in the same ownership, as the damaged or destroyed building.

A use commenced under this clause must not continue after 3 years of its commencement unless in accordance with this planning scheme.

A building or works constructed or carried out under this clause for a use that was carried out in a building damaged or destroyed by an emergency, must be on the same land, or on contiguous land in the same ownership, as the damaged or destroyed building and must be completed within 18 months of the date that building was damaged or destroyed by an emergency.

Unless in accordance with the written agreement of the responsible authority, the combined gross floor area of all buildings constructed under this clause on contiguous land in the same ownership must not exceed 100 square metres.

52.07-5 Vegetation removal requirement

04/11/2022
VC226

Vegetation must only be removed, destroyed or lopped to the minimum extent necessary:

- To enable the removal of a building, equipment or other material that was damaged or destroyed by an emergency within 3 years of the date it was damaged or destroyed; or
- To enable the repair or reconstruction of a fence that was damaged or destroyed by an emergency within 3 years of the date it was damaged or destroyed for a combined maximum width of 4 metres either side of the fence.

This requirement does not apply to:

- The removal, destruction or lopping of vegetation within 10 metres of a building constructed for accommodation under this clause; or
- The removal, destruction or lopping of vegetation (other than a tree) within 30 metres of a building constructed for accommodation under this clause; or
- The removal, destruction or lopping of vegetation (other than a tree) within 50 metres of a building constructed for accommodation under this clause in a Bushfire Management Overlay.

52.07-6 Other development requirements

04/11/2022
VC226

Development of land in a Bushfire Management Overlay or Erosion Management Overlay that would require a permit, or would be prohibited, under the overlay were it not for the exemption in clause 52.07-1, must be sited to the satisfaction of the responsible authority.

Development of land in a Heritage Overlay that would require a permit, or would be prohibited, under the overlay were it not for the exemption in clause 52.07-1, must be carried out to the satisfaction of the responsible authority.

Development of land in an Urban Floodway Zone, Floodway Overlay, Land Subject to Inundation Overlay or Special Building Overlay that would require a permit, or would be prohibited, under the overlay were it not for the exemption in clause 52.07-1, must be sited to the satisfaction of the relevant floodplain management authority.

52.07-7 Exemptions for extractive industry

06/10/2023
VC247

Any requirement of a planning permit, including any condition, or any provision of this planning scheme, that limits, or has the effect of limiting, the hours or days during which an extractive industry may be carried out, does not apply to the quarrying and processing of materials and the dispatch, delivery, loading or unloading of materials if:

- The materials are directly associated with recovery; and
- The quarrying and processing of materials and the dispatch, delivery, loading or unloading of materials occurs within 24 months of an emergency.

52.07-8 Meaning of terms

22/11/2022
VC228

In this clause:

- ***emergency*** means:
  - a bushfire; or
  - an earthquake, flood, wind-storm or other natural event;
- ***recovery*** means the assisting of persons and communities affected by emergencies to achieve a proper and effective level of functioning.

52.08 EARTH AND ENERGY RESOURCES INDUSTRY

24/01/2020
VC160

Purpose

To encourage land to be used and developed for exploration and extraction of earth and energy resources in accordance with acceptable environmental standards.

To ensure that geothermal energy extraction, greenhouse gas sequestration, mining and petroleum production are not prohibited land uses.

To ensure that planning controls for the use and development of land for the exploration and extraction of earth and energy resources are consistent with other legislation governing these land uses.

52.08-1 Permit requirement

24/01/2020
VC160

A permit is required to use and develop land for earth and energy resources industry unless the table to this clause specifically states that a permit is not required.

Table of exemptions

No permit is required to use or develop land for earth and energy resources industry if the following conditions are met:	
Extractive industry	Complies with Section 77T of the *Mineral Resources (Sustainable Development) Act 1990*.
Geothermal energy exploration	Complies with the *Geothermal Energy Resources Act 2005*.
Geothermal energy extraction	Complies with Section 62 of the *Geothermal Energy Resources Act 2005*.
Greenhouse gas sequestration exploration	Complies with Section 189 of the *Greenhouse Gas Geological Sequestration Act 2008*.
Greenhouse gas sequestration	Complies with Section 191 of the *Geological Sequestration Act 2008*.
Mineral exploration	Complies with Section 43(3) of the *Mineral Resources (Sustainable Development) Act 1990*.
Mining	Complies with Section 42(7) or Section 42A *Mineral Resources (Sustainable Development) Act 1990*; or Complies with Section 47A of the *Electricity Industry Act 1993*.
Petroleum exploration	Complies with Section 118 of the *Petroleum Act 1998*.
Petroleum production	Complies with Section 120 of the *Petroleum Act 1998*.
Stone exploration	Must not be costeaning or bulk sampling.

52.08-2 Application requirements for mining

24/01/2020
VC160

An application to use and develop land for mining must be accompanied by:

- A copy of a work plan or a variation to an approved work plan that has received statutory endorsement under section 77TD of the *Mineral Resources (Sustainable Development) Act 1990*.
- The written notice of statutory endorsement under section 77TD(1) of the *Mineral Resources (Sustainable Development) Act 1990*.
- Any conditions specified under section 77TD(3) of the *Mineral Resources (Sustainable Development) Act 1990*.

52.08-3 Referral requirements for mining

14/05/2021
VC198

An application to use or develop land for mining must be referred under section 55 of the Act to the person or body specified as the referral authority in Clause 66.

Unless the referral authority is the Head, Transport for Victoria, the referral requirement in Clause 66 does not apply if a copy of a work plan or variation to an approved work plan accompanying the application was given to the referral authority under section 77TE of the *Mineral Resources (Sustainable Development) Act 1990*.

52.09 EXTRACTIVE INDUSTRY AND EXTRACTIVE INDUSTRY INTEREST AREAS

24/01/2020
VC160

Purpose

To ensure that use and development of land for extractive industry does not adversely affect the environment or amenity of the area during or after extraction.

To ensure that excavated areas can be appropriately rehabilitated.

To ensure that stone resources, which may be required by the community for future use, are protected from inappropriate use and development.

52.09-1 Application

24/01/2020
VC160

This clause applies to an application to use or develop land:

- For extractive industry;
- Within an Extractive Industry Interest Area; or
- Within 500 metres of an existing or proposed extractive industry operation.

52.09-2 Application requirements

24/01/2020
VC160

An application to use and develop land for extractive industry must be accompanied by:

- A copy of a work plan or a variation to an approved work plan that has received statutory endorsement under section 77TD of the *Mineral Resources (Sustainable Development) Act 1990.*
- The written notice of statutory endorsement under section 77TD(1) of the *Mineral Resources (Sustainable Development) Act 1990.*
- Any conditions specified under section 77TD(3) of the *Mineral Resources (Sustainable Development) Act 1990.*

These requirements do not apply if the proposed extractive industry is exempt from:

- The requirement to obtain a work plan under section 77G of the *Mineral Resources (Sustainable Development) Act 1990;* or
- The provisions of the *Mineral Resources (Sustainable Development) Act 1990* under section 5AA of that Act.

52.09-3 Referral of applications

22/03/2022
VC219

An application must be referred under section 55 of the Act to the person or body specified as the referral authority in Clause 66, if the application is to use or develop land for:

- Extractive industry; or
- Accommodation in a rural zone is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

Unless the referral authority is the Head, Transport for Victoria, the referral requirement in Clause 66 does not apply if a copy of a work plan or variation to an approved work plan accompanying the application was given to the referral authority under section 77TE of the *Mineral Resources (Sustainable Development) Act 1990*.

52.09-4 Decision guidelines

24/01/2020
VC160

Before deciding on an application to use and develop land for extractive industry, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The effect of the proposed extractive industry on any native flora and fauna on and near the land.
- The impact of the proposed extractive industry on sites of cultural and historic significance, including any effects on Aboriginal places.
- The effect of the proposed extractive industry on the natural and cultural landscape of the surrounding land and the locality generally.
- The ability of the proposed extractive industry to contain any emissions within the boundaries of the land in accordance with relevant legislation.
- The effect of vehicular traffic, noise, blasting, dust and vibration on the amenity of the surrounding area.
- The ability to rehabilitate the affected land to a form or for a use which is compatible with the natural systems or visual appearance of the surrounding area.
- The ability to rehabilitate the land so it can be used for a purpose or purposes beneficial to the community.
- The effect of the proposed extractive industry on groundwater quality and the impact on any affected water uses.
- The impact of the proposed extractive industry on surface drainage and surface water quality.
- Any proposed provisions, conditions or requirements in a work plan that has received statutory endorsement under the *Mineral Resources (Sustainable Development) Act 1990*.

52.09-5 Permit conditions for extractive industry

24/01/2020
VC160

A permit to use and develop land for extractive industry must not include conditions which require the use to cease by a specified date unless either:

- The subject land is situated in or adjoins land which is being developed or is proposed to be developed for urban purposes.
- Such condition is suggested by the applicant.

A permit to use and develop land for extractive industry must include:

- A condition that allows for a period of not less than five years for the use and development to commence before the permit expires under section 68 of the Act.
- Conditions that are consistent with the requirements specified in Clause 52.09-6.

52.09-6 Requirements for extractive industry

24/01/2020
VC160

The use and development of land for extractive industry must comply with the following requirements, to the satisfaction of the responsible authority:

- Except in accordance with a permit, no alteration may be made to the natural condition or topography of the land within 20 metres of the boundary of land. This does not apply to driveways, drains, bund walls or landscaping.
- Shrubs and trees must be planted and maintained to screen activity on the land.
- Parking areas must be provided for employees' cars and all vehicles used on the land.

52.09-7 Notice of an application

22/03/2022
VC219

Notice of the following kinds of applications must be given in accordance with section 52(1)(c) of the Act to the person or body specified as the person or body to be notified in Clause 66.05:

- An application to use or subdivide land or construct a building for accommodation, child care centre, education centre or hospital:

  - Within an Extractive Industry Interest Area.
  - On land which is within 500 metres of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

- An application to construct a building or construct or carry out works on land for which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.
- An application to use or develop land for accommodation in a rural zone if the building or works associated with the accommodation is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

This requirement does not apply to:

- An application to extend a building or works.
- An application that is required to be referred to the Secretary under section 55 of the Act.

52.10 RECONSTRUCTION AFTER AN EMERGENCY

05/10/2021
VC208

Purpose

To facilitate the reconstruction of buildings and works damaged or destroyed as a result of an emergency.

To facilitate the re-establishment of businesses and services after an emergency.

To facilitate the continued use of land for dwellings after an emergency.

52.10-1 Use exemptions - dwelling

18/12/2024
VC272

Any requirement of this planning scheme to obtain a permit or any provision of this planning scheme that prohibits the use of land, requires the use of land to be carried out in a particular manner, or requires a specified thing to be done to the satisfaction of a specified person or body, does not apply to the use of land (other than land in the Urban Floodway Zone) for a dwelling if the following requirements are met:

- A dwelling on the land must have been damaged or destroyed as a result of an emergency after 1 January 2019.
- The use must commence within 7 years after the date the dwelling was damaged or destroyed.
- The dwelling must not be a building that was constructed under clause 52.07.
- The land must not be used for more than the number of dwellings the land was lawfully used for before the dwelling was damaged or destroyed.
- Access to the dwelling must be provided via an all-weather road with dimensions adequate to accommodate emergency vehicles.
- The dwelling must be connected to reticulated sewerage, if available. If reticulated sewerage is not available, all wastewater from the dwelling must be treated and retained within the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017* for an on-site wastewater management system.
- The dwelling must be connected to a reticulated potable water supply or have an alternative potable water supply with adequate storage for domestic use as well as for fire fighting purposes.
- The dwelling must be connected to a reticulated electricity supply or have an alternative energy source.

52.10-2 Exemption from notice and review

18/12/2024
VC272

An application under any provision of this planning scheme to use or develop land (other than the subdivision of land) is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if the following requirements are met:

- A building or works on the land must have been damaged or destroyed as a result of an emergency after 1 January 2019.
- A use must be a use that was lawfully carried out on the land immediately before the building or works was damaged or destroyed and cannot continue without the building or works being reconstructed.
- A development must be for:
  - The repair of the damaged or destroyed building or works; or
  - The construction of a building, or the construction or carrying out of works, to replace the damaged or destroyed building or works.

- The application must be lodged within 7 years of the date the building was damaged or destroyed.
- If the application is to use or develop land for a dwelling:
  - A dwelling on the land must have been damaged or destroyed as a result of an emergency after 1 January 2019.
  - The application must only be for the number of dwellings that were damaged or destroyed.

52.10-3 Meaning of terms

05/10/2021
VC208

In this clause, ***emergency*** means:

- a bushfire; or
- an earthquake, flood, wind-storm or other natural event.

52.10-4 Transitional provision

05/10/2021
VC208

Clause 52.10-2 of this planning scheme, as in force immediately before the approval date of Amendment VC208, continues to apply to an application lodged before that date for land on which a building was damaged or destroyed by a bushfire after 1 January 2019.

52.11 HOME BASED BUSINESS

31/07/2018
VC148

Purpose

To ensure that the amenity of the neighbourhood is not adversely affected by a business conducted in or from a dwelling.

52.11-1 Requirements to be met

15/03/2024
VC256

A home based business must meet the following requirements:

- The person conducting the home based business must use the dwelling as their principal place of residence.
- No more than two persons who does not live in the dwelling may work in the home based business at any one time.
- The net floor area used in conducting the business including the storage of any materials or goods must not exceed 100 square metres or one-third of the net floor area of the dwelling, whichever is the lesser. This does not apply to the education or care of children. The net floor area includes out-buildings and works normal to a dwelling.
- The business must not impose a load on any utility greater than normally required for domestic use.
- The business must not adversely affect the amenity of the neighbourhood in any way including:
  - The appearance of any building, works or materials used.
  - The parking of motor vehicles.
  - The transporting of materials or goods to or from the dwelling.
  - The hours of operation.
  - Electrical interference.
  - The storage of chemicals, gasses or other hazardous materials.
  - Emissions from the site.
- No motor vehicle may be adjusted, modified, serviced or repaired for gain.
- Only one commercial vehicle associated with a home business not exceeding 2 tonnes capacity and with or without a trailer registered to a resident of the dwelling may be present at any time. The vehicle must not be fuelled or repaired on the site.
- No goods other than goods manufactured or serviced in the home based business may be offered for sale. This requirement does not apply to goods offered for sale online.
- Materials used or goods manufactured, serviced or repaired in the home based business must be stored within a building.
- No goods manufactured, serviced or repaired may be displayed so that they are visible from outside the site.
- Any goods offered for sale online must not be collected from the dwelling.

In this clause, a **commercial vehicle** means:

- any motor vehicle which is used or intended to be used for carrying goods in the course of any business; or
- a commercial motor vehicle within the meaning of the Road Safety Act 1986.

52.11-2 Permit requirement

15/03/2024
VC256

Despite the requirements of Clause 52.11-1, a permit may be granted for a home based business:

- Which allows no more than three people who do not live in the dwelling to work in the business at any one time; or
- Which has a floor area not exceeding 200 square metres or one-third of the net floor area of the dwelling, whichever is the lesser.
- Which allows no more than one additional commercial vehicle, not exceeding two tonnes capacity and with or without a trailer registered to a resident of the dwelling, to be present at any time.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- Whether there is a need for additional parking or loading facilities.
- The effect of any vehicle parking, storage or washing facilities on the amenity and character of the street.
- Whether the site is suitable for the particular home based business and is compatible with the surrounding use and development.
- Whether there is a need for landscaping to screen any outbuildings or car parking or loading areas or any other area relating to the home based business.

52.12 BUSHFIRE PROTECTION EXEMPTIONS

05/08/2020
VC176

Purpose

To facilitate the removal of vegetation in specified circumstances to support the protection of human life and property from bushfire.

To facilitate the construction and protection of community fire refuges and private bushfire shelters.

52.12-1 Exemptions to create defendable space around buildings used for accommodation

05/08/2020
VC176

Any requirement of a planning permit, including any condition, which has the effect of prohibiting the removal, destruction or lopping of vegetation, or any requirement of this planning scheme to obtain a planning permit, or any provision of this planning scheme that prohibits the removal, destruction or lopping of vegetation or requires the removal, destruction or lopping of vegetation to be carried out in a particular manner, does not apply to any of the following:

- The removal, destruction or lopping of any vegetation within 10 metres of an existing building used for accommodation if all of the following requirements are met:
  - The building must be located in an area that is designated as a bushfire prone area under the *Building Act 1993*.
  - The building must have been:
    - constructed before 10 September 2009; or
    - approved by a planning permit or a building permit issued before 10 September 2009; or
    - constructed to replace a dwelling or dependent persons unit that was damaged or destroyed by a bushfire that occurred between 1 January 2009 and 31 March 2009.
- The removal, destruction or lopping of any vegetation, except trees, within 30 metres of an existing building used for accommodation if all of the following requirements are met:
  - The building must be located in an area that is designated as a bushfire prone area under the *Building Act 1993*.
  - The building must have been:
    - constructed before 10 September 2009; or
    - approved by a planning permit or a building permit issued before 10 September 2009; or
    - constructed to replace a dwelling or dependent persons unit that was damaged or destroyed by a bushfire that occurred between 1 January 2009 and 31 March 2009.
- The removal, destruction or lopping of any vegetation, except trees, within 50 metres of an existing building used for accommodation if all of the following requirements are met:
  - The building must be located in the Bushfire Management Overlay.
  - The building must have been:
    - constructed before 10 September 2009; or
    - lawfully constructed without a planning permit before 18 November 2011; or
    - approved by a planning permit or a building permit issued before 10 September 2009 and constructed before 18 November 2011; or
    - constructed to replace a dwelling or dependent persons unit that was damaged or destroyed by a bushfire that occurred between 1 January 2009 and 31 March 2009.

52.12-2 Exemption for vegetation removal along a fenceline

05/08/2020
VC176

Any requirement of a planning permit, including any condition, which has the effect of prohibiting the removal, destruction or lopping of vegetation, or any requirement of this planning scheme to obtain a planning permit, or any provision of this planning scheme that prohibits the removal, destruction or lopping of vegetation or requires the removal, destruction or lopping of vegetation to be carried out in a particular manner, does not apply to the removal, destruction or lopping of any vegetation along a boundary fence between properties in different ownership if all of the following requirements are met:

- The fence must be located in an area that is designated as a bushfire prone area under the *Building Act 1993*.
- The fence must have been constructed before 10 September 2009.
- The clearing alongside both sides of the fence when combined must not exceed 4 metres in width, except where land has already been cleared 4 metres or more along one side of the fence, then up to 1 metre can be cleared along the other side of the fence.

52.12-3 Exemption for buildings and works associated with a community fire refuge

05/08/2020
VC176

Any requirement in this scheme relating to the construction of a building or the construction or carrying out of works does not apply to modifying an existing building to create a community fire refuge in accordance with Ministerial Direction No. 4, Construction Requirements for a Community Fire Refuge (1 October 2015) of the *Project Development and Construction Management Act 1994*.

52.12-4 Exemption for buildings and works associated with a private bushfire shelter

05/08/2020
VC176

Any requirement in this planning scheme relating to the construction of a building or the construction or carrying out of works does not apply to buildings and works associated with a private bushfire shelter (a Class 10c building within the meaning of the Building Regulations 2018), provided the total area of all buildings and works does not exceed 30 square metres.

This clause does not apply to land in the Urban Floodway Zone, Erosion Management Overlay, Floodway Overlay, Land Subject to Inundation Overlay, Special Building Overlay or Heritage Overlay.

52.12-5 Exemption to create defendable space for a dwelling under Clause 44.06 of this planning scheme

25/02/2025
VC257

Any requirement of a planning permit, including any condition, which has the effect of prohibiting the removal, destruction or lopping of vegetation, or any requirement of this planning scheme to obtain a planning permit, or any provision of this planning scheme that prohibits the removal, destruction or lopping of vegetation or requires the removal, destruction or lopping of vegetation to be carried out in a particular manner, does not apply to the removal, destruction or lopping of vegetation to enable the construction of a dwelling, or the alteration or extension of an existing dwelling, and create its defendable space if all of the following requirements are met:

- Land is in the Bushfire Management Overlay.
- Land is in the General Residential Zone, Residential Growth Zone, Neighbourhood Residential Zone, Housing Choice and Transport Zone, Urban Growth Zone, Low Density Residential Zone, Township Zone, Rural Living Zone, Farming Zone or Rural Activity Zone.
- The removal, destruction or lopping of vegetation:
  - Does not exceed the distance specified in Table 1 to Clause 53.02-3 of this planning scheme, based on the bushfire attack level determined by a relevant building surveyor in deciding an application for a building permit under the *Building Act 1993* for a dwelling or alteration or extension to the dwelling; or

- Is required to be undertaken by a condition in a planning permit issued after 31 July 2014 under Clause 44.06 of this scheme for a dwelling or an alteration or extension to the dwelling.

Note: The effect of clause 52.12-5 is that if an application for building and works is made and all requirements of the clause are met, that application is not required to be accompanied by a permit application to remove the vegetation covered by this clause.

52.13 VICTORIA'S CONTAINER DEPOSIT SCHEME

14/11/2022
VC227

52.13-1 Purpose

26/09/2023
VC246

To facilitate an automated collection point and a container deposit scheme centre to support waste reduction and recycling under Victoria's container deposit scheme.

To ensure an automated collection point and a container deposit scheme centre are designed and sited to minimise impacts on the land and surrounding land uses.

52.13-2 Application

26/09/2023
VC246

This clause applies to the use or development of an automated collection point and a container deposit scheme centre.

52.13-3 Automated collection point requirements

26/09/2023
VC246

An automated collection point should not:

- Be attached to another building.
- Be more than 3 metres in height. This includes an attached sign.
- Restrict a vehicular or pedestrian accessway to or from the land or an entry or exit to a building.

52.13-4 Container deposit scheme centre requirements

26/09/2023
VC246

A container deposit scheme centre should collect, consolidate, store, sort or recover materials in a fully enclosed and roofed building.

In an industrial zone, Commercial 2 Zone or Port Zone, a container deposit scheme centre should be at least 30 metres from land (not a road):

- In a residential zone (other than a Mixed Use Zone or Township Zone) or a Rural Living Zone.
- Used for, or in a Public Acquisition Overlay to be acquired for, a hospital, an education centre or a corrective institution.

In any other zone, a container deposit scheme centre should:

- Be at least 60 metres from land (not a road):
  - Used for accommodation, child care centre, pre-school centre, primary school, secondary school, education centre, informal outdoor recreation, hospital or a corrective institution.
  - To be acquired for a hospital, an education centre or a corrective institution.
- Not operate machinery to collect, consolidate, store, sort or recover materials between 5pm and 8am the following day.
- Not have more than 4 vehicle movements by the operator collecting or delivering materials to the container deposit scheme centre between 5pm and 8am the following day.

52.13-5 Permit exemption for an automated collection point

26/09/2023
VC246

Any requirement in a zone or overlay, or a schedule to a zone or overlay, to obtain a permit to construct a building or construct or carry out works does not apply to an automated collection point if the requirements of clause 52.13-3 and clause 52.13-6 are met.

This exemption does not apply to a requirement in any of the following overlays if an application for one or more automated collection points has a combined gross floor area of 2 square metres or more, and a building height of 2.5 metres or more:

Other than for a maximum of two automated collection points that are no greater than 2 square metres in total area and less than 2.5 metres in height, this exemption does not apply to a requirement in a:

- Bushfire Management Overlay if the automated collection point is located less than 10 meters from a building used for accommodation, education centre, hospital, leisure and recreation, or place of assembly.
- Environmental Significance Overlay.
- Floodway Overlay.
- Heritage Overlay.
- Land Subject to Inundation Overlay.
- Public Acquisition Overlay.
- Significant Landscape Overlay.
- Special Building Overlay.

52.13-6 Permit exemption requirement for an automated collection point

26/09/2023
VC246

For the purposes of clause 52.13-5, an automated collection point with a gross floor area less than 2 square metres, and a building height less than 2.5 metres must:

- Be set back at least 30 metres from land (not a road) not in the same ownership in a residential zone (other than a Mixed Use Zone or Township Zone) or a Rural Living Zone.
- Be set back at least 30 metres from a dwelling in a Township Zone.
- Not be located on vacant land in a residential or rural zone.
- Not be located in an area set aside for vehicle access or occupy a car parking space.
- Be of muted, non-reflective external colours and finishes.

For the purposes of clause 52.13-5, an automated collection point with a gross floor area of 2 square metres or more, and a building height of 2.5 metres or more must:

- Occupy no more than:
  - 4 existing car parking spaces on the land; or,
  - 5 existing car parking spaces on the land if the land contains 50 or more car parking spaces.
- Be set back at least 4 metres from the frontage.
- Be set back at least 30 metres from land (not a road) not in the same ownership in a residential zone, Rural Living Zone or Urban Growth Zone.
- Not be located on vacant land in a residential or rural zone.
- Be of muted, non-reflective external colours and finishes.

52.13-7 Exemption from car parking requirements for an automated collection point

26/09/2023
VC246

An automated collection point is exempt from the requirements of clause 52.06.

52.13-8 Exemption from permit conditions for an automated collection point

26/09/2023
VC246

Any requirement of a permit, or any permit condition, that requires the provision of car parking, or requires land to be set aside for vehicle access or car parking, does not apply to the use or development of land for an automated collection point if the requirements of clause 52.13-3 are met.

52.13-9 Application requirements

26/09/2023
VC246

An application must be accompanied by the following information as appropriate:

- A site context plan that specifies the location and nature of land use within 100 metres of site boundaries.
- A site and layout plan that includes:
  - Design for safe pedestrian and vehicle movements.
  - Any additional lighting to be included and any proposed baffling.
  - Any existing automated collection points on the site.
- An operational plan that includes:
  - Operating days and hours.
  - Noise, emissions and amenity attenuation measures. This may include a report on how noise and amenity impacts from the use will be reduced.
  - Safety and access details including how the use will be serviced, emptied and how materials will be moved to and from the site.
  - Details and methods of managing the collection, consolidation, storage sorting and recovery of materials within a building to reduce noise and amenity impacts on surrounding land.
  - Details of traffic and car parking requirements generated by the use.

52.13-10 Decision guidelines

26/09/2023
VC246

Before deciding on an application, in addition to the decision guidelines in clause 65, the responsible authority must consider, as appropriate:

- The effect on existing car parking provision if an automated collection point is located on existing car parking spaces.
- The setback of the development from a frontage and from land (not a road) not in the same ownership in a residential zone, Rural Living Zone or Urban Growth Zone.
- The effect of siting an automated collection point on vacant land in a residential or rural zone.
- The effect of external colours and finishes.
- The size, density and number of automated collection points including the cumulative impact of automated collection points on the land.
- Whether a proposed operational plan reduces noise and other impacts on nearby land uses.
- Safe pedestrian and vehicle movements on the land.
- The effect of noise, emissions, traffic movements and other amenity impacts on adjoining land uses.
- In a zone other than an industrial zone, Commercial 2 Zone or Port Zone the effect of noise, emissions, traffic movements and other amenity impacts of a container deposit scheme centre on adjacent and nearby sensitive land uses.

52.13-11 Exemption from notice and review

26/09/2023
VC246

An application to use or develop land for an automated collection point including the construction of or putting up for display a sign in conjunction with an automated collection point is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

An application to use or develop a container deposit scheme centre, including the construction of or putting up for display a sign in conjunction with a container deposit scheme centre is exempt from:

- In an industrial zone, Commercial 2 Zone and Port Zone, the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.
- In any other zone, the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

52.13-12 Transitional provisions

26/09/2023
VC246

The requirements of this clause introduced by Amendment VC246 do not apply to:

- An application for an automated collection point or container deposit scheme centre lodged before the approval date of Amendment VC246.
- An application for an amendment of a permit for an automated collection point or container deposit scheme centre under section 72 of the Act if the original permit application was lodged before the approval date of Amendment VC246.

52.14 2009 BUSHFIRE - REPLACEMENT BUILDINGS

31/07/2018
VC148

Purpose

To support the rebuilding of dwellings, dependent persons' units and buildings used for agriculture damaged or destroyed by the 2009 Victorian bushfires.

52.14-1 Scope

14/12/2020
VC188

This clause applies to:

- The construction of a building or the construction and carrying out of works, associated with rebuilding:
  - a dwelling or dependent person's unit; or
  - a building used for agriculture,

  that was damaged or destroyed by a bushfire that occurred between 1 January 2009 and 31 March 2009.
- The use of land for:
  - a dwelling or dependent person's unit that is rebuilt in accordance with this clause; or
  - agriculture to the extent that the use relates to a building that was destroyed by a bushfire that occurred between 1 January 2009 and 31 March 2009 and that use cannot continue unless that building is rebuilt.
- The removal, destruction or lopping of vegetation to enable the construction, use and maintenance of a building rebuilt in accordance with this Clause.

This clause does not apply to land in a Heritage Overlay.

For the avoidance of doubt, any planning permit exemption provided by the scheme continues to apply to the use and development specified in this Clause.

52.14-2 Exemption from planning scheme requirements

20/01/2022
VC205

Any requirement of the scheme to obtain a permit or any provision in the scheme which prohibits the use or development of land or requires the use or development of land to be carried out in a particular manner does not apply to the use and development specified in Clause 52.14-1 provided the following requirements are met:

Site plan

Before the commencement of construction of a building or the construction or carrying out of works, a site plan must be provided to and approved by the responsible authority. The site plan must show:

- The boundaries of the property.
- The location of any damaged or destroyed dwelling, dependent person's unit or building used for agriculture.
- The proposed location of the replacement dwelling, dependent person's unit or building used for agriculture.
- The existing and proposed access to the lot.

- Vegetation to be removed destroyed or lopped to enable rebuilding including construction of vehicle access, water storage and waste water treatment.
- For replacement dwellings and dependent persons' units on land in a Farming Zone, Rural Conservation Zone, Rural Activity Zone, Green Wedge Zone, Green Wedge A Zone or the Rural Living Zone:
  - The location and dimensions of vehicle access.
  - The location and storage of water for potable and fire fighting purposes if the dwelling or dependent person's unit cannot be connected to a reticulated potable water supply.
  - The location of the waste water treatment system if waste water is to be retained and treated on site.

The site plan must be submitted to the responsible authority by 30 September 2017.

Commencement of development

- The development must commence within two years after the approval of a site plan by the responsible authority and must be completed within two years after the development commences. The responsible authority may allow an extension of time on the request of the owner or the occupier of the land to which the approved site plan applies, provided that request is made before the expiry of the applicable period or within three months of the expiry of the applicable period.

Compliance with site plan

- The development must comply with the approved site plan.

Use and development conditions

- The land must not be used for more than the number of dwellings or dependent persons' units that were damaged or destroyed.
- The removal, destruction or lopping of vegetation to enable the maintenance of a building must not exceed 10 metres beyond the building.
- For land in the Farming Zone, Rural Conservation Zone, Rural Activity Zone, Green Wedge Zone, Green Wedge A Zone or the Rural Living Zone:
  - Access to the dwelling or dependent person's unit must be provided via an all weather road with dimensions adequate to accommodate emergency vehicles.
  - The dwelling or dependent person's unit must be connected to a reticulated sewerage system or if not available, the waste water must be managed to the satisfaction of the responsible authority.
  - The dwelling or dependent person's unit must be connected to a reticulated potable water supply or have an alternative potable water supply with adequate storage for domestic use as well as for fire fighting purposes.
  - The dwelling or dependent person's unit must be connected to a reticulated electricity supply or have an alternative energy source.
- A building must be constructed of materials that are non-reflective and of muted tones in the following locations:
  - Land in an Environmental Significance Overlay, Design and Development Overlay or Significant Landscape Overlay.
  - Land in a Green Wedge Zone, Green Wedge A Zone or Rural Conservation Zone in the municipal districts of the Shire of Yarra Ranges and the Shire of Nillumbik.

- For land in a Restructure Overlay, a building must be consistent with any Restructure Plan.
- For land adjacent to a Transport Zone 2 or Land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority and the purpose of the acquisition is for a road, access must not be created or altered.

52.14-3 Land in an Erosion Management Overlay

31/07/2018
VC148

For land in an Erosion Management Overlay in the municipal district of the Shire of Yarra Ranges, in addition to the requirements specified in Clause 52.14-2, the written authorisation of the responsible authority must be obtained prior to:

- Constructing a building or constructing and carrying out works; or
- Removing, destroying or lopping vegetation.

52.14-4 Land in a Floodway Overlay, Land Subject to Inundation Overlay or Special Building Overlay

31/07/2018
VC148

For land in a Floodway Overlay, Land Subject to Inundation Overlay or Special Building Overlay, in addition to the requirements specified in Clause 52.14-2, the written authorisation of the relevant flood plain management authority must be obtained prior to the commencement of construction of a building or the construction or carrying out of works.

52.14-5 Decision guidelines

31/07/2018
VC148

Before deciding on approval of the site plan, in addition to the decision guidelines in Clause 65 and any other requirements of the Act, the responsible authority must consider, as appropriate:

- The extent to which the siting of the building and associated development can reasonably achieve compliance with other relevant requirements of this scheme.
- The extent to which the replacement dwelling or dependent person's unit can be located on the land to assist the minimisation of risk to life and property from bushfire.

52.15 HELIPORT AND HELICOPTER LANDING SITE

29/10/2015
VC101

Purpose

To ensure the amenity impacts of a heliport and a helicopter landing site on surrounding areas is considered.

52.15-1 Permit requirement

20/03/2023
VC229

A permit is required to use or develop any land for a heliport or a helicopter landing site even if it is ancillary to another use on the land, unless the table to this Clause specifically states that a permit is not required.

Table of exemptions for use

No permit is required to use land for a helicopter landing site if any of the following apply:	
Emergency services	The helicopter landing site is used by a helicopter engaged in the provision of emergency service operations.
Agriculture	The helicopter landing site is used by a helicopter engaged in agricultural activity in conjunction with the use of any land for agriculture.
Public land management	The helicopter landing site is used by a helicopter engaged in the provision of public land management activities conducted by or on behalf of any of the following: ▪ Department of Energy, Environment and Climate Action; ▪ The Department of Transport and Planning; ▪ Parks Victoria; or ▪ The Great Ocean Road Coast and Parks Authority, whether on private land or not.
General	The helicopter landing site where either: ▪ The landing point is located more than 500 metres from a building used for a sensitive use (accommodation, child care centre, education centre and hospital) that is not associated with the helicopter operation and more than 200 metres from a shipping channel in the Port of Melbourne, provided: – The number of flight movements does not exceed eight in a 30 day period and four in a 24 hour period (for the purposes of this provision the take off and landing of a helicopter are separate flight movements). – Flight movements do not take place before 7am or after sunset on a weekday. – Flight movements do not take place before 8am or after sunset on a weekend or holiday; or ▪ The landing point is located more than 1000 metres from a building used for a sensitive use that is not associated with the helicopter operation and more than 200 metres from a shipping channel in the Port of Melbourne.

52.15-2 Application requirements

18/12/2012
VC93

An application to use or develop land for a heliport or a helicopter landing site must be accompanied by the following information, as appropriate:

- A site plan, including:
  - Site boundaries and dimensions.
  - The current land use.
  - The existing siting and layout of buildings and works.
  - The proposed siting and layout of buildings and works.
  - Existing vegetation and proposed vegetation removal.

- Vehicle and pedestrian access.

An application to use land for a heliport or a helicopter landing site must be accompanied by the following information:

- A location plan, including:
  - The siting and use of buildings on adjacent properties.
  - The direction and distance to any building used for a sensitive use (accommodation, child care centre, education centre and hospital) that is not associated with the helicopter operation and is located within 500 metres of the proposed heliport or helicopter landing site.
- A written report which:
  - Demonstrates a suitable separation distance between the landing point of a heliport or helicopter landing site and any building used for a sensitive use that is not associated with the helicopter operation by either:
  - Locating the proposed heliport or helicopter landing site at least 150 metres for helicopters of less than 2 tonnes all-up weight, or 250 metres for helicopters of less than 15 tonnes all-up weight, or
  - Providing an acoustic report by a suitably qualified consultant.
  - Includes details of the proposed frequency of flight movements.
  - Includes the proposed hours of operation.

52.15-3 Decision guidelines

18/12/2012
VC93

Before deciding on an application to use land for a heliport or a helicopter landing site, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- Whether the proposal achieves a suitable separation distance from a nearby sensitive use, having regard to the Noise Control Guidelines (Environment Protection Authority, 2008).
- The effect of the proposal on nearby sensitive uses in terms of the proposed frequency of flight movements and hours of operation.

52.16 NATIVE VEGETATION PRECINCT PLAN

14/07/2022
VC213

Purpose

To provide for the protection, management and removal of native vegetation through the use of a native vegetation precinct plan incorporated into this scheme.

To ensure that there is no net loss to biodiversity as a result of the removal, destruction or lopping of native vegetation. This is achieved by applying the following three step approach in accordance with the *Guidelines for the removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, 2017) (the Guidelines):

1. Avoid the removal, destruction or lopping of native vegetation.
2. Minimise impacts from the removal, destruction or lopping of native vegetation that cannot be avoided.
3. Provide an offset to compensate for the biodiversity impact if a permit is granted to remove, destroy or lop native vegetation.

To manage the removal, destruction or lopping of native vegetation to minimise land and water degradation.

52.16-1 Application

12/12/2017
VC138

This clause applies to land if a native vegetation precinct plan corresponding to that land is incorporated into this scheme and listed in the schedule to this clause.

52.16-2 Native vegetation precinct plans

14/07/2022
VC213

A native vegetation precinct plan is a plan relating to native vegetation within a defined area which is incorporated into this scheme and listed in the schedule to this clause.

A native vegetation precinct plan may form part of a more general strategic or precinct structure plan.

A native vegetation precinct plan must include the information and provide for the matters set out in section 10.1 of the Guidelines.

52.16-3 Permit requirement

12/12/2017
VC138

A permit is required to remove, destroy or lop any native vegetation, including dead native vegetation. This does not apply:

- If the removal, destruction or lopping of native vegetation is in accordance with a native vegetation precinct plan incorporated into this scheme. Any conditions or requirements specified in the plan must be met.
- To the removal, destruction or lopping of native vegetation specified in the table to Clause 52.16-8, unless a native vegetation precinct plan specifies otherwise.

52.16-4 Application requirements

14/07/2022
VC213

An application to remove, destroy or lop native vegetation must comply with the application requirements specified in the Guidelines.

52.16-5 Decision guidelines

14/07/2022
VC213

Before deciding on an application, in addition to the decision guidelines at Clause 65, the responsible authority must consider the decision guidelines specified in the Guidelines as appropriate.

52.16-6 Offset requirements

14/07/2022
VC213

If a permit is required to remove, destroy or lop native vegetation, the biodiversity impacts from the removal, destruction or lopping of native vegetation must be offset in accordance with the Guidelines. The conditions on the permit for the removal, destruction or lopping of native vegetation must specify the offset requirement and timing to secure the offset.

52.16-7 Transitional provisions

20/03/2023
VC229

The requirements of this clause in force immediately before the commencement of Amendment VC138 continue to apply to an application for:

- A permit lodged before that date.
- An amendment to a permit if:
  - the original permit application was lodged before that date; or
  - the original permit application was one that benefited from the following transitional provision.
- A permit lodged within 12 months after that date, if the Secretary to the Department of Environment, Land Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*) has stated in writing that a report about the proposed removal, destruction or lopping of native vegetation has been generated by the Department's native vegetation information systems within 12 months before that date.

52.16-8 Table of exemptions

16/08/2024
VC262

The requirement to obtain a permit does not apply to:	
Conservation work	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of conservation work: ▪ which provides an overall improvement for biodiversity; and ▪ with written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Crown land	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to manage Crown land: ▪ by or on behalf of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*), the Great Ocean Road Coast and Parks Authority or Parks Victoria, and in accordance with the *Procedure for the removal, destruction or lopping of native vegetation on Crown land*; or ▪ with written permission from the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Emergency works	Native vegetation that is to be removed, destroyed or lopped: ▪ in an emergency by or on behalf of a public authority or municipal council to create an emergency access associated with emergency works; or ▪ where it presents an immediate risk of personal injury or damage to property. Only that part of the vegetation that presents the immediate risk may be removed, destroyed or lopped under this exemption.
Extractive industry	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of extractive industry in accordance with a work plan approved under the *Mineral Resources (Sustainable Development) Act 1990* and authorised by a work authority under that Act.
Fire protection	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out any of the following fire protection activities:

The requirement to obtain a permit does not apply to:	
	▪ fire fighting; ▪ planned burning; ▪ making or maintenance of a fuelbreak or fire fighting access track (or any combination thereof) that does not exceed a combined width of 6 metres; ▪ making a strategic fuelbreak up to 40 metres wide by, or on behalf of, a public authority in accordance with a strategic fuelbreak plan approved by the Secretary to the Department of Environment, Land, Water and Planning (as constituted under *Part 2 of the Conservation, Forests and Lands Act 1987*); ▪ in accordance with a fire prevention notice issued under either: – section 87 of the *Fire Rescue Victoria Act 1958*; – section 65 of the *Forests Act 1958*; or – section 41 of the *Country Fire Authority Act 1958*. ▪ keeping native vegetation clear of, or minimising the risk of bushfire ignition from, an electric line in accordance with a code of practice prepared under Part 8 of the *Electricity Safety Act 1998*; ▪ minimising the risk to life and property from bushfire on a roadside of a public road managed by the relevant responsible road authority, and carried out by or on behalf of that authority, in accordance with written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the Conservation, Forest and Lands Act 1987). In this exemption, roadside, public road and responsible road authority have the same meanings as in section 3 of the *Road Management Act 2004*. *Note: Additional permit exemptions for bushfire protection are provided at Clause 52.12.*
Geothermal energy exploration and extraction	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary in accordance with an operation plan approved under the *Geothermal Energy Resources Act 2005*.
Greenhouse gas sequestration and exploration	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary in accordance with an operation plan approved under the *Greenhouse Gas Geological Sequestration Act 2008*.
Land management or directions notice	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to comply with a land management notice or directions notice served under the *Catchment and Land Protection Act 1994*.
Land use conditions	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to comply with a land use condition served under the *Catchment and Land Protection Act 1994*.
Mineral exploration and mining	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by the holder of an exploration mining, prospecting, or retention license issued under the *Mineral Resources (Sustainable Development) Act 1990*: ▪ that is low impact exploration within the meaning of Schedule 4A of the *Mineral Resources (Sustainable Development) Act 1990*; or ▪ in accordance with a work plan approved under Part 3 of the *Mineral Resources (Sustainable Development) Act 1990*. *Note: Schedule 4A of the Mineral Resources (Sustainable Development) Act 1990 specifies limits on the extent of native vegetation that may be removed as part of low impact exploration.*
Pest animal burrows	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the removal of pest animal burrows in accordance with the written agreement of an officer of the department responsible for administering the *Flora and Fauna Guarantee Act 1988*.
Planted vegetation	Native vegetation that is to be removed, destroyed or lopped that was either planted or grown as a result of direct seeding for Crop raising or Grazing animal production.

The requirement to obtain a permit does not apply to:	
	This exemption does not apply to native vegetation planted or managed with public funding for the purpose of land protection or enhancing biodiversity unless the removal, destruction or lopping of the native vegetation is in accordance with written permission of the agency (or its successor) that provided the funding.
Railways	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to maintain the safe and efficient function of an existing railway, or railway access road, in accordance with written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Regrowth	Native vegetation that is to be removed, destroyed or lopped that has naturally established or regenerated on land lawfully cleared of naturally established native vegetation, and is: ▪ bracken (*Pteridium esculentum*); or ▪ within the boundary of a timber production plantation, as indicated on a Plantation Development Notice or other documented record, and has established after the plantation. This exemption does not apply to land where native vegetation has been destroyed or otherwise damaged as a result of flood, fire or other natural disaster.
Road safety	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by or on behalf of a public authority or municipal council to maintain the safe and efficient function of an existing road in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Stone exploration	▪ Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of Stone exploration. The maximum extent of native vegetation that may be removed, destroyed or lopped under this exemption on contiguous land in the same ownership in a five year period must not exceed any of the following: ▪ 1 hectare of native vegetation which does not include a tree. ▪ 15 native trees with trunk diameter of less than 40 centimetres at a height of 1.3 metres above ground level. ▪ 5 native trees with trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level. This exemption does not apply to costeaning and bulk sampling activities.
Surveying	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by, or on behalf of, a licensed surveyor (within the meaning of section 3 of the *Surveying Act 2004*) using hand-held tools to establish a sightline for the measurement of land.
Traditional owners	Native vegetation that is to be removed, destroyed or lopped by a person acting under, and in accordance with: ▪ a natural resource agreement under Part 6 of the *Traditional Owner Settlement Act 2010*; or ▪ an authorisation order made under sections 82 or 84 of the *Traditional Owner Settlement Act 2010* as those sections were in force immediately before the commencement of section 24 of the *Traditional Owner Settlement Amendment Act in 2016* (1 May 2017).
Utility installations	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary: ▪ to maintain the safe and efficient function of a Minor utility installation; or ▪ by or on behalf of a utility service provider to maintain or construct a utility installation in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).

52.16-9 Melbourne Strategic Assessment Levy Area

14/07/2022
VC213

The following provisions apply to the removal, destruction or lopping of native vegetation in the levy area within the meaning of the *Melbourne Strategic Assessment (Environment Mitigation Levy) Act 2020*.

Despite clauses 52.16-4, 52.16-5, 52.16-6 and anything in the Guidelines:

- An application to remove, destroy or lop native vegetation is not required to be accompanied by an offset statement providing evidence that an offset that meets the offset requirements for the native vegetation to be removed has been identified and can be secured in accordance with the Guidelines.
- Before deciding on an application, a responsible authority is not required to consider whether an offset that meets the offset requirements for the native vegetation to be removed has been identified and can be secured in accordance with the Guidelines.
- The biodiversity impacts of the removal, destruction or lopping of native vegetation are not required to be offset in accordance with the Guidelines.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 52.16 NATIVE VEGETATION PRECINCT PLAN

1.0 Native vegetation precinct plan

08/07/2021
C211brim

Name of plan
None specified

52.17 NATIVE VEGETATION

14/07/2022
VC213

Purpose

To ensure that there is no net loss to biodiversity as a result of the removal, destruction or lopping of native vegetation. This is achieved by applying the following three step approach in accordance with the *Guidelines for the removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, 2017) (the Guidelines):

1. Avoid the removal, destruction or lopping of native vegetation.

2. Minimise impacts from the removal, destruction or lopping of native vegetation that cannot be avoided.

3. Provide an offset to compensate for the biodiversity impact if a permit is granted to remove, destroy or lop native vegetation.

To manage the removal, destruction or lopping of native vegetation to minimise land and water degradation.

52.17-1 Permit requirement

12/12/2017
VC138

A permit is required to remove, destroy or lop native vegetation, including dead native vegetation. This does not apply:

- If the table to Clause 52.17-7 specifically states that a permit is not required.
- If a native vegetation precinct plan corresponding to the land is incorporated into this scheme and listed in the schedule to Clause 52.16.
- To the removal, destruction or lopping of native vegetation specified in the schedule to this clause.

52.17-2 Application requirements

14/07/2022
VC213

An application to remove, destroy or lop native vegetation must comply with the application requirements specified in the Guidelines.

52.17-3 Property vegetation plans

12/12/2017
VC138

A permit granted to remove, destroy or lop native vegetation in accordance with a property vegetation plan must include the following condition:

"This permit will expire if one of the following circumstances applies:

- The removal, destruction or lopping of native vegetation does not start within two years of the date of this permit.
- The removal, destruction or lopping of native vegetation is not completed within ten years of the date of this permit."

52.17-4 Decision guidelines

12/12/2017
VC138

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider the decision guidelines specified in the Guidelines as appropriate.

52.17-5 Offset requirements

14/07/2022
VC213

If a permit is required to remove, destroy or lop native vegetation, the biodiversity impacts from the removal, destruction or lopping of native vegetation must be offset, in accordance with the Guidelines. The conditions on the permit for the removal, destruction or lopping of native vegetation must specify the offset requirement and the timing to secure the offset.

52.17-6 Transitional provisions

20/03/2023
VC229

The requirements of this clause in force immediately before the commencement of Amendment VC138 continue to apply to an application for:

- A permit lodged before that date.
- An amendment to a permit if:
  - the original permit application was lodged before that date; or
  - the original permit application was one that benefited from the following transitional provision.
- A permit lodged within 12 months after that date, if the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*) has stated in writing that a report about the proposed removal, destruction or lopping of native vegetation has been generated by the Department's native vegetation information systems within 12 months before that date.

52.17-7 Table of exemptions

16/08/2024
VC262

The requirement to obtain a permit does not apply to:	
Conservation work	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of conservation work: ▪ which provides an overall improvement for biodiversity; and ▪ with written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Crown land	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to manage Crown land: ▪ by or on behalf of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*), the Great Ocean Road Coast and Parks Authority or Parks Victoria, and in accordance with the *Procedure for the removal, destruction or lopping of native vegetation on Crown land*; or ▪ with written permission from the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Dead native vegetation	Native vegetation that is dead. This exemption does not apply to a standing dead tree with a trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level.
Emergency works	Native vegetation that is to be removed, destroyed, or lopped: ▪ in an emergency by, or on behalf of, a public authority or municipal council to create an emergency access associated with emergency works; or ▪ where it presents an immediate risk of personal injury or damage to property. Only that part of the vegetation that presents the immediate risk may be removed, destroyed or lopped under this exemption.

The requirement to obtain a permit does not apply to:	
Existing buildings	Native vegetation that is to be removed, destroyed, or lopped to the minimum extent necessary to enable the use or maintenance of a building constructed in accordance with a planning or building permit issued before 15 September 2008. This exemption does not apply to: ▪ the operation or maintenance of a fence; or ▪ native vegetation located more than 10 metres measured from the outermost point of the building.
Existing buildings and works in the Farming Zone and Rural Activity Zone	Native vegetation that is to be removed, destroyed, or lopped to the minimum extent necessary to enable the use or maintenance of an existing building or works used for Agricultural production, including a dam, utility service, bore, horticultural trellising and accessway in the Farming Zone or the Rural Activity Zone. This exemption does not apply to: ▪ the use or maintenance of a Dwelling; or ▪ the operation or maintenance of a fence; or ▪ native vegetation located more than 10 metres measured from the outermost point of the building or works.
Extractive industry	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of extractive industry in accordance with a work plan approved under the *Mineral Resources (Sustainable Development) Act 1990* and authorised by a work authority under that Act.
Fences	Native vegetation that is to be removed, destroyed, or lopped to the minimum extent necessary to enable: ▪ the operation or maintenance of an existing fence; or ▪ the construction of a boundary fence between properties in different ownership. The clearing along both sides of the fence when combined must not exceed 4 metres in width, except where land has already been cleared 4 metres or more along one side of the fence, then up to 1 metre can be cleared along the other side of the fence.
Fire protection	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to carry out any of the following fire protection activities: ▪ fire fighting; ▪ planned burning; ▪ making or maintenance of a fuelbreak or firefighting access track (or any combination thereof) that does not exceed a combined width of 6 metres; ▪ making a strategic fuelbreak up to 40 metres wide by, or on behalf of, a public authority in accordance with a strategic fuelbreak plan approved by the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*); ▪ in accordance with a fire prevention notice issued under either: – section 87 of the *Fire Rescue Victoria Act 1958*; – section 65 of the *Forests Act 1958*; or – section 41 of the *Country Fire Authority Act 1958*.

The requirement to obtain a permit does not apply to:	
	▪ keeping native vegetation clear of, or minimising the risk of bushfire ignition from, an electric line in accordance with a code of practice prepared under Part 8 of the *Electricity Safety Act 1998*; ▪ minimising the risk to life and property from bushfire on a roadside of a public road managed by the relevant responsible road authority, and carried out by or on behalf of that authority, in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*). In this exemption, roadside, public road and responsible road authority have the same meanings as in section 3 of the *Road Management Act 2004*. *Note: Additional permit exemptions for bushfire protection are provided at Clause 52.12.*
Geothermal energy exploration and extraction	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary in accordance with an operation plan approved under the *Geothermal Energy Resources Act 2005*.
Grasses	Native grass that is to be mowed or slashed for maintenance only, provided that the grass is: ▪ located within a lawn, garden or other landscaped area; or ▪ maintained at a height of at least 10 centimetres above ground level.
Grazing	Native vegetation that is to be removed, destroyed or lopped by domestic stock grazing on: ▪ freehold land; or ▪ Crown land in accordance with a license, permit or lease granted under applicable legislation.
Greenhouse gas sequestration and exploration	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary in accordance with an operation plan approved under the *Greenhouse Gas Geological Sequestration Act 2008*.
Harvesting for timber production – naturally established native vegetation	Naturally established native vegetation that is to be removed, destroyed or lopped to enable timber harvesting operations and associated activities that are in accordance with the *Code of Practice for Timber Production 2014 (as amended 2022)* (Department of Environment, Land, Water and Planning, 2022) and are: ▪ undertaken on public land under a licence or permit issued under section 52 of the *Forests Act 1958*; or ▪ authorised in accordance with Part 5 of the *Sustainable Forests (Timber) Act 2004*.
Land management or directions notice	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to comply with a land management notice or directions notice served under the *Catchment and Land Protection Act 1994*.
Land use conditions	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to comply with a land use condition served under the *Catchment and Land Protection Act 1994*.

The requirement to obtain a permit does not apply to:	
Lopping and pruning for maintenance	Lopping or pruning native vegetation, for maintenance only, provided no more than 1/3 of the foliage of each individual plant is lopped or pruned. This exemption does not apply to: ▪ the pruning or lopping of the trunk of a native tree; or ▪ native vegetation on a roadside or railway reservation.
Mineral exploration and extraction	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by the holder of an exploration, mining, prospecting, or retention license issued under the *Mineral Resources (Sustainable Development) Act 1990*: ▪ that is low impact exploration within the meaning of Schedule 4A of the *Mineral Resources (Sustainable Development) Act 1990*; or ▪ in accordance with a work plan approved under Part 3 of the *Mineral Resources (Sustainable Development) Act 1990*. *Note: Schedule 4A of the Mineral Resources (Sustainable Development) Act 1990 specifies limits on the extent of native vegetation that may be removed as part of low impact exploration.*
New buildings and works in the Farming Zone and Rural Activity Zone	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the construction of a building or works used for Agricultural production, including a dam, utility service, bore and accessway, in the Farming Zone or the Rural Activity Zone. The maximum extent of native vegetation that may be removed, destroyed or lopped under this exemption on contiguous land in the same ownership in a five year period must not exceed any of the following: ▪ 1 hectare of native vegetation which does not include a tree. ▪ 15 native trees with a trunk diameter of less than 40 centimetres at a height of 1.3 metres above ground level. ▪ 5 native trees with a trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level. This exemption does not apply to the construction or operation of a pivot irrigation system or horticultural trellising.
New dwellings in the Farming Zone and Rural Activity Zone	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the construction of a dwelling in the Farming Zone or Rural Activity Zone. The maximum extent of native vegetation removed, destroyed or lopped under this exemption on contiguous land in the same ownership in a five year period must not exceed any of the following: ▪ 300 square metres of native vegetation which does not include a tree. ▪ 5 native trees with a trunk diameter of less than 40 centimetres at a height of 1.3 metres above ground level. ▪ 1 native tree with a trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level. This exemption does not apply native vegetation removed, destroyed or lopped to enable the construction of a swimming pool, tennis court or horse ménage.

The requirement to obtain a permit does not apply to:	
Personal use	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to obtain reasonable amounts of wood for personal use by the owner or lawful occupier of the land. For the purpose of this exemption personal use means uses such as heating and cooking, building and fence construction on land, and hobbies such as arts and craft. This exemption does not apply to: ▪ contiguous land in one ownership that has an area of less than 10 hectares; ▪ the removal, destruction or lopping of native vegetation by means other than cutting or chopping; or ▪ a standing native tree (including a dead tree) with a trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level.
Pest animal burrows	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the removal of pest animal burrows in the Farming Zone or the Rural Activity Zone: ▪ in accordance with written agreement of an officer of the department responsible for administering the *Flora and Fauna Guarantee Act 1988*; or ▪ provided the maximum extent of native vegetation removed, destroyed or lopped on contiguous land in the same ownership in a five year period does not exceed any of the following: – 1 hectare of native vegetation which does not include a tree; or – 15 native trees with a trunk diameter of less than 20 centimetres at a height of 1.3 metres above ground level.
Planted vegetation	Native vegetation that is to be removed, destroyed or lopped that was either planted or grown as a result of direct seeding. This exemption does not apply to native vegetation planted or managed with public funding for the purpose of land protection or enhancing biodiversity unless the removal, destruction or lopping of the native vegetation is in accordance with written permission of the agency (or its successor) that provided the funding.
Railways	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to maintain the safe and efficient function of an existing railway, or railway access road, in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Regrowth	Native vegetation that is to be removed, destroyed or lopped that has naturally established or regenerated on land lawfully cleared of naturally established native vegetation, and is: ▪ less than 10 years old; or ▪ bracken (*Pteridium esculentum*); or

The requirement to obtain a permit does not apply to:	
	▪ within the boundary of a timber production plantation, as indicated on a Plantation Development Notice or other documented record, and has established after the plantation; or ▪ less than ten years old at the time of a property vegetation plan being signed by the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*), and is: – shown on that plan as being 'certified regrowth'; and – on land that is to be used or maintained for cultivation or pasture during the term of that plan. This exemption does not apply to land where native vegetation has been destroyed or otherwise damaged as a result of flood, fire or other natural disaster.
Road safety	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by and on behalf of a public authority or municipal council to maintain the safe and efficient function of an existing road in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Site area	Native vegetation that is to be removed, destroyed or lopped on land, together with all contiguous land in one ownership, which has an area of less than 0.4 hectares. This exemption does not apply to native vegetation on a roadside or rail reservation.
Stock movements on roads	Native vegetation that is to be removed, or destroyed by stock being moved along a road. This exemption does not apply to grazing as a result of holding stock in a temporary fence (including an electric fence) on a roadside for the purpose of feeding.
Stone exploration	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the carrying out of Stone exploration. The maximum extent of native vegetation that may be removed, destroyed or lopped under this exemption on contiguous land in the same ownership in a five year period must not exceed any of the following: ▪ 1 hectare of native vegetation which does not include a tree. ▪ 15 native trees with a trunk diameter of less than 40 centimetres at a height of 1.3 metres above ground level. ▪ 5 native trees with a trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level. This exemption does not apply to costeaning and bulk sampling activities.
Surveying	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by, or on behalf of, a licenced surveyor (within the meaning of section 3 of the *Surveying Act 2004*) using hand-held tools to establish a sightline for the measurement of land.
Traditional owners	Native vegetation that is to be removed, destroyed or lopped by a person acting under, and in accordance with:

The requirement to obtain a permit does not apply to:	
	▪ a natural resource agreement under Part 6 of the *Traditional Owner Settlement Act 2010*; or ▪ an authorisation order made under sections 82 or 84 of the *Traditional Owner Settlement Act 2010* as those sections were in force immediately before the commencement of section 24 of the *Traditional Owner Settlement Amendment Act* in 2016 (1 May 2017).
Tram stops	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by or on behalf of the Head, Transport for Victoria to construct a tram stop, including a tram stop shelter.
Transport land	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary by or on behalf of the Head, Transport for Victoria on land in a Transport Zone, or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority, to construct or maintain transport system infrastructure, in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Utility installations	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary: ▪ to maintain the safe and efficient function a Minor utility installation; or ▪ by or on behalf of a utility service provider to maintain or construct a utility installation in accordance with the written agreement of the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).
Vehicle access from public roads	Native vegetation that is to be removed, destroyed, or lopped to the minimum extent necessary to enable the construction or maintenance of a vehicle access across a road reserve from a property boundary to a public road. This exemption only applies to properties which share a common boundary with the road reserve, and the total width of clearing must not exceed 6 metres. This exemption does not apply where there is a practical opportunity to site the accessway to avoid the removal, destruction or lopping of native vegetation. In this exemption, roadside and public road have the same meanings as in section 3 of the *Road Management Act 2004*. *Note: Under the Road Management Act 2004 the written consent of the coordinating road authority is required to conduct any works, including removing a tree or other vegetation, in, on, under or over a road.*
Weeds	Native vegetation that is to be removed, destroyed or lopped to the minimum extent necessary to enable the removal or destruction of a weed listed in the schedule to Clause 52.17. The maximum extent of native vegetation that may be removed, destroyed or lopped under this exemption on contiguous land in the same ownership in a five year period must not exceed any of the following: ▪ 1 hectare of native vegetation which does not include a tree. ▪ 15 native trees with a trunk diameter of less than 20 centimetres at a height of 1.3 metres above ground level.

52.17-8 Melbourne Strategic Assessment Levy Area

14/07/2022
VC213

The following provisions apply to the removal, destruction or lopping of native vegetation in the levy area within the meaning of the *Melbourne Strategic Assessment (Environment Mitigation Levy) Act 2020*.

Despite clauses 52.17-2, 52.17-4, 52.17-5 and anything in the Guidelines:

- An application to remove, destroy or lop native vegetation is not required to be accompanied by an offset statement providing evidence that an offset that meets the offset requirements for the native vegetation to be removed has been identified and can be secured in accordance with the Guidelines.
- Before deciding on an application, a responsible authority is not required to consider whether an offset that meets the offset requirements for the native vegetation to be removed has been identified and can be secured in accordance with the Guidelines.
- The biodiversity impacts of the removal, destruction or lopping of native vegetation are not required to be offset in accordance with the Guidelines.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 52.17 NATIVE VEGETATION

1.0 Scheduled area

08/07/2021
C211brim

Area	Description of native vegetation for which no permit is required to remove, destroy or lop
Those areas marked PAO5 on Maps 10PAO and 11PAO	All native vegetation

2.0 Scheduled weed

08/07/2021
C211brim

Area	Description of weed
None specified	

52.18 CORONAVIRUS (COVID-19) PANDEMIC AND RECOVERY EXEMPTIONS

28/10/2022
VC224

Purpose

To support Victoria's social and economic recovery from the coronavirus (COVID-19) pandemic through exemptions that enable outdoor dining and facilitate the reopening and safe operation of hospitality and other businesses.

52.18-1 Operation

11/10/2024
VC270

This clause contains exemptions from the requirements of this planning scheme and exemptions from conditions of permits.

The exemptions in this clause prevail over any inconsistent provision in this planning scheme or condition of a permit.

The exemptions in this clause do not apply to a requirement in the Heritage Overlay relating to the construction or carrying out of works to an existing building, the alteration of an existing building, or the painting of an existing building, other than a building constructed or placed under an exemption in this clause.

A use or development carried out under an exemption in this clause must comply with the requirements in clause 52.18-6.

In this clause:

- ***drink*** includes liquor;
- ***exemption period*** means the period when a pandemic declaration under the *Public Health and Wellbeing Act 2008* in relation to coronavirus (COVID-19) is in force and for 36 months after;
- ***hospitality*** means:
  - the preparation or sale of food or drink for immediate consumption on, or off, the land; or
  - the consumption of food or drink;
- ***public land*** means Crown land and land that is owned by, vested in or controlled by a Minister, government department, public authority or municipal council.

52.18-2 Public land exemptions

28/10/2022
VC224

Any requirement in this planning scheme relating to the use of land does not apply to the use of public land for an art and craft centre, education centre, hospitality, leisure and recreation, office, place of assembly, market or shop during the exemption period if the requirements of clause 52.18-6 are met.

Any requirement in this planning scheme relating to the construction of a building or the construction or carrying out of works on public land does not apply to a temporary building or moveable building associated with the use of land for an art and craft centre, education centre, hospitality, leisure and recreation, office, place of assembly, market or shop during the exemption period if the requirements of clause 52.18-6 are met.

52.18-3 Food and drink business extension exemptions

28/10/2022
VC224

Any requirement in this planning scheme relating to the use of land does not apply to the use of land for hospitality during the exemption period if the use is associated with the existing use of adjoining land for a food and drink premises, function centre, nightclub or winery, and the requirements of clause 52.18-6 are met.

Any requirement in this planning scheme relating to the construction of a building or the construction or carrying out of works does not apply to a temporary building or moveable building associated with the use of the land for hospitality during the exemption period if the requirements of clause 52.18-6 are met.

52.18-4 Car parking exemption

28/10/2022
VC224

Any requirement of this planning scheme relating to the provision of car parking does not apply to a use commenced under an exemption in this clause, or the existing use of land for a food and drink premises, function centre, nightclub or winery, during the exemption period.

52.18-5 Permit condition exemptions

28/10/2022
VC224

The following exemptions apply to permits issued before the approval date of Amendment VC193 and which allow:

- the use or development of land for a food and drink premises, function centre, nightclub or winery; or
- the use or development of land for the sale or consumption of liquor associated with the use of the land for a food and drink premises, function centre, nightclub or winery.

Any requirement of a permit, including any condition, relating to the layout or location of the preparation, sale or consumption of food or drink on the land does not apply during the exemption period if the requirements of clause 52.18-6 are met. This exemption does not apply to a condition relating to the maximum number of patrons, hours of operation (including any condition that applies to a particular outdoor area), location or playing of music, or noise levels.

Any requirement of a permit, including any condition, relating to the layout or location of development on the land does not apply to the construction or placing of a temporary building or moveable building, or the construction or carrying out of works, under an exemption in this clause if the requirements of clause 52.18-6 are met.

Any requirement of a permit, including any condition, that requires the provision of car parking, or requires land to be set aside for vehicle access or car parking, does not apply to the alteration of an existing use of land under an exemption in this clause during the exemption period if the requirements of clause 52.18-6 are met.

52.18-6 Use and development requirements

15/03/2024
VC256

The following requirements apply to the use and development of land carried out under an exemption in this clause.

The use of the land must not:

- Continue after the exemption period unless in accordance with the requirements of this planning scheme.
- Unreasonably affect the amenity of the neighbourhood, including through:
  - Transport of materials, goods or commodities to or from the land.
  - Appearance of any building, works or materials.
  - Emission of noise, artificial light, vibration, smell, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit or oil.

Land in, or within 30 metres of, a residential zone must not be used for the outdoor consumption of food or drink between the hours of 10.00pm and 7.00am. The responsible authority may vary this requirement to extend the hours of the use.

The use or development of land must not impede access required by emergency services or for waste collection.

The height of a building constructed or placed under an exemption in this clause must not exceed 3.6 metres.

A building must not be constructed or placed under an exemption in this clause within 1 metre of adjacent land in a residential zone if the height of the building exceeds 1.8 metres.

The siting of a building in a Bushfire Management Overlay or Erosion Management Overlay that would require a permit under the overlay were it not for an exemption in this clause must be to the satisfaction of the responsible authority.

The siting of a building in a Floodway Overlay, Land Subject to Inundation Overlay or Special Building Overlay that would require a permit under the overlay were it not for an exemption in this clause must be to the satisfaction of the relevant floodplain management authority.

A building constructed or placed under an exemption in this clause must be removed from the land before the end of the exemption period.

52.19 TELECOMMUNICATIONS FACILITY

04/11/2022
VC226

Purpose

To ensure that telecommunications infrastructure is provided in an efficient and cost-effective manner to meet community needs.

To facilitate an effective state-wide telecommunications network consistent with proper and orderly planning.

To support the provision of telecommunications facilities with minimal impact on the amenity of the area.

52.19-1 Permit requirement

04/11/2022
VC226

A permit is required to construct a building or construct or carry out works for a telecommunications facility. This does not apply to the construction of a building or the construction or carrying out of works for any of the following:

- A low-impact facility specified in the *Telecommunications (Low-impact Facilities) Determination 2018* (Cth).
- The inspection and maintenance of a facility as defined in the *Telecommunications Act 1997* (Cth).
- A facility authorised by a facility installation permit issued under the *Telecommunications Act 1997* (Cth).
- An activity authorised under clause 6(2) of Division 3 of Schedule 3 of the *Telecommunications Act 1997* (Cth).
- An activity carried out by a body listed in sections 46 to 51 (inclusive) of the *Telecommunications Act 1997* (Cth) pursuant to legislation applying to that body.
- A temporary defence facility.
- A telecommunications facility equipment shelter.
- A telecommunications line forming part of a telecommunications network connected to a building, caravan or mobile home.
- An optical fibre ground wire that replaces an electricity ground wire on a high-voltage transmission tower that supports powerlines designed to operate at 222,000 volts or greater.
- A telecommunications facility located underground if any ground disturbed in constructing or installing the facility is reinstated.
- A telecommunications dish with a diameter of 1.2 metres or less.
- A telecommunications dish with a diameter of more than 1.2 metres and less than or equal to 2.4 metres if the following requirements are met:
  - If the dish is in a Heritage Overlay, it must not be visible from a street (other than a lane) or public park.
  - If the dish is in a residential zone, it must:
    - Be set back from the side or rear boundary 1 metre, plus 0.3 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres.
    - Be set back at least 3 metres from a boundary opposite an existing habitable room window.
    - Not be visible from the street (other than a lane) or a public park.

- A telecommunications tower that replaces an existing light pole on public land if the following requirements are met:
  - The public land manager must be a municipal council.
  - The tower must not be more than 8 metres higher than the light pole.
- A telecommunications tower that replaces an existing telecommunications tower on the same land if the following requirements are met:
  - The tower must not be in a residential zone, or a Significant Landscape Overlay, Heritage Overlay or Neighbourhood Character Overlay.
  - The tower must not be more than 8 metres higher than the existing tower.
  - The tower must not be a lattice tower.
  - The tower must be located within 20 metres of the existing tower.
  - The existing tower must be removed within 60 days of the new tower commencing operation.
- The extension of an existing telecommunications tower if the following requirements are met:
  - The tower must not be in a residential zone.
  - The height of the extension must not exceed 8 metres.
  - The tower must not have been previously extended without a permit.
  - The tower must have been constructed for 12 months before the extension.
- A telecommunications facility on a building if the following requirements are met:
  - If the building is in a residential zone, the height of the facility must not be more than 1 metre higher than the building height of the building.
  - If the building is in a zone other than a residential zone, the height of the facility must not be more than 8 metres higher than the building height of the building.
- A telecommunications facility that provides service coverage during routine or emergency maintenance of an existing facility, construction or installation of a new facility, or additional service coverage for an event, if the following requirements are met:
  - The height of the facility must not exceed 25 metres above its base or the height of the existing facility, whichever is the greater.
  - The facility must not be located on the land for more than a total of 4 months in any 12 month period.

52.19-2 Land in public ownership

04/11/2022
VC226

An application affecting land in a public land zone must be accompanied by written confirmation from the public land manager that the public land manager consents generally or conditionally:

- To the application being made; or
- To the application being made and to the proposed development.

This requirement does not apply if the applicant is the public land manager.

52.19-3 Exemptions from notice and review

04/11/2022
VC226

An application under any provision of this planning scheme to construct a building or construct or carry out works for a telecommunications facility is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to:

- An application under a Significant Landscape Overlay, a Heritage Overlay, or Neighbourhood Character Overlay.
- An application under a public land zone if the responsible authority is not the public land manager.
- An application for any of the following:
  - A telecommunications dish.
  - A telecommunications facility on a building within 100 metres of a residential zone.
  - A telecommunications facility on a building within 100 metres of a dwelling not on the same land or land in contiguous ownership.
  - A telecommunications tower in a residential zone.
  - A telecommunications tower within 100 metres of a residential zone.
  - A telecommunications tower within 100 metres of a dwelling not on the same land or land in contiguous ownership.

An application under any provision of this planning scheme to use or develop land for a telecommunications facility is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if the telecommunications facility is funded, or partly funded, by the Commonwealth through the Mobile Black Spot Program or the State of Victoria.

52.19-4 Application requirements

04/11/2022
VC226

An application must be accompanied by the following information as appropriate:

- A site analysis and design response explaining the design, siting, construction and operation of the telecommunications facility.
- Site boundaries and dimensions.
- The purpose and location of all buildings and works required in the construction of the facility.
- The location of all existing buildings and works to be retained and demolished.
- The location of all proposed buildings and works including dimensions, elevations, materials, colours and finishes.
- The location and use of all buildings on adjoining properties.
- The location of all adjoining streets and access ways.
- Australian Height Datum levels.
- Natural drainage lines, watercourses, coastal dunes, beach systems and wetlands.
- Proposals for the rehabilitation of the land on which development is to occur.
- Roads and parking areas.
- Materials, landscaping, external lighting, colour and reflectivity.

52.19-5 Decision guidelines

04/11/2022
VC226

Before deciding on an application, in addition to the decision guidelines of clause 65, the responsible authority must consider, as appropriate:

- The design, siting, construction and operation of the telecommunications facility.
- The effect of the telecommunications facility on adjacent land.

52.20 GOVERNMENT FUNDED HOUSING DEVELOPMENT

19/12/2024
VC273

Purpose

To facilitate the use and development of land for housing projects funded wholly or partly, by the Victorian or Commonwealth Government.

To ensure that development does not unreasonably impact on the amenity of adjoining dwellings or small second dwellings.

52.20-1 Application

19/12/2024
VC273

This clause applies to the use or development of land that is:

- Funded wholly or partly, by the Victorian or Commonwealth Government; and
- Carried out by or on behalf of the Chief Executive Officer, Homes Victoria.

This clause does not apply to:

- The subdivision of land.
- The use or development of land in an industrial zone, rural zone or Port Zone.
- The use or development of land in a Bushfire Management Overlay.
- A use or development to which Clause 51.01 - Specific Site and Exclusions, or Clause 45.12 - Specific Controls Overlay, or any schedule to the clauses apply.
- A use or development that would not require a permit under a provision of this planning scheme were it not for the exemption in Clause 52.20-2.
- A use or development that is inconsistent with an applicable Statement of Planning Policy.
- A development for which an environment effects statement has been, or is required to be, prepared under the *Environment Effects Act 1978*.

In this clause, ***Chief Executive Officer, Homes Victoria*** means 'Chief Executive Officer, Homes Victoria' as defined in the *Housing Act 1983* and the body corporate established under the *Housing Act 1983*.

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

52.20-2 Exemption from planning scheme requirements

20/12/2021
VC207

Any requirement of this planning scheme to obtain a permit or any provision of this planning scheme that prohibits the use or development of land, requires the use or development of land to be carried out in a particular manner, or requires a specified thing to be done to the satisfaction of a specified person or body, does not apply to any use or development Clause 52.20 applies to if requirements of this clause are met.

This exemption does not apply to a requirement in Clauses 45.03 (Environmental Audit Overlay), 45.07 (City Link Project Overlay), 45.08 (Melbourne Airport Environs Overlay), 51.03 (Upper Yarra Valley & Dandenong Ranges Regional Strategy Plan) or 52.02 (Easements, Restrictions and Reserves), or in any schedule to those clauses.

52.20-3 Use and development requirements

19/12/2024
VC273

The use and development of land must be carried out in accordance with the plans and documents approved under this clause, to the satisfaction of the Minister for Planning. Plans and documents may be amended to the satisfaction of the Minister for Planning.

The use and development of land to be carried out to the satisfaction of the Minister for Planning must not commence until funding from the Victorian or Commonwealth Government is approved.

52.20-4 Consultation requirements

14/07/2022
VC230

Before plans, documents and information required under Clause 52.20-5 are submitted:

- Public consultation, and consultation with the relevant municipal council, on the plans, documents and information proposed to be submitted under Clause 52.20-5; and
- A report that summarises the consultation undertaken, feedback received, and explains how the feedback has been considered and responded to, must be completed.

The requirements of Clause 52.20-4 must be undertaken to the satisfaction of the Minister for Planning and may be varied or waived by the Minister for Planning.

52.20-5 Requirements for plans and documents

31/03/2025
VC267

The following plans, documents and information must be prepared and submitted to the satisfaction of the Minister for Planning:

- Written confirmation from Homes Victoria or the Chief Executive Officer, Homes Victoria that the application is funded, either wholly or partly, by the Victorian or Commonwealth Government.
- A project boundary plan that shows the boundary of the land on which the use or development will be undertaken.
- A site description and analysis plan that accurately describes the natural, physical, cultural heritage, built heritage, landscape, vegetation, access and any other notable features, characteristics and significance of the site and surrounding area including the existing use and development of the site and surrounding land.
- A description of the proposed use including:
  - The activities that will be carried out.
  - The likely effects, if any, on the site and surrounding land and land uses, including noise levels, traffic, air-borne emissions, emissions to land and water, light spill, glare, solar access and hours of operation.
- Detailed plans and elevations of the proposed development drawn to scale and dimensioned, including details of any buildings or works proposed to be demolished or removed, and any vegetation proposed to be retained or removed.
- Explanation of how the proposed use or development derives from and responds to the site description and analysis plan.
- A report that addresses the proposed use or development and how:
  - It responds to the purposes, objectives, decision guidelines or statements of significance or risk of any zone, overlay, or other provision that would apply to the use or development were it not for the exemptions in Clause 52.20-2. This does not include Clauses 54, 55, 57, 58 and 59.
  - A proposed use that is not a dwelling or residential building is in conjunction with that use.
  - It complies with Clause 52.20-8 Native vegetation requirement.
- A design review report prepared by a suitably qualified architect or urban designer that demonstrates how the project achieves good quality design outcomes.
- A schedule of works and development including staging and the expected commencement and completion times.
- A report that details how the proposed development responds to the development standards of:
  - Clause 52.20-6 for the construction or extension of a dwelling.

  - Clause 52.20-6 and Clause 52.20-7 for the construction or extension of an apartment development or residential building or the construction or extension a dwelling in or forming part of an apartment development or residential building. The development standards of Clause 52.20-6.8 does not apply to an apartment development or residential building of 5 or more storeys. The development standards of Clauses 52.20-6.5, 52.20-6.14, 52.20-6.18 and 52.20-6.21 do not apply to an apartment development or residential building.

- If the Minister for Planning has decided that an assessment through an environment effects statement under the Environment Effects Act 1978 is not required for the proposed development and the decision is subject to conditions:
  - A report that details how each condition has been considered and addressed in the design, construction and operation of the proposed development.
  - A copy of any report, plan or other document required to be prepared under those conditions.
- A plan for the management or mitigation of potential adverse effects or impacts on the environment or amenity from the proposed use or development, during and following construction.
- If the use or development would require a permit were it not for the exemption in Clause 52.20-2 and a copy of the application for that permit would be required to be given to a referral authority under section 55 of the Act, the comments of that referral authority on the proposed use or development.
- Any other plan, document or information the Minister for Planning considers necessary to assist the assessment of the proposed use or development or the plans and documents required to be prepared under this clause. This may include street elevations, three dimensional modelling or other methods to describe the proposal.
- A report that demonstrates that the environmental conditions of the land are or will be suitable for the use and development including any significant effects which the use or development may have on the environment or which the environment may have on the use or development including water, noise, air or land pollution impacts on the environment, amenity or human health.

The requirements of this clause may be:

- Satisfied for separate components or stages of a use or development, but each requirement must be satisfied prior to the commencement of that component or stage.
- Varied or waived by the Minister for Planning.

52.20-6 Development standards for dwellings and buildings

01/01/2024
VC250

52.20-6.1 Infrastructure

Development should be connected to reticulated services, including reticulated sewerage, drainage and electricity.

Development should not unreasonably exceed the capacity of utility services and infrastructure, including reticulated services and roads.

In areas where utility services or infrastructure have little or no spare capacity, developments should provide for the upgrading of or mitigation of the impact on services or infrastructure.

52.20-6.2 Street setback

Walls of buildings should be set back from streets at least the distance specified in Table 1. Porches, pergolas and verandahs that are less than 3.6 metres high and eaves may encroach not more than 2.5 metres into the setbacks of this standard.

Table 1 Street setback

Development context	Minimum setback from front street (metres)	Minimum setback from a side street (metres)
There is an existing building on both the abutting allotments facing the same street, and the site is not on a corner.	The same distance as the setback of the front wall of either existing building on the abutting allotments facing the front street or 7 metres, whichever is the lesser.	Not applicable.
There is an existing building on one abutting allotment facing the same street and no existing building on the other abutting allotment facing the same street, and the site is not on a corner.	The same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 7 metres, whichever is the lesser.	Not applicable.
There is no existing building on either of the abutting allotments facing the same street, and the site is not on a corner.	6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Not applicable.
The site is on a corner.	If there is a building on the abutting allotment facing the front street, the same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 7 metres, whichever is the lesser. If there is no building on the abutting allotment facing the front street, 6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Front walls of new development fronting the side street of a corner site should be setback at least the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 3 metres, whichever is the lesser. Side walls of new development on a corner site should be setback the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 2 metres, whichever is the lesser.

52.20-6.3 Permeability

The site area covered by the pervious surfaces should be at least 20 percent of the site.

52.20-6.4 Safety

Entrances to dwellings should not be obscured or isolated from the street and internal accessways.

Planting which creates unsafe spaces along streets and accessways should be avoided.

Developments should be designed to provide good lighting, visibility and surveillance of car parks and internal accessways.

Private spaces within developments should be protected from inappropriate use as public thoroughfares.

52.20-6.5 Access

The width of accessways or car spaces that front existing streets should not exceed:

- 33 per cent of the street frontage, or
- if the width of the street frontage is less than 20 metres, 40 per cent of the street frontage.

No more than one single-width crossover should be provided for each dwelling fronting a street.

The location of crossovers should maximise the retention of on-street car parking spaces.

The number of access points to a road in a Transport Zone 2 or a Transport Zone 3 should be minimised.

Developments must provide for access for service, emergency and delivery vehicles.

52.20-6.6 Parking location

Car parking facilities should:

- Be reasonably close and convenient to dwellings.
- Be secure.
- Be well ventilated if enclosed.

Shared accessways or car parks of other dwellings should be located at least 1.5 metres from the windows of habitable rooms. This setback may be reduced to 1 metre where there is a fence at least 1.5 metres high or where window sills are at least 1.4 metres above the accessway.

52.20-6.7 Car parking

A minimum 0.6 car spaces should be provided to each dwelling. A minimum 1 car space should be provided to each 4 bedrooms of a residential building.

Car parking for other land uses must be to the satisfaction of the Minister for Planning.

Car spaces may be covered or uncovered.

If in calculating the number of car parking spaces the result is not a whole number, the required number of car parking spaces is to be rounded down to the nearest whole number greater than 1.

Accessway design

Accessways must:

- Be at least 3 metres wide.
- Have an internal radius of at least 4 metres at changes of direction or intersection or be at least 4.2 metres wide.
- Allow vehicles parked in the last space of a dead-end accessway in public carparks to exit in a forward direction with one manoeuvre.
- Provide at least 2.1 metres headroom beneath overhead obstructions, calculated for a vehicle with a wheel base of 2.8 metres.

- If the accessway serves four or more car spaces or connects to a road in a Transport Zone 2 or a Transport Zone 3, the accessway must be designed so that cars can exit the site in a forward direction.
- Provide a passing area at the entrance at least 6.1 metres wide and 7 metres long if the accessway serves ten or more carparking spaces and is either more than 50 metres long or connects to a road in a Transport Zone 2 or a Transport Zone 3.
- Have a corner splay or area at least 50 percent clear of visual obstructions extending at least 2 metres along the frontage road from the edge of an exit lane and 2.5 metres along the exit lane from the frontage, to provide a clear view of pedestrians on the footpath of the frontage road. The area clear of visual obstructions may include an adjacent entry or exit lane where more than one lane is provided, or adjacent landscaped areas, provided the landscaping in those areas is less than 900mm in height.

Car parking spaces

Car parking spaces and accessways must have the minimum dimensions as outlined in Table 2.

Table 2: Minimum dimensions of car parking spaces and accessways


Angle of car parking spaces to access way	Accessway width	Car space width	Car space length
Parallel	3.6 m	2.3 m	6.7 m
45º	3.5 m	2.6 m	4.9 m
60º	4.9 m	2.6 m	4.9 m
90º	6.4 m	2.6 m	4.9 m
	5.8 m	2.8 m	4.9 m
	5.2 m	3.0 m	4.9 m
	4.8 m	3.2 m	4.9 m

Note: Some dimensions in Table 2 vary from those shown in the Australian Standard AS2890.1-2004 (off street). The dimensions shown in Table 2 allocate more space to aisle widths and less to marked spaces to provide improved operation and access. The dimensions in Table 2 are to be used in preference to the Australian Standard AS2890.1-2004 (off street) except for disabled spaces which must achieve Australian Standard AS2890.6-2009 (disabled).

A wall, fence, column, tree, tree guard or any other structure that abuts a car space must not encroach into the area marked 'clearance required' on Diagram 1, other than:

- A column, tree or tree guard, which may project into a space if it is within the area marked 'tree or column permitted' on Diagram 1.
- A structure, which may project into the space if it is at least 2.1 metres above the space.

Diagram 1 Clearance to car parking spaces



Car spaces in garages or carports must be at least 6 metres long and 3.5 metres wide for a single space and 5.5 metres wide for a double space measured inside the garage or carport.

Where parking spaces are provided in tandem (one space behind the other) an additional 500mm in length must be provided between each space.

Disabled car parking spaces must be designed in accordance with Australian Standard AS2890.6-2009 (disabled) and the Building Code of Australia. Disabled carparking spaces may encroach into an accessway width specified in Table 2 by 500mm.

Gradients

Accessway grades must not be steeper than 1:10 (10 percent) within 5 metres of the frontage to ensure safety for pedestrians and vehicles. The design must have regard to the wheel base of the vehicle being designed for; pedestrian and vehicular traffic volumes; the nature of the carpark; and the slope and configuration of the vehicle crossover at the site frontage. This does not apply to accessways serving three dwellings or less.

Ramps (except within 5 metres of the frontage) must have the maximum grades as outlined in Table 3 and be designed for vehicles travelling in a forward direction.

Table 3: Ramp gradients

Type of car park	Length of ramp	Maximum grade
Public car parks	20 metres or less	1:5 (20%)
	longer than 20 metres	1:6 (16.7%)
Private or residential car parks	20 metres or less	1:4 (25%)
	longer than 20 metres	1:5 (20%)

Where the difference in grade between two sections of ramp or floor is greater than 1:8 (12.5 per cent) for a summit grade change, or greater than 1:6.7 (15 percent) for a sag grade change, the ramp must include a transition section of at least 2 metres to prevent vehicles scraping or bottoming.

Plans must include an assessment of grade changes of greater than 1:5.6 (18 percent) or less than 3 metres apart for clearances, to the satisfaction of the Minister for Planning.

Mechanical parking

Mechanical parking may be used to meet the carparking standard provided:

- At least 25 percent of the mechanical carparking spaces can accommodate a vehicle height of at least 1.8 metres.
- Carparking spaces that require the operation of the system are not allocated to visitors unless used in a valet parking situation.
- The design and operation is to the satisfaction of the Minister for Planning.

Urban design

Ground level carparking, garage doors and accessways must not visually dominate public space.

Carparking within buildings (including visible portions of partly submerged basements) must be screened or obscured where possible, including through the use of occupied tenancies, landscaping, architectural treatments and art works.

Design of carparks must take into account their use as entry points to the site.

Design of new internal streets in developments must maximise on street parking opportunities.

Safety

Car parking must be well lit and clearly signed.

The design of carparks must maximise natural surveillance and pedestrian visibility from adjacent buildings.

Pedestrian access to carparking areas from the street must be convenient.

Pedestrian routes through car parking areas and building entries and other destination points must be clearly marked and separated from traffic in high activity parking areas.

Landscaping

The layout of car parking areas must provide for water sensitive urban design treatment and landscaping.

Landscaping and trees must be planted to provide shade and shelter, soften the appearance of ground level car parking and aid in the clear identification of pedestrian paths.

Ground level carparking spaces must include trees planted with flush grilles. Spacing of trees must be determined having regard to the expected size of the selected species at maturity.


52.20-6.8 Side and rear setbacks

A new building not on or within 200mm of a boundary to a residential zone should be set back from side or rear boundaries 1 metre, plus 0.3 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres. Diagram 2 details the standard.

Sunblinds, verandahs, porches, eaves, fascias, gutters, masonry chimneys, flues, pipes, domestic fuel or water tanks, and heating or cooling equipment or other services may encroach not more than 0.5 metres into the setbacks of this standard.

Landings having an area of not more than 2 square metres and less than 1 metre high, stairways, ramps, pergolas, shade sails and carports may encroach into the setbacks of this standard.

Diagram 2 Side and rear setbacks



52.20-6.9 Walls on boundaries

A new wall constructed on or within 200mm of a side or rear boundary of a lot or a carport constructed on or within 1 metre of a side or rear boundary of lot should not abut the boundary for a length of more than:

- 10 metres plus 25 per cent of the remaining length of the boundary of an adjoining lot, or
- Where there are existing or simultaneously constructed walls or carports abutting the boundary on an abutting lot, the length of the existing or simultaneously constructed walls or carports whichever is the greater.

A new wall or carport may fully abut a side or rear boundary where slope and retaining walls or fences would result in the effective height of the wall or carport being less than 2 metres on the abutting property boundary.

A building on a boundary includes a building set back up to 200mm from a boundary.

The height of a new wall constructed on or within 200mm of a side or rear boundary or a carport constructed on or within 1 metre of a side or rear boundary should not exceed an average of 3.2 metres with no part higher than 3.6 metres unless abutting a higher existing or simultaneously constructed wall.


52.20-6.10 Daylight to existing windows

Buildings opposite an existing habitable room window should provide for a light court to the existing window that has a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky. The calculation of the area may include land on the abutting lot.

Walls or carports more than 3 metres in height opposite an existing habitable room window should be set back from the window at least 50 per cent of the height of the new wall if the wall is within a 55 degree arc from the centre of the existing window. The arc may be swung to within 35 degrees of the plane of the wall containing the existing window.

Where the existing window is above ground floor level, the wall height is measured from the floor level of the room containing the window.


Diagram 3 Daylight to existing windows



52.20-6.11 North-facing windows

If a north-facing habitable room window of an existing dwelling or small second dwelling is within 3 metres of a boundary on an abutting lot, a building should be setback from the boundary 1 metre, plus 0.6 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres, for a distance of 3 metres from the edge of each side of the window. A north-facing window is a window with an axis perpendicular to its surface oriented north 20 degrees west to north 30 degrees east.

Diagram 4 North-facing windows



52.20-6.12 Overshadowing open space

Where sunlight to the secluded private open space of an existing dwelling or small second dwelling is reduced, at least 75 per cent, or 40 square metres with minimum dimension of 3 metres, whichever is the lesser area, of the secluded private open space should receive a minimum of five hours of sunlight between 9 am and 3 pm on 22 September.

If existing sunlight to the secluded private open space of an existing dwelling or small second dwelling is less than the requirements of this standard, the amount of sunlight should not be further reduced.

52.20-6.13 Overlooking

A habitable room window, balcony, terrace, deck or patio should be located and designed to avoid direct views into the secluded private open space of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio. Views should be measured within a 45 degree angle from the plane of the window or perimeter of the balcony, terrace, deck or patio, and from a height of 1.7 metres above floor level.

A habitable room window, balcony, terrace, deck or patio with a direct view into a habitable room window of an existing dwelling or a small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio should be either:

- Offset a minimum of 1.5 metres from the edge of one window to the edge of the other.
- Have sill heights of at least 1.7 metres above floor level.
- Have fixed, obscure glazing in any part of the window below 1.7 metre above floor level.
- Have permanently fixed external screens to at least 1.7 metres above floor level and be no more than 25 per cent transparent.


Obscure glazing in any part of the window below 1.7 metres above floor level may be openable provided that there are no direct views as specified in this standard.

Screens used to obscure a view should be:

- Perforated panels or trellis with a maximum of 25 per cent openings or solid translucent panels.
- Permanent, fixed and durable.
- Designed and coloured to blend in with the development.

This standard does not apply to a new habitable room window, balcony, terrace, deck or patio which faces a property boundary where there is a visual barrier at least 1.8 metres high and the floor level of the habitable room, balcony, terrace, deck or patio is less than 0.8 metres above ground level at the boundary.

Diagram 5 Overlooking open space



52.20-6.14 Noise impacts

Noise sources, such as mechanical plant, should not be located near bedrooms of immediately adjacent existing dwellings or small second dwellings.

Noise sensitive rooms and secluded private open spaces of new dwellings and residential buildings should take account of noise sources on immediately adjacent properties.

Dwellings and residential buildings close to busy roads, railway lines or industry should be designed to limit noise levels in habitable rooms.

52.20-6.15 Daylight to new windows

A window in a habitable room should be located to face:

- An outdoor space clear to the sky or a light court with a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky, not including land on an abutting lot, or
- A verandah provided it is open for at least one third of its perimeter, or
- A carport provided it has two or more open sides and is open for at least one third of its perimeter.

52.20-6.16 Private open space

A dwelling (other than an apartment) should have private open space consisting of:

- An area of secluded private open space with a minimum area of 25 square metres, a minimum dimension of 3 metres and convenient access from a living room; or
- A balcony of 8 square metres with a minimum width of 1.6 metres and convenient access from a living room; or
- A roof-top area of 10 square metres with a minimum width of 2 metres and convenient access from a living room.


Secluded private open space may be located in the front setback if it is no more than 30% of the street frontage.

52.20-6.17 Solar access to open space

The private open space should be located on the north side of the dwelling if appropriate.

The southern boundary of secluded private open space should be set back from any wall on the north of the space at least (2 + 0.9h) metres, where 'h' is the height of the wall.

Diagram 6 Solar access to open space



52.20-6.18 Storage

A dwelling should have convenient access to at least 6 cubic metres of externally accessible, secure storage space.

52.20-6.19 Front fence

A front fence within 3 metres of a street should not exceed a maximum height of:

- 2 metres for streets in a Transport Zone 2, and
- 1.5 metres in other streets or where secluded private open space is proposed within the front setback, the front fence may reach a height of up to 1.8 metres for not more than 30% of the length of the boundary.

52.20-6.20 Common property

Developments should clearly delineate public, communal and private areas.

Common property, where provided, should be functional and capable of efficient management.

52.20-6.21 Site services

The design and layout of buildings should provide sufficient space (including easements where required) and facilities for services to be installed and maintained efficiently and economically.

Bin and recycling enclosures, mailboxes and other site facilities should be adequate in size, durable, waterproof and blend in in with the development.

Bin and recycling enclosures should be located for convenient access by residents.

Mailboxes should be provided and located for convenient access as required by Australia Post.

52.20-7 Development standards for apartments

15/03/2024
VC256

52.20-7.1 Energy efficiency

Buildings should be:

- Oriented to make appropriate use of solar energy.
- Sited and designed to ensure that the energy efficiency of existing dwellings or small second dwellings on adjoining lots is not unreasonably reduced.
- Sited and designed to ensure that the performance of existing rooftop solar energy systems on dwellings or small second dwellings on adjoining lots in a General Residential Zone, Neighbourhood Residential Zone or Township Zone are not unreasonably reduced. The existing rooftop solar energy system must exist at the date the application is lodged.

Living areas and private open space should be located on the north side of the development, if practicable.

Developments should be designed so that solar access to north-facing windows is optimised.

Dwellings located in a climate zone identified in Table 4 should not exceed the maximum NatHERS annual cooling load.

Table 4 Cooling load

NatHERS climate zone	NatHERS maximum cooling load MJ/M^2 per annum
Climate zone 21 Melbourne	30
Climate zone 22 East Sale	22
Climate zone 27 Mildura	69
Climate zone 60 Tullamarine	22
Climate zone 62 Moorabbin	21
Climate zone 63 Warrnambool	21
Climate zone 64 Cape Otway	19
Climate zone 66 Ballarat	23

Note: Refer to NatHERS zone map, Nationwide House Energy Rating Scheme (Commonwealth Department of Environment and Energy).

52.20-7.2 Communal open space

A development of 10 or more dwellings should provide a minimum area of communal outdoor open space of 30 square metres.

If a development contains 13 or more dwellings, the development should also provide an additional minimum area of communal open space of 2.5 square metres per dwelling or 220 square metres, whichever is the lesser. This additional area may be indoors or outdoors and consist of multiple separate areas of communal open space.

Each area of communal open space should be:

- Accessible to all residents.
- A useable size, shape and dimension.
- Capable of efficient management.
- Located to:
  - Provide passive surveillance opportunities, where appropriate.
  - Provide outlook for as many dwellings as practicable.
  - Avoid overlooking into habitable rooms and private open space of new dwellings.
  - Minimise noise impacts to new and existing dwellings or small second dwellings.

Any area of communal outdoor open space should be landscaped and include canopy cover and trees.

52.20-7.3 Solar access to communal outdoor open space

The communal outdoor open space should be located on the north side of a building, if appropriate.

At least 50 per cent or 125 square metres, whichever is the lesser, of the primary communal outdoor open space should receive a minimum of two hours of sunlight between 9am and 3pm on 21 June.

52.20-7.4 Landscaping

Development should retain existing trees and canopy cover.

Development should provide for the replacement of any significant trees that have been removed in the 12 months prior to the application being made.

Development should:

- Provide the canopy cover and deep soil area specified in Table 5. Existing trees can be used to meet the canopy cover requirements of Table 5.
- Provide canopy cover through canopy trees that are:
  - Located in an area of deep soil specified in Table 6. Where deep soil cannot be provided, trees should be provided in planters specified in Table 6.
  - Consistent with the canopy diameter and height at maturity specified in Table 7.
  - Located in communal outdoor open space or common areas or street frontages.
- Comprise smaller trees, shrubs and ground cover, including flowering native species.
- Include landscaping, such as climbing plants or smaller plant in planters, in the street frontage and in outdoor areas, including communal outdoor open space.
- Shade outdoor areas exposed to summer sun through landscaping or shade structures and use paving and surface materials that lower surface temperatures and reduce heat absorption.

- Be supported by irrigation systems which utilise alternative water sources such as rainwater, stormwater, and recycled water.
- Protect any predominant landscape features of the area.
- Take into account the soil type and drainage pattern of the site.
- Provide a safe, attractive and functional environment for residents.
- Specify landscape themes, vegetation (location and species), irrigation systems, paving and lighting.

Table 5 Canopy cover and deep soil requirements

Site area	Canopy cover	Deep soil
1000 square metres or less	5% of site area Include at least 1 Type A tree	5% of site area or 12 square metres whichever is the greater
1001 - 1500 square metres	50 square metres plus 20% of site area above 1,000 square metres Include at least 1 Type B tree	7.5% of site area
1501 - 2500 square metres	150 square metres plus 20% of site area above 1,500 square metres Include at least 2 Type B trees or 1 Type C tree	10% of site area
2501 square metres or more	350 square metres plus 20% of site area above 2,500 square metres Include at least 2 Type B trees or 1 Type C tree	15% of site area

Table 6 Soil requirements for trees

Tree type	Tree in deep soil Area of deep soil	Tree in planter Volume of planter	Depth of planter soil
A	12 square metres (min. plan dimension 2.5 metres)	12 cubic metres (min. plan dimension 2.5 metres)	0.8 metre
B	49 square metres (min. plan dimension 4.5 metres)	28 cubic metres (min. plan dimension 4.5 metres)	1 metre
C	121 square metres (min. plan dimension 6.5 metres)	64 cubic metres (min. plan dimension 6.5 metres)	1.5 metre

Note: Where multiple trees share the same section of soil the total required amount of soil can be reduced by 5% for every additional tree, up to a maximum reduction of 25%.

Table 7 Tree types

Tree types	Minimum canopy diameter at maturity	Minimum height at maturity
A	4 metres	4 metres
B	8 metres	8 metres
C	12 metres	12 metres

52.20-7.5 Integrated water and stormwater management

Buildings should be connected to a non-potable dual pipe reticulated water supply, where available from the water authority.

The stormwater management system should be:

- Designed to meet the current best practice performance objectives for stormwater quality as contained in the *Urban Stormwater - Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999).
- Designed to maximise infiltration of stormwater, water and drainage of residual flows into permeable surfaces, tree pits and treatment areas.

52.20-7.6 Building setback

The built form of the development should respect the existing urban context and respond to the features of the site.

Buildings should be set back from side and rear boundaries, and other buildings within the site to:

- Ensure adequate daylight into new habitable room windows.
- Avoid direct views into habitable room windows and private open space of new and existing dwellings or small second dwellings. Developments should avoid relying on screening to reduce views.
- Provide an outlook from dwellings that creates a reasonable visual connection to the external environment.

52.20-7.7 Noise impacts

Noise sources, such as mechanical plants should not be located near bedrooms of immediately adjacent existing dwellings or small second dwellings.

The layout of new dwellings and buildings should minimise noise transmission within the site.

Noise sensitive rooms (such as living areas and bedrooms) should be located to avoid noise impacts from mechanical plants, lifts, building services, non-residential uses, car parking, communal areas and other dwellings or small second dwellings.

New dwellings should be designed and constructed to include acoustic attenuation measures to reduce noise levels from off-site noise sources.

Buildings within a noise influence area specified in Table 8 should be designed and constructed to achieve the following noise levels:

- Not greater than 35dB(A) for bedrooms, assessed as an LAeq,8h from 10pm to 6am.
- Not greater than 40dB(A) for living areas, assessed LAeq,16h from 6am to 10pm.

Buildings, or part of a building screened from a noise source by an existing solid structure, or the natural topography of the land, do not need to meet the specified noise level requirements.

Noise levels should be assessed in unfurnished rooms with a finished floor and the windows closed.

Table 8 Noise influence area

Noise Source	Noise influence area
Zone interface	
Industry	300 metres from the Industrial 1, 2 and 3 zone boundary
Roads	
Freeways, tollways and other roads carrying 40,000 Annual Average Daily Traffic Volume	300 metres from the nearest trafficable lane
Railways	
Railway servicing passengers in Victoria	80 metres from the centre of the nearest track
Railway servicing freight outside Metropolitan Melbourne	80 metres from the centre of the nearest track
Railway servicing freight in Metropolitan Melbourne	135 metres from the centre of the nearest track

Note: The noise influence area should be measured from the closest part of the building to the noise source.

52.20-7.8 Accessibility

At least 50 per cent of dwellings should have:

- A clear opening width of at least 850mm at the entrance to the dwelling and main bedroom.
- A clear path with a minimum width of 1.2 metres that connects the dwelling entrance to the main bedroom, an adaptable bathroom and the living area.
- A main bedroom with access to an adaptable bathroom.
- At least one adaptable bathroom that meets all of the requirements of either Design A or Design B specified in Table 9.

Table 9 Bathroom design

	Design option A	Design option B
Door opening	A clear 850mm wide door opening.	A clear 820mm wide door opening located opposite the shower
Door design	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards that is clear of the circulation area and has readily removable hinges.	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards and has readily removable hinges.

	Design option A	Design option B
Circulation area	A clear circulation area that is: ▪ A minimum area of 1.2 metres by 1.2 metres. ▪ Located in front of the shower and the toilet. ▪ Clear of the toilet, basin and the door swing. The circulation area for the toilet and shower can overlap.	A clear circulation area that is: ▪ A minimum width of 1 metre. ▪ The full length of the bathroom and a minimum length of 2.7 metres. ▪ Clear of the toilet and basin. The circulation area can include a shower area.
Path to circulation area	A clear path with a minimum width of 900mm from the door opening to the circulation area.	Not applicable.
Shower	A hobless (step-free) shower.	A hobless (step-free) shower that has a removable shower screen and is located on the furthest wall from the door opening.
Toilet	A toilet located in the corner of the room.	A toilet located closest to the door opening and clear of the circulation area.

52.20-7.9 Building entry and circulation

Entries to dwellings and buildings should:

- Be visible and easily identifiable.
- Provide shelter, a sense of personal address and a transitional space around the entry.

The layout and design of buildings should:

- Clearly distinguish entrances to residential and non-residential areas.
- Provide windows to building entrances and lift areas.
- Provide visible, safe and attractive stairs from the entry level to encourage use by residents.
- Provide common areas and corridors that:
  - Include at least one source of natural light and natural ventilation.
  - Avoid obstruction from building services.
  - Maintain clear sight lines.

52.20-7.10 Private open space

A dwelling should have private open space consisting of at least one of the following:

- An area at ground level of at least 25 square metres, with a minimum dimension of 3 metres and convenient access from a living room.
- A balcony with an area and dimensions specified in Table 10 and convenient access from a living room. If a cooling or heating unit is located on a balcony, the balcony should provide an additional area of 1.5 square metres.

- An area on a podium or other similar base of at least 15 square metres, with a minimum dimension of 3 metres and convenient access from a living room.
- An area on a roof of at least 10 square metres, with a minimum dimension of 2 metres and convenient access from a living room.

If the finished floor level of a dwelling is 40 metres or more above ground level, the requirements of Table 10 do not apply if at least the area specified in Table 11 is provided as living area or bedroom area in addition to the minimum area specified in Table 13 or Table 14.

Table 10 Balcony size

Orientation of dwelling	Dwelling type	Minimum area	Minimum dimension
North (between north 20 degrees west to north 30 degrees east)	All	8 square metres	1.7 metres
South (between south 30 degrees west to south 20 degrees east)	All	8 square metres	1.2 metres
Any other orientation	Studio or 1 bedroom dwelling	8 square metres	1.8 metres
	2 bedroom dwelling	8 square metres	2 metres
	3 or more bedroom dwelling	12 square metres	2.4 metres

Table 11 Additional living area or bedroom area

Dwelling type	Additional area
Studio or 1 bedroom dwelling	8 square metres
2 bedroom dwelling	8 square metres
3 or more bedroom dwelling	12 square metres

52.20-7.11 Storage

Each dwelling should have convenient access to usable and secure storage space.

The total minimum storage space (including kitchen, bathroom and bedroom storage) should meet the requirements specified in Table 12.

Table 12 Storage

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
Studio	8 cubic metres	5 cubic metres
1 bedroom dwelling	10 cubic metres	6 cubic metres
2 bedroom dwelling	14 cubic metres	9 cubic metres

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
3 or more bedroom dwelling	18 cubic metres	12 cubic metres

52.20-7.12 Waste and recycling

Developments should include dedicated areas for:

- Waste and recycling enclosures which are:
  - Adequate in size, durable, waterproof and blend in with the development.
  - Adequately ventilated.
  - Located and designed for convenient access by residents and made easily accessible to people with limited mobility.
- Adequate facilities for bin washing. These areas should be adequately ventilated.
- Collection, separation and storage of waste and recyclables, including where appropriate opportunities for on-site management of food waste through composting or other waste recovery as appropriate.
- Collection, storage and reuse of garden waste, including opportunities for on-site treatment, where appropriate, or off-site removal for reprocessing.
- Adequate circulation to allow waste and recycling collection vehicles to enter and leave the site without reversing.
- Adequate internal storage space within each dwelling to enable the separation of waste, recyclables and food waste where appropriate.

Waste and recycling management facilities should be designed and managed in accordance with a Waste Management Plan approved by the Minister for Planning and:

- Be designed to meet the better practice design options specified in *Waste Management and Recycling in Multi-unit Developments* (Sustainability Victoria, 2019).
- Protect public health and amenity of residents and adjoining premises from the impacts of odour, noise and hazards associated with waste collection vehicle movements.

52.20-7.13 Functional layout

Bedrooms should:

- Meet the minimum internal room dimensions specified in Table 13.
- Provide an area in addition to the minimum internal room dimensions and area to accommodate a wardrobe.

Living areas (excluding dining and kitchen areas) should meet the minimum internal room dimension and area specified in Table 14.

Table 13 Bedroom dimensions

Bedroom type	Minimum width	Minimum depth	Minimum area
Main bedroom	3 metres	3.4 metres	10.2 sqm
All other bedrooms	3 metres	3 metres	9 sqm

Table 14 Living area dimensions

Dwelling type	Minimum width	Minimum area
Studio and 1 bedroom dwelling	3.3 metres	10 sqm
2 or more bedroom dwelling	3.6 metres	12 sqm

52.20-7.14 Room depth

Single aspect habitable rooms should not exceed a room depth of 2.5 times the ceiling height.

The depth of a single aspect, open plan, habitable room may be increased to 9 metres if all the following requirements are met:

- The room combines the living area, dining area and kitchen.
- The kitchen is located furthest from the window.
- The ceiling height is at least 2.7 metres measured from finished floor level to finished ceiling level. This excludes where services are provided above the kitchen.

The room depth should be measured from the external surface of the habitable room window to the rear wall of the room

52.20-7.15 Windows

Habitable rooms should have a window in an external wall of the building.

A window may provide daylight to a bedroom from a smaller secondary area within the bedroom where the window is clear to the sky. The secondary area should be:

- A minimum width of 1.2 metres.
- A maximum depth of 1.5 times the width, measured from the external surface of the window.

52.20-7.16 Natural ventilation

The design and layout of dwellings should maximise openable windows, doors or other ventilation devices in external walls of the building, where appropriate.

At least 40 per cent of dwellings should provide effective cross ventilation that has:

- A maximum breeze path through the dwelling of 18 metres.
- A minimum breeze path through the dwelling of 5 metres.
- Ventilation openings with approximately the same area.

The breeze path is measured between the ventilation openings on different orientations of the dwelling.

52.20-7.17 Integration with the street

Development should be oriented to front existing and proposed streets.

Along street frontages, development should:

- Incorporate pedestrian entries, windows, balconies or other active spaces.
- Limit blank walls.
- Limit high front fencing, unless consistent with the existing urban context.

- Provide low and visually permeable front fences, where proposed.
- Conceal car parking and internal waste collection areas from the street.

Development next to existing public open space should be designed to complement the open space and facilitate passive surveillance.

52.20-7.18 Access

Vehicle crossovers should be minimised.

Car parking entries should be consolidated, minimised in size, integrated with the façade and where practicable located at the side or rear of the building.

Pedestrian and cyclist access should be clearly delineated from vehicle access.

The location of crossovers should maximise pedestrian safety and the retention of on-street car parking spaces and street trees.

Development must provide access for service, emergency and delivery vehicles.

52.20-7.19 Site services

Development should provide adequate space (including easements where required) for site services to be installed and maintained efficiently and economically.

Meters and utility services should be designed as an integrated component of the building or landscape.

Mailboxes and other site facilities should be adequate in size, durable, weather-protected, located for convenient access and integrated into the overall design of the development.

52.20-7.20 External walls and materials

External walls should be finished with materials that:

- Do not easily deteriorate or stain.
- Weather well over time.
- Are resilient to the wear and tear from their intended use.

External wall design should facilitate safe and convenient access for maintenance.

52.20-7.21 Wind impacts

Development of five or more storeys should:

- not cause unsafe wind conditions specified in Table 15 in public land, publicly accessible areas on private land, private open space and communal open space; and
- achieve comfortable wind conditions specified in Table 15 in public land and publicly accessible areas on private land

within a distance of half the greatest length of the building, or half the total height of the building measured outwards on the horizontal plane from the ground floor building façade, whichever is greater.

Trees and landscaping should not be used to mitigate wind impacts. This does not apply to sitting areas, where trees and landscaping may be used to supplement fixed wind mitigation elements.

Wind mitigation elements, such as awnings and screens should be located within the site boundary, unless consistent with the existing urban context or preferred future development of the area.

Table 15 Wind conditions

Unsafe	Comfortable
Annual maximum 3 second gust wind speed exceeding 20 metres per second with a probability of exceedance of 0.1% considering at least 16 wind directions.	Hourly mean wind speed or gust equivalent mean speed (3 second gust wind speed divided by 1.85), from all wind directions combined with probability of exceedance less than 20% of the time, equal to or less than: ▪ 3 metres per second for sitting areas. ▪ 4 metres per second for standing areas. ▪ 5 metres per second for walking areas.

52.20-8 Native vegetation requirements

20/03/2023
VC229

In this clause:

- ***Guidelines*** means the *Guidelines for removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, December 2017);
- ***levy area*** has the same meaning as in the *Melbourne Strategic Assessment (Environment Mitigation Levy) Act 2020*;
- ***Secretary*** means the Secretary to the Department of Environment, Land, Water and Planning as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*.

Before the removal, destruction or lopping of native vegetation outside the levy area:

- Information about the native vegetation in accordance with the application requirements 1, 5 and 9 in Table 4 of the Guidelines must be provided to the satisfaction of the Secretary.
- The biodiversity impacts from the native vegetation must be offset in accordance with the *Guidelines*.
- Evidence that the required offset has been secured must be provided to the satisfaction of the Secretary.

The requirements of Clause 52.20-8 do not apply to any native vegetation identified in the table of exemptions to Clause 52.17-7.

The Secretary may vary the timing of the offset requirement if the Secretary considers there are exceptional circumstances to warrant the variation.

The secured offset for a project may be reconciled at the completion of a project in accordance with the *Assessor's handbook – Applications to remove, destroy or lop native vegetation* (Department of Environment, Land, Water and Planning, October 2018) to the satisfaction of Secretary.

Before the removal, destruction or lopping of native vegetation inside the levy area, information about the native vegetation in accordance with the application requirements 1 and 5 in Table 4 of the Guidelines must be provided to the satisfaction of the Secretary.

The requirements of this clause may be satisfied for separate components or stages of a development. However, each requirement must be satisfied prior to the removal, destruction or lopping of native vegetation for that component or stage.

52.20-9 Transitional provision

20/03/2023
VC229

The development standards at Clause 52.20-7 for apartment developments and residential buildings in force immediately before the approval date of Amendment VC207 continue to apply to a use or development that has received written confirmation from the Chief Executive Officer, Homes Victoria that an application is funded, either wholly or partly, under Victoria's Big Housing Build program, signed before 30 June 2022.

52.21 PRIVATE TENNIS COURT

31/07/2018
VC148

Purpose

To ensure that tennis courts used in association with a dwelling are sited and constructed to minimise the effects of the development on nearby properties.

To ensure that the use of tennis courts in association with a dwelling does not cause unreasonable disturbance to adjoining residents or adversely affect the residential amenity of adjoining areas.

52.21-1 Application

31/07/2018
VC148

This clause applies to any private tennis court which is used in association with a dwelling.

52.21-2 Permit requirement

19/01/2006
VC37

A permit is not required under any provision of this scheme to construct, use or illuminate a private tennis court if the performance requirements specified in the Code of Practice - Private Tennis Court Development Revision 1 March 1999 are met.

A permit is required to construct, use or illuminate a private tennis court:

- If any of the performance requirements specified in the Code of Practice - Private Tennis Court Development Revision 1 March 1999 are not met.
- If the land is in an Environmental Significance Overlay, a Vegetation Protection Overlay, a Significant Landscape Overlay, a Heritage Overlay, an Urban Floodway Zone, a Floodway Overlay or a Land Subject to Inundation Overlay and a permit is required for any of the following:
  - To construct a building or construct or carry out works.
  - To remove, destroy, prune or lop a tree or vegetation.

52.21-3 Application requirements

19/01/2006
VC37

Unless the circumstances do not require, an application under this clause must be accompanied by the following information:

- A copy of title of the land.
- A layout plan to a scale of not less than 1:200.
- The location of dwellings on adjoining land within 10 metres of the court site showing habitable room windows.
- Existing and proposed site levels.
- Location of vegetation to be removed.
- Proposed landscaping.
- Illumination levels and the position and height of light poles and fencing.
- Description of fencing material.
- The location of easements.
- Volume of excavated material to be brought to or removed from the site.
- Means of access to the site.
- Construction method and timing.

52.21-4 Notice provisions

31/07/2018
VC148

An application for a permit to construct, use or illuminate a private tennis court under any provision of this scheme is exempt from the notice requirements of section 52(1)(a), (b) and (d) of the Act.

In accordance with section 52(1)(c) of the Act notice of an application to construct, use or illuminate a private tennis court under any provision of this scheme must be given by ordinary post to the owners and occupiers of adjoining and opposite properties.

52.21-5 Decision guidelines

19/01/2006
VC37

Before deciding on an application under this Clause, in addition to the decision guidelines in Clause 65, the responsible authority must consider the relevant objectives and considerations specified in the Code of Practice - Private Tennis Court Development Revision 1 March 1999.

52.22 COMMUNITY CARE ACCOMMODATION

26/10/2018
VC152

Purpose

To facilitate the establishment of community care accommodation.

To support the confidentiality of community care accommodation.

52.22-1 Application

26/10/2018
VC152

This clause applies to the use and development of land for community care accommodation.

52.22-2 Use exemption

28/02/2025
VC274

Any requirement in the Activity Centre Zone, Capital City Zone, Commercial 1 Zone, General Residential Zone, Housing Choice and Transport Zone, Low Density Residential Zone, Mixed Use Zone, Neighbourhood Residential Zone, Precinct Zone, Residential Growth Zone, Rural Living Zone or Township Zone to obtain a permit to use land for community care accommodation does not apply if all of the following requirements are met:

- Any condition opposite the use 'community care accommodation' in the table of uses in the zone or schedule to the zone is met.
- The use is:
  - funded by, or carried out by or on behalf of, a government department or public authority, including a public authority established for a public purpose under a Commonwealth Act; or
  - funded by, or carried out by, a registered National Disability Insurance Scheme (NDIS) provider if the design of the building is certified to the NDIS Specialist Disability Accommodation Design Standard by an accredited third party NDIS Specialist Disability Accommodation assessor.
- No more than 20 clients are accommodated. This does not include staff.
- No more than 5 persons at any one time who are not accommodated on the land may access support services provided on the land.

52.22-3 Buildings and works exemption

31/03/2025
VC267

Any requirement in the General Residential Zone, Housing Choice and Transport Zone, Low Density Residential Zone, Mixed Use Zone, Neighbourhood Residential Zone, Residential Growth Zone, Rural Living Zone or Township Zone to obtain a permit to construct a building or construct or carry out works for community care accommodation does not apply if all of the following requirements are met:

- The development is:
  - funded by, or carried out by or on behalf of, a government department or public authority, including a public authority established for a public purpose under a Commonwealth Act; or
  - funded by, or carried out by, a registered NDIS provider if the design of the building is certified to the NDIS Specialist Disability Accommodation Design Standard by an accredited third party NDIS Specialist Disability Accommodation assessor.

- The development is in the General Residential Zone or Neighbourhood Residential Zone, a garden area must be provided in accordance with the minimum garden area requirement specified in the zone.
- The development is in the General Residential Zone, Housing Choice and Transport Zone, Mixed Use Zone, Neighbourhood Residential Zone, Residential Growth Zone or Township Zone, the standards B2-1, B2-3, B2-4, B4-1, B4-2, B4-3, B4-4 and B5-2 of clause 55 must be met.

52.22-4 Exemption from notice and review

04/11/2022
VC226

An application under any provision of this planning scheme to use land or construct a building or construct or carry out works for community care accommodation is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if the application is made by or on behalf of:

- A government department or public authority, including a public authority established for a public purpose under a Commonwealth Act; or
- A registered NDIS provider if the design of the building is certified to the NDIS Specialist Disability Accommodation Design Standard by an accredited third party NDIS Specialist Disability Accommodation assessor.

52.22-5 Meaning of terms

04/11/2022
VC226

In this clause:

- National Disability Insurance Scheme has the same meaning as part 4 section 9 of the *National Disability Insurance Scheme Act 2013*.
- Registered NDIS provider has the same meaning as part 4 section 9 of the *National Disability Insurance Scheme Act 2013*.

52.23 ROOMING HOUSE

26/10/2018
VC152

Purpose

To facilitate the establishment of domestic-scale rooming houses.

52.23-1 Application

26/10/2018
VC152

This clause applies to use and development of land for a rooming house.

52.23-2 Use exemption

28/02/2025
VC274

Any requirement in the Activity Centre Zone, Capital City Zone, Commercial 1 Zone, General Residential Zone, Housing Choice and Transport Zone, Mixed Use Zone, Neighbourhood Residential Zone, Precinct Zone, Residential Growth Zone or Township Zone to obtain a permit to use land for a rooming house does not apply if all of the following requirements are met:

- Any condition opposite the use 'rooming house' in the table of uses in the zone or schedule to the zone is met.
- The total floor area of all buildings on the land, measured from the outside of external walls or the centre of party walls, does not exceed 300 square metres, excluding outbuildings.
- No more than 12 persons are accommodated.
- No more than 9 bedrooms are provided.

52.23-3 Buildings and works exemption

25/02/2025
VC257

Any requirement in the General Residential Zone, Housing Choice and Transport Zone, Mixed Use Zone, Neighbourhood Residential Zone, Residential Growth Zone or Township Zone to obtain a permit to construct a building or construct or carry out works for a rooming house does not apply if all of the following requirements are met:

- No more than 9 bedrooms are developed on the land.
- Bedrooms can only be accessed from within the building.
- The total floor area of all buildings on the land, measured from the outside of external walls or the centre of party walls, does not exceed 300 square metres, excluding outbuildings.
- If the development is in the General Residential Zone or Neighbourhood Residential Zone, a garden area is provided in accordance with the minimum garden area requirement specified in the zone.
- Shared entry facilities and common areas, including a kitchen and living area, are provided.

52.25 CREMATORIUM

19/01/2006
VC37

Purpose

To ensure that crematoria in cemeteries are developed and used in an appropriate manner.

Permit required

A permit is required to develop and use a crematorium on land that is used for cemetery purposes.

This does not apply to land in the Springvale Crematorium.

Decision guidelines

Before deciding on an application to use and develop land for a crematorium, in addition to the decision guidelines in Clause 65, the responsible authority must consider:

- The provision of landscaping and screen planting.
- The location and design of the buildings to be constructed.
- The effect on traffic movement generated by the use.
- The provision of parking facilities.

52.26 [NO CONTENT]

31/07/2018
VC148

52.27 [NO CONTENT]

01/07/2025
VC286

08/07/2021
C211brim

SCHEDULE TO CLAUSE 52.27 LICENSED PREMISES

1.0 Permit not required

08/07/2021
C211brim

Land	Type of licence
None specified	

2.0 Permit may not be granted

08/07/2021
C211brim

Land	Type of licence
None specified	

52.28 GAMING

31/07/2018
VC148

52.28-1 Purpose

18/10/2006
VC39

To ensure that gaming machines are situated in appropriate locations and premises.

To ensure the social and economic impacts of the location of gaming machines are considered.

To prohibit gaming machines in specified shopping complexes and strip shopping centres.

52.28-2 Gaming objectives

31/07/2018
VC148

A schedule to this clause may specify objectives to be achieved in relation to the installation or use of a gaming machine.

52.28-3 Permit requirement

31/07/2018
VC148

A permit is required to install or use a gaming machine.

This does not apply in either of the following circumstances:

- Clause 52.28-4 or Clause 52.28-5 specifically prohibit a gaming machine.
- the gaming machine is in an approved venue under the *Gambling Regulation Act 2003* on 18 October 2006 and the maximum number of gaming machines for the approved venue on 18 October 2006 is not exceeded.

52.28-4 Prohibition of a gaming machine in a shopping complex

31/07/2018
VC148

Installation or use of a gaming machine is prohibited on land specified in a schedule to this clause.

This does not apply to a gaming machine in an approved venue under the *Gambling Regulation Act 2003* on 18 October 2006; and the maximum number of gaming machines for the approved venue on 18 October 2006 is not exceeded.

52.28-5 Prohibition of a gaming machine in a strip shopping centre

31/07/2018
VC148

Installation or use of a gaming machine is prohibited in a strip shopping centre if:

- the strip shopping centre is specified in the schedule to this clause.
- the schedule provides that a gaming machine is prohibited in all strip shopping centres on land covered by this planning scheme.

This does not apply to a gaming machine in an approved venue under the *Gambling Regulation Act 2003* on 18 October 2006; and the maximum number of gaming machines for the approved venue on 18 October 2006 is not exceeded.

A strip shopping centre is an area that meets all of the following requirements:

- it is zoned for commercial use;
- it consists of at least two separate buildings on at least two separate and adjoining lots;
- it is an area in which a significant proportion of the buildings are shops;
- it is an area in which a significant proportion of the lots abut a road accessible to the public generally;

but it does not include the Capital City Zone in the Melbourne Planning Scheme.

52.28-6 Locations for gaming machines

31/07/2018
VC148

A schedule to this clause may specify guidelines relating to locations for gaming venues and machines.

52.28-7 Venues for gaming machines

31/07/2018
VC148

A schedule to this clause may specify guidelines relating to venues for gaming machines.

52.28-8 Application requirements

31/07/2018
VC148

An application must be accompanied by any information specified in a schedule to this overlay.

52.28-9 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines of Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The compatibility of the proposal with adjoining and nearby land uses.
- The capability of the site to accommodate the proposal.
- Whether the gaming premises provides a full range of hotel facilities or services to patrons or a full range of club facilities or services to members and patrons.
- Any other matters specified in the schedule to this clause.

27/06/2024
C225brim

SCHEDULE TO CLAUSE 52.28 GAMING

1.0 Objectives

27/06/2024
C225brim

To balance the recreational and leisure values of electronic gambling with the need to ensure the wellbeing of the community.

To ensure the density of electronic gaming machines does not exceed the Melbourne metropolitan average.

To ensure that gaming venues contribute to net community benefit.

2.0 Prohibition of a gaming machine in a shopping complex

27/06/2024
C225brim

Installation or use of a gaming machine as specified in Clause 52.28-4 is prohibited on land described in Table 1 below.

Table 1

Name of shopping complex and locality	Land description
Aqua Gardens Shopping Centre	28A Hume Drive, Sydenham
Cairnlea Town Shopping Centre	100 Furlong Rd, 80 Carmody Drive, 18 Wattle Grove Road, Cairnlea
Deer Park Shopping Centre	Land bounded by Hampshire Road, Service Street, Hertford Road and George Street, Sunshine
Delahey Village Shopping Centre	171-179, 181-183, 264, 266, 268 Taylors Road, Delahey
Derrimut Vilage Shopping Centre	20 Mt Derrimut Rd, Derrimut
Keilor Downs Plaza, Keilor Downs	Land on the north side of Taylors Road, Keilor Downs
Market Towers Shopping Centre	Lot 1 on PS407843, 303-313 Hampshire Rd, Sunshine
Sunshine Plaza Shopping Centre	Land bounded by Hampshire Road, Service Street, Hertford Road and George Street, Sunshine
Taylors Lakes Shopping Centre, Taylors Lakes	Land on the south side of Melton Highway and north of Shoppers Way, Taylors Lakes
The Avenue Shopping Centre	Land on the northeast corner of Corella Road and The Avenue, Ardeer – 136 The Avenue, Sunshine West
Watergardens Shopping Centre, Keilor	Land marked “Shopping Centre Footprint’ on plan titled ‘Watergardens Brimbank Shopping Centre’ dated 27-3-97

3.0 Prohibition of a gaming machine in a strip shopping centre

27/06/2024
C225brim

A gaming machine as specified in Clause 52.28-5 is prohibited in a strip shopping centre specified in Table 2 below.

Table 2

Name of strip shopping centre and locality	Land description
Arthur Street Shopping Centre, St Albans	82-84 (even numbers) Arthur St, St; 31-37 (odd numbers) Taylors Rd; shop 1/82 and 82-96 (even numbers) Leslie St
Ballarat Road Shopping Centre, Sunshine	507-513 (odd numbers), Ballarat Rd; 2 Derrimut St
Ballarat Road Shopping Centre, Sunshine	361-367 (odd numbers) Ballarat Rd
Ballarat Road Shopping Centre, Sunshine	461-489 (odd numbers) (including 461B) Ballarat Rd
Ballarat Road Shopping Centre, Deer Park	801A-D (all numbers), 801-835 (odd numbers) (including 817A) Ballarat Rd; 6 Miles St; 1 Burnside St; 1-5 (odd numbers), 2 and 10-24 (even numbers) Canterbury St; 85-93 (odd numbers) Station Rd
Bell Street Shopping Centre, Sunshine	1, 1A, 1B, 1C Bell St; 142 Glengala Rd
Berkshire Road Shopping Centre, Sunshine	59-73 (odd numbers) Berkshire Rd
Berkshire Road Shopping Centre, Sunshine	1-1A Berkshire Rd
Community Hub Shopping Centre	80 Community Hub, Sydenham
Conrad Street Shopping Centre, St Albans	35-47 (odd numbers) and 51-53 (odd numbers) Conrad St; 44 Arthur St
Copernicus Way Shopping Centre, Keilor Downs	129-131 (odd numbers) Copernicus Way
David Drive Shopping Centre	1A Davide Drive, Sunshine West
Disraeli Street Shopping Centre, St Albans	27-29 (odd numbers) Disraeli St
Dumfries Street Shopping Centre, Deer Park	67-77 (odd numbers) Dumfries St
Fitzgerald Road Shopping Centre, Ardeer	104-112 (even numbers) Fitzgerald Rd
Fosters Road Shopping Centre, Keilor Park	1-11 (odd numbers) (including 1A, 1B, 3B, 5A, 7A, 9A) and 11A Fosters Rd
Furlong Road Shopping Centre, Sunshine	18-44 (even numbers) Furlong Rd
Glengala Road Shopping Centre, Ardeer	214, 287, 287A, 287B, 289 Glengala Rd
Glengala Road Shopping Centre, Sunshine	64-86 (even numbers) and 79-103 (odd numbers) Glengala Rd
Hampshire Road Shopping Centre, Sunshine	66-94 (even numbers) (including shops 1-7 (all numbers) of 94), 77-93 (odd numbers) Hampshire Rd
Harvester Rd Centre, Sunshine	491-499 (odd numbers) (including 495A, 495B, 497A) Ballarat Rd; 103 and 105 Harvester Rd; 429-439 (odd numbers) Hampshire Rd
Hatchlands Drive Shopping Centre	8 Hatchlands Drive Deer Park

Name of strip shopping centre and locality	Land description
Hertford Road Shopping Centre, Sunshine	1, 12-18 (even numbers) Hertford Rd; 330, 330A and 332 Hampshire Rd
Holt Street Shopping Centre, Ardeer	45-51 (odd numbers) Holt St
Ingoldsby Court Shopping Centre	17-19 Ingoldsby Court Delahey
John Street Shopping Centre, St Albans	17-24 (all numbers) John St
Kings Road Shopping Centre, St Albans	54-70 (even numbers) (including 66A) Kings Rd
Main Road East Shopping Centre, St Albans	Shops 1-7 (all numbers) of 110, 110-120 (even numbers) and shops 1-3 (all numbers) of 120 Main Rd East
Maxweld Street Shopping Centre, Ardeer	29A-31 (odd numbers) and 50-54 (even numbers) Maxweld St
McArthur Avenue Shopping Centre, St Albans	2, 4, 4A, 4B McArthur Ave
McIntyre Road Shopping Centre, Sunshine	55-91 (odd numbers) McIntyre Rd
Melton Highway Shopping Centre, Taylors Lakes	1-65 (odd numbers) (including lot 1 LP137254) Melton Hwy; 565 Sunshine Ave (including lots 1 and 2 LP401438); 900-920 (even numbers) Old Calder Hwy, 575, 585, 595 Melton Hwy Hillside, 525-527 Melton Hwy, 2 Overton Lea Boulevard Sydenham
Metherall Street Shopping Centre, Sunshine	57 and 61 Metherall St
Old Calder Highway Shopping Centre, Keilor	662-702 (even numbers) Old Calder Hwy; 1-5/17, 1-19/19, 19-25 (all numbers) Arabin St; 23 Hunter St
Parmelia Drive Shopping Centre, Taylors Lakes	81-83 Parmelia Drive
Perth Avenue Shopping Centre, Sunshine	31-43 (odd numbers) Perth Avenue
Porter Street Shopping Centre, Deer Park	1-5 (odd numbers) Porter Street
St Albans Shopping Centre, St Albans	1-71 (odd numbers) Alfrieda St; 1 Collins St; 4-22 (even numbers) East Esplanade; 276-330 (even numbers) and 311-329 (odd numbers) Main Rd East; lot 1 LP143365 and CP360382 Main Rd East; 45-103 (odd numbers), 171-179 (odd numbers) and 340-360 (even numbers) Main Rd West; 1-3 (odd numbers) Princess St; 2-6 (even numbers), 10-16 (even numbers) Victoria Cr
Sage Avenue Shopping Centre, St Albans	8 Sage Avenue; 38 Main Rd East; lot 3 LP143365 Sunshine Avenue
St Albans Road Shopping Centre, St Albans	51-63 (odd numbers) St Albans Road
Stradbroke Drive Shopping Centre, St Albans	44-56 (even numbers) Stradbroke Drive
Suffolk Road Shopping Centre, Sunshine	15-23 (odd numbers) Suffolk Road

Name of strip shopping centre and locality	Land description
Sunshine Shopping Centre, Sunshine	2, 2A, 5-25 (odd numbers) Clarke St; 5-7 (odd numbers) Dawson St; 1-3, 7-11, 21-29 (odd numbers), 14-24, part 26, 28 (even numbers) Devonshire Rd; 1-15 (odd numbers), 40-42 (even numbers) Dickson St; 111-117 (odd numbers), 132-138 (even numbers) Durham Rd; 193-207, 213-233, 245-277 (odd numbers), 232-252, 260-270, 278-294 (even numbers) Hampshire Rd; 54-66 (even numbers) Station Pl; 7-31 (odd numbers), 10, 10A, 27A, 29A, 31A-31B Sun Cr; 1A, 1-14 and 14A City Place; 12, 12A, 14, 14A, 16, 16A-22 (even numbers) Watt St; 16-28 (even numbers) Withers St
Sunshine Avenue/Stenson Road Shopping Centre, Kealba	158 Sunshine Avenue
Tallintyre Road Shopping Centre, Sunshine	2-10 (even numbers) Tallintyre Road
Taylors Road Shopping Centre, Delahey	350 Taylors Road
Theodore Street Shopping Centre, St Albans	57, 57A, 59, 59A, 61, 61A, 63, 63A Theodore Street
Truro Crescent Shopping Centre, Keilor Lodge	2-4 (even numbers) Truro Crescent
Warwick Road Shopping Centre, Sunshine	68-86 (even numbers) Warwick Road
Willaton Street Shopping Centre, St Albans	1-7 (odd numbers) Willaton Street
Willys Avenue Shopping Centre, Keilor Downs	53-55 (odd numbers) Willys Avenue

4.0 Locations for gaming machines

27/06/2024
C225brim

Gaming venues and machines should be located:

- Outside areas of high socio-economic disadvantage.
- Outside activity centres.
- Beyond 400 metres of train stations.

5.0 Venues for gaming machines

27/06/2024
C225brim

Gaming machines should be located:

- In venues that provide a full range of hotel or club services and facilities available to members and patrons, and where gaming is not the primary use.

6.0 Application requirements

27/06/2024
C225brim

The following application requirements apply to an application for a permit under Clause 52.28, in addition to those specified elsewhere in the scheme and must accompany an application, as appropriate, to the satisfaction of the responsible authority:

- Details of the existing and proposed distribution of electronic gaming machines in Brimbank.
- Details of the existing electronic gaming expenditure in Brimbank in the three years prior to the application.
- A forecast of electronic gaming expenditure at the proposed venue.

- Details of any electronic gaming machine expenditure likely to be transferred from other venues.
- Where electronic gaming machines are to be relocated from other gaming premises, including gaming premises in other municipalities, an assessment of the likely social and economic benefits and impact of the proposal on those gaming premises and the local area within which those gaming premises are located.
- Where electronic gaming machines are proposed to be moved from one part of the municipality to another, details of the relative social and economic differences between the two locations, by measures of Socio Economic Index for Areas (SEIFA) indices and Australian Bureau of Statistics (ABS) data.
- Operating hours of the gaming venue.
- Details of the nature and extent of community benefits expected from the proposal and how these will be secured and distributed to the local community.
- A venue management plan identifying strategies to manage patron behaviour and minimise problem gambling.

7.0 Decision guidelines

27/06/2024
C225brim

None specified.

52.29 LAND ADJACENT TO THE PRINCIPAL ROAD NETWORK

20/01/2022
VC205

Purpose

To ensure appropriate access to the Principal Road Network or land planned to form part of the Principal Road Network.

To ensure appropriate subdivision of land adjacent to Principal Road Network or land planned to form part of the Principal Road Network.

52.29-1 Application

20/01/2022
VC205

This clause applies to land adjacent to a road in the Transport Zone 2 or land in a Public Acquisition Overlay if a transport manager (other than a municipal council) is the acquiring authority, and the purpose of the acquisition is for a road.

52.29-2 Permit requirement

20/01/2022
VC205

A permit is required to:

- Create or alter access to:
  - A road in a Transport Zone 2.
  - Land in a Public Acquisition Overlay if a transport manager (other than a municipal council) is the acquiring authority and the acquisition is for the purpose of a road.
- Subdivide land adjacent to:
  - A road in a Transport Zone 2.
  - Land in a Public Acquisition Overlay if a transport manager (other than a municipal council) is the acquiring authority and the acquisition is for the purpose of a road.

52.29-3 Permit not required

14/05/2021
VC198

A permit is not required to:

- Create or alter access, or subdivide land, if carried out by or on behalf of the Head, Transport for Victoria.
- Realign a boundary.
- Subdivide an existing building, provided the building is already connected to services and no new access is required.
- Subdivide land into two lots, provided no new access is required.

52.29-4 Referral of applications

20/01/2022
VC205

An application must be referred under section 55 of the Act to the person or body specified as the referral authority in clause 66.03.

52.29-5 Exemption from notice and review

31/07/2018
VC148

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

52.29-6 Decision guidelines

20/01/2022
VC205

Before deciding on an application, in addition to the decision guidelines in clause 65, the responsible authority must consider:

- The Municipal Planning Strategy and the Planning Policy Framework.

- The views of the relevant road authority.
- The effect of the proposal on the operation of the road and on public safety.
- Any policy made by the relevant road authority pursuant to schedule 2, clause 3 of the *Road Management Act 2004* regarding access between a controlled access road and adjacent land.

52.30 STATE PROJECTS

12/02/2024
VC254

Purpose

To facilitate the development and delivery of projects by or on behalf of, or jointly or in partnership with, or funded by the State of Victoria or a public authority, or on Crown land.

52.30-1 Application

20/03/2023
VC229

This clause applies to any project decided by the Minister for Planning under clause 52.30-2 to be a state project.

In this clause:

- ***Chief Executive Officer, Homes Victoria*** means 'Chief Executive Officer, Homes Victoria' as defined in the *Housing Act 1983* and the body corporate established under the *Housing Act 1983*;
- ***green wedge land*** has the same meaning as in Division 1 of Part 3AA of the Act;
- ***Guidelines*** means the *Guidelines for removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, December 2017);
- ***levy area*** has the same meaning as in the *Melbourne Strategic Assessment (Environment Mitigation Levy) Act 2020;*
- ***project*** means:
  - use or development of land; or
  - creation or alteration of access to a road in a Transport Zone; or
  - creation, variation or removal of an easement or restriction; or
  - variation or removal of a condition in the nature of an easement in a Crown grant;
- ***restriction*** has the same meaning as in the *Subdivision Act 1988;*
- ***Secretary*** means the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

52.30-2 State project decision

12/02/2024
VC254

The exemption in clause 52.30-3 applies if the Minister for Planning is satisfied that a proposed project is a state project which:

- will be:
  - carried out by or on behalf of, or jointly or in partnership with, the State of Victoria or a public authority; or
  - funded, or partly funded by, the State of Victoria or a public authority; or
  - carried out on Crown land;
- is consistent with any Great Ocean Road strategic framework plan, Statement of Planning Policy or Yarra Strategic Plan that applies to the land;
- will not subdivide green wedge land into more lots or into smaller lots than allowed for by this planning scheme;

- is consistent with any approved regional strategy plan under Part 3A of the Act and any approved strategy plan under Part 3C or Part 3D of the Act; and
- does not form part of public works declared under section 3, or works subject to a notice under section 8B(4)(a)(i), or does not require an environment effects statement under the *Environment Effects Act 1978*.

In deciding whether a proposed project is a state project, the Minister for Planning may, where relevant:

- Consider the objectives of planning in Victoria.
- Have regard to any relevant Minister's directions.
- Have regard to the *Victoria Planning Provisions*.
- Take into account any significant effects which the Minister considers the proposed use or development may have on the environment or which the Minister considers the environment may have on the proposed use or development.
- Take into account any significant social effects and economic effects which the Minister considers the proposed use or development may have.
- Consider any existing specific control under clause 45.12 or 51.01 that applies to the proposed use or development.

52.30-3 Exemption from planning scheme requirements

12/02/2024
VC254

Any requirement of this planning scheme to obtain a permit or any provision of this planning scheme that prohibits a project, requires a project to be carried out in a particular manner, or requires a specified thing to be done to the satisfaction of a specified person or body, does not apply to a project decided by the Minister for Planning under clause 52.30-2 to be a state project if the requirements of clause 52.30 are met.

This exemption does not apply to the following:

- The subdivision of green wedge land into more lots or into smaller lots than allowed for by this planning scheme.
- A development for which an environment effects statement has been, or is required to be, prepared under the *Environment Effects Act 1978*.
- A use or development carried out by or on behalf of, or jointly or in partnership with, the Chief Executive Officer, Homes Victoria.
- A use or development to which clauses 52.03, 52.35 or 52.36 apply.
- A requirement in clauses 45.07, 45.08 or 51.03, or in any schedule to those clauses.

52.30-4 Project requirement

29/09/2022
VC222

The project must be carried out generally in accordance with the plans and documents approved under this clause, to the satisfaction of the Minister for Planning.

52.30-5 Consultation requirements

29/09/2022
VC222

Before the project commences:

- Public consultation, including consultation with relevant public authorities and the municipal council for the municipal district within which the proposed project will be carried out, must be carried out to the satisfaction of the Minister for Planning.
- A report that summarises the consultation undertaken and the feedback received, and explains how the feedback has been considered and responded to must be prepared to the satisfaction of the Minister for Planning.

The requirements of this clause may be varied or waived by the Minister for Planning.

52.30-6 Other pre-commencement requirements

12/02/2024
VC254

Before the project commences, the following plans, documents and information must be prepared and submitted to the satisfaction of the Minister for Planning:

- A plan that shows the boundary of the land on which the project will be carried out.
- A site and context description that accurately describes and analyses the natural, physical, cultural heritage, built heritage, landscape, vegetation, access and any other notable features, characteristics and significance of the land and surrounding area, including any existing use and development.
- A description of the proposed use including:
  - The activities that will be carried out.
  - The likely effects, if any, on the land, and surrounding land and land uses, including noise levels, traffic, air-borne emissions, emissions to land and water, light spill, glare, solar access and hours of operation.
- Detailed plans and elevations of the proposed development drawn to scale and dimensioned, including details of any buildings or works proposed to be demolished or removed, and any vegetation proposed to be retained or removed.
- A report that addresses how the proposed project responds to purposes, objectives, or statements of significance or risk of any zone, overlay, or other provision that would apply to the proposed project but for the exemption in clause 52.30-3.
- A schedule of works and development including staging and the expected commencement and completion times.
- If the Minister for Planning has decided that an assessment under the *Environment Effects Act 1978* is not required for the proposed development and the Minister's decision is subject to conditions:
  - A report that details how each condition has been considered and addressed in the design, construction and operation of the proposed development.
  - A copy of any report, plan or other document required to be prepared under those conditions.
- A plan for the management or mitigation of potential adverse effects or impacts on the environment or amenity from the proposed use or development, during and following construction.
- If the proposed project would require a permit but for the exemption in clause 52.30-3 and a copy of the application for that permit would be required to be given to a referral authority under section 55 of the Act, the comments of that referral authority on the proposed project.
- A report that demonstrates that the environmental conditions of the land are or will be suitable for the proposed use or development including any significant effects which the use or development may have on the environment or which the environment may have on the use or development including water, noise, air or land pollution impacts on the environment, amenity or human health.
- Any other plan, document or information the Minister for Planning considers necessary to assist the Minister's assessment of the proposed project or the plans and documents required to be prepared under this clause.

The requirements of this clause may be:

- Satisfied in separate components or stages of a project, but each requirement must be satisfied prior to the commencement of that component or stage.
- May be varied or waived by the Minister for Planning.

The plans and other documents required by this clause may be amended during the project to the satisfaction of the Minister for Planning.

52.30-7 Native vegetation requirements

25/03/2021
VC194

Before the removal, destruction or lopping of native vegetation outside the levy area:

- Information about the native vegetation in accordance with application requirements in Tables 4 and 5 of the Guidelines must be prepared to the satisfaction of the Secretary.
- The biodiversity impacts from the removal, destruction or lopping of that native vegetation must be offset in accordance with the Guidelines.
- Evidence that the required offset has been secured must be provided to the satisfaction of the Secretary.

The Secretary may vary the timing of the offset requirement.

The secured offset for a state project to which this clause applies may be reconciled at the completion of a project to the satisfaction of the Secretary.

Before the removal, destruction or lopping of native vegetation inside the levy area, information about the native vegetation in accordance with application requirements in Tables 4 and 5 (other than requirement 9) of the Guidelines must be prepared to the satisfaction of the Secretary.

The information requirements of this clause may be varied or waived by the Secretary.

The requirements of this clause may be satisfied in separate components or stages of a development, but each requirement must be satisfied before the removal, destruction or lopping of native vegetation for that component or stage.

52.31 LOCAL GOVERNMENT PROJECTS

25/03/2021
VC194

Purpose

To facilitate the development of land by or on behalf of municipal councils.

52.31-1 Permit exemptions

25/03/2021
VC194

Any requirement in a zone or a schedule to a zone to obtain a permit to construct a building or construct or carry out works does not apply to the development of land carried out by or on behalf of a municipal council. This exemption does not apply to:

- A development with an estimated cost of more than $10 million.
- A development in the Urban Floodway Zone unless the development is carried out to the satisfaction of the relevant floodplain management authority.
- A development associated with the use of land for accommodation, earth and energy resources industry, energy generation facility, industry or warehouse.
- A development for which an environment effects statement has been, or is required to be, prepared under the *Environment Effects Act 1978*.
- A development for which the Minister for Planning has decided that an assessment through an environment effects statement under the *Environment Effects Act 1978* is not required if the Minister's decision is subject to conditions.

Any requirement in the Floodway Overlay, Land Subject to Inundation Overlay and Special Building Overlay to obtain a permit to construct a building or construct or carry out works does not apply to the development of land carried out by or on behalf of a municipal council to the satisfaction of the relevant floodplain management authority.

This clause prevails over any inconsistent provision in this planning scheme.

52.31-2 Exemption from notice and review

25/03/2021
VC194

An application under any provision of this planning scheme to develop land by or on behalf of a municipal council is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act. This exemption does not apply to:

- An application for a development with an estimated cost of more than $10 million.
- An application for a development associated with the use of land for accommodation, earth and energy resources industry, energy generation facility, industry or warehouse.
- An application to remove, destroy or lop more than:
  - 0.5 hectares of native vegetation other than a tree; or
  - 15 native trees with a trunk diameter of less than 40 centimetres at a height of 1.3 metres above ground level; or
  - 5 native trees with a trunk diameter of 40 centimetres or more at a height of 1.3 metres above ground level.

52.32 WIND ENERGY FACILITY

31/07/2018
VC148

Purpose

To facilitate the establishment and expansion of wind energy facilities, in appropriate locations, with minimal impact on the amenity of the area.

52.32-1 Application

03/08/2021
VC206

This clause applies to land used and developed or proposed to be used and developed for a wind energy facility.

52.32-2 Use and development of land

03/08/2021
VC206

A permit is required to use and develop land for a wind energy facility.

The use and development of land for a wind energy facility is prohibited at a location listed in the table to this clause unless the condition opposite the location specified in the table is met.

Table to Clause 52.32-2

Location	Condition
On land where any turbine (measured from the centre of the tower at ground level) that forms part of the facility is located within one kilometre of an existing dwelling. This does not apply to a wind energy facility that is located on land in a residential zone, an industrial zone, a commercial zone or a special purpose zone.	Must meet the requirements of clause 52.32-3.
Land described in a schedule to the *National Parks Act 1975*	Must be principally used to supply electricity to a facility used in conjunction with conservation, recreation, administration or accommodation use of the land.
Land declared a Ramsar wetland as defined under section 17 of the *Environment Protection and Biodiversity Conservation Act 1999* (Cwth)	
Land listed in a schedule to Clause 52.32-2	Must be on land in a residential zone, industrial zone, commercial zone or special purpose zone and must be integrated as part of the development of the land.

52.32-3 Turbine within one kilometre of a dwelling

03/08/2021
VC206

An application that includes a proposed turbine within one kilometre of an existing dwelling must be accompanied by:

- A plan showing all dwellings within one kilometre of a proposed turbine (measured from the centre of the tower at ground level).
- Evidence of the written consent of any owner as at the date of that application of an existing dwelling located within one kilometre of a proposed turbine (measured from the centre of the tower at ground level) that forms part of a wind energy facility. This does not apply to an application to amend such a permit under section 72 or section 97I of the Act unless the amendment of the permit would:

- increase the number of turbines; or
- change the location of a turbine so that the centre of the tower (at ground level) is located closer to an existing dwelling (within one kilometre of a permitted turbine) than the centre of the tower (at ground level) of the closest permitted turbine to that dwelling.

This does not apply to a wind energy facility that is located on land in a residential zone, an industrial zone, a commercial zone or a special purpose zone.

52.32-4 Application requirements

04/07/2023
VC234

An application must be accompanied by the following information as appropriate:

Site and context analysis

A site and context analysis may use a site plan, photographs or other techniques to accurately describe the site and surrounding area and must include the following information:

- In relation to the site:
  - Site shape, dimensions and size
  - Orientation and contours
  - Current land use
  - The existing use and siting of buildings or works on the land
  - Existing vegetation types, condition and coverage
  - The landscape of the site
  - Species of flora and fauna listed under the *Flora and Fauna Guarantee Act 1988* and the *Environment Protection and Biodiversity Conservation Act 1999* (Cwth)
  - Sites of cultural heritage significance
  - Wind characteristics
  - Any other notable features, constraints or other characteristics of the site.
- In relation to the surrounding area:
  - Existing land uses
  - Above-ground utilities
  - Access to infrastructure
  - Direction and distances to nearby dwellings, townships, urban areas, significant conservation and recreation areas, water features, tourist routes and walking tracks, major roads, airports, aerodromes and existing and proposed wind energy facilities
  - The siting and use of buildings on adjacent properties
  - Views to and from the site, including views from existing dwellings and key vantage points including major roads, walking tracks, tourist routes and regional population growth corridors
  - Sites of flora and fauna listed under the *Flora and Fauna Guarantee Act 1988* and *Environment Protection and Biodiversity Conservation Act 1999* (Cwth), including significant habitat corridors, and movement corridors for these fauna
  - Sites of cultural heritage significance
  - National Parks, State Parks, Coastal Reserves and other land subject to the *National Parks Act 1975*

- Land declared a Ramsar wetland as defined under section 17 of the *Environment Protection and Biodiversity Conservation Act 1999* (Cwth)
- Location of any land included in the schedule to clause 52.32-2 of the planning scheme
- Any other notable features or characteristics of the area
- Bushfire risks.

Design response

- Detailed plans of the proposed development.
- Plans and elevations of transmission infrastructure and electricity utility works required to connect the facility to the electricity network, and access road options.
- Accurate visual simulations illustrating the development in the context of the surrounding area and from key public view points.
- A rehabilitation plan for the site.
- A written report(s), including:
  - A description of the proposal.
  - An explanation of how the proposed design derives from and responds to the site analysis.
  - A description of how the proposal responds to any significant landscape features for the area identified in the planning scheme.
  - An assessment of:
    - the visual impact of the proposal on the surrounding landscape.
    - the visual impact on abutting land that is described in a schedule to the *National Parks Act 1975* and Ramsar wetlands and coastal areas.
    - the impact of the proposal on any species (including birds and bats) listed under the *Flora and Fauna Guarantee Act 1988* or the *Environment Protection and Biodiversity Conservation Act 1999* (Cwth).
    - the impacts upon Aboriginal or non-Aboriginal cultural heritage.
  - A statement of why the site is suitable for the wind energy facility.
  - An environmental management plan including any rehabilitation and monitoring requirements.
- A pre-construction (predictive) noise assessment report prepared by a suitably qualified and experienced acoustician that:
  - Reports on a pre-construction (predictive) noise assessment conducted in accordance with *New Zealand Standard NZS6808:2010, Acoustics - Wind Farm Noise*.
  - Provides an assessment of whether the proposed wind energy facility will comply with the noise limit for that facility under Division 5 Part 5.3 of the *Environment Protection Regulations 2021*.

  - Where the proposed wind energy facility will be the subject of a wind turbine noise agreement under Division 5 of Part 5.3 of the *Environment Protection Regulations 2021,* specifies the premises of the relevant landowner (including any particular buildings) to which the agreement relates and provides an assessment of whether the proposed wind energy facility will comply with the modified noise limit for that facility specified in the agreement.
  - Is prepared on the basis that the relevant noise standard under Division 5 of Part 5.3 of the *Environment Protection Regulations 2021* will be *New Zealand Standard NZS6808:2010, Acoustics - Wind Farm Noise* and includes an assessment of whether a high amenity noise limit is applicable under Section 5.3 of the standard.

- A report prepared by an environmental auditor appointed under Part 8.3 of the *Environment Protection Act 2017* that verifies whether or not the pre-construction (predictive) noise assessment was conducted in accordance with *New Zealand Standard NZS6808:2010, Acoustics - Wind Farm Noise*.

If in the opinion of the responsible authority a requirement of the site and context analysis or design response is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

52.32-5 Decision guidelines

04/07/2023
VC234

Before deciding on an application, in addition to the decision guidelines of Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The effect of the proposal on the surrounding area in terms of noise, blade glint, shadow flicker and electromagnetic interference.
- The impact of the development on significant views, including visual corridors and sightlines.
- The impact of the facility on the natural environment and natural systems.
- The impact of the facility on cultural heritage.
- The impact of the facility on aircraft safety.
- *Policy and Planning Guidelines for Development of Wind Energy Facilities in Victoria* (Department of Environment, Land, Water and Planning, November 2021).

52.32-6 Anemometer

03/08/2021
VC206

Despite anything to the contrary in this scheme a permit may be granted to use and develop land for the purpose of wind measurement by an anemometer for a period of more than three years.

52.32-7 Application to amend a permit under section 72 of the Act

03/08/2021
VC206

An application to amend a permit made under section 72 of the Act is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if the amendment of the permit does not:

- increase the number of turbines; or
- increase the maximum height of a turbine.

52.32-8 Application to amend a permit under section 97I of the Act

03/08/2021
VC206

An application to amend a referred wind energy facility permit made under section 97I of the Act is wholly exempt from the requirements of section 97E(1) of the Act if the application does not seek to:

- increase the total number of turbines; or
- increase the maximum height of a turbine.

The requirements of section 97E(1) of the Act are modified so as to require referral of objections and submissions to an advisory committee established under section 151 of the Act if an application to amend a referred wind energy facility permit made under section 97I of the Act does not seek to:

- increase the total number of turbines by more than 15%; or
- increase the maximum height of a turbine by more than 20%.

31/07/2018
VC148

SCHEDULE TO CLAUSE 52.32 WIND ENERGY FACILITY

1.0 Wind energy facility prohibition

31/07/2018
VC148

Land where a Wind energy facility is prohibited
None specified

52.33 POST BOXES AND DRY STONE WALLS

31/07/2018
VC148

Purpose

To conserve historic post boxes and dry stone walls.

Permit requirement

A permit is required to demolish or remove a post box constructed before 1930.

A permit is required to demolish, remove or alter a dry stone wall constructed before 1940 on land specified in the schedule to this provision. This does not apply to:

- Dry stone structures other than walls and fences.
- The demolition or removal of a section of a dry stone wall to install a gate.
- The reconstruction of damaged or collapsing walls which are undertaken to the same specifications and using the same materials as the existing walls.

Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The significance of the post box or dry stone wall.
- Any applicable heritage study, statement of significance and conservation policy.
- Whether the proposal will adversely affect the significance of the post box or dry stone wall.
- Whether the proposal will adversely affect the significance, character or appearance of the area.

31/07/2018
VC148

SCHEDULE TO CLAUSE 52.33 POST BOXES AND DRY STONE WALLS

1.0 Permit requirement for dry stone walls

31/07/2018
VC148

Land
None specified

52.34 BICYCLE FACILITIES

31/07/2018
VC148

Purpose

To encourage cycling as a mode of transport.

To provide secure, accessible and convenient bicycle parking spaces and associated shower and change facilities.

52.34-1 Provision of bicycle facilities

19/01/2006
VC37

A new use must not commence or the floor area of an existing use must not be increased until the required bicycle facilities and associated signage has been provided on the land.

Where the floor area occupied by an existing use is increased, the requirement for bicycle facilities only applies to the increased floor area of the use.

52.34-2 Permit requirement

31/07/2018
VC148

A permit may be granted to vary, reduce or waive any requirement of Clause 52.34-5 and Clause 52.34-6.

52.34-3 Exemption from notice and review

31/07/2018
VC148

An application is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

52.34-4 Decision guidelines

14/01/2025
VC237

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- Whether the proposed number, location and design of bicycle facilities meets the purpose of this clause.
- The location of the proposed land use and the distance a cyclist would need to travel to reach the land.
- The users of the land and their opportunities for bicycle travel.
- Whether showers and change rooms provided on the land for users other than cyclists are available to cyclists.
- The opportunities for sharing of bicycle facilities by multiple uses, either because of variation of bicycle parking demand over time or because of efficiencies gained from the consolidation of shared bicycle facilities.
- *Australian Standard AS2890.3:2015, Parking Facilities Part 3: Bicycle Parking* (Standards Australia, 2015)
- Any relevant bicycle parking strategy or equivalent.

52.34-5 Required bicycle facilities

28/02/2025
VC274

Tables 1, 2 and 3 to this clause set out the number and type of bicycle facilities required. Bicycle facilities are required if the use is listed in column 1 of the table. The number of bicycle facilities required for a use is the sum of columns 2 and 3 of the tables.

If a schedule to the Precinct Zone specifies the number of bicycle spaces required for a use listed in column 1 of Table 1, that requirement is taken to be the required number of bicycle spaces for that use for the purpose of this clause.

If a schedule to the Precinct Zone specifies the number of bicycle spaces required for a use not listed in column 1 of Table 1, that use is deemed to be a use listed in column 1 of the table and the corresponding required number of spaces is deemed to be a requirement specified in column 2 or 3 of the table, as applicable.

If in calculating the number of bicycle facilities the result is not a whole number, the required number of bicycle facilities is the nearest whole number. If the fraction is one-half, the requirement is the next whole number.

A bicycle space for an employee or resident must be provided:

- Either in a bicycle locker or at a bicycle rail in a lockable compound.
- In accordance with any requirement specified in a schedule to the Precinct Zone.

A bicycle space for a visitor, shopper or student must be provided:

- At a bicycle rail.
- In accordance with any requirement specified in a schedule to the Precinct Zone.

Table 1 to Clause 52.34-5 Bicycle spaces

Use	Employee/Resident	Visitor/Shopper/Student
Amusement parlour	None	2 plus 1 to each 50 sq m of net floor area
Convenience restaurant	1 to each 25 sq m of floor area available to the public	2
Dwelling	In developments of four or more storeys, 1 to each 5 dwellings	In developments of four or more storeys, 1 to each 10 dwellings
Education centre (excluding Child care centre) other than specified in this table	1 to each 20 employees	1 to each 20 full-time students
Hospital	1 to each 15 beds	1 to each 30 beds
Hotel	1 to each 25 sq m of bar floor area available to the public, plus 1 to each 100 sq m of lounge floor area available to the public	1 to each 25 sq m of bar floor area available to the public, plus 1 to each 100 sq m of lounge floor area available to the public
Industry other than specified in this table	1 to each 1000 sq m of net floor area	None
Library	1 to each 500 sq m of net floor area	4 plus 2 to each 200 sq m of net floor area
Major sports and recreation facility	1 to each 1500 spectator places	1 to each 250 spectator places
Market	1 to each 50 stalls	1 to each 10 stalls
Medical centre	1 to each 8 practitioners	1 to each 4 practitioners
Minor sports and recreation facility	1 per 4 employees	1 to each 200 sq m of net floor area
Motel	1 to each 40 rooms	None
Office other than specified in this table	1 to each 300 sq m of net floor area if the net floor area exceeds 1000 sq m	1 to each 1000 sq m of net floor area if the net floor area exceeds 1000 sq m
Place of assembly other than specified in this table	1 to each 1500 sq m of net floor area	2 plus 1 to each 1500 sq m of net floor area
Primary school	1 to each 20 employees	1 to each 5 pupils over year 4

Use	Employee/Resident	Visitor/Shopper/Student
Residential building other than specified in this table	In developments of four or more storeys, 1 to each 10 lodging rooms	In developments of four or more storeys, 1 to each 10 lodging rooms
Restaurant	1 to each 100 sq m of floor area available to the public	2 plus 1 to each 200 sq m of floor area available to the public if the floor area available to the public exceeds 400 sq m.
Retail premises other than specified in this table	1 to each 300 sq m of leasable floor area	1 to each 500 sq m of leasable floor area
Secondary school	1 to each 20 employees	1 to each 5 pupils
Service industry	1 to each 800 sq m of net floor area	None
Shop	1 to each 600 sq m of leasable floor area if the leasable floor area exceeds 1000 sq metres	1 to each 500 sq m of leasable floor area if the leasable floor area exceeds 1000 sq metres
Take-away food premises	1 to each 100 sq m of net floor area	1 to each 50 sq m of net floor area

Table 2 to Clause 52.34-5 Showers

USE	Employee/Resident	Visitor/Shopper/Student
Any use listed in Table 1	If 5 or more employee bicycle spaces are required, 1 shower for the first 5 employee bicycle spaces, plus 1 to each 10 employee bicycle spaces thereafter.	None

Table 3 to Clause 52.34-5 – Change rooms

USE	Employee/Resident	Visitor/Shopper/Student
Any use listed in Table 1	1 change room or direct access to a communal change room to each shower. The change room may be a combined shower and change room.	None

52.34-6 Design of bicycle spaces

31/07/2018
VC148

Bicycle spaces should:

- Provide a space for a bicycle of minimum dimensions of 1.7 metres in length, 1.2 metres in height and 0.7 metres in width at the handlebars.
- Be located to allow a bicycle to be ridden to within 30 metres of the bicycle parking space.
- Be located to provide convenient access from surrounding bicycle routes and main building entrances.
- Not interfere with reasonable access to doorways, loading areas, access covers, furniture, services and infrastructure.
- Not cause a hazard.
- Be adequately lit during periods of use.

Bicycle rails

A bicycle rail must:

- Be securely fixed to a wall or to the floor or ground.
- Be in a highly visible location for bicycle security (when not in a compound).
- Be of a shape that allows a cyclist to easily lock the bicycle frame and wheels.
- Be located to allow easy access to park, lock and remove the bicycle.

Bicycle compounds and lockers

A bicycle compound or a bicycle locker must:

- Be located to provide convenient access to other bicycle facilities including showers and change rooms.
- Be fully enclosed.
- Be able to be locked.
- If outside, provide weather protection for the bicycle.

A bicycle locker must provide a bicycle parking space for at least one bicycle.

A bicycle compound must:

- Include wall or floor rails for bicycle parking.
- Provide an internal access path of at least 1.5 metres in width.

52.34-7 Bicycle signage

31/07/2018
VC148

If bicycle facilities are required by this clause, bicycle signage that directs the cyclists to the bicycle facilities must be provided to the satisfaction of the responsible authority.

Bicycle signage should:

- Be at least 0.3 metres wide and 0.45 metres high.
- Display a white bicycle on a blue background on the top half of the sign.
- Display information about the direction of facilities on the bottom half of the sign.

52.35 MAJOR ROAD PROJECTS

14/05/2021
VC198

52.35-1 Purpose

14/05/2021
VC198

To facilitate the delivery of projects carried out by or on behalf of Major Road Projects Victoria.

52.35-2 Application

14/05/2021
VC198

This clause applies to the use and development of land for a project carried out by or on behalf of Major Road Projects Victoria.

This clause does not apply to:

- The subdivision of land.
- The use or development of land for a promotion sign or a major promotion sign.
- A use or development that would not require a permit under a provision of this planning scheme but for the provisions of clause 52.35.
- A use or development to which clause 52.03 applies.
- A use or development for a project if a document has been incorporated into this planning scheme expressly for the project and the use and development is carried out on land to which the specific control contained in the document applies.
- A use or development carried out in accordance with a permit issued on or before the approval date of Amendment VC198.
- A use or development for which a planning permit is granted by the responsible authority in accordance with the provisions of this planning scheme which would apply in the absence of the exemption in clause 52.35-3.
- A development for which an environment effects statement has been, or is required by the Minister for Planning to be, prepared under the *Environment Effects Act 1978*.

The provisions of clause 52.35 prevail over any inconsistent provision in this planning scheme.

52.35-3 Exemption from planning scheme requirements

14/05/2021
VC198

Any requirement of this planning scheme to obtain a permit or any provision of this planning scheme that prohibits or restricts the use or development of land, requires the use or development of land to be carried out in a particular manner, or requires a specified thing to be done to the satisfaction of a specified person or body, does not apply to a use or development to which this clause 52.35 applies if the requirements of clause 52.35 are met.

This exemption does not apply to a requirement in clauses 45.08 or 51.03, or in any schedule to those clauses.

52.35-4 Use and development requirements

14/05/2021
VC198

The use and development of land must be carried out generally in accordance with the plans and documents approved by the Minister for Planning under clause 52.35, to the satisfaction of the Minister for Planning.

The construction of a building or the construction or carrying out of works in a Floodway Overlay, Land Subject to Inundation Overlay, Special Building Overlay or Urban Floodway Zone must be carried out to the satisfaction of the relevant floodplain management authority.

The use and development of land in a Public Acquisition Overlay must be carried out to the satisfaction of the relevant acquiring authority.

52.35-5 Consultation requirements

14/05/2021
VC198

Before the commencement of the use or development:

- Public consultation, including consultation with relevant public authorities and the municipal council for the municipal district within which the proposed use or development will be carried out, must be carried out to the satisfaction of the Minister for Planning.
- A report that summarises the consultation undertaken and feedback received, and explains how the feedback has been considered and responded to must be prepared to the satisfaction of the Minister for Planning.

The requirements of this clause may be varied or waived by the Minister for Planning.

52.35-6 Project boundary requirement

14/05/2021
VC198

Before the use or development commences, a plan that shows the boundary of the land on which the use or development will be carried out must be prepared to the satisfaction of the Minister for Planning.

The plan may be prepared in stages and may be amended to the satisfaction of the Minister for Planning.

52.35-7 Other pre-commencement requirements

14/05/2021
VC198

Before the use or development (other than a preparatory use or development) commences, the following plans, documents and information must be prepared to the satisfaction of the Minister for Planning:

- A description of the natural, physical, cultural heritage, built heritage, landscape, vegetation, access and any other notable features, characteristics and significance of the site and surrounding area including the existing use and development of the site and surrounding land.
- A description of the project.
- An explanation of how the proposed use or development responds to the decision guidelines in this planning scheme that would have applied to an application for a permit for the proposed use or development but for the provisions of this clause 52.35.
- If the land is in the Heritage Overlay and the proposed development would require a permit under the overlay but for the exemption in clause 52.35-3:
  - An assessment of the impact of the proposed development on the heritage significance of the heritage place.
  - Site plans and elevations showing the extent of the proposed development on the land.
  - Photographs of any buildings or works to be demolished or removed, including photographs of the exterior and interior of the building and contextual images of the building's environs and setting.
- If the land is in an Environmental Significance Overlay, a Significant Landscape Overlay or a Vegetation Protection Overlay and the proposed development would require a permit under the overlay but for the exemption in clause 52.35-3, an explanation of how the proposed development responds to any environmental, vegetation or landscape significance or objective specified in a schedule to the overlay.
- An explanation of how the proposed use or development is consistent with any applicable Statement of Planning Policy.
- A statement outlining landscape and urban design measures or treatments required to address any amenity impacts as part of the project.

- An environmental management framework, prepared having regard to consultation undertaken with each relevant municipal council on environmental management for the use or development or measures to avoid or minimise adverse environmental impacts, that includes:
  - A summary of key construction methodologies.
  - An overarching framework of measures to reduce and manage environmental and amenity effects during construction.
  - A summary of performance monitoring and reporting processes, including any auditing, to ensure environmental and amenity impacts are reduced and managed during construction.
  - A plan for engagement with each relevant municipal council, the community and other stakeholders during construction, including enquiries and complaints management.

  The environmental management framework must be accompanied by a summary of the consultation with each relevant municipal council that informed the preparation of the environmental management framework.
- If the Minister for Planning has decided that an assessment under the *Environment Effects Act 1978* is not required for the proposed development and the decision is subject to conditions:
  - A report that details how each condition has been considered and addressed in the design, construction and operation of the proposed development.
  - A copy of any report, plan or other document required to be prepared under those conditions.
- Any other information the Minister for Planning considers necessary to assist the Minister's assessment of the plans and documents required to be submitted under this clause.

The requirements of this clause:

- May be satisfied in separate components or stages of a project, but each requirement must be satisfied before the commencement of the use and development for that component or stage.
- May be varied or waived by the Minister.

The plans and other documents required by this clause may be amended to the satisfaction of the Minister for Planning.

52.35-8 Native vegetation requirements

14/05/2021
VC198

In this clause:

- ***Guidelines*** means the *Guidelines for removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, December 2017);
- ***levy area*** has the same meaning as in the *Melbourne Strategic Assessment (Environment Mitigation Levy) Act 2020*;
- ***Secretary*** means the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).

Before the removal, destruction or lopping of native vegetation outside the levy area to enable a preparatory use or development, information about that native vegetation in accordance with application requirements 1, 5, 9, 10 and 11 in Tables 4 and 5 to the Guidelines must be prepared to the satisfaction of the Secretary.

Before the removal, destruction or lopping of native vegetation outside the levy area (other than to enable a preparatory use or development):

- Information about the native vegetation in accordance with the application requirements 1, 5, 9, 10, and 11 in Tables 4 and 5 of the Guidelines must be prepared to the satisfaction of the Secretary.

- The biodiversity impacts from the removal, destruction or lopping of that native vegetation must be offset in accordance with the Guidelines to the satisfaction of the Secretary. The biodiversity impacts from the removal, destruction or lopping of native vegetation outside the levy area to enable a preparatory use or development must be included in the total biodiversity impacts when determining the offset to the satisfaction of the Secretary.
- Evidence that the required offset has been secured must be provided to the satisfaction of the Secretary.

The timing of the offset requirement may be varied by the Secretary. The secured offset for a project may be reconciled at the completion of a project to the satisfaction of the Secretary.

Before the removal, destruction or lopping of native vegetation inside the levy area, information about the native vegetation in accordance with the application requirements 1, 5, 10 and 11 in Tables 4 and 5 of the Guidelines must be prepared to the satisfaction of the Secretary.

The requirements of this clause may be satisfied in separate components or stages of a development, but each requirement must be satisfied before the removal, destruction or lopping of native vegetation for that component or stage.

52.35-9 Preparatory use and development

14/05/2021
VC198

For the purposes of clause 52.35, a preparatory use or development is a use or development required to prepare for the construction of a project or a component or stage of a project. It is limited to the following:

- Use and development that would not require a permit under a provision of this planning scheme but for the exemption in clause 52.35-3.
- Works associated with investigating, testing and surveying land.
- Creation and use of construction access points, accessways and working platforms.
- Site establishment works including construction of temporary site fencing and hoarding, site offices, and hardstand and laydown areas.
- Construction and use of temporary car parking.
- Construction or installation of environment and traffic controls, including designated ‘no-go' zones.
- Construction, protection, modification, removal or relocation of utility services, rail signalling, overhead and associated infrastructure.
- Salvage and relocation of cultural heritage material and other management actions required to be carried out in compliance with:
  - a cultural heritage management plan prepared and/or approved under the *Aboriginal Heritage Act 2006* or otherwise in compliance with that Act; or
  - the conditions of any permit or consent granted under the *Heritage Act 2017* or otherwise in compliance with that Act.
- Demolition or removal of a building (other than a building in a Heritage Overlay) or works to the minimum extent necessary to enable another preparatory use or development.
- Removal, destruction or lopping of vegetation (other than a tree in the Heritage Overlay specified below) to the minimum extent necessary to enable another preparatory use or development.

For the purposes of clause 52.35, preparatory development does not include:

- Demolition or removal of a building in a Heritage Overlay.
- Removal, destruction or lopping of a tree in a Heritage Overlay if the schedule to the overlay specifies the heritage place as one where tree controls apply.

52.36 RAIL PROJECTS

14/05/2021
VC198

52.36-1 Purpose

14/05/2021
VC198

To facilitate the delivery of projects carried out by or on behalf of Rail Projects Victoria.

52.36-2 Application

14/05/2021
VC198

This clause applies to the use and development of land for a project carried out by or on behalf of Rail Projects Victoria.

This clause does not apply to:

- The subdivision of land.
- The use or development of land for a promotion sign or a major promotion sign.
- A use or development that would not require a permit under a provision of this planning scheme but for the provisions of clause 52.36.
- A use or development to which clause 52.03 applies.
- A use or development for a project if a document has been incorporated into this planning scheme expressly for the project and the use and development is carried out on land to which the specific control contained in the document applies.
- A use or development carried out in accordance with a permit issued on or before the approval date of Amendment VC198.
- A use or development for which a planning permit is granted by the responsible authority in accordance with the provisions of this planning scheme which would apply in the absence of the exemption in clause 52.36-3.
- A development for which an environment effects statement has been, or is required by the Minister for Planning to be, prepared under the *Environment Effects Act 1978*.

The provisions of clause 52.36 prevail over any inconsistent provision in this planning scheme.

52.36-3 Exemption from planning scheme requirements

14/05/2021
VC198

Any requirement of this planning scheme to obtain a permit or any provision of this planning scheme that prohibits or restricts the use or development of land, requires the use or development of land to be carried out in a particular manner, or requires a specified thing to be done to the satisfaction of a specified person or body, does not apply to a use or development to which this clause 52.36 applies if the requirements of clause 52.36 are met.

This exemption does not apply to a requirement in clauses 45.08 or 51.03, or in any schedule to those clauses.

52.36-4 Use and development requirements

20/01/2022
VC205

The use and development of land must be carried out generally in accordance with the plans and documents approved by the Minister for Planning under clause 52.36, to the satisfaction of the Minister for Planning.

The construction of a building or the construction or carrying out of works in a Floodway Overlay, Land Subject to Inundation Overlay, Special Building Overlay or Urban Floodway Zone must be carried out to the satisfaction of the relevant floodplain management authority.

The creation or alteration of access to a road in a Transport Zone 2, or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority and the purpose of the acquisition is for a road, must be carried out to the satisfaction of the Head, Transport for Victoria.

The use and development of land in a Public Acquisition Overlay must be carried out to the satisfaction of the relevant acquiring authority.

52.36-5 Consultation requirements

14/05/2021
VC198

Before the commencement of the use or development:

- Public consultation, including consultation with relevant public authorities and the municipal council for the municipal district within which the proposed use or development will be carried out, must be carried out to the satisfaction of the Minister for Planning.
- A report that summarises the consultation undertaken and feedback received, and explains how the feedback has been considered and responded to must be prepared to the satisfaction of the Minister for Planning.

The requirements of this clause may be varied or waived by the Minister for Planning.

52.36-6 Project boundary requirement

14/05/2021
VC198

Before the use or development commences, a plan that shows the boundary of the land on which the use or development will be carried out must be prepared to the satisfaction of the Minister for Planning.

The plan may be prepared in stages and may be amended to the satisfaction of the Minister for Planning.

52.36-7 Other pre-commencement requirements

14/05/2021
VC198

Before the use or development (other than a preparatory use or development) commences, the following plans, documents and information must be prepared to the satisfaction of the Minister for Planning:

- A description of the natural, physical, cultural heritage, built heritage, landscape, vegetation, access and any other notable features, characteristics and significance of the site and surrounding area including the existing use and development of the site and surrounding land.
- A description of the project.
- An explanation of how the proposed use or development responds to the decision guidelines in this planning scheme that would have applied to an application for a permit for the proposed use or development but for the provisions of this clause 52.36.
- If the land is in the Heritage Overlay and the proposed development would require a permit under the overlay but for the exemption in clause 52.36-3:
  - An assessment of the impact of the proposed development on the heritage significance of the heritage place.
  - Site plans and elevations showing the extent of the proposed development on the land.
  - Photographs of any buildings or works to be demolished or removed, including photographs of the exterior and interior of the building and contextual images of the building's environs and setting.
- If the land is in an Environmental Significance Overlay, a Significant Landscape Overlay or a Vegetation Protection Overlay and the proposed development would require a permit under the overlay but for the exemption in clause 52.36-3, an explanation of how the proposed development responds to any environmental, vegetation or landscape significance or objective specified in a schedule to the overlay.
- An explanation of how the proposed use or development is consistent with any applicable Statement of Planning Policy.

- An environmental management framework, prepared having regard to consultation undertaken with each relevant municipal council on environmental management for the use or development or measures to avoid or minimise adverse environmental impacts, that includes:
  - A summary of key construction methodologies.
  - An overarching framework of measures to reduce and manage environmental and amenity effects during construction.
  - A summary of performance monitoring and reporting processes, including any auditing, to ensure environmental and amenity impacts are reduced and managed during construction.
  - A plan for engagement with each relevant municipal council, the community and other stakeholders during construction, including enquiries and complaints management.

  The environmental management framework must be accompanied by a summary of the consultation with each relevant municipal council that informed the preparation of the environmental management framework.
- If the Minister for Planning has decided that an assessment under the *Environment Effects Act 1978* is not required for the proposed development and the decision is subject to conditions:
  - A report that details how each condition has been considered and addressed in the design, construction and operation of the proposed development.
  - A copy of any report, plan or other document required to be prepared under those conditions.
- Any other information the Minister for Planning considers necessary to assist the Minister's assessment of the plans and documents required to be submitted under this clause.

The requirements of this clause:

- May be satisfied in separate components or stages of a project, but each requirement must be satisfied before the commencement of the use and development for that component or stage.
- May be varied or waived by the Minister.

The plans and other documents required by this clause may be amended to the satisfaction of the Minister for Planning.

52.36-8 Native vegetation requirements

14/05/2021
VC198

In this clause:

- ***Guidelines*** means the *Guidelines for removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, December 2017);
- ***levy area*** has the same meaning as in the *Melbourne Strategic Assessment (Environment Mitigation Levy) Act 2020*;
- ***Secretary*** means the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).

Before the removal, destruction or lopping of native vegetation outside the levy area to enable a preparatory use or development, information about that native vegetation in accordance with application requirements 1, 5, 9, 10 and 11 in Tables 4 and 5 to the Guidelines must be prepared to the satisfaction of the Secretary.

Before the removal, destruction or lopping of native vegetation outside the levy area (other than to enable a preparatory use or development):

- Information about the native vegetation in accordance with application requirements 1, 5, 9 10, and 11 in Tables 4 and 5 of the Guidelines must be prepared to the satisfaction of the Secretary.

- The biodiversity impacts from the removal, destruction or lopping of that native vegetation must be offset in accordance with the Guidelines to the satisfaction of the Secretary. The biodiversity impacts from the removal, destruction or lopping of native vegetation outside the levy area to enable a preparatory use or development must be included in the total biodiversity impacts when determining the offset to the satisfaction of the Secretary.
- Evidence that the required offset has been secured must be provided to the satisfaction of the Secretary.

The timing of the offset requirement may be varied by the Secretary. The secured offset for a project may be reconciled at the completion of a project to the satisfaction of the Secretary.

Before the removal, destruction or lopping of native vegetation inside the levy area, information about the native vegetation in accordance with the application requirements 1, 5, 10 and 11 in Tables 4 and 5 of the Guidelines must be prepared to the satisfaction of the Secretary.

The requirements of this clause may be satisfied in separate components or stages of a development, but each requirement must be satisfied before the removal, destruction or lopping of native vegetation for that component or stage.

52.36-9 Preparatory use and development

14/05/2021
VC198

For the purposes of clause 52.36, a preparatory use or development is a use or development required to prepare for the construction of a project or a component or stage of a project. It is limited to the following:

- Use and development that would not require a permit under a provision of this planning scheme but for the exemption in clause 52.36-3.
- Works associated with investigating, testing and surveying land.
- Creation and use of construction access points, accessways and working platforms.
- Site establishment works including construction of temporary site fencing and hoarding, site offices, and hardstand and laydown areas.
- Construction and use of temporary car parking.
- Construction or installation of environment and traffic controls, including designated ‘no-go' zones.
- Construction, protection, modification, removal or relocation of utility services, rail signalling, overhead and associated infrastructure.
- Salvage and relocation of cultural heritage material and other management actions required to be carried out in compliance with:
  - a cultural heritage management plan prepared and/or approved under the *Aboriginal Heritage Act 2006* or otherwise in compliance with that Act; or
  - the conditions of any permit or consent granted under the *Heritage Act 2017* or otherwise in compliance with that Act.
- Demolition or removal of a building (other than a building in a Heritage Overlay) or works to the minimum extent necessary to enable another preparatory use or development.
- Removal, destruction or lopping of vegetation (other than a tree in the Heritage Overlay specified below) to the minimum extent necessary to enable another preparatory use or development.

For the purposes of clause 52.36, preparatory development does not include:

- Demolition or removal of a building in a Heritage Overlay.
- Removal, destruction or lopping of a tree in a Heritage Overlay if the schedule to the overlay specifies the heritage place as one where tree controls apply.

53 GENERAL REQUIREMENTS AND PERFORMANCE STANDARDS

31/07/2018
VC148

53.01 PUBLIC OPEN SPACE CONTRIBUTION AND SUBDIVISION

25/02/2025
VC257

A person who proposes to subdivide land must make a contribution to the council for public open space in an amount specified in the schedule to this clause (being a percentage of the land intended to be used for residential, industrial or commercial purposes, or a percentage of the site value of such land, or a combination of both). If no amount is specified, a contribution for public open space may still be required under section 18 of the *Subdivision Act 1988*.

This requirement does not apply if a public open space contribution requirement is specified in a schedule to the Built Form Overlay.

53.01-1 Exemption from public open space requirement specified in the scheme

31/07/2018
VC148

A subdivision is exempt from a public open space requirement specified in this scheme if:

- It is one of the following classes of subdivision:
  - Class 1: The subdivision of a building used for residential purposes provided each lot contains part of the building. The building must have been constructed or used for residential purposes immediately before 30 October 1989 or a planning permit must have been issued for the building to be constructed or used for residential purposes immediately before that date.
  - Class 2: The subdivision of a commercial or industrial building provided each lot contains part of the building.
- It is for the purpose of excising land to be transferred to a public authority, council or a Minister for a utility installation.
- It subdivides land into two lots and the council considers it unlikely that each lot will be further subdivided.

53.01-2 Exemption from public open space requirement under section 18(8)(a) of the Subdivision Act 1988

31/07/2018
VC148

For the purposes of section 18(8)(a) of the *Subdivision Act 1988*, the following classes of subdivision are exempt from the public open space requirement:

- Class 1: The subdivision of a building used for residential purposes provided each lot contains part of the building. The building must have been constructed or used for residential purposes immediately before 30 October 1989 or a planning permit must have been issued for the building to be constructed or used for residential purposes immediately before that date.
- Class 2: The subdivision of a commercial or industrial building provided each lot contains part of the building.

Note: Check section 18A of the Subdivision Act 1988 for other requirements that apply to a public open space requirement specified in the planning scheme.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 53.01 PUBLIC OPEN SPACE CONTRIBUTION AND SUBDIVISION

1.0

08/07/2021
C211brim

Subdivision and public open space contribution

Type or location of subdivision	Amount of contribution for public open space
All commercial and residential	5%
All industrial	2.5%

53.02 BUSHFIRE PLANNING

31/07/2018
VC148

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To ensure that the development of land prioritises the protection of human life and strengthens community resilience to bushfire.

To ensure that the location, design and construction of development appropriately responds to the bushfire hazard.

To ensure development is only permitted where the risk to life, property and community infrastructure from bushfire can be reduced to an acceptable level.

To specify location, design and construction measures for a single dwelling that reduces the bushfire risk to life and property to an acceptable level.

53.02-1 Application

25/02/2025
VC257

This clause applies to an application under Clause 44.06 - Bushfire Management Overlay, unless the application meets all of the requirements specified in a schedule to Clause 44.06.

Clause 53.02-3 applies to an application to construct a single dwelling or construct or carry out works associated with a single dwelling if all of the following requirements are met:

- The land is zoned Neighbourhood Residential Zone, General Residential Zone, Residential Growth Zone, Housing Choice and Transport Zone, Urban Growth Zone, Low Density Residential Zone, Township Zone or Rural Living Zone.
- There is only one dwelling on the lot.
- The application meets all of the approved measures contained in Clause 53.02-3.

Clause 53.02-4 applies to all other applications.

53.02-2 Operation

31/07/2018
VC148

The provisions of this clause contain:

- **Objectives.** An objective describes the outcome that must be achieved in a completed development.
- **Approved measures (AM).** An approved measure meets the objective.
- **Alternative measures (AltM).** An alternative measure may be considered where the responsible authority is satisfied that the objective can be met. The responsible authority may consider other unspecified alternative measures.
- **Decision guidelines**. The decision guidelines set out the matters that the responsible authority must consider before deciding on an application, including whether any proposed alternative measure is appropriate.

A schedule to Clause 44.06 may specify substitute approved measures, additional alternative measures and additional or substitute decision guidelines.

A substitute approved measure specified in a schedule to Clause 44.06 substitutes the applicable approved measure contained in this clause.

53.02-3 Dwellings in existing settlements – Bushfire protection objective

31/07/2018
VC148

To specify bushfire design and construction measures for a single dwelling or alteration and extension to an existing dwelling that reduces the risk to life and property to an acceptable level.

Approved measures

Measure	Requirement
AM 1.1	A building is sited to ensure the site best achieves the following: ▪ The maximum separation distance between the building and the bushfire hazard. ▪ The building is in close proximity to a public road. ▪ Access can be provided to the building for emergency service vehicles.
AM 1.2	A building provides the defendable space in accordance with Table 1 Columns A, B, C, D or E and Table 6 to Clause 53.02-5. Adjoining land may be included as defendable space where there is a reasonable assurance that the land will remain or continue to be managed in that condition as part of the defendable space. A building is constructed to the bushfire attack level: ▪ That corresponds to the defendable space provided in accordance with Table 1 to Clause 53.02-5, or ▪ The next lower bushfire attack level that corresponds to the defendable space provided in accordance with Table 1 to Clause 53.02-5 where all of the following apply: – A private bushfire shelter (a Class 10c building within the meaning of the Building Regulations 2006) is constructed on the same land as the dwelling. – A minimum bushfire attack level of BAL12.5 is provided in all circumstances.
AM 1.3	A building is provided with: ▪ A static water supply for fire fighting and property protection purposes specified in Table 4 to Clause 53.02-5. The water supply may be in the same tank as other water supplies provided that a separate outlet is reserved for fire fighting water supplies. ▪ Vehicle access that is designed and constructed as specified in Table 5 to Clause 53.02-5.

53.02-3.1 Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The bushfire hazard site assessment and the bushfire management statement submitted with the application.
- Whether all of the the approved measures have been incorporated into the application.

53.02-4 Bushfire protection objectives

14/12/2023
VC253

53.02-4.1 Landscape, siting and design objectives

Development is appropriate having regard to the nature of the bushfire risk arising from the surrounding landscape.

Development is sited to minimise the risk from bushfire.

Development is sited to provide safe access for vehicles, including emergency vehicles.

Building design minimises vulnerability to bushfire attack.

Approved measures

Measure	Requirement
AM 2.1	The bushfire risk to the development from the landscape beyond the site can be mitigated to an acceptable level.
AM 2.2	A building is sited to ensure the site best achieves the following: ▪ The maximum separation distance between the building and the bushfire hazard. ▪ The building is in close proximity to a public road. ▪ Access can be provided to the building for emergency service vehicles.
AM 2.3	A building is designed to be responsive to the landscape risk and reduce the impact of bushfire on the building.

53.02-4.2 Defendable space and construction objective

Defendable space and building construction mitigate the effect of flame contact, radiant heat and embers on buildings.

Approved measures

Measure	Requirement
AM 3.1	A building used for a dwelling (including an extension or alteration to a dwelling), small second dwelling, industry, office or retail premises is provided with defendable space in accordance with: ▪ Table 2 Columns A, B or C and Table 6 to Clause 53.02-5 wholly within the title boundaries of the land; or ▪ If there are significant siting constraints, Table 2 Column D and Table 6 to Clause 53.02-5. The building is constructed to the bushfire attack level that corresponds to the defendable space provided in accordance with Table 2 to Clause 53.02-5.
AM 3.2	A building used for accommodation (other than a dwelling or small second dwelling), a child care centre, an education centre, a hospital, leisure and recreation or a place of assembly is: ▪ Provided with defendable space in accordance with Table 3 and Table 6 to Clause 53.02-5 wholly within the title boundaries of the land. ▪ Constructed to a bushfire attack level of BAL12.5.

Alternative measures

Measure	Requirement
AltM 3.3	Adjoining land may be included as defendable space where there is a reasonable assurance that the land will remain or continue to be managed in that condition as part of the defendable space.
AltM 3.4	Defendable space and the bushfire attack level is determined using Method 2 of *AS3959:2018 Construction of buildings in bushfire prone areas* (Standards Australia) subject to any guidance published by the relevant fire authority.

Measure	Requirement
AltM 3.5	A building used for a dwelling (including an extension or alteration to a dwelling) may provide defendable space to the property boundary where it can be demonstrated that: ▪ The lot has access to urban, township or other areas where: – Protection can be provided from the impact of extreme bushfire behaviour. – Fuel is managed in a minimum fuel condition. – There is sufficient distance or shielding to protect people from direct flame contact or harmful levels of radiant heat. ▪ Less defendable space and a higher construction standard is appropriate having regard to the bushfire hazard landscape assessment. ▪ The dwelling is constructed to a bushfire attack level of BAL FZ. This alternative measure only applies where the requirements of **AM 3.1** cannot be met.
AltM 3.6	A building used for accommodation (other than a dwelling or small second dwelling), child care centre, education centre, hospital, leisure and recreation or place of assembly may provide defendable space in accordance with Table 2 Columns A, B or C and Table 6 to Clause 53.02-5 where it can be demonstrated that: ▪ An integrated approach to risk management has been adopted that considers: – The characteristics of the likely future occupants including their age, mobility and capacity to evacuate during a bushfire emergency. – The intended frequency and nature of occupation. – The effectiveness of proposed emergency management arrangements, including a mechanism to secure implementation. ▪ Less defendable space and a higher construction standard is appropriate having regard to the bushfire hazard landscape assessment.

53.02-4.3 Water supply and access objectives

A static water supply is provided to assist in protecting property.

Vehicle access is designed and constructed to enhance safety in the event of a bushfire.

Approved measures

Measure	Requirement
AM 4.1	A building used for a dwelling (including an extension or alteration to a dwelling), a small second dwelling, industry, office or retail premises is provided with: ▪ A static water supply for fire fighting and property protection purposes specified in Table 4 to Clause 53.02-5. ▪ Vehicle access that is designed and constructed as specified in Table 5 to Clause 53.02-5. The water supply may be in the same tank as other water supplies provided that a separate outlet is reserved for fire fighting water supplies.
AM 4.2	A building used for accommodation (other than a dwelling or small second dwelling), child care centre, education centre, hospital, leisure and recreation or place of assembly is provided with:

Measure	Requirement
	▪ A static water supply for fire fighting and property protection purposes of 10,000 litres per 1,500 square metres of floor space up to 40,000 litres. ▪ Vehicle access that is designed and constructed as specified in Table 5 to Clause 53.02-5. ▪ An integrated approach to risk management that ensures the water supply and access arrangements will be effective based on the characteristics of the likely future occupants including their age, mobility and capacity to evacuate during a bushfire emergency. The water supply may be in the same tank as other water supplies provided that a separate outlet is reserved for fire fighting water supplies.

53.02-4.4 Subdivision objectives

To provide lots that are capable of being developed in accordance with the objectives of Clause 53.02.

To specify at the subdivision stage bushfire protection measures to develop a lot with a single dwelling on land zoned for residential or rural residential purposes.

Measure	Requirement
AM 5.1	An application to subdivide land, other than where **AM 5.2** applies, demonstrates that each proposed lot is capable of meeting: ▪ The defendable space in accordance with Table 2 Columns A, B or C and Table 6 to Clause 53.02-5. ▪ The approved measures in Clause 53.02-4.1 and Clause 53.02-4.3.
AM 5.2	An application to subdivide land zoned for residential or rural residential purposes must be accompanied by a plan that shows: ▪ Each lot satisfies the approved measure in **AM 2.1**. ▪ A building envelope for a single dwelling on each lot that complies with **AM 2.2** and provides defendable space in accordance with: – Columns A or B of Table 2 to Clause 53.02-5 for a subdivision that creates 10 or more lots; or – Columns A, B or C of Table 2 to Clause 53.02-5 for a subdivision that creates less than 10 lots. The bushfire attack level that corresponds to the defendable space provided in accordance with Table 2 to Clause 53.02-5 must be noted on the building envelope. ▪ Defendable space wholly contained within the boundaries of the proposed subdivision. ▪ Defendable space may be shared between lots within the subdivision. Defendable space for a lot may utilse communal areas, such as roads, where that land can meet the requirements for defendable space. ▪ Vegetation management requirements in accordance with Table 6 to implement and maintain the defendable space required under this approved measure. ▪ Water supply and vehicle access that complies with **AM 4.1**.
AM 5.3	An application to subdivide land to create 10 or more lots provides a perimeter road adjoining the hazardous vegetation to support fire fighting.

Measure	Requirement
AM 5.4	A subdivision manages the bushfire risk to future development from existing or proposed landscaping, public open space and communal areas.

Alternative measure

Measure	Requirement
AltM 5.5	A building envelope for a subdivision that creates 10 or more lots required under **AM 5.2** may show defendable space in accordance with Table 2 Column C and Table 6 to Clause 53.02-5 where it can be demonstrated that: ▪ All other requirements of **AM 5.2** have been met. ▪ Less defendable space and a higher construction standard is appropriate having regard to the bushfire hazard landscape assessment.

53.02-4.5 Decision guidelines

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The bushfire hazard landscape assessment, the bushfire hazard site assessment and the bushfire management statement submitted with the application.
- The impact of any State, regional or local bushfire management and prevention actions occurring around the site and in the wider area on the bushfire hazard and the level of risk to the proposed development.
- Whether the proposed development meets the objectives of Clause 53.02-4 regardless of other measures which may be available, including private bushfire shelters, community shelters and the presence of places of last resort.
- Whether the proposed measures can be practically implemented and maintained in conjunction with the ongoing use of the land.
- Whether the use of an alternative measure meets the relevant objective having regard to the bushfire hazard and the nature of any constraint that prevents the applicable approved measure from being implemented.
- If one or more of the objectives in Clause 53.02-4 will not be achieved in the completed development, whether the development will, taking all relevant factors into account, reduce the bushfire risk to a level that warrants it proceeding.
- Whether the risk arising from the broader landscape can be mitigated to an acceptable level or warrants the development not proceeding.

53.02-5
20/03/2023
VC229

Tables : Defendable space, construction, water supply, vehicle access, vegetation management and outbuilding construction requirements

Table 1 Defendable space and construction

Slope	Vegetation Type	Defendable space distance from building facade (metres)				
		Column A	Column B	Column C	Column D	Column E
All upslopes and flat land (0 degrees)	Forest	48	35	25	19	< 19
	Woodland	33	24	16	12	< 12
	Scrub	27	19	13	10	< 10
	Shrubland	19	13	9	7	< 7
	Mallee/ Mulga	17	12	8	6	< 6
	Rainforest	23	16	11	8	< 8
	Grassland	19	13	9	6	< 6
Downslope >0 to 5 degrees	Forest	57	43	32	24	< 24
	Woodland	41	29	21	15	< 15
	Scrub	31	22	15	11	< 11
	Shrubland	22	15	10	7	< 7
	Mallee/ Mulga	20	13	9	7	< 7
	Rainforest	29	20	14	10	< 10
	Grassland	22	15	10	7	< 7
Downslope >5 to 10 degrees	Forest	69	53	39	31	< 31
	Woodland	50	37	26	20	< 20
	Scrub	35	24	17	12	< 12
	Shrubland	25	17	11	8	< 8
	Mallee/ Mulga	23	15	10	7	< 7
	Rainforest	36	26	18	13	< 13
	Grassland	25	17	11	8	< 8
Downslope >10 to 15 degrees	Forest	82	64	49	39	< 39
	Woodland	60	45	33	25	< 25
	Scrub	39	28	19	14	< 14
	Shrubland	28	19	13	9	< 9

Slope	Vegetation Type	Defendable space distance from building facade (metres)				
		Column A	Column B	Column C	Column D	Column E
	Mallee/ Mulga	26	18	11	8	< 8
	Rainforest	45	33	23	17	< 17
	Grassland	28	20	13	9	< 9
Downslope >15 to 20 degrees	Forest	98	78	61	50	< 50
	Woodland	73	56	41	32	< 32
	Scrub	43	31	21	15	< 15
	Shrubland	31	22	15	10	< 10
	Mallee/ Mulga	29	20	13	9	< 9
	Rainforest	56	42	29	22	< 22
	Grassland	32	23	15	11	< 11

		BAL 12.5	BAL19	BAL29	BAL40	BALFZ
Downslope >20 degrees	All vegetation	Defendable space and the bushfire attack level is determined using Method 2 of AS3959:2018 Construction of buildings in bushfire prone areas (Standards Australia) subject to any guidance published by the relevant fire authority.				
All slopes	Low threat vegetation	Defendable space is to be provided for a distance of 50 metres, or the property boundary whichever is the lesser, for buildings constructed to all bushfire attack levels. The minimum construction standard is BAL 12.5.				
All slopes	Modified vegetation	Defendable space is to be provided for a distance of 50 metres, or the property boundary whichever is the lesser, for buildings constructed to all bushfire attack levels. The minimum construction standard is BAL 29.				

Note 1: Slope and vegetation type is determined through the bushfire hazard site assessment.

Note 2: Modified vegetation is vegetation that doesn't fit into the vegetation classifications in AS3959:2018 Construction of buildings in bushfire prone areas (the standard) because it:
- has been modified, altered or is managed due to urban development, or gardening,
- has different fuel loads from those assumed in the standard,
- has limited or no understorey vegetation, or
- is not low-threat or low-risk vegetation as defined in the standard.

Table 2 Defendable space and construction

Slope	Vegetation	Defendable space distance from building facade (metres)			
		Column A	Column B	Column C	Column D
All upslopes and flat land (0 degrees)	Forest	48	35	25	19
	Woodland	33	24	16	12

Slope	Vegetation	Defendable space distance from building facade (metres)			
		Column A	Column B	Column C	Column D
	Scrub	27	19	13	10
	Shrubland	19	13	9	7
	Mallee/ Mulga	17	12	8	6
	Rainforest	23	16	11	8
	Grassland	19	13	9	6
Downslope >0 to 5 degrees	Forest	57	43	32	24
	Woodland	41	29	21	15
	Scrub	31	22	15	11
	Shrubland	22	15	10	7
	Mallee/ Mulga	20	13	9	7
	Rainforest	29	20	14	10
	Grassland	22	15	10	7
Downslope >5 to 10 degrees	Forest	69	53	39	31
	Woodland	50	37	26	20
	Scrub	35	24	17	12
	Shrubland	25	17	11	8
	Mallee/ Mulga	23	15	10	7
	Rainforest	36	26	18	13
	Grassland	25	17	11	8
Downslope >10 to 15 degrees	Forest	82	64	49	39
	Woodland	60	45	33	25
	Scrub	39	28	19	14
	Shrubland	28	19	13	9
	Mallee/ Mulga	26	18	11	8
	Rainforest	45	33	23	17
	Grassland	28	20	13	9
Downslope >15 to 20 degrees	Forest	98	78	61	50
	Woodland	73	56	41	32

Slope	Vegetation	Defendable space distance from building facade (metres)			
		Column A	Column B	Column C	Column D
	Scrub	43	31	21	15
	Shrubland	31	22	15	10
	Mallee/ Mulga	29	20	13	9
	Rainforest	56	42	29	22
	Grassland	32	23	15	11
		BAL12.5	BAL19	BAL29	BAL40
Downslope >20 degrees	All vegetation	Defendable space and the bushfire attack level is determined using Method 2 of AS3959:2018 Construction of buildings in bushfire prones areas (Standards Australia) subject to any guidance published by the relevant fire authority.			
All slopes	Low threat vegetation	Defendable space is to be provided for a distance of 50 metres, or the property boundary whichever is the lesser, for buildings constructed to all bushfire attack levels. The minimum construction standard is BAL 12.5.			
All slopes	Modified vegetation	Defendable space is to be provided for a distance of 50 metres, or the property boundary whichever is the lesser, for buildings constructed to all bushfire attack levels. The minimum construction standard is BAL 29.			

Note 1: Slope and vegetation type is determined through the bushfire hazard site assessment.

Note 2: Modified vegetation is vegetation that doesn't fit into the vegetation classifications in AS3959:2018 Construction of buildings in bushfire prone areas (the standard) because it:
- has been modified, altered or is managed due to urban development, or gardening,
- has different fuel loads from those assumed in the standard,
- has limited or no understorey vegetation, or
- is not low-threat or low-risk vegetation as defined in the standard.

Table 3 Defendable space

Vegetation class	Defendable space distance from building facade (metres)				
	Upslope and flat land (0 degrees)	Downslope (degrees)			
		>0-5	>5-10	>10-15	>15-20
Forest	60	70	85	105	125
Woodland	40	50	62	75	95
Shrubland	25	28	32	36	41
Scrub	35	40	45	50	55
Mallee/Mulga	23	26	30	35	40
Rainforest	30	36	46	60	70

Vegetation class	Defendable space distance from building facade (metres)				
	Upslope and flat land (0 degrees)	Downslope (degrees)			
		>0-5	>5-10	>10-15	>15-20
Grassland	35	40	45	50	55

Table 4 Water supply requirements

Capacity, fittings and access

Lot sizes (square meters)	Hydrant available	Capacity (litres)	Fire authority fittings and access required
Less than 500	Not applicable	2,500	No
500-1,000	Yes	5,000	No
500-1,000	No	10,000	Yes
1,001 and above	Not applicable	10,000	Yes

Note 1: A hydrant is available if it is located within 120 metres of the rear of the building

Fire authority requirements

Unless otherwise agreed in writing by the relevant fire authority, the water supply must:

- Be stored in an above ground water tank constructed of concrete or metal.
- Have all fixed above ground water pipes and fittings required for firefighting purposes made of corrosive resistant metal.
- Include a separate outlet for occupant use.

Where a 10,000 litre water supply is required, fire authority fittings and access must be provided as follows:

- Be readily identifiable from the building or appropriate identification signs to the satisfaction of the relevant fire authority.
- Be located within 60 metres of the outer edge of the approved building.
- The outlet/s of the water tank must be within 4 metres of the accessway and unobstructed.
- Incorporate a separate ball or gate valve (British Standard Pipe (BSP 65 millimetre) and coupling (64 millimetre CFA 3 thread per inch male fitting).
- Any pipework and fittings must be a minimum of 65 millimetres (excluding the CFA coupling).

Table 5 Vehicle access design and construction

Vehicle access (or part thereof) of a length specified in Column A implements the design and construction requirements specified in Column B.

Column A	Column B
Length of access is less than 30 metres	There are no design and construction requirements if fire authority access to the water supply is not required under **AM4.1**.

Column A	Column B
Length of access is less than 30 metres	Where fire authority access to the water supply is required under **AM4.1** fire authority vehicles should be able to get within 4 metres of the water supply outlet.
Length of access is greater than 30 metres	The following design and construction requirements apply: ▪ All-weather construction. ▪ A load limit of at least 15 tonnes. ▪ Provide a minimum trafficable width of 3.5 metres. ▪ Be clear of encroachments for at least 0.5 metres on each side and at least 4 metres vertically. ▪ Curves must have a minimum inner radius of 10 metres. ▪ The average grade must be no more than 1 in 7 (14.4%) (8.1°) with a maximum grade of no more than 1 in 5 (20%) (11.3°) for no more than 50 metres. ▪ Dips must have no more than a 1 in 8 (12.5 per cent) (7.1 degrees) entry and exit angle.
Length of access is greater than 100 metres	A turning area for fire fighting vehicles must be provided close to the building by one of the following: ▪ A turning circle with a minimum radius of eight metres. ▪ A driveway encircling the dwelling. ▪ The provision of other vehicle turning heads – such as a T or Y head – which meet the specification of Austroad Design for an 8.8 metre Service Vehicle.
Length of access is greater than 200 metres	▪ Passing bays must be provided at least every 200 metres. ▪ Passing bays must be a minimum of 20 metres long with a minimum trafficable width of 6 metres.

Note 1: The length of access should be measured from a public road to either the building or the water supply outlet, whichever is longer.

Table 6 Vegetation management requirement

Vegetation management requirement
Defendable space is provided and is managed in accordance with the following requirements: ▪ Grass must be short cropped and maintained during the declared fire danger period. ▪ All leaves and vegetation debris must be removed at regular intervals during the declared fire danger period. ▪ Within 10 metres of a building, flammable objects must not be located close to the vulnerable parts of the building. ▪ Plants greater than 10 centimetres in height must not be placed within 3 metres of a window or glass feature of the building. ▪ Shrubs must not be located under the canopy of trees. ▪ Individual and clumps of shrubs must not exceed 5 square metres in area and must be separated by at least 5 metres.

Vegetation management requirement
▪ Trees must not overhang or touch any elements of the building. ▪ The canopy of trees must be separated by at least 5 metres. ▪ There must be a clearance of at least 2 metres between the lowest tree branches and ground level. Unless specified in a schedule or otherwise agreed in writing to the satisfaction of the relevant fire authority.

Table 7 Outbuilding construction requirement

Building construction condition
The proposed outbuilding is separated from the adjacent building by a wall that extends to the underside of a non-combustible roof covering and: ▪ has a FRL of not less than 60/60/60 for loadbearing walls and -/60/60 for non-load bearing walls when tested from the attached structure side, or ▪ is of masonry, earth wall or masonry-veneer construction with the masonry leaf of not less than 90 millimetres in thickness. Any openings in the wall shall be protected in accordance with the following: i. Doorways – by FLR -/60/30 self-closing fire doors ii. Windows – by FRL -/60/- fire windows permanently fixed in the closed position iii. Other openings – by construction with a FRL of not less than -/60/- *Note: Control and construction joints, subfloor vents, weepholes and penetrations for pipes and conduits need not comply with Item iii.*

Note 1: These conditions are required for some non habitable outbuildings ancillary to a dwelling that do not require referral to the relevant fire authority. Applications for non habitable outbuildings can also use the bushfire protection measures in Clause 53.02 however referral to the relevant fire authority will be required.

53.03 RESIDENTIAL RETICULATED GAS SERVICE CONNECTION

01/01/2024
VC250

Purpose

To prohibit residential reticulated gas connections to new dwellings, new apartment developments and new residential subdivisions.

53.03-1 Application

01/01/2024
VC250

This clause applies to an application for a permit under any provision of this scheme that is for or includes:

- construction of a new dwelling (other than a caretaker's house) or a new apartment development.
- the subdivision of land where the subdivision provides for or is for one or more purposes that include residential development.

This clause does not apply to an application for a permit that is solely for:

- the alteration or extension of an existing dwelling or apartment development.
- the subdivision of land or a building to create lots each containing an existing dwelling or apartment.
- the subdivision of land or a building to create lots each of which are intended to contain a dwelling or an apartment authorised by a planning permit that has been issued for the land.

53.03-2 Building and works requirement

01/01/2024
VC250

A permit must not be granted for construction of a new dwelling or a new apartment development that is to be connected to a reticulated gas service.

A permit granted for buildings and works in relation to an application to which this clause applies must include the following mandatory condition(s) as relevant:

For a dwelling:

"Any new dwelling allowed by this permit must not be connected to a reticulated gas service (within the meaning of clause 53.03 of the relevant planning scheme). This condition continues to have force and effect after the development authorised by this permit has been completed."

For an apartment development:

"Any new apartment development allowed by this permit must not be connected to a reticulated gas service (within the meaning of clause 53.03 of the relevant planning scheme). This condition continues to have force and effect after the development authorised by this permit has been completed."

53.03-3 Subdivision requirement

01/01/2024
VC250

A permit must not be granted for a subdivision that includes a lot that is to be connected to a reticulated gas service. This does not apply to:

- a lot that will not be used for, or include, a dwelling; or
- a lot that contains an existing dwelling or apartment; or
- a lot where a permit has been granted for a dwelling or apartment on the land in the lot.

A permit granted for subdivision in relation to an application to which this clause applies must include the following mandatory condition:

"Any lot shown on the endorsed plan must not be connected to a reticulated gas service (within the meaning of clause 53.03 of the relevant planning scheme). This does not apply to:

- *a lot that will not be used for, or include, a dwelling; or*

- *a lot that contains an existing dwelling or apartment; or*
- *a lot where a permit has been granted for a dwelling or apartment on the land in the lot.*

This condition continues to have force and effect after a statement of compliance under the Subdivision Act 1988 has been issued and the subdivision authorised by this permit has been completed."

53.03-4 Application requirements

01/01/2024
VC250

An application for a permit to which this clause applies must, in addition to those application requirements specified elsewhere in the scheme, be accompanied by details of the proposed energy provision other than a connection to a reticulated gas service, as appropriate, to the satisfaction of the responsible authority.

53.03-5 Transitional provisions

01/01/2024
VC250

The requirements of this clause introduced by Amendment VC250 do not apply to:

- An application lodged before the approval date of Amendment VC250.
- An application for an amendment to a permit under section 72 of the Act with respect to a permit issued in accordance with the above transitional provision.

53.03-6 Definitions

01/01/2024
VC250

In this clause:

Connected to a reticulated gas service means:

- In the case of a building, reticulated natural gas is directly supplied to the building. This does not include liquefied petroleum gas (LPG).
- In the case of a subdivision for residential purposes, reticulated natural gas is directly supplied to a lot. This does not include liquefied petroleum gas (LPG).

New dwelling means:

- A new building, buildings, or part of a building, constructed to be used as a dwelling (other than a caretaker's house) not including the alteration or extension of an existing dwelling.
- A new building, buildings, or part of a building, connected to an existing dwelling and constructed to be used as a separate dwelling (other than a caretaker's house), provided the use does not incorporate any part of what was the gross floor area (excluding external or party walls) of the existing dwelling.
- A new outbuilding or swimming pool associated with an existing or proposed dwelling, provided it is not within the gross floor area (excluding external or party walls) of an existing dwelling.

It does not include a new apartment development.

New apartment development means a new building, buildings, or part of a building, constructed to contain one or more apartments, whether or not any other use is provided for, but does not include the extension or alteration of, or the addition of new apartments to, an existing apartment development.

53.04 CONVENIENCE RESTAURANT AND TAKE-AWAY FOOD PREMISES

31/07/2018
VC148

53.04-1 Application

31/07/2018
VC148

These requirements only apply to land in a residential zone.

53.04-2 Decision guidelines

20/01/2022
VC205

Before deciding on an application to use land for a convenience restaurant or take-away food premises or to construct a building or construct or carry out works associated with a convenience restaurant or take-away food premises, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- Any policy in this scheme relating to convenience restaurants or take-away food premises.
- Whether the location is appropriate for a convenience restaurant or take-away food premises having regard to:
  - Amenity of the neighbourhood.
  - Proximity of the land to non-residential uses and zones.
  - Effect of the use on heritage and environment features.
  - Capacity of the land to contain significant off-site effects.
  - Access to land in a Transport Zone 2 or Transport Zone 3.
  - The suitability of the land for a residential use.
- The effect on the amenity or character of the street or neighbourhood having regard to:
  - Massing and proportions of any building.
  - Ground floor height above ground level.
  - Ceiling heights.
  - Roof form and pitch.
  - Facade articulation.
  - Window and door proportions.
  - Building features including verandas, towers, eaves, parapets and decorative elements.
  - Building materials, patterns textures and colours.
- Whether the site layout and the design of buildings, noise attenuation measures, landscaping, car parking, vehicle access lanes, loading bays, rubbish bins, plant and equipment, lights, signs, drive through facilities and playgrounds are designed to prevent significant loss of amenity to adjoining land due to noise, emission of noise, emission of light or glare, loss of privacy, litter or odour.
- Whether any special measure may be necessary to protect the amenity of adjoining land in residential use, including buffer planting, noise attenuation measures and litter collection arrangements.
- The adequacy of traffic measures to:
  - Provide safe pedestrian movement.
  - Achieve safe, efficient vehicle movement on site and access to and egress from the land.

  - Avoid disruption to traffic flow on land in a Transport Zone 2 or Transport Zone 3.
  - Prevent inappropriate use of local residential streets.
- The adequacy of car parking, loading and drive through queuing spacing to accommodate customers at peak periods and employee requirements on the land.

53.05 FREEWAY SERVICE CENTRE

14/05/2021
VC198

Purpose

To ensure that freeway service centres are appropriately designed and located.

To ensure that access to a freeway service centre from a freeway is designed to the requirements of the Head, Transport for Victoria.

To ensure that freeway service centres with access to a rural freeway provide only essential services and facilities which encourage drivers to stop and take an effective break at appropriate intervals in the interests of driver safety.

To ensure that any new freeway service centre meets an identifiable need to provide essential services and facilities along a freeway where those services and facilities are not readily available.

To ensure that the use of land for a freeway service centre does not adversely affect the amenity of surrounding land uses.

53.05-1 Requirements to be met

14/08/2023
VC236

Facilities and services

A freeway service centre must provide only essential services and facilities. These essential services and facilities must be available at all times. Essential services and facilities that a freeway service centre must include are:

- Designated parking areas.
- Undercover fuel sales area.
- An area of not more than 240 square metres for the sale of food, drinks and other convenience goods.
- An indoor sit-down eating area.
- A safe play area for children.
- Public toilets.
- A public telephone.

A freeway service centre with access to a rural freeway must also provide local and regional tourist information.

A freeway service centre must not include:

- Mechanical repairs (other than the emergency repair of vehicles).
- Retail facilities of more than 240 square metres.
- Video hire.
- Post office services or facilities.
- Entertainment facilities, amusement machines or gaming machines.
- The sale, distribution or consumption of alcohol unless associated with a residential hotel/motel.
- Car or truck wash facilities.

A freeway service centre with access to a rural freeway must not include overnight accommodation (other than for a caretaker or site manager).

Access to freeway service centres

No vehicular access between a freeway service centre with access to a metropolitan freeway and the local road network may be permitted.

An application to use or develop land for a freeway service centre must be referred under section 55 of the Act to the person or body specified as the referral authority in Clause 66.02.

A permit must not be granted for a freeway service centre until approval for access to the freeway has been given by the person or body specified as the referral authority in Clause 66.02.

In accordance with section 62(1)(a) of the Act, a permit granted for a freeway service centre must include the condition:

"This permit will expire if one of the following circumstances applies:

- The development is not commenced within two years of the date of this permit.
- The development is not completed within four years of the date of this permit.

The responsible authority may extend the periods referred to if a request is made in writing before the permit expires or within three months afterwards."

Metropolitan freeway service centre adjoining a residential zone

If the site for a freeway service centre with access to a metropolitan freeway adjoins a residential zone:

- A landscape buffer at least 3 metres wide must be provided on the site along the common boundary and must be planted and maintained to the satisfaction of the responsible authority.
- Except for the landscape buffer strip, all of the site not occupied by buildings must be sealed to prevent dust.
- External lights must be directed away from the residential zone to prevent light spill and glare.

53.05-2 Decision guidelines

31/07/2018
VC148

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The Freeway Service Centres Design Guidelines, May 1997.

53.06 LIVE MUSIC ENTERTAINMENT VENUES

28/09/2020
VC183

Purpose

To recognise that live music is an important part of the State's culture and economy.

To encourage the retention of existing and the development of new live music entertainment venues.

To protect live music entertainment venues from the encroachment of noise sensitive residential uses.

To ensure that noise sensitive residential uses are satisfactorily protected from unreasonable levels of live music and entertainment noise.

To ensure that the primary responsibility for noise attenuation rests with the agent of change.

53.06-1 Application

28/09/2020
VC183

This clause applies to an application required under any zone of this scheme to use land for, or to construct a building or construct or carry out works associated with:

- A live music entertainment venue.
- A noise sensitive residential use that is within 50 metres of a live music entertainment venue.
- A noise sensitive residential use that is in an area specified in clause 1.0 of the schedule to this clause

This clause does not apply to:

- The extension of an existing dwelling.
- A noise sensitive residential use that is in an area specified in clause 2.0 of the schedule to this clause.

53.06-2 Meaning of terms

14/12/2023
VC253

In this clause:

- ***live music entertainment venue*** means:
  - a food and drink premises, nightclub, function centre or residential hotel that includes live music entertainment
  - a rehearsal studio
  - any other venue used for the performance of music and specified in clause 3.0 of the schedule to this clause, subject to any specified condition or limitation.
- ***noise sensitive residential use*** means a community care accommodation, dwelling, residential aged care facility, residential village, retirement village, rooming house or small second dwelling.

53.06-3 Requirements to be met

04/05/2022
VC210

A live music entertainment venue must be designed, constructed and managed to minimise noise emissions from the premises and provide acoustic attenuation measures that would protect a noise sensitive residential use within 50 metres of the venue.

A noise sensitive residential use must be designed and constructed to include acoustic attenuation measures that will reduce noise levels from any:

- Indoor live music entertainment venue to below the noise limits specified in the Environment Protection Regulations under the *Environment Protection Act 2017* and the incorporated Noise Protocol (Publication 1826, Environment Protection Authority, November 2020)
- Outdoor live music entertainment venue to below 45dB(A), assessed as an L_{eq} over 15 minutes.

For the purpose of assessing whether the above noise standards are met, the noise measurement point may be located inside a habitable room of a noise sensitive residential use with windows and doors closed (consistent with EPA Publication 1826).

A permit may be granted to reduce or waive these requirements if the responsible authority is satisfied that an alternative measure meets the purpose of this clause.

53.06-4 Application requirements

28/09/2020
VC183

An application must be accompanied by the following information, as appropriate:

- A site analysis, including plans detailing:
  - the existing and proposed layout of the use, buildings or works, including all external windows and doors
  - the location of any doors, windows and open space areas of existing properties in close proximity to the site.
- If the application is associated with a noise sensitive residential use:
  - the location of any live music entertainment venues within 50 metres of the site
  - the days and hours of operation of identified venues.
- If the application is associated with a live music entertainment venue:
  - the location of any noise sensitive residential uses within 50 metres of the site
  - the days and hours of operation of that venue
  - the times during which live music will be performed.
- Details of existing and proposed acoustic attenuation measures.
- An assessment of the impact of the proposal on the functioning of live music venues.

If in the opinion of the responsible authority an application requirement is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

53.06-5 Decision guidelines

28/09/2020
VC183

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The extent to which the siting, layout, design and construction minimise the potential for noise impacts.
- Whether existing or proposed noise sensitive residential uses will be satisfactorily protected from unreasonable live music and entertainment noise.
- Whether the proposal adversely affects any existing uses.
- The social and economic significance of an existing live music entertainment venue.
- The impact of the proposal on the functioning of live music venues.

18/02/2021
GC175

SCHEDULE TO CLAUSE 53.06 LIVE MUSIC ENTERTAINMENT VENUES

1.0 Areas to which Clause 53.06 does apply

04/05/2022
VC210

Name of area	Description
None specified	

2.0 Areas to which Clause 53.06 does not apply

04/05/2022
VC210

Name of area	Description
None specified	

3.0 Other venues to which Clause 53.06 applies

04/05/2022
VC210

Name of venue	Address	Condition or limitation
None specified		

53.07 SHIPPING CONTAINER STORAGE

31/07/2018
VC148

Application

This clause applies to all land except land which is in a Special Use Zone established for the purpose of port and port-related activities, or is in a Port Zone.

53.07-1 Decision guidelines

20/01/2022
VC205

Before deciding on an application to use land for shipping container storage, or construct a building or construct or carry out works associated with shipping container storage, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- Whether the location is appropriate for shipping container storage having regard to:
  - The zoning of the land.
  - Amenity of the neighbourhood.
  - Proximity of the land to residential uses and zones or other sensitive uses.
  - Access to a road in a Transport Zone 2 or a Transport Zone 3.
  - Access to rail facilities.
  - Capacity and suitability of the road network to accommodate the type and volume of vehicle traffic generated by the use.
  - Capacity of the site to accommodate the proposed use.
- The effect on the environment and the amenity and character of the neighbourhood having regard to:
  - Existing and planned use of land in the neighbourhood.
  - Location, height and setback of shipping container stacks, particularly near road boundaries.
  - Location of facilities for the cleaning, repair, servicing, painting or fumigation of shipping containers.
  - Hours of operation.
  - Design, construction and maintenance of external storage and vehicle movement areas.
  - Treatment and disposal of wastewater.
- Whether the site layout and the design of buildings, landscaping, vehicle access lanes, loading bays, wash bays, lighting and fencing are designed to avoid or minimise any significant off-site impacts due to the emission of noise, light, glare, dust, fumes or drainage.
- Whether any special measure may be necessary to protect the environment and the amenity of nearby sensitive uses, including noise attenuation measures, dust minimisation measures and waste storage arrangements.
- The need for landscaping and fencing to screen or soften the appearance of shipping container storage areas, particularly near road boundaries.
- The adequacy and effect of the landscaping on the appearance of the site, taking into account the streetscape character, the size of the site, and the height, mass and scale of shipping container stacks on the site.
- The adequacy of traffic measures to:

  - Achieve safe, efficient vehicle movement on site and access to and egress from the land.
  - Prevent inappropriate use of local residential streets.
- The adequacy of truck parking, loading and truck queuing spacing to accommodate truck movements at peak periods and employee requirements on the land.

53.08 CATTLE FEEDLOT

31/07/2018
VC148

Purpose

To facilitate the establishment and expansion of cattle feedlots in Victoria in a manner which is consistent with orderly and proper planning and the protection of the environment.

53.08-1 Requirements to be met

31/07/2018
VC148

All use and development of cattle feedlots must comply with the Victorian Code for Cattle Feedlots - August 1995.

The Code must be complied with to the satisfaction of the responsible authority.

53.09 POULTRY FARM

11/04/2019
VC156

Purpose

To facilitate the establishment and expansion of poultry farms, including broiler farms, in a manner that is consistent with orderly and proper planning and the protection of the environment.

53.09-1 Application

21/09/2018
VC150

This clause applies to permit applications to use land or construct a building or construct or carry out works for a poultry farm, including to increase the farm capacity of an existing poultry farm.

53.09-2 Permit not required – Outdoor range area for existing broiler farm

21/09/2018
VC150

Any requirement of this scheme relating to the use of land or to the construction of a building or the construction or carrying out of works does not apply to the use and development of land for an outdoor range area in association with an existing broiler farm provided the following requirements are met:

- There are no more than 150,000 chickens permitted on the land at any time.
- The number of chickens on the land is not increased.

This exemption does not apply to the requirements of any overlay that applies to the land.

53.09-3 Requirement – Broiler farm

21/09/2018
VC150

An application to use land or construct a building or construct or carry out works for a broiler farm must comply with the *Victorian Code for Broiler Farms 2009 (plus 2018 amendments)*.

This requirement does not apply if:

- There are no more than 10,000 chickens permitted on the land at any time; or
- The number of chickens on the land is not increased.

53.09-4 Exemption from notice and review

11/04/2019
VC156

The following applications are exempt from the notice requirements of section 52 (1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act:

- An application to use land or construct a building or construct or carry out works for a new broiler farm, or to increase the farm capacity of an existing broiler farm, if the application meets the requirements of a "Class A Broiler Farm", as specified in the *Victorian Code for Broiler Farms 2009 (plus 2018 amendments)*.
- An application to use land or construct a building or construct or carry out works for a poultry farm for the production of chicken meat or chicken eggs, if the application meets the following requirements:
  - The number of chickens does not exceed 5,000 for egg production or 10,000 for meat production.
  - The outdoor stocking density does not exceed 1,500 chickens per hectare.
  - A Nutrient Management Plan demonstrates chickens are kept outdoors on paddocks with:
    - A minimum of 50% ground cover; and
    - Mobile housing and feeding infrastructure that is relocated at least every two weeks.
  - An area used as a poultry range, including associated buildings and works, meets the setback requirements specified in Table 1.

Table 1 Minimum setbacks

Chicken numbers	Minimum distance to a building used for a sensitive use (accommodation, child care centre, education centre and hospital)	Minimum distance to land in a residential zone
1,000 chickens or less	50 metres	200 metres
More than 1,000 chickens	100 metres	400 metres

53.09-5 Notice of an application

21/09/2018
VC150

Notice of an application to use or develop land to establish a new broiler farm, or to increase the farm capacity of an existing broiler farm, that meets the requirements of a Special Class Broiler Farm or Farm Cluster as specified in the *Victorian Code for Broiler Farms 2009 (plus 2018 amendments)*, must be given under Section 52(1)(c) of the Act to the person or body specified as a person or body to be notified in Clause 66.05.

53.09-6 Decision guidelines

21/09/2018
VC150

Before deciding on an application to use land or construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The purpose of the relevant zone.
- The design, height, setback and appearance of the proposed buildings and works.
- The proposed landscaping.
- The need to protect amenity of existing uses on adjoining land.
- The impact of the use of the land on the surrounding area, including from the emission of noise, light, vibration, odour, dust, or waste products.
- The impact of the proposal on any wetlands, waterways or water bodies.
- The likely environmental impact on the natural physical features and biodiversity of the land, including consideration of any Nutrient Management Plan submitted with the application.
- Whether the development will support and enhance agricultural production.
- The requirements of the *Victorian Low Density Mobile Outdoor Poultry Farm Planning Permit Guidelines* (June 2018).

53.10 USES AND ACTIVITIES WITH POTENTIAL ADVERSE IMPACTS

26/05/2020
VC175

Purpose

To identify those types of uses and activities, which if not appropriately designed and located, may cause offence or unacceptable risk to the neighbourhood.

53.10-1 Threshold distance

26/09/2023
VC246

The threshold distance referred to in the table to this clause is the shortest distance from any part of the land to:

- land (not a road) in an Activity Centre Zone, Capital City Zone, Commercial 1 Zone, Docklands Zone, residential zone or Rural Living Zone; or
- land used for a hospital, an education centre or a corrective institution; or
- land in a Public Acquisition Overlay to be acquired for a hospital, an education centre or a corrective institution.

An application to use land for an industry, utility installation or warehouse for a purpose listed in the table to this clause must be referred to the Environment Protection Authority under section 55 of the Act if the threshold distance is not to be met or no threshold distance is specified.

Table to Clause 53.10-1

Type of use or activity (purpose)	Threshold distance (metres)
Basic metal products	
Iron or steel production:	
▪ up to 1,000,000 tonnes per year	500
▪ exceeding 1,000,000 tonnes per year	1,000
Non-ferrous metal production:	
▪ up to 100 tonnes per year	100
▪ between 100 and 2,000 tonnes per year	300
▪ exceeding 2,000 tonnes per year	500
▪ aluminium by electrolysis	2,000
Chemical, petroleum and coal products	
Ammunition, explosives and fireworks production	1,000
Biocides production and storage	1,000
Briquette production	300
Chemical product manufacture other than listed within this group	300
Coke processing	500
Cosmetics and toiletries production	100

Type of use or activity (purpose)	Threshold distance (metres)
Fertiliser production	1,000
Gasworks	1,000
Industrial gases production	1,000
Organic and inorganic industrial chemicals production other than those listed within this group	2,000
Other petroleum or coal production	500
Paints and inks manufacture, blending and mixing exceeding 2,000 tonnes per year	500
Petroleum refinery	2,000
Pharmaceutical and veterinary chemical production	1,000
Polyester and synthetic resins production, exceeding 2,000 tonnes per year	1,000
Rubber production:	
▪ synthetic rubber, exceeding 2,000 tonnes per year	1,000
▪ using either organic solvents or carbon black	300
▪ using sulphur	1,000
Soap and detergent production	500
Fabricated metal products	
Abrasive blast cleaning	500
Boiler maker	100
Metal coating and finishing	500
Structural or sheet metal production	500
Food and beverages	
Alcoholic and non-alcoholic beverage production, exceeding 5,000 litres per day	500
Animal processing	1,000
Bakery (other than one ancillary to a shop):	
▪ exceeding 200 tonnes per year	100
▪ night-time operations, exceeding 200 tonnes per year	500
Flour mill, exceeding 200 tonnes per year	250
Food production other than those listed within this group:	
▪ exceeding 200 tonnes per year	250

Type of use or activity (purpose)	Threshold distance (metres)
▪ including frying, drying or roasting, exceeding 200 tonnes per year	500
Grain and stockfeed mill and handling facility	
▪ with meat meals or tallow	500
▪ no meat meals or tallow	250
Maltworks, exceeding 200 tonnes per year	500
Manufacture of milk products, exceeding 200 tonnes per year	300
Milk depot	100
Pet food production	500
Production of vegetable oils and animal fats using solvents, exceeding 200 tonnes per year	500
Seafood processor, exceeding 200 tonnes per year	500
Smallgoods production:	
▪ exceeding 200 tonnes per year	100
▪ including smoking and drying, exceeding 200 tonnes per year	500
Miscellaneous manufacturing	
Printing and coating works with heated curing ovens	500
Rendering and casings works	1,000
Non-metallic mineral products	
Bitumen batching plant	1,000
Cement production in amounts:	
▪ up to 5,000 tonnes per year	300
▪ between 5,000 and 150,000 tonnes per year	500
▪ exceeding 150,000 tonnes per year	1,000
Cement, lime, clay bricks, tiles and pipe refractories, with a design production rate exceeding 10,000 tonnes per year:	500
Concrete batching plant, with a production rate exceeding 5,000 tonnes per year	300
Glass and glass production including glass wool and fibreglass	500
Plaster or plaster articles production, exceeding 5,000 tonnes per year	200
Rock wool manufacture	500

Type of use or activity (purpose)	Threshold distance (metres)
Solar salt manufacture	1,000
Other premises	
Automotive body, paint and interior repair	100
Rural industry handling, processing or packing agricultural produce	300
Paper and paper products	
Paper or paper pulp production:	
▪ involving combustion of sulphur or sulphur containing materials	5,000
▪ from semi-processed materials	100
▪ from prepared cellulose and rags	200
▪ by other methods than above	None specified
Recreational, personal and other services	
Dry cleaning for commercial and institutional customers, or in bulk quantities	100
Laundry for commercial and institutional customers, or in bulk quantities	100
Textiles	
Carpet backing with latex	500
Dyeing or finishing of cotton, linen and woollen yarns and textiles	300
Leather and artificial leather goods production	300
Leather tanning and dressing:	
▪ up to 250 tonnes per year	300
▪ exceeding 250 tonnes per year	2,000
Rope, cordage and twine production	100
Treatment or production of natural and synthetic fibres and textiles	1,000
Treatment or production of textiles using carbon disulphide	500
Wool scouring	200
Transport and storage	
Bus depot	200
Depot for refuse collection vehicles	100
Storage of bulk volatile organic compounds in quantities greater than 1,000 tonnes	1,000

Type of use or activity (purpose)	Threshold distance (metres)
Storage of petroleum products and crude oil in tanks exceeding 2,000 tonnes capacity:	
▪ with fixed roofs	300
▪ with floating roofs	100
Storage of wet-salted or unprocessed hides	250
Waste, recycling and resource recovery	
Chemical or oil recycling	1,000
Combustion, treatment or bio-reaction of waste to produce energy	None specified
Composting and other organic materials recycling	None specified
Container deposit scheme centre exceeding 1,000 square metres gross floor area	200
Hazardous waste storage or treatment	1,000
Landfill	None specified
Other recourse recovery or recycling operations	None specified
Soil conditioning or blending	None specified
Transfer station (other than Automated collection point and Container deposit scheme centre):	
▪ accepting organic wastes	500
▪ other	200
Used plastics treatment or processing	500
Waste tyre recycling and re-treading	1,000
Vehicle recycling or disposal	500
Water and wastewater	
Sewage treatment plant, exceeding a design or actual flow rate of 5,000 litres per day	None specified
Water treatment plant	None specified
Wood, wood products and furniture	
Charcoal production:	
▪ by the retort process	500
▪ other than by the retort process	1,000
Joinery	100

Type of use or activity (purpose)	Threshold distance (metres)
Sawmill, wood products and furniture	500
Wood preservation plant:	
up to 10,000 cubic metres of timber per year	100
exceeding 10,000 cubic metres of timber per year	300

53.11 TIMBER PRODUCTION

31/07/2018
VC148

53.11-1 Timber production on Crown land

31/07/2018
VC148

Any requirement of this scheme which:

- requires timber production to be conducted in a particular way
- requires that a permit be obtained to use or develop land for timber production or to carry out timber production in a particular way
- requires that some aspect of timber production be carried out to the satisfaction of the responsible authority

does not apply to timber production on unalienated land of the Crown managed and controlled by the Minister responsible for administering the *Forests Act 1958* and the *Sustainable Forests (Timber) Act 2004*, or the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forest and Lands Act 1987*), whether or not occupied under a licence or other right. All requirements of this scheme apply to Crown land which has been leased.

53.11-2 Timber production to comply with the Code of Practice for Timber Production

20/03/2023
VC229

All timber production activities (except agroforestry (the simultaneous and substantial production of forest and other agricultural products from the same land unit), windbreaks and commercial plantations of 5 hectares or less) must comply with the *Code of Practice for Timber Production 2014 (as amended 2022)* (Department of Environment, Land, Water and Planning, 2022). In accordance with Section 6(4A) of the *Planning and Environment Act 1987*, this applies whether the use of land for timber production is commenced before or after the coming into effect of this requirement.

The Code must be complied with to the satisfaction of the responsible authority.

A permit may require that matters required by the Code must be done to the satisfaction of the responsible authority or a Minister, public authority or referral authority, and may require the responsible authority to seek comments from any other person or authority before making a decision.

53.11-3 Road repairs

31/07/2018
VC148

After a Timber Harvesting Plan is lodged with the responsible authority under the Code and before the commencement of harvesting operations, the responsible authority, in consultation with the forest owner or manager, must establish the condition of any roads which are proposed to be used as a cartage route.

The forest owner or manager must advise the responsible authority when harvesting operations are complete. After receiving this advice, the responsible authority, in consultation with the forest owner or manager, must establish the condition of any roads which were used as a cartage route.

It is the responsibility of the forest owner or manager to restore any roads which were used as a cartage route to the same condition that they were in before the commencement of harvesting operations to the extent of any damage caused as a result of the harvesting operations.

The cartage of timber associated with harvesting operations is extraordinary traffic for the purpose of Section 112 of the *Road Management Act 2004*.

53.11-4 Decision guidelines

31/07/2018
VC148

Before deciding on an application to use or develop land for timber production, in addition to the decision guidelines in Clause 65, the responsible authority must consider:

- The need to encourage plantation establishment and timber production in locations where it is of significance to national, state and regional economies, and in areas affected by salinity and other forms of land degradation.
- The role of native forest and plantations in:
  - Protecting water quality.
  - Conserving flora and fauna.
  - Preventing land degradation, including soil erosion, salinisation and water logging.
  - Preventing adverse effects on groundwater recharge.
- The preservation of and impact on the natural environment, cultural heritage and visual amenity.
- Whether it is appropriate to require environmental protection standards greater than those in the Code.

53.12 RACING DOG HUSBANDRY

08/08/2019
VC159

Purpose

To ensure the use and development of land for racing dog husbandry is consistent with orderly and proper planning.

53.12-1 Requirement

08/08/2019
VC159

An application to use land, or construct a building or construct or carry out works, for racing dog husbandry under a provision of a rural zone must comply with *Planning requirements for racing dog keeping and training* (Department of Environment, Land, Water and Planning, August 2017).

This requirement does not apply to an application to construct a building or construct or carry out works associated with a use that is a Section 1 use in the Table of uses of the zone.

53.12-2 Exemption from notice and review

31/07/2018
VC148

An application to which the requirement in Clause 53.12-1 applies is exempt from the notice requirements of section 52(1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if the approved measures specified in *Planning requirements for racing dog keeping and training* (Department of Environment, Land, Water and Planning, August 2017) are met.

53.13 RENEWABLE ENERGY FACILITY (OTHER THAN WIND ENERGY FACILITY)

17/09/2019
VC161

Purpose

To facilitate the establishment and expansion of renewable energy facilities, in appropriate locations, with minimal impact on the amenity of the area.

53.13-1 Application

17/09/2019
VC161

This clause applies to an application under any provision of this planning scheme to use or develop land for a renewable energy facility (other than a wind energy facility).

53.13-2 Application requirements

01/07/2021
VC203

An application must be accompanied by the following information, as appropriate:

- A site and context analysis, including:
  - A site plan, photographs or other techniques to accurately describe the site and the surrounding area.
  - A location plan showing the full site area, local electricity grid, access roads to the site and direction and distance to nearby accommodation, hospital or education centre.
- A design response, including:
  - Detailed plans of the proposed development including, the layout and height of the facility and associated building and works, materials, reflectivity, colour, lighting, landscaping, the electricity distribution starting point (where the electricity will enter the distribution system), access roads and parking areas.
  - Accurate visual simulations illustrating the development in the context of the surrounding area and from key public view points.
  - The extent of vegetation removal and a rehabilitation plan for the site.
  - Written report and assessment, including:
    - An explanation of how the proposed design derives from and responds to the site analysis.
    - A description of the proposal, including the types of process to be utilised, materials to be stored and the treatment of waste.
    - Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority.
    - the potential amenity impacts such as noise, glint, light spill, emissions to air, land or water, vibration, smell and electromagnetic interference.
    - the effect of traffic to be generated on roads.
    - the impact upon Aboriginal or non-Aboriginal cultural heritage.
    - the impact of the proposal on any species listed under the *Flora and Fauna Guarantee Act 1988* or *Environment Protection and Biodiversity Conservation Act 1999*.
    - A statement of why the site is suitable for a renewable energy facility including, a calculation of the greenhouse benefits.
    - An environmental management plan including, a construction management plan, any rehabilitation and monitoring.

53.13-3 Decision guidelines

28/10/2022
VC224

Before deciding on an application, in addition to the decision guidelines of Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The effect of the proposal on the surrounding area in terms of noise, glint, light spill, vibration, smell and electromagnetic interference.
- The impact of the proposal on significant views, including visual corridors and sightlines.
- The impact of the proposal on strategically important agricultural land.
- The impact of the proposal on the protection of declared irrigation districts.
- The impact of the proposal on the natural environment and natural systems.
- The impact of the proposal on the road network.
- *Solar Energy Facilities Design and Development Guideline* (Department of Environment, Land, Water and Planning, October 2022).

53.13-4 Amendment VC161 transitional provisions

17/09/2019
VC161

Clauses 19.01-2S and 53.13 of this planning scheme, as in force immediately before the approval date of Amendment VC161, continue to apply to an application to use or develop land for a renewable energy facility (other than a wind energy facility) lodged before the approval date of Amendment VC161.

Clauses 14.02-3S and 66.02-12 of this planning scheme do not apply to an application to use or develop land for a renewable energy facility (other than a wind energy facility) lodged before the approval date of Amendment VC161.

53.14 RESOURCE RECOVERY

31/07/2018
VC148

Purpose

To facilitate the establishment and expansion of a Transfer station and/or a Materials recycling facility in appropriate locations with minimal impact on the environment and amenity of the area.

53.14-1 Application

31/07/2018
VC148

This clause applies to all land used and developed or proposed to be used and developed for:

- A Transfer station;
- A Materials recycling facility.

53.14-2 Application requirements

01/07/2021
VC203

An application must be accompanied by the following information:

- A location plan showing the site and surrounding uses including distances to nearby sensitive uses such as residential, hospital or education uses.
- A detailed site plan showing the layout and height of buildings and works, materials, reflectivity, colour, lighting, landscaping, access roads and parking areas.
- Plans or other media showing anticipated views of the facility from sensitive use locations.
- A written report(s) including:
  - Identification of the purpose of the use.
  - A description of the proposal including the materials to be processed, the types of processes to be used and any materials to be stored and handled.
  - Proposed hours of operation.
  - Likely traffic generation including heavy vehicles.
  - Whether a Development Licence, Operating Licence, Permit or Registration is required from the Environment Protection Authority.
- An assessment of:
  - Potential amenity impacts such as noise, odour, emissions to air, land or water, vibration, dust, light spill, visual impact.
  - The impact of traffic generation on local roads.

53.14-3 Decision Guidelines

14/01/2025
VC237

Before deciding on an application, in addition to the Decision Guidelines of Clause 65, the responsible authority must consider:

- The contribution of the proposal to achieving resource recovery targets established by the Victorian Government.
- The impact of the proposal on the amenity of the surrounding area.
- The *Victorian Recycling Infrastructure Plan* (Department of Energy, Environment and Climate Action, October 2024).
- Relevant guidelines applicable to the application including the guideline for *Designing, Constructing and Operating Composting Facilities* (Environmental Protection Authority, 2015), the *Guide to Best Practice for Organics Recovery* (Sustainability Victoria, 2009) and the *Guide to Best Practice at Resource Recovery Centres* (Sustainability Victoria, 2009).

53.15 STATEMENT OF UNDERLYING PROVISIONS

31/07/2018
VC148

Purpose

To specify the planning scheme provisions which would have applied to land reserved for a public purpose pursuant to section 6(2)(i) of the *Planning and Environment Act 1987* if the land had not been reserved for that purpose.

53.15-01 Application

31/07/2018
VC148

In relation to any land identified in the schedule to this clause, the provisions of the planning scheme which would have applied to that land if it had not been reserved for a public purpose are the provisions which are contained in the relevant incorporated document, also identified in the schedule to this clause.

The incorporated document may contain some or all of the provisions which would have applied to the relevant land under this scheme if the land had not been reserved for a public purpose.

The incorporated document may also contain a statement or explanation of the strategic basis for those provisions. Alternatively, the incorporated document may make reference to a separate document, not forming part of the incorporated document, which contains a statement or explanation of the strategic basis for those provisions.

31/07/2018
VC148

SCHEDULE TO CLAUSE 53.15 STATEMENT OF UNDERLYING PROVISIONS

1.0 Incorporated statement

31/07/2018
VC148

Land	Incorporated Document
None specified	None specified

53.16 PIG FARM

11/04/2019
VC156

Purpose

To facilitate the establishment and expansion of pig farms in a manner that is consistent with orderly and proper planning and the protection of the environment.

53.16-1 Application

21/09/2018
VC150

This clause applies to permit applications to use land or construct a building or construct or carry out works for a pig farm, including to increase the farm capacity of an existing pig farm.

53.16-2 Exemption from notice and review

04/05/2022
VC210

An application to use land or construct a building or construct or carry out works for a pig farm is exempt from the notice requirements of section 52 (1)(a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act if the following requirements are met:

- The number of pigs does not exceed 150 sows or 1,000 Standard Pig Units as calculated in Table 1.
- The outdoor stocking density does not exceed 12 Standard Pig Units per hectare as calculated in Table 1.
- A Nutrient Management Plan demonstrates pigs are kept outdoors on paddocks with:
  - A minimum of 50% ground cover; and
  - Mobile housing and feeding infrastructure that is relocated at least every three months.
- Any area used as a pig range, including associated buildings and works, is setback a minimum distance of:
  - 100 metres from a building used for a sensitive use (accommodation, a child care centre, an education centre or a hospital), and
  - 400 metres from land in a residential zone.

Table 1 Standard Pig Unit conversion factors

Pig Class	Mass Range (kg)	Age Range (weeks)	SPU Factor
Gilt	100 – 160	24 -30	1.8
Boar	100 – 300	24 – 128	1.6
Gestating sow	160 – 230	-	1.6
Lactating sow	160 – 230	-	2.5
Sucker	1.4 – 8	0 – 4	0.1
Weaner	8 – 25	4 – 10	0.5
Grower	24 – 55	10 – 16	1.0
Finisher	55 – 100	16 – 24	1.6

Pig Class	Mass Range (kg)	Age Range (weeks)	SPU Factor
Heavy Finisher	100 – 130	24 -30	1.8

Note: Adapted from the National Environmental Guidelines for Piggeries 2010

53.16-3 Decision guidelines

21/09/2018
VC150

Before deciding on an application to use land or construct a building or construct or carry out works, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The purpose of the relevant zone.
- The design, height, setback and appearance of the proposed buildings and works.
- The proposed landscaping.
- The need to protect amenity of existing uses on adjoining land.
- The impact of the use of the land on the surrounding area, including from the emission of noise, light, vibration, odour, dust, or waste products.
- The impact of the proposal on any wetlands, waterways or water bodies.
- The likely environmental impact on the natural physical features and biodiversity of the land, including consideration of any Nutrient Management Plan submitted with the application.
- Whether the development will support and enhance agricultural production.
- The requirements of the *Victorian Low Density Mobile Outdoor Pig Farm Planning Permit Guidelines* (June 2018).

53.17 RESIDENTIAL AGED CARE FACILITY

14/12/2023
VC253

Purpose

To facilitate the development of well-designed residential aged care facilities to meet existing and future needs.

To recognise that residential aged care facilities have a different scale and built form to the surrounding neighbourhood.

To ensure residential aged care facilities do not unreasonably impact on the amenity of adjoining dwellings or small second dwellings.

53.17-1 Application

25/02/2025
VC257

This clause applies to an application to construct a building or construct or carry out works for a residential aged care facility in the General Residential Zone, Housing Choice and Transport Zone, Mixed Use Zone, Neighbourhood Residential Zone, Residential Growth Zone or Township Zone.

53.17-2 Application requirements

26/10/2018
VC152

An application must be accompanied by:

- A site and context description.
- A design response.
- A landscape plan.

Site and context description

The site and context description may use a site plan, photographs or other techniques and must include:

- Site shape, size, orientation and easements.
- Levels of the site and the difference in levels between the site and surrounding properties.
- The location of existing buildings on the site and on adjacent properties, including the location and height of walls built to the boundary of the site.
- The use of adjacent buildings and land.
- The location of secluded private open space and habitable room windows of adjacent properties which have an outlook to the site within 9 metres.
- Solar access to the site and to adjacent properties.
- Any contaminated soils and filled areas, where known.
- Location of significant trees existing on the site and any significant trees removed from the site in the 12 months prior to the application being made, where known.
- Street frontage features such as poles, street trees and kerb crossovers.
- Any other notable features or characteristics of the site.

If in the opinion of the responsible authority a requirement of the site and context description is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

Design response

The design response must explain how the proposed design:

- Responds to the site and context description.
- Meets the requirements of this clause.

Landscape plan

The landscape plan must include:

- Landscaping of communal open space for the enjoyment of residents and staff.
- Landscaping along the boundaries of the site.
- On-site management of run-off from paved areas.
- Retaining significant trees where possible.

53.17-3 Development requirements

25/02/2025
VC257

Operation

If there is any inconsistency between a requirement in this clause and a requirement in another provision of this planning scheme, this clause prevails.

Building height

In the Neighbourhood Residential Zone, General Residential Zone and Township Zone the maximum building height must not exceed 16 metres.

In the Mixed Use Zone and Residential Growth Zone the maximum building height should not exceed 16 metres.

In the Housing Choice and Transport Zone the maximum building height must not exceed:

- 21.5 metres for land shown on a planning scheme map as **HCTZ1**.
- 16 metres for land shown on a planning scheme map as **HCTZ2**.

Street setback

Walls of buildings should be set back from streets the distance specified in the table:

Development context	Minimum setback from front street (metres)	Minimum setback from a side street (metres)
There is an existing building on both the abutting allotments facing the same street, and the site is not on a corner.	The average distance of the setbacks of the front walls of the existing buildings on the abutting allotments facing the front street or 9 metres, whichever is the lesser. This does not include a porte cochère.	Not applicable
There is an existing building on one abutting allotment facing the same street and no existing building on the other abutting allotment facing the same street, and the site is not on a corner.	The same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 9 metres, whichever is the lesser. This does not include a porte cochère.	Not applicable
There is no existing building on either of the abutting allotments facing the same street, and the site is not on a corner.	6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Not applicable
The site is on a corner.	If there is a building on the abutting allotment facing the front street, the same distance as the setback of the front wall	Front walls of new development fronting the side street of a corner site should be setback at


Development context	Minimum setback from front street (metres)	Minimum setback from a side street (metres)
	of the existing building on the abutting allotment facing the front street or 9 metres, whichever is the lesser. This does not include a porte cochère. If there is no building on the abutting allotment facing the front street, 6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	least the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 4 metres, whichever is the lesser. Side walls of new development on a corner site should be setback the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 2 metres, whichever is the lesser.

Side and rear setbacks

A new building not on or within 200mm of a boundary should be set back from side or rear boundaries by 1metre, plus 0.3 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres.

Screens, sunblinds, verandahs, porches, eaves, fascias, gutters, masonry chimneys, flues, pipes, domestic fuel or water tanks, and heating or cooling equipment or other services may encroach not more than 0.5 metres into the setbacks of this standard.

Landings having an area of not more than 2 square metres and less than 1 metre high, stairways, ramps, pergolas, shade sails and carports may encroach into the setbacks of this standard.



Walls on boundaries

A new wall constructed on or within 200mm of a side or rear boundary of a lot or a carport constructed on or within 1 metre of a side or rear boundary of lot should not abut the boundary for a length of more than:

- 10 metres plus 25 per cent of the remaining length of the boundary of an adjoining lot, or
- Where there are existing or simultaneously constructed walls or carports abutting the boundary on an abutting lot, the length of the existing or simultaneously constructed walls or carports;

whichever is the greater.

A new wall or carport may fully abut a side or rear boundary where slope and retaining walls or fences would result in the effective height of the wall or carport being less than 2 metres on the abutting property boundary.

A building on a boundary includes a building set back up to 200mm from a boundary.


The height of a new wall constructed on or within 200mm of a side or rear boundary or a carport constructed on or within 1 metre of a side or rear boundary should not exceed an average of 3.2 metres with no part higher than 3.6 metres unless abutting a higher existing or simultaneously constructed wall.

Daylight to existing windows

Buildings opposite an existing habitable room window should provide for a light court to the existing window that has a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky. The calculation of the area may include land on the abutting lot.


Walls or carports more than 3 metres in height opposite an existing habitable room window should be set back from the window at least 50 per cent of the height of the new wall if the wall is within a 55 degree arc from the centre of the existing window. The arc may be swung to within 35 degrees of the plane of the wall containing the existing window.

Where the existing window is above ground floor level, the wall height is measured from the floor level of the room containing the window.



North-facing windows

If a north-facing habitable room window of an existing dwelling or small second dwelling is within 3 metres of a boundary on an abutting lot, a building should be setback from the boundary 1 metre, plus 0.6 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres, for a distance of 3 metres from the edge of each side of the window. A north-facing window is a window with an axis perpendicular to its surface oriented north 20 degrees west to north 30 degrees east.



Overshadowing open space

Where sunlight to the secluded private open space of an existing dwelling or small second dwelling is reduced, at least 75 per cent, or 40 square metres with minimum dimension of 3 metres, whichever is the lesser area, of the secluded private open space should receive a minimum of five hours of sunlight between 9 am and 3 pm on 22 September.

If existing sunlight to the secluded private open space of an existing dwelling or small second dwelling is less than the requirements of this standard, the amount of sunlight should not be further reduced.

Overshadowing solar energy systems

Buildings should be sited and designed to ensure that the performance of existing rooftop solar energy systems on dwellings or small second dwellings on adjoining lots in a General Residential Zone, Neighbourhood Residential Zone or Township Zone are not unreasonably reduced. The existing rooftop solar energy system must exist at the date the application is lodged.

Overlooking

A habitable room window, balcony, terrace, deck or patio should be located and designed to avoid direct views into the secluded private open space of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio. Views should be measured within a 45 degree angle from the plane of the window or perimeter of the balcony, terrace, deck or patio, and from a height of 1.7 metres above floor level.

A habitable room window, balcony, terrace, deck or patio with a direct view into a habitable room window of existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio should be either:


- Offset a minimum of 1.5 metres from the edge of one window to the edge of the other.
- Have sill heights of at least 1.2 metres above floor level.
- Have fixed, obscure glazing in any part of the window below 1.2 metres above floor level.
- Have permanently fixed external screens to at least 1.2 metres above floor level and be no more than 25 per cent transparent.

Obscure glazing in any part of the window below 1.2 metres above floor level may be openable provided that there are no direct views as specified in this standard.

Screens used to obscure a view should be:

- Perforated panels or trellis with a maximum of 25 per cent openings or solid translucent panels.
- Permanent, fixed and durable.
- Designed and coloured to blend in with the development.

This standard does not apply to a new habitable room window, balcony, terrace, deck or patio which faces a property boundary where there is a visual barrier at least 1.8 metres high and the floor level of the habitable room, balcony, terrace, deck or patio is less than 0.8 metres above ground level at the boundary.



Noise impacts

Noise sources, such as mechanical plant, should not be located near bedrooms of immediately adjacent existing dwellings or small second dwellings.

Daylight to new windows

A window in a habitable room should be located to face:

- An outdoor space clear to the sky or a light court with a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky, not including land on an abutting lot, or
- A verandah provided it is open for at least one third of its perimeter, or
- A carport provided it has two or more open sides and is open for at least one third of its perimeter.

Site coverage

The site area covered by buildings should not exceed 80 percent.

Access

Access ways should be designed to:

- Provide direct access to on-site designated areas for car and bicycle parking.
- Provide direct access to the building for emergency vehicles.
- Provide access for service and delivery vehicles to on-site loading bays and storage areas.

- Ensure vehicles can enter and exit a development in a forward direction.
- Provide a carriageway width of at least 5.5 metres and an internal radius of at least 4 metres at a change of direction.
- The number and location of access points from streets to the site and the design of crossovers must be to the requirements of the relevant road authority.
- Shared access ways or car parks should be located at least 1.5 metres from the windows of habitable rooms. This setback may be reduced by 1 metre where there is a fence at least 1.5 metres high or where window sills are at least 1.4 metres above the access way.

Building entry

The main pedestrian entry to a building should:

- Have convenient access from a street.
- Be sheltered from the weather.
- Have convenient access from on-site car parking.
- Have a designated vehicle standing area suitable for use by a community bus and a disabled parking area should be provided in an area that is convenient for the drop-off and pick-up of residents.

Communal open space

Accessible and useable communal open space should be provided for residents and staff.

Front fence

A front fence within 3 metres of a street should not exceed:

- 2 metres in height in streets in a Transport Zone 2; and
- 1.5 metres in height on all other streets.

53.17-4 Decision guidelines

14/12/2023
VC253

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- The Municipal Planning Strategy and the Planning Policy Framework.
- How the proposed development responds to the site and context description.
- Where the requirements of this clause are not met, the impact on the amenity of the adjoining dwellings or small second dwellings.
- The proposed amenity for future residents of the residential aged care facility.
- The effect of overshadowing on an appropriately located existing rooftop solar energy system on an adjoining lot.

53.18 STORMWATER MANAGEMENT IN URBAN DEVELOPMENT

26/10/2018
VC154

Purpose

To ensure that stormwater in urban development, including retention and reuse, is managed to mitigate the impacts of stormwater on the environment, property and public safety, and to provide cooling, local habitat and amenity benefits.

53.18-1 Application

28/10/2022
VC224

This clause applies to an application under a provision of a zone to subdivide land, construct a building, or construct or carry out works, other than the following applications:

- An application under a provision of the Farming Zone, Green Wedge Zone, Green Wedge A Zone, Low Density Residential Zone, Public Conservation and Resource Zone, Transport Zone 2, Transport Zone 3, Rural Activity Zone, Rural Conservation Zone, Rural Living Zone, Urban Floodway Zone or Urban Growth Zone (Part A – No precinct structure plan applies).
- A VicSmart application.
- An application to subdivide land in a residential zone for residential purposes.
- An application to construct or extend a dwelling, fence or residential building in a residential zone.
- An application for development associated with the use of land for agriculture or earth and energy resources industry.
- An application to construct a building or construct or carry out works associated with one dwelling on a lot.
- An application to alter, extend or make structural changes to an existing building provided the gross floor area of the building is not increased by more than 50 square metres.
- An application to construct a building with a gross floor area not exceeding 50 square metres.
- An application to construct or carry out works with an area not exceeding 50 square metres.
- An application to subdivide land into lots each containing an existing building or car parking space.
- An application to construct a building or to construct or carry out works on a lot if all of the following requirements are met:
  - The lot was created in accordance with a permit granted under this planning scheme.
  - The application for that permit was assessed against the requirements of this clause.
- An application for land affected by a development plan or incorporated plan that was approved or incorporated in this planning scheme before the approval date of Amendment VC154.
- An application lodged before the approval date of Amendment VC154.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before the approval date of Amendment VC154.

Transitional provisions

Clause 53.18 of this scheme, as in force immediately before the approval date of Amendment VC224, continues to apply to:

- An application for a planning permit lodged before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was lodged before that date.

53.18-2 Operation

26/10/2018
VC154

The provisions of this clause contain:

- **Objectives**. An objective describes the desired outcome to be achieved in the completed development.
- **Standards**. A standard contains the requirements to meet the objective.

  A standard should normally be met. However, if the responsible authority is satisfied that an application for an alternative solution meets the objective, the alternative solution may be considered.

53.18-3 Requirements

26/10/2018
VC154

An application to subdivide land:

- Must meet all of the objectives of Clauses 53.18-4 and 53.18-6.
- Should meet all of the standards of Clauses 53.18-4 and 53.18-6.

An application to construct a building or construct or carry out works:

- Must meet all of the objectives of Clauses 53.18-5 and 53.18-6.
- Should meet all of the standards of Clauses 53.18-5 and 53.18-6.

An application must be accompanied by details of the proposed stormwater management system, including drainage works and retention, detention and discharges of stormwater to the drainage system.

53.18-4 Stormwater management objectives for subdivision

03/02/2022
VC199

To minimise damage to properties and inconvenience to the public from stormwater.

To ensure that the street operates adequately during major storm events and provides for public safety.

To minimise increases in stormwater and protect the environmental values and physical characteristics of receiving waters from degradation by stormwater.

To encourage stormwater management that maximises the retention and reuse of stormwater.

To encourage stormwater management that contributes to cooling, local habitat improvements and provision of attractive and enjoyable spaces.

Standard W1

The stormwater management system should be:

- Designed and managed in accordance with the requirements and to the satisfaction of the relevant drainage authority.
- Designed and managed in accordance with the requirements and to the satisfaction of the water authority where reuse of stormwater is proposed.
- Designed to meet the current best practice performance objectives for stormwater quality as contained in the *Urban Stormwater - Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999).
- Designed to ensure that flows downstream of the subdivision site are restricted to pre-development levels unless increased flows are approved by the relevant drainage authority and there are no detrimental downstream impacts.
- Designed to contribute to cooling, improving local habitat and providing attractive and enjoyable spaces.

The stormwater management system should be integrated with the overall development plan including the street and public open space networks and landscape design.

For all storm events up to and including the 20% Average Exceedance Probability (AEP) standard:

- Stormwater flows should be contained within the drainage system to the requirements of the relevant authority.
- Ponding on roads should not occur for longer than 1 hour after the cessation of rainfall.

For storm events greater than 20% AEP and up to and including 1% AEP standard:

- Provision must be made for the safe and effective passage of stormwater flows.
- All new lots should be free from inundation or to a lesser standard of flood protection where agreed by the relevant floodplain management authority.
- Ensure that streets, footpaths and cycle paths that are subject to flooding meet the safety criteria da Vave < 0.35 m2/s (where, da = average depth in metres and Vave = average velocity in metres per second).

The design of the local drainage network should:

- Ensure stormwater is retarded to a standard required by the responsible drainage authority.
- Ensure every lot is provided with drainage to a standard acceptable to the relevant drainage authority. Wherever possible, stormwater should be directed to the front of the lot and discharged into the street drainage system or legal point of discharge.
- Ensure that inlet and outlet structures take into account the effects of obstructions and debris build up. Any surcharge drainage pit should discharge into an overland flow in a safe and predetermined manner.
- Include water sensitive urban design features to manage stormwater in streets and public open space. Where such features are provided, an application must describe maintenance responsibilities, requirements and costs.

Any flood mitigation works must be designed and constructed in accordance with the requirements of the relevant floodplain management authority.

53.18-5 Stormwater management objectives for buildings and works

26/10/2018
VC154

To encourage stormwater management that maximises the retention and reuse of stormwater.

To encourage development that reduces the impact of stormwater on the drainage system and filters sediment and waste from stormwater prior to discharge from the site.

To encourage stormwater management that contributes to cooling, local habitat improvements and provision of attractive and enjoyable spaces.

To ensure that industrial and commercial chemical pollutants and other toxicants do not enter the stormwater system.

Standard W2

The stormwater management system should be designed to:

- Meet the current best practice performance objectives for stormwater quality as contained in the *Urban Stormwater - Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999).
- Minimise the impact of chemical pollutants and other toxicants including by, but not limited to, bunding and covering or roofing of storage, loading and work areas.
- Contribute to cooling, improving local habitat and providing attractive and enjoyable spaces.

53.18-6 Site management objectives

26/10/2018
VC154

To protect drainage infrastructure and receiving waters from sedimentation and contamination.

To protect the site and surrounding area from environmental degradation prior to and during construction of subdivision works.

Standard W3

An application should describe how the site will be managed prior to and during the construction period and may set out requirements for managing:

- Erosion and sediment.
- Stormwater.
- Litter, concrete and other construction wastes.
- Chemical contamination.

53.18-7 Decision guidelines

26/10/2018
VC154

Before deciding on an application, in addition to the decision guidelines in Clause 65, the responsible authority must consider, as appropriate:

- Any relevant water and stormwater management objective, policy or statement set out in this planning scheme.
- The capacity of the site to incorporate stormwater retention and reuse and other water sensitive urban design features.
- Whether the development has utilised alternative water sources and/or incorporated water sensitive urban design.
- Whether stormwater discharge from the site will adversely affect water quality entering the drainage system.
- The capacity of the drainage network to accommodate additional stormwater.
- Whether the stormwater treatment areas can be effectively maintained.
- Whether the owner has entered into an agreement to contribute to off-site stormwater management in lieu of providing an on-site stormwater management system.

53.19 NON-GOVERNMENT SCHOOLS

03/12/2019
VC165

Purpose

To facilitate new non-government schools.

To facilitate upgrades and extensions to existing non-government schools.

53.19-1 Application

04/12/2020
VC180

This clause applies to an application under any provision of this scheme, other than a VicSmart application, to use or develop land for a primary school, secondary school, or education centre that is ancillary to, carried out in conjunction with, and on the same land or contiguous land in the same ownership as, a primary school or secondary school.

53.19-2 Exemption from review

04/12/2020
VC180

An application to which Clause 53.19 applies is exempt from the decision requirements of section 64(1), (2), and (3), and the review rights of section 82(1) of the Act.

53.19-3 Transitional provisions

04/12/2020
VC180

Clause 53.19 of this scheme, as in force immediately before the approval date of Amendment VC180, continues to apply to:

- An application for a planning permit made before that date.
- An application for an amendment of a permit under section 72 of the Act, if the original permit application was made before that date.

53.20 HOUSING BY OR ON BEHALF OF HOMES VICTORIA

14/12/2023
VC253

Purpose

To facilitate the development of well-designed social housing and affordable housing to meet existing and future needs.

To increase the social housing and affordable housing stock in Victoria.

To ensure the development of housing by or on behalf of the Chief Executive Officer, Homes Victoria does not unreasonably impact on the amenity of adjoining dwellings or small second dwellings.

53.20-1 Application

04/07/2025
VC258

This clause applies to an application under a provision of a residential zone (other than the Low Density Residential Zone) to construct or extend a dwelling, or to construct or extend a front fence, if the application is made by or on behalf of the Chief Executive Officer, Homes Victoria.

This clause does not apply to an application that meets the requirements of clause 53.23-1.

In this clause, ***Chief Executive Officer, Homes Victoria*** means 'Chief Executive Officer, Homes Victoria' as defined in the *Housing Act 1983* and the body corporate established under the *Housing Act 1983*.

53.20-2 Operation

14/12/2023
VC253

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

An application to construct or extend a dwelling, or to construct or extend a front fence, should meet the standards in Clause 53.20-6.

An application to construct or extend an apartment development, or to construct or extend a dwelling in or forming part of an apartment development, should meet the standards in Clause 53.20-6 and Clause 53.20-7 except for the standard in:

- Clause 53.20-6.5.
- Clause 53.20-6.10 for an apartment development of 5 or more storeys.

The standards in Clause 53.20-6 and Clause 53.20-7 should normally be met. However, an alternative design solution may be considered if the responsible authority is satisfied that the proposal does not unreasonably impact on the amenity of an existing dwelling or small second dwelling on the site or on an adjacent site.

53.20-3 Exemption from planning scheme provisions

31/03/2025
VC267

The following provisions of this planning scheme do not apply:

- The Municipal Planning Strategy or Municipal Strategic Statement and the Planning Policy Framework.
- An application requirement or decision guideline of a zone.
- A requirement to meet Clauses 54, 55, 57 and 58 of a zone.
- A schedule to a zone except for a specified building height requirement.
- Clauses 52.06 and 65.

53.20-4 Exemption from notice and review

20/12/2021
VC207

An application under any provision of this scheme is exempt from the notice requirements of section 52(1) (a), (b) and (d), the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

53.20-5 Application requirements

20/03/2023
VC229

An application must be accompanied by the following information, as appropriate:

- Where the application is made on behalf of the Chief Executive Officer, Homes Victoria, a letter from Homes Victoria confirming that the application is made on behalf of the Chief Executive Officer, Homes Victoria.
- An urban context report. The urban context report may use a site plan, photographs or other techniques and must include an accurate description of:
  - Lot boundaries, site shape, size, orientation and easements on the subject site.
  - Levels and contours of the site and the difference in levels between the site and adjoining properties.
  - The location and height of existing buildings on the site and adjoining properties.
  - The use of adjoining buildings.
  - The location of secluded private open space of adjoining properties and the location of trees, fences and other landscape elements.
  - Solar access to the site and to adjoining properties.
  - Street frontage features such as poles, street lights, street trees and kerb crossovers.
  - The location of local shops, public transport services and public open spaces within walking distance.
  - Movement systems through and around the site.
  - Any other notable feature or characteristic of the site.
  - An assessment of the characteristics of the area including:
    - Any environmental features such as vegetation, topography and significant views.
    - The pattern of subdivision.
    - Street design and landscape.
    - The pattern of development.
    - Building form, scale and rhythm.
    - Connection to the public realm.
    - Architectural style, building details and materials.
    - Significant off-site noise sources.
    - For an apartment application, the relevant NatHERS climate zones.
    - Social and economic activity.
    - Any other notable or cultural characteristics of the area.
- A design response. The design response must explain how the proposed design:
  - Responds to any relevant planning provision.
  - Derives from and responds to the urban context report.

- The design response must include correctly proportioned street elevations or photographs showing the development in the context of adjacent buildings.

53.20-6 Development standards

01/01/2024
VC250

53.20-6.1 Infrastructure

Development should be connected to reticulated services, including reticulated sewerage, drainage and electricity.

Development should not unreasonably exceed the capacity of utility services and infrastructure, including reticulated services and roads.

In areas where utility services or infrastructure have little or no spare capacity, developments should provide for the upgrading of or mitigation of the impact on services or infrastructure.

53.20-6.2 Street setback

Walls of buildings should be set back from streets at least the distance specified in Table 1. Porches, pergolas and verandahs that are less than 3.6 metres high and eaves may encroach not more than 2.5 metres into the setbacks of this standard.

Table 1 Street setback

Development context	Minimum setback from front street (metres)	Minimum setback from a side street (metres)
There is an existing building on both the abutting allotments facing the same street, and the site is not on a corner.	The same distance as the setback of the front wall of either existing building on the abutting allotments facing the front street or 7 metres, whichever is the lesser.	Not applicable.
There is an existing building on one abutting allotment facing the same street and no existing building on the other abutting allotment facing the same street, and the site is not on a corner.	The same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 7 metres, whichever is the lesser.	Not applicable.
There is no existing building on either of the abutting allotments facing the same street, and the site is not on a corner.	6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Not applicable.
The site is on a corner.	If there is a building on the abutting allotment facing the front street, the same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 7 metres, whichever is the lesser.	Front walls of new development fronting the side street of a corner site should be setback at least the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 3 metres, whichever is the lesser.

Development context	Minimum setback from front street (metres)	Minimum setback from a side street (metres)
	If there is no building on the abutting allotment facing the front street, 6 metres for streets in a Transport Zone 2, and 4 metres for other streets.	Side walls of new development on a corner site should be setback the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 2 metres, whichever is the lesser.

53.20-6.3 Site coverage

The site area covered by buildings should not exceed 60 per cent.

53.20-6.4 Permeability

The site area covered by the pervious surfaces should be at least 20 percent of the site.

53.20-6.5 Energy efficiency

Buildings should be:

- Oriented to make appropriate use of solar energy.
- Sited and designed to ensure that the energy efficiency of existing dwellings or small second dwellings on adjoining lots is not unreasonably reduced.
- Sited and designed to ensure that the performance of existing roof top solar energy systems on dwellings or small second dwellings on adjoining lots in a General Residential Zone, Neighbourhood Residential Zone or Township Zone are not unreasonably reduced. The existing roof top solar energy system must exist at the date the application is lodged.

Living areas and private open space should be located on the north side of the development, if practicable.

Developments should be designed so that solar access to north-facing windows is maximised.

53.20-6.6 Safety

Entrances to dwellings should not be obscured or isolated from the street and internal accessways.

Planting which creates unsafe spaces along streets and accessways should be avoided.

Developments should be designed to provide good lighting, visibility and surveillance of car parks and internal accessways.

Private spaces within developments should be protected from inappropriate use as public thoroughfares.

53.20-6.7 Access

Vehicle crossovers should be minimised.

Car parking entries should be consolidated, minimised in size, integrated with the façade and where practicable located at the side or rear of the building.

Pedestrian and cyclist access should be clearly delineated from vehicle access.

The location of crossovers should maximise pedestrian safety and the retention of on-street car parking spaces and street trees.

Developments must provide for access for service, emergency and delivery vehicles.

53.20-6.8 Parking location

Car parking facilities should:

- Be reasonably close and convenient to dwellings.
- Be secure.
- Be well ventilated if enclosed.

Shared accessways or car parks of other dwellings should be located at least 1.5 metres from the windows of habitable rooms. This setback may be reduced to 1 metre where there is a fence at least 1.5 metres high or where window sills are at least 1.4 metres above the accessway.

53.20-6.9 Car parking

A minimum 0.6 car spaces should be provided to each dwelling. Car spaces may be covered or uncovered.

If in calculating the number of car parking spaces the result is not a whole number, the required number of car parking spaces is to be rounded down to the nearest whole number greater than 1.

Accessway design

Accessways must:

- Be at least 3 metres wide.
- Have an internal radius of at least 4 metres at changes of direction or intersection or be at least 4.2 metres wide.
- Allow vehicles parked in the last space of a dead-end accessway in public carparks to exit in a forward direction with one manoeuvre.
- Provide at least 2.1 metres headroom beneath overhead obstructions, calculated for a vehicle with a wheel base of 2.8 metres.
- If the accessway serves four or more car spaces or connects to a road in a Transport Zone 2 or a Transport Zone 3, the accessway must be designed so that cars can exit the site in a forward direction.
- Provide a passing area at the entrance at least 6.1 metres wide and 7 metres long if the accessway serves ten or more carparking spaces and is either more than 50 metres long or connects to a road in a Transport Zone 2 or a Transport Zone 3.
- Have a corner splay or area at least 50 percent clear of visual obstructions extending at least 2 metres along the frontage road from the edge of an exit lane and 2.5 metres along the exit lane from the frontage, to provide a clear view of pedestrians on the footpath of the frontage road. The area clear of visual obstructions may include an adjacent entry or exit lane where more than one lane is provided, or adjacent landscaped areas, provided the landscaping in those areas is less than 900mm in height.

Car parking spaces

Car parking spaces and accessways must have the minimum dimensions as outlined in Table 2.

Table 2: Minimum dimensions of car parking spaces and accessways


Angle of car parking spaces to access way	Accessway width	Car space width	Car space length
Parallel	3.6 m	2.3 m	6.7 m
45º	3.5 m	2.6 m	4.9 m
60º	4.9 m	2.6 m	4.9 m
90º	6.4 m	2.6 m	4.9 m
	5.8 m	2.8 m	4.9 m
	5.2 m	3.0 m	4.9 m
	4.8 m	3.2 m	4.9 m

Note: Some dimensions in Table 2 vary from those shown in the Australian Standard AS2890.1-2004 (off street). The dimensions shown in Table 2 allocate more space to aisle widths and less to marked spaces to provide improved operation and access. The dimensions in Table 2 are to be used in preference to the Australian Standard AS2890.1-2004 (off street) except for disabled spaces which must achieve Australian Standard AS2890.6-2009 (disabled).

A wall, fence, column, tree, tree guard or any other structure that abuts a car space must not encroach into the area marked 'clearance required' on Diagram 1, other than:

- A column, tree or tree guard, which may project into a space if it is within the area marked 'tree or column permitted' on Diagram 1.
- A structure, which may project into the space if it is at least 2.1 metres above the space.

Diagram 1 Clearance to car parking spaces



Car spaces in garages or carports must be at least 6 metres long and 3.5 metres wide for a single space and 5.5 metres wide for a double space measured inside the garage or carport.

Where parking spaces are provided in tandem (one space behind the other) an additional 500mm in length must be provided between each space.

Disabled car parking spaces must be designed in accordance with Australian Standard AS2890.6-2009 (disabled) and the Building Code of Australia. Disabled carparking spaces may encroach into an accessway width specified in Table 2 by 500mm.

Gradients

Accessway grades must not be steeper than 1:10 (10 percent) within 5 metres of the frontage to ensure safety for pedestrians and vehicles. The design must have regard to the wheel base of the vehicle being designed for; pedestrian and vehicular traffic volumes; the nature of the carpark; and the slope and configuration of the vehicle crossover at the site frontage. This does not apply to accessways serving three dwellings or less.

Ramps (except within 5 metres of the frontage) must have the maximum grades as outlined in Table 3 and be designed for vehicles travelling in a forward direction.

Table 3: Ramp gradients

Type of car park	Length of ramp	Maximum grade
Public car parks	20 metres or less	1:5 (20%)
	longer than 20 metres	1:6 (16.7%)
Private or residential car parks	20 metres or less	1:4 (25%)
	longer than 20 metres	1:5 (20%)

Where the difference in grade between two sections of ramp or floor is greater that 1:8 (12.5 per cent) for a summit grade change, or greater than 1:6.7 (15 percent) for a sag grade change, the ramp must include a transition section of at least 2 metres to prevent vehicles scraping or bottoming.

Plans must include an assessment of grade changes of greater than 1:5.6 (18 percent) or less than 3 metres apart for clearances, to the satisfaction of the responsible authority.

Mechanical parking

Mechanical parking may be used to meet the carparking requirement provided:

- At least 25 percent of the mechanical carparking spaces can accommodate a vehicle height of at least1.8 metres.
- Carparking spaces that require the operation of the system are not allocated to visitors unless used in a valet parking situation.
- The design and operation is to the satisfaction of the responsible authority.

Urban design

Ground level carparking, garage doors and accessways must not visually dominate public space.

Carparking within buildings (including visible portions of partly submerged basements) must be screened or obscured where possible, including through the use of occupied tenancies, landscaping, architectural treatments and art works.

Design of carparks must take into account their use as entry points to the site.

Design of new internal streets in developments must maximise on street parking opportunities.

Safety

Car parking must be well lit and clearly signed.

The design of carparks must maximise natural surveillance and pedestrian visibility from adjacent buildings.

Pedestrian access to carparking areas from the street must be convenient.

Pedestrian routes through car parking areas and building entries and other destination points must be clearly marked and separated from traffic in high activity parking areas.

Landscaping

The layout of car parking areas must provide for water sensitive urban design treatment and landscaping.

Landscaping and trees must be planted to provide shade and shelter, soften the appearance of ground level car parking and aid in the clear identification of pedestrian paths.

Ground level carparking spaces must include trees planted with flush grilles. Spacing of trees must be determined having regard to the expected size of the selected species at maturity.


53.20-6.10 Side and rear setbacks

A new building not on or within 200mm of a boundary to a residential zone should be set back from side or rear boundaries 1 metre, plus 0.3 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres. Diagram 2 details the standard.

Sunblinds, verandahs, porches, eaves, fascias, gutters, masonry chimneys, flues, pipes, domestic fuel or water tanks, and heating or cooling equipment or other services may encroach not more than 0.5 metres into the setbacks of this standard.

Landings having an area of not more than 2 square metres and less than 1 metre high, stairways, ramps, pergolas, shade sails and carports may encroach into the setbacks of this standard.

Diagram 2 Side and rear setbacks



53.20-6.11 Walls on boundaries

A new wall constructed on or within 200mm of a side or rear boundary of a lot or a carport constructed on or within 1 metre of a side or rear boundary of lot should not abut the boundary for a length of more than:

- 10 metres plus 25 per cent of the remaining length of the boundary of an adjoining lot, or
- Where there are existing or simultaneously constructed walls or carports abutting the boundary on an abutting lot, the length of the existing or simultaneously constructed walls or carports whichever is the greater.

A new wall or carport may fully abut a side or rear boundary where slope and retaining walls or fences would result in the effective height of the wall or carport being less than 2 metres on the abutting property boundary.

A building on a boundary includes a building set back up to 200mm from a boundary.

The height of a new wall constructed on or within 200mm of a side or rear boundary or a carport constructed on or within 1 metre of a side or rear boundary should not exceed an average of 3.2 metres with no part higher than 3.6 metres unless abutting a higher existing or simultaneously constructed wall.


53.20-6.12 Daylight to existing windows

Buildings opposite an existing habitable room window should provide for a light court to the existing window that has a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky. The calculation of the area may include land on the abutting lot.

Walls or carports more than 3 metres in height opposite an existing habitable room window should be set back from the window at least 50 per cent of the height of the new wall if the wall is within a 55 degree arc from the centre of the existing window. The arc may be swung to within 35 degrees of the plane of the wall containing the existing window.

Where the existing window is above ground floor level, the wall height is measured from the floor level of the room containing the window.


Diagram 3 Daylight to existing windows



53.20-6.13 North-facing windows

If a north-facing habitable room window of an existing dwelling or a small second dwelling is within 3 metres of a boundary on an abutting lot, a building should be setback from the boundary 1 metre, plus 0.6 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres, for a distance of 3 metres from the edge of each side of the window. A north-facing window is a window with an axis perpendicular to its surface oriented north 20 degrees west to north 30 degrees east.

Diagram 4 North-facing windows



53.20-6.14 Overshadowing open space

Where sunlight to the secluded private open space of an existing dwelling or small second dwelling is reduced, at least 75 per cent, or 40 square metres with minimum dimension of 3 metres, whichever is the lesser area, of the secluded private open space should receive a minimum of five hours of sunlight between 9 am and 3 pm on 22 September.

If existing sunlight to the secluded private open space of an existing dwelling or small second dwelling is less than the requirements of this standard, the amount of sunlight should not be further reduced.

53.20-6.15 Overlooking

A habitable room window, balcony, terrace, deck or patio should be located and designed to avoid direct views into the secluded private open space of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio. Views should be measured within a 45 degree angle from the plane of the window or perimeter of the balcony, terrace, deck or patio, and from a height of 1.7 metres above floor level.

A habitable room window, balcony, terrace, deck or patio with a direct view into a habitable room window of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio should be either:

- Offset a minimum of 1.5 metres from the edge of one window to the edge of the other.
- Have sill heights of at least 1.7 metres above floor level.
- Have fixed, obscure glazing in any part of the window below 1.7 metre above floor level.
- Have permanently fixed external screens to at least 1.7 metres above floor level and be no more than 25 per cent transparent.


Obscure glazing in any part of the window below 1.7 metres above floor level may be openable provided that there are no direct views as specified in this standard.

Screens used to obscure a view should be:

- Perforated panels or trellis with a maximum of 25 per cent openings or solid translucent panels.
- Permanent, fixed and durable.
- Designed and coloured to blend in with the development.

This standard does not apply to a new habitable room window, balcony, terrace, deck or patio which faces a property boundary where there is a visual barrier at least 1.8 metres high and the floor level of the habitable room, balcony, terrace, deck or patio is less than 0.8 metres above ground level at the boundary.

Diagram 5 Overlooking open space



53.20-6.16 Noise impacts

Noise sources, such as mechanical plant, should not be located near bedrooms of immediately adjacent existing dwellings or small second dwellings.

Noise sensitive rooms and secluded private open spaces of new dwellings and residential buildings should take account of noise sources on immediately adjacent properties.

Dwellings and residential buildings close to busy roads, railway lines or industry should be designed to limit noise levels in habitable rooms.

53.20-6.17 Daylight to new windows

A window in a habitable room should be located to face:

- An outdoor space clear to the sky or a light court with a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky, not including land on an abutting lot, or
- A verandah provided it is open for at least one third of its perimeter, or
- A carport provided it has two or more open sides and is open for at least one third of its perimeter.

53.20-6.18 Private open space

A dwelling (other than an apartment) should have private open space consisting of:

- An area of secluded private open space with a minimum area of 25 square metres, a minimum dimension of 3 metres and convenient access from a living room; or
- A balcony of 8 square metres with a minimum width of 1.6 metres and convenient access from a living room; or
- A roof-top area of 10 square metres with a minimum width of 2 metres and convenient access from a living room.


Secluded private open space may be located in the front setback if it is no more than 30% of the street frontage.

53.20-6.19 Solar access to open space

The private open space should be located on the north side of the dwelling if appropriate.

The southern boundary of secluded private open space should be set back from any wall on the north of the space at least (2 + 0.9h) metres, where 'h' is the height of the wall.

Diagram 6 Solar access to open space



53.20-6.20 Storage

Each dwelling should have convenient access to at least 6 cubic metres of externally accessible, secure storage space.

53.20-6.21 Front fence

A front fence within 3 metres of a street should not exceed a maximum height of:

- 2 metres for streets in a Transport Zone 2.
- 1.5 metres in other streets or where secluded private open space is proposed within the front setback, the front fence may reach a height of up to 1.8 metres for not more than 30% of the length of the boundary.

53.20-6.22 Common property

Developments should clearly delineate public, communal and private areas.

Common property, where provided, should be functional and capable of efficient management.

53.20-6.23 Site services

Development should provide space (including easements where required) for site services to be installed and maintained efficiently and economically.

Meters and utility services should be designed as an integrated component of the building or landscape.

Bin and recycling enclosures, mailboxes and other site facilities should be adequate in size, durable, waterproof and blend in with the development.

Mailboxes and other site facilities should be adequate in size, durable, weather-protected, located for convenient access and integrated into the overall design of the development.

53.20-7 Development standards for apartments

14/12/2023
VC253

53.20-7.1 Energy efficiency

Buildings should be:

- Oriented to make appropriate use of solar energy.
- Sited and designed to ensure that the energy efficiency of existing dwellings or small second dwellings on adjoining lots is not unreasonably reduced.
- Sited and designed to ensure that the performance of existing rooftop solar energy systems on dwellings or small second dwellings on adjoining lots in a General Residential Zone, Neighbourhood Residential Zone or Township Zone are not unreasonably reduced. The existing rooftop solar energy system must exist at the date the application is lodged.

Living areas and private open space should be located on the north side of the development, if practicable.

Developments should be designed so that solar access to north-facing windows is optimised.

Dwellings located in a climate zone identified in Table 4 should not exceed the maximum NatHERS annual cooling load.

Table 4 Cooling load

NatHERS climate zone	NatHERS maximum cooling load MJ/M^2 per annum
Climate zone 21 Melbourne	30
Climate zone 22 East Sale	22
Climate zone 27 Mildura	69
Climate zone 60 Tullamarine	22
Climate zone 62 Moorabbin	21
Climate zone 63 Warrnambool	21

NatHERS climate zone	NatHERS maximum cooling load MJ/M^2 per annum
Climate zone 64 Cape Otway	19
Climate zone 66 Ballarat	23

Note: Refer to NatHERS zone map, Nationwide House Energy Rating Scheme (Commonwealth Department of Environment and Energy).

53.20-7.2 Communal open space

A development of 10 or more dwellings should provide a minimum area of communal outdoor open space of 30 square metres.

If a development contains 13 or more dwellings, the development should also provide an additional minimum area of communal open space of 2.5 square metres per dwelling or 220 square metres, whichever is the lesser. This additional area may be indoors or outdoors and consist of multiple separate areas of communal open space.

Each area of communal open space should be:

- Accessible to all residents.
- A useable size, shape and dimension.
- Capable of efficient management.
- Located to:
  - Provide passive surveillance opportunities, where appropriate.
  - Provide outlook for as many dwellings as practicable.
  - Avoid overlooking into habitable rooms and private open space of new dwellings.
  - Minimise noise impacts to new and existing dwellings or small second dwellings.
- Any area of communal outdoor open space should be landscaped and include canopy cover and trees.

53.20-7.3 Solar access to communal outdoor open space

The communal outdoor open space should be located on the north side of a building, if appropriate.

At least 50 per cent or 125 square metres, whichever is the lesser, of the primary communal outdoor open space should receive a minimum of two hours of sunlight between 9am and 3pm on 21 June.

53.20-7.4 Landscaping

Development should retain existing trees and canopy cover.

Development should provide for the replacement of any significant trees that have been removed in the 12 months prior to the application being made.

Development should:

- Provide the canopy cover and deep soil areas specified in Table 5. Existing trees can be used to meet the canopy cover requirements of Table 5.
- Provide canopy cover through canopy trees that are:

  - Located in an area of deep soil specified in Table 6. Where deep soil cannot be provided trees should be provided in planters specified in Table 6.
  - Consistent with the canopy diameter and height at maturity specified in Table 7.
  - Located in communal outdoor open space or common areas or street frontages.
- Comprise smaller trees, shrubs and ground cover, including flowering native species.
- Include landscaping, such as climbing plants or smaller plants in planters, in the street frontage and in outdoor areas, including communal outdoor open space.
- Shade outdoor areas exposed to summer sun through landscaping or shade structures, and use paving and surface materials that lower surface temperatures and reduce heat absorption.
- Be supported by irrigation systems which utilise alternative water sources such as rainwater, stormwater and recycled water.
- Protect any predominant landscape features of the area.
- Take into account the soil type and drainage patterns of the site.
- Provide a safe, attractive and functional environment for residents.
- Specify landscape themes, vegetation (location and species), irrigation systems, paving and lighting.

Table 5 Canopy cover and deep soil requirements

Site area	Canopy cover	Deep soil
1000 square metres or less	5% of site area Include at least 1 Type A tree	5% of site area or 12 square metres whichever is the greater
1001 – 1500 square metres	50 square metres plus 20% of site area above 1,000 square metres Include at least 1 Type B tree	7.5% of site area
1501 – 2500 square metres	150 square metres plus 20% of site area above 1,500 square metres Include at least 2 Type B trees or 1 Type C tree	10% of site area
2501 square metres or more	350 square metres plus 20% of site area above 2,500 square metres Include at least 2 Type B trees or 1 Type C tree	15% of site area

Table 6 Soil requirements for trees

Tree type	Tree in deep soil	Tree in planter	
	Area of deep soil	Volume of planter soil	Depth of planter soil

Tree type	Tree in deep soil	Tree in planter	
A	12 square metres (min. plan dimension 2.5 metres)	12 cubic metres (min. plan dimension of 2.5 metres)	0.8 metre
B	49 square metres (min. plan dimension 4.5 metres)	28 cubic metres (min. plan dimension of 4.5 metres)	1 metre
C	121 square metres (min. plan dimension 6.5 metres)	64 cubic metres (min. plan dimension of 6.5 metres)	1.5 metres

Note: Where multiple trees share the same section of soil the total required amount of soil can be reduced by 5% for every additional tree, up to a maximum reduction of 25%

Table 7 Tree types

Tree type	Minimum canopy diameter at maturity	Minimum height at maturity
A	4 metres	6 metres
B	8 metres	8 metres
C	12 metres	12 metres

53.20-7.5 Integrated water and stormwater management

Buildings should be connected to a non-potable dual pipe reticulated water supply, where available from the water authority.

The stormwater management system should be:

- Designed to meet the current best practice performance objectives for stormwater quality as contained in the *Urban Stormwater – Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999).
- Designed to maximise infiltration of stormwater, water and drainage of residual flows into permeable surfaces, tree pits and treatment areas.

53.20-7.6 Building setback

The built form of the development should respect the existing urban context and respond to the features of the site.

Buildings should be set back from side and rear boundaries, and other buildings within the site to:

- Ensure adequate daylight into new habitable room windows.
- Avoid direct views into habitable room windows and private open space of new and existing dwellings or small second dwellings. Developments should avoid relying on screening to reduce views.
- Provide an outlook from dwellings that creates a reasonable visual connection to the external environment.

53.20-7.7 Noise impacts

Noise sources, such as mechanical plants should not be located near bedrooms of immediately adjacent existing dwellings or small second dwellings.

The layout of new dwellings and buildings should minimise noise transmission within the site.

Noise sensitive rooms (such as living areas and bedrooms) should be located to avoid noise impacts from mechanical plants, lifts, building services, non-residential uses, car parking, communal areas, and other dwellings or small second dwellings.

New dwellings should be designed and constructed to include acoustic attenuation measures to reduce noise levels from off-site noise sources.

Buildings within a noise influence area specified in Table 8 should be designed and constructed to achieve the following noise levels:

- Not greater than 35dB(A) for bedrooms, assessed as an LAeq,8h from 10pm to 6am.
- Not greater than 40dB(A) for living areas, assessed LAeq,16h from 6am to 10pm.

Buildings, or part of a building screened from a noise source by an existing solid structure, or the natural topography of the land, do not need to meet the specified noise level requirements.

Noise levels should be assessed in unfurnished rooms with a finished floor and the windows closed.

Table 8 Noise influence area

Noise Source	Noise influence area
Zone interface	
Industry	300 metres from the Industrial 1, 2 and 3 zone boundary
Roads	
Freeways, tollways and other roads carrying 40,000 Annual Average Daily Traffic Volume	300 metres from the nearest trafficable lane
Railways	
Railway servicing passengers in Victoria	80 metres from the centre of the nearest track
Railway servicing freight outside Metropolitan Melbourne	80 metres from the centre of the nearest track
Railway servicing freight in Metropolitan Melbourne	135 metres from the centre of the nearest track

Note: The noise influence area should be measured from the closest part of the building to the noise source.

53.20-7.8 Accessibility

At least 50 per cent of dwellings should have:

- A clear opening width of at least 850mm at the entrance to the dwelling and main bedroom.
- A clear path with a minimum width of 1.2 metres that connects the dwelling entrance to the main bedroom, an adaptable bathroom and the living area.

- A main bedroom with access to an adaptable bathroom.
- At least one adaptable bathroom that meets all of the requirements of either Design A or Design B specified in Table 9.

Table 9 Bathroom design

	Design option A	Design option B
Door opening	A clear 850mm wide door opening.	A clear 820mm wide door opening located opposite the shower
Door design	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards that is clear of the circulation area and has readily removable hinges.	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards and has readily removable hinges.
Circulation area	A clear circulation area that is: ▪ A minimum area of 1.2 metres by 1.2 metres. ▪ Located in front of the shower and the toilet. ▪ Clear of the toilet, basin and the door swing. The circulation area for the toilet and shower can overlap.	A clear circulation area that is: ▪ A minimum width of 1 metre. ▪ The full length of the bathroom and a minimum length of 2.7 metres. ▪ Clear of the toilet and basin. The circulation area can include a shower area.
Path to circulation area	A clear path with a minimum width of 900mm from the door opening to the circulation area.	Not applicable.
Shower	A hobless (step-free) shower.	A hobless (step-free) shower that has a removable shower screen and is located on the furthest wall from the door opening.
Toilet	A toilet located in the corner of the room.	A toilet located closest to the door opening and clear of the circulation area.

53.20-7.9 Building entry and circulation

Entries to dwellings and buildings should:

- Be visible and easily identifiable.
- Provide shelter, a sense of personal address and a transitional space around the entry.

The layout and design of buildings should:

- Clearly distinguish entrances to residential and non-residential areas.

- Provide windows to building entrances and lift areas.
- Provide visible, safe and attractive stairs from the entry level to encourage use by residents.
- Provide common areas and corridors that:
  - Include at least one source of natural light and natural ventilation.
  - Avoid obstruction from building services.
  - Maintain clear sight lines.

53.20-7.10 Private open space

A dwelling should have private open space consisting of at least one of the following:

- An area at ground level of 25 square metres, with a minimum dimension of 3 metres and convenient access from a living room.
- An area on a podium or other similar base of at least 15 square metres, with a minimum dimension of 3 metres at a podium or other similar base and convenient access from a living room.
- A balcony with at least the area and dimensions specified in Table 10 and convenient access from a living room.
- An area on a roof of 10 square metres with a minimum dimension of 2 metres and convenient access from a living room.

If a cooling or heating unit is located on a balcony, the minimum balcony area specified in Table 10 should be increased by at least 1.5 square metres.

If the finished floor level of a dwelling is 40 metres or more above ground level, the requirements of Table 10 do not apply if at least the area specified in Table 11 is provided as living area or bedroom area in addition to the minimum area specified in Table 13 or Table 14.

Table 10 Balcony size

Dwelling type	Minimum area	Minimum dimension
Studio or 1 bedroom dwelling	8 square metres	1.8 metres
2 bedroom dwelling	8 square metres	2 metres
3 or more bedroom dwelling	12 square metres	2.4 metres

Table 11 Additional living area or bedroom area

Dwelling type	Additional area
Studio or 1 bedroom dwelling	8 square metres
2 bedroom dwelling	8 square metres
3 or more bedroom dwelling	12 square metres

53.20-7.11 Storage

Each dwelling should have convenient access to usable and secure storage space.

The total minimum storage space (including kitchen, bathroom and bedroom storage) should meet the requirements specified in Table 9.

Table 12 Storage

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
Studio	8 cubic metres	5 cubic metres
1 bedroom dwelling	10 cubic metres	6 cubic metres
2 bedroom dwelling	14 cubic metres	9 cubic metres
3 or more bedroom dwelling	18 cubic metres	12 cubic metres

53.20-7.12 Waste and recycling

Developments should include dedicated areas for:

- Waste and recycling enclosures which are:
  - Adequate in size, durable, waterproof and blend in with the development.
  - Adequately ventilated.
  - Located and designed for convenient access by residents and made easily accessible to people with limited mobility.
- Adequate facilities for bin washing. These areas should be adequately ventilated.
- Collection, separation and storage of waste and recyclables, including where appropriate opportunities for on-site management of food waste through composting or other waste recovery as appropriate.
- Collection, storage and reuse of garden waste, including opportunities for on-site treatment, where appropriate, or off-site removal for reprocessing.
- Adequate circulation to allow waste and recycling collection vehicles to enter and leave the site without reversing.
- Adequate internal storage space within each dwelling to enable the separation of waste, recyclables and food waste where appropriate.

Waste and recycling management facilities should be designed and managed in accordance with a Waste Management Plan approved by the responsible authority and:

- Be designed to meet the better practice design options specified in *Waste Management and Recycling in Multi-unit Developments* (Sustainability Victoria, 2019).
- Protect public health and amenity of residents and adjoining premises from the impacts of odour, noise and hazards associated with waste collection vehicle movements.

53.20-7.13 Functional layout

Bedrooms should:

- Meet the minimum internal room dimensions specified in Table 13.
- Provide an area in addition to the minimum internal room dimensions to accommodate a wardrobe.

Living areas (excluding dining and kitchen areas) should meet the minimum internal room dimension and area specified in Table 14.

Table 13 Bedroom dimensions

Bedroom type	Minimum width	Minimum depth	Minimum area
Main bedroom	3 metres	3.4 metres	10.2 sqm
All other bedrooms	3 metres	3 metres	9 sqm

Table 14 Living area dimensions

Dwelling type	Minimum width	Minimum area
Studio and 1 bedroom dwelling	3.3 metres	10 sqm
2 or more bedroom dwelling	3.6 metres	12 sqm

53.20-7.14 Room depth

Single aspect habitable rooms should not exceed a room depth of 2.5 times the ceiling height.

The depth of a single aspect, open plan, habitable room may be increased to 9 metres if all the following requirements are met:

- The room combines the living area, dining area and kitchen.
- The kitchen is located furthest from the window.
- The ceiling height is at least 2.7 metres measured from finished floor level to finished ceiling level. This excludes where services are provided above the kitchen.

The room depth should be measured from the external surface of the habitable room window to the rear wall of the room.

53.20-7.15 Windows

Habitable rooms should have a window in an external wall of the building.

A window may provide daylight to a bedroom from a smaller secondary area within the bedroom where the window is clear to the sky. The secondary area should be:

- A minimum width of 1.2 metres.
- A maximum depth of 1.5 times the width, measured from the external surface of the window.

53.20-7.16 Natural ventilation

The design and layout of dwellings should maximise openable windows, doors or other ventilation devices in external walls of the building, where appropriate.

At least 40 per cent of dwellings should provide effective cross ventilation that has:

- A maximum breeze path through the dwelling of 18 metres.
- A minimum breeze path through the dwelling of 5 metres.
- Ventilation openings with approximately the same area.

The breeze path is measured between the ventilation openings on different orientations of the dwelling.

53.20-7.17 Integration with the street

Development should be oriented to front existing and proposed streets.

Along street frontages, development should:

- Incorporate pedestrian entries, windows, balconies or other active spaces.
- Limit blank walls.
- Limit high front fencing, unless consistent with the existing urban context.
- Provide low and visually permeable front fences, where proposed.
- Conceal car parking and internal waste collection areas from the street.

Development next to existing public open space should be designed to complement the open space and facilitate passive surveillance.

53.20-7.18 External walls and materials

External walls should be finished with materials that:

- Do not easily deteriorate or stain.
- Weather well over time.
- Are resilient to the wear and tear from their intended use.

External wall design should facilitate safe and convenient access for maintenance.

53.20-7.19 Wind impacts

Development should:

- not cause unsafe wind conditions specified in Table 15 in public land, publicly accessible areas on private land, private open space and communal open space; and
- achieve comfortable wind conditions specified in Table 15 in public land and publicly accessible areas on private land

within a distance of half the greatest length of the building, or half the total height of the building measured outwards on the horizontal plane from the ground floor building façade, whichever is greater.

Trees and landscaping should not be used to mitigate wind impacts. This does not apply to sitting areas, where trees and landscaping may be used to supplement fixed wind mitigation elements.

Wind mitigation elements, such as awnings and screens should be located within the site boundary, unless consistent with the existing urban context or preferred future development of the area.

Table 15: Wind conditions

Unsafe	Comfortable
Annual maximum 3 second gust wind speed exceeding 20 metres per second with a probability of exceedance of 0.1% considering at least 16 wind directions.	Hourly mean wind speed or gust equivalent mean speed (3 second gust wind speed divided by 1.85), from all wind directions combined with probability of exceedance less than 20% of the time, equal to or less than:

Unsafe	Comfortable
	▪ 3 metres per second for sitting areas. ▪ 4 metres per second for standing areas. ▪ 5 metres per second for walking areas.

53.20-9 Transitional provision

20/03/2023
VC229

The development standards for apartments at clause 53.20-6 and clause 53.20-7 introduced by Amendment VC207, do not apply to an application to construct or extend a dwelling, or to construct or extend a front fence if:

- Funded wholly or partly, under Victoria's Big Housing Build program;
- The application is made by or on behalf of the Chief Executive Officer, Homes Victoria; and
- The written confirmation from Homes Victoria or the Chief Executive Officer, Homes Victoria that the application is funded, either wholly or partly, under Victoria's Big Housing Build program has been signed before 30 June 2022.

53.20-10 Decision guidelines

14/12/2023
VC253

Before deciding on an application, the responsible authority must consider, as appropriate:

- How the proposed development responds to the site and context description.
- Where a development standard of this clause is not met, the impact on the amenity of the adjoining dwellings or small second dwellings of varying the standard.
- The effect of overshadowing on an appropriately located existing rooftop solar energy system on an adjoining lot.

53.21 STATE TRANSPORT PROJECTS

17/02/2022
VC200

Purpose

To facilitate the delivery of transport projects carried out by or on behalf of the State of Victoria.

53.21-1 Application

20/03/2023
VC229

This clause applies to an application under any provision of this planning scheme, other than a VicSmart application or an application to subdivide land, made by or on behalf of the Head, Transport for Victoria or the Secretary to the Department of Transport and Planning.

53.21-2 Exemption from review

17/02/2022
VC200

An application to which clause 53.21 applies is exempt from the decision requirements of section 64(1), (2), and (3), and the review rights of section 82(1) of the Act.

53.22 SIGNIFICANT ECONOMIC DEVELOPMENT

20/09/2023
VC242

Purpose

To prioritise and facilitate the planning, assessment and delivery of projects that will make a significant contribution to Victoria's economy and provide substantial public benefit, including jobs for Victorians.

To provide for the efficient and effective use of land and facilitate use and development with high quality urban design, architecture and landscape architecture.

53.22-1 Application

04/07/2025
VC258

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

This clause applies to an application under any provision of this planning scheme if all the following are met:

- The applicant submits written confirmation that the application is an application to which this clause applies.
- The conditions corresponding to a category in Table 1 are met.

This clause does not apply to an application to subdivide land, other than an application to subdivide land that includes either:

- A renewable energy facility; or
- A utility installation used to:
  - Transmit or distribute electricity; or
  - Store electricity if the installed capacity is 1 megawatt or greater.

In this clause, ***Invest Victoria*** means the body called 'Invest Victoria', established as an Administrative Office in relation to the Department of Jobs, Skills, Industry and Regions under an Order made under section 11 of the *Public Administration Act 2004*.

Table 1

Category	Condition
Category 1	The application must include a use specified in Table 2 and the conditions corresponding to that use must be met. If the application includes more than one use in Table 2, only one use must meet the corresponding conditions, except where the application includes an energy generation facility or transport terminal, in which case all conditions corresponding to those uses must be met. The application must not include a use that requires a permit if that use is not specified in Table 2. Information demonstrating the likely feasibility of the proposed development is provided to the satisfaction of the Minister for Planning. This must include written advice from the Chief Executive Officer or delegate, Invest Victoria. This does not apply to an application for the use or development of land for an energy

Category	Condition
	generation facility, renewable energy facility, transport terminal, utility installation or warehouse (fuel depot).
Category 2	The application must include a use specified in Table 2. The conditions corresponding to that use do not need to be met. The application may also include a use that is not specified in Table 2. The proposed use or development must be: ▪ carried out by or on behalf of, or jointly or in partnership with, the State of Victoria or a public authority; or ▪ funded, or partly funded, by the State of Victoria, the Commonwealth or a public authority; or ▪ carried out on Crown land.
Category 3	The application must include a use specified in Table 2. The conditions corresponding to that use do not need to be met. The application may also include a use that is not specified in Table 2. The Minister for Planning has advised in writing that they are satisfied the proposed use or development of land is of significance having regard to the: ▪ Purpose of clause 53.22. ▪ Estimated cost of development. ▪ Extent to which the development supports or implements planning policy. Information demonstrating the likely feasibility of the proposed development is provided to the satisfaction of the Minister for Planning. This must include written advice from the Chief Executive Officer or delegate, Invest Victoria.

Table 2

Use	Condition
Camping and caravan park **Group accommodation** **Food and drink premises (other than bar, convenience restaurant and take away food premises)** **Leisure and recreation** **Place of assembly** **Recreational boat facility** **Residential hotel**	The estimated cost of the proposed development as specified in a report prepared by a suitably qualified quantity surveyor must be one of the following to the satisfaction of the Minister for Planning: ▪ At least $10 million if any part of the land is in metropolitan Melbourne. ▪ At least $5 million if the land is not in metropolitan Melbourne.

Use	Condition
Winery	
Agriculture **Data centre** **Industry** **Research centre** **Saleyards**	The estimated cost of the proposed development as specified in a report prepared by a suitably qualified quantity surveyor must be one of the following to the satisfaction of the Minister for Planning: ▪ At least $20 million if any part of the land is in metropolitan Melbourne. ▪ At least $10 million if the land is not in metropolitan Melbourne.
Hospital **Medical centre** **Warehouse**	The estimated cost of the proposed development as specified in a report prepared by a suitably qualified quantity surveyor must be one of the following to the satisfaction of the Minister for Planning: ▪ At least $30 million if any part of the land is in metropolitan Melbourne; or ▪ At least $10 million if the land is not in metropolitan Melbourne.
Tertiary institution	The estimated cost of the proposed development as specified in a report prepared by a suitably qualified quantity surveyor must be one of the following to the satisfaction of the Minister for Planning: ▪ At least $30 million if any part of the land is in metropolitan Melbourne; or ▪ At least $20 million if the land is not in metropolitan Melbourne.
Transport terminal	Must only be used to transport gas.
Retail premises (other than food and drink premises)	The estimated cost of the proposed development as specified in a report prepared by a suitably qualified quantity surveyor must be one of the following to the satisfaction of the Minister for Planning: ▪ At least $100 million if any part of the land is in metropolitan Melbourne; or ▪ At least $20 million if the land is not in metropolitan Melbourne.
Earth and energy resources industry (other than extractive industry, mining, mineral exploration, petroleum exploration, petroleum production and stone exploration)	The estimated cost of the proposed development as specified in a report prepared by a suitably qualified quantity surveyor must be at least $30 million to the satisfaction of the Minister for Planning.
Extractive industry	The estimated value of the resource to be extracted must be at least $30 million to the satisfaction of the Minister for Planning.

Use	Condition
Mining and mineral exploration	The estimated cost of the proposed development as specified in a report prepared by a suitably qualified quantity surveyor must be at least $10 million to the satisfaction of the Minister for Planning.
Office	Must meet one of the following to the satisfaction of the Minister for Planning: ▪ The combined gross floor area of all buildings (excluding basement and above ground car parking facilities) associated with the proposed use or development must be at least 10,000 square metres if any part of the land is in metropolitan Melbourne; or ▪ The combined gross floor area of all buildings (excluding basement and above ground car parking facilities) associated with the proposed use or development must be at least 5,000 square metres if the land is not in metropolitan Melbourne.
Renewable energy facility	An installed capacity of 1 megawatt or greater must be proposed.
Energy generation facility	An installed capacity of 1 megawatt or greater must be proposed. Must only be a gas-powered energy generation facility.
Utility installation (other than data centre)	A utility installation used to: ▪ Transmit or distribute electricity; or ▪ Store electricity if the installed capacity is 1 megawatt or greater; or ▪ Transmit or distribute gas. must be proposed.

53.22-2 Planning scheme requirements

04/07/2025
VC258

The responsible authority may waive or vary any of the following:

- Any building height or setback requirement.
- Any application requirement in this planning scheme if in the opinion of the responsible authority the requirement is not relevant to the assessment of the application.

This does not apply to the following:

- A decision that would be inconsistent with an approved Statement of Planning Policy for a declared area; and
- A requirement in clauses 45.07, 45.08 or 51.03, or in any schedule to those clauses.

53.22-3 Application requirements

04/07/2025
VC258

An application must be accompanied by the following information, as appropriate:

- A report or other documents demonstrating the likely feasibility of the development.
- A report prepared by a suitably qualified quantity surveyor which specifies the estimated cost of the development.
- For extractive industry, a report prepared by a suitably qualified person specifying the estimated value of the resource to be extracted.

53.22-4 Exemption from review

20/09/2023
VC242

An application under any provision of this planning scheme is exempt from the decision requirements of sections 64(1), (2) and (3), and the review rights of sections 82(1) of the Act.

53.22-5 Decision guidelines

04/07/2025
VC258

Before deciding on an application the responsible authority must consider, as appropriate:

- The purpose of the clause.
- The views of the Office of the Victorian Government Architect.

53.22-6 Transitional provision

20/09/2023
VC242

Clause 53.22 does not apply to:

- An application for a permit lodged before the approval date of Amendment VC242.
- An application for an amendment of a permit under section 72 of the Act if the original permit application was lodged before the approval date of Amendment VC242.

53.23 SIGNIFICANT RESIDENTIAL DEVELOPMENT WITH AFFORDABLE HOUSING

04/07/2025
VC258

Purpose

To facilitate residential development that contributes to the provision of affordable housing to meet existing and future needs.

To facilitate the redevelopment and renewal of public housing stock to meet existing and future needs.

To facilitate residential development carried out by the State of Victoria or jointly or in partnership with the private sector, including via innovative funding, investment and partnership approaches.

To facilitate residential development with high quality urban design, architecture and landscape architecture.

To provide opportunities for non-residential use and development in association with residential development.

53.23-1 Application

04/07/2025
VC258

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

This clause applies to an application under any provision of this planning scheme if all of the following are met:

- The applicant submits written confirmation that the application is an application to which this clause applies.
- The application includes the proposed use or development of land for accommodation (other than camping and caravan park, group accommodation, residential hotel and small second dwelling).
- The conditions corresponding to a category in Table 1 are met.

This clause does not apply to an application to subdivide land.

In this clause:

- ***Chief Executive Officer, Homes Victoria*** means 'Chief Executive Officer, Homes Victoria' as defined in the *Housing Act 1983* and the body corporate established under the *Housing Act 1983*.
- ***Invest Victoria*** means the body called 'Invest Victoria', established as an Administrative Office in relation to the Department of Jobs, Skills, Industry and Regions under an Order made under section 11 of the *Public Administration Act 2004*.

Table 1

Category	Condition
Category 1	The estimated cost of the proposed development of land for accommodation (other than camping and caravan park, group accommodation, residential hotel and small second dwelling) as specified in a report prepared by a suitably qualified quantity surveyor must be one of the following to the satisfaction of the Minister for Planning: ▪ At least $50 million if any part of the land is in metropolitan Melbourne. ▪ At least $15 million if the land is not in metropolitan Melbourne.

Category	Condition
	The application includes an affordable housing report required under clause 53.23-3 that demonstrates how the affordable housing contribution specified in clause 53.23-4 (being at least 10 per cent of the total number of dwellings in the proposed development provided as affordable housing or an alternative contribution towards the provision of affordable housing) is intended to be provided if a permit is granted. Information demonstrating the likely feasibility of the proposed development is provided to the satisfaction of the Minister for Planning. This must include written advice from the Chief Executive Officer or delegate, Invest Victoria.
Category 2	The proposed use or development of land for accommodation (other than camping and caravan park, group accommodation, residential hotel and small second dwelling) will be: ▪ carried out by or on behalf of, or jointly or in partnership with, the State of Victoria or a public authority; or ▪ funded, or partly funded, by the State of Victoria, the Commonwealth or a public authority; or ▪ carried out on Crown land. If the application is made by or on behalf of the Chief Executive Officer, Homes Victoria, the proposed development includes at least 10 dwellings.
Category 3	The Minister for Planning has advised in writing that they are satisfied the proposed use or development of land for accommodation (other than camping and caravan park, group accommodation, residential hotel and small second dwelling) is of significance having regard to: ▪ The purpose of clause 53.23. ▪ Whether a contribution towards affordable housing is proposed. ▪ The estimated cost of the proposed development. ▪ The location of the proposed development and whether it has convenient access to jobs, services, infrastructure and community facilities. ▪ Whether the design, liveability and sustainability of the proposed development is exemplary.

Category	Condition
	Information demonstrating the likely feasibility of the proposed development is provided to the satisfaction of the Minister for Planning. This must include written advice from the Chief Executive Officer or delegate, Invest Victoria.

53.23-2 Planning scheme requirements

04/07/2025
VC258

The responsible authority may waive or vary any of the following:

- A minimum garden area requirement.
- Any building height or setback requirement.
- A condition opposite a use in Section 2 in a zone or a schedule to a zone.
- Any application requirement in this planning scheme if in the opinion of the responsible authority the requirement is not relevant to the assessment of the application.

This does not apply to the following:

- A decision that would be inconsistent with an approved Statement of Planning Policy for a declared area; and
- A requirement in clauses 45.07, 45.08 or 51.03, or in any schedule to those clauses.

Clauses 45.09 and 52.06 of this planning scheme do not apply to a use or development proposed in an application where:

- the proposed development will be funded, or partly funded, by the State of Victoria or the Commonwealth; or
- the application is made by or on behalf of the Chief Executive Officer, Homes Victoria.

The provisions of clauses 54.05-2, 55.03-5, 57.03-5 and 58.05-3 of this planning scheme do not apply to:

- an application for a proposed development funded, or partly funded, by the State of Victoria or the Commonwealth; or
- an application made by or on behalf of the Chief Executive Officer, Homes Victoria.

An application for a proposed development that will be funded, or partly funded, by the State of Victoria or the Commonwealth, or an application made by or on behalf of the Chief Executive Officer, Homes Victoria should meet the following standards:

- A minimum 0.6 car parking spaces should be provided to each dwelling. Car parking spaces may be covered or uncovered. If in calculating the number of car parking spaces the result is not a whole number, the required number of car parking spaces is to be rounded down to the nearest whole number greater than 1. Car parking for other land uses in the proposed development must be to the satisfaction of the responsible authority.
- A dwelling (other than an apartment) should have private open space consisting of:
  - an area of secluded private open space with a minimum area of 25 square metres, a minimum dimension of 3 metres and convenient access from a living room; or

- a balcony of 8 square metres with a minimum width of 1.6 metres and convenient access from a living room; or
- a roof-top area of 10 square metres with a minimum width of 2 metres and convenient access from a living room.

- Secluded private open space may be located in the front setback if it is no more than 30 per cent of the street frontage.

53.23-3 Application requirements

04/07/2025
VC258

An application must be accompanied by the following information, as appropriate:

- A report prepared by a suitably qualified quantity surveyor which specifies the estimated cost of the proposed development of land for accommodation to the satisfaction of the Minister for Planning.
- A report (affordable housing report) that outlines how a proposed contribution to the provision of affordable housing is intended to be provided should a permit be granted, including the following:
  - The nature of the proposed contribution.
  - The methodology for the delivery of the proposed contribution.
  - The proposed monetary value of the contribution (as a percentage of the estimated cost of the proposed development of land for accommodation).
- If the application includes a non-residential use or development, information about the purpose of the use and the types of activities proposed to be carried out.
- An application for a use or development that will be funded, or partly funded, by Homes Victoria must be accompanied by a letter from the Chief Executive Officer or delegate, Homes Victoria, consenting generally or conditionally to the application being made.
- An application for a use or development that will be funded, or partly funded, by the Commonwealth, must be accompanied by a letter from the Chief Executive Officer, Housing Australia confirming the funding.

53.23-4 Permit condition requirement

04/07/2025
VC258

The responsible authority must include the following condition in deciding to grant a permit:

"Before the use or development of the land begins, excluding demolition, excavation, piling, site preparation works, and works to remediate contaminated land, the owner of the land must enter into an agreement with the responsible authority under section 173 of the Act, in a form to the satisfaction of the responsible authority, that provides for a contribution towards affordable housing (affordable housing contribution) by way of either of the following options:

- *At least 10 per cent of the total number of dwellings in the development must be provided as affordable housing for sale or lease to a registered housing agency or to Homes Victoria. The details of when and how the affordable housing will be delivered and the total value of the affordable housing contribution must be set out in the agreement. The affordable housing dwellings provided should be representative of the approved dwelling mix to the satisfaction of the responsible authority.*
- *An alternative contribution towards the provision of affordable housing must be provided to the satisfaction of the responsible authority. The details of when and how the alternative contribution is to be made and the total value of the affordable housing contribution must be set out in the agreement to the satisfaction of the responsible authority.*

The land owner must pay the responsible authority's reasonable costs of the preparation, execution, registration and ending of the section 173 agreement (where applicable)."

The above requirement to include a condition does not apply if any of the following apply:

- The responsible authority is satisfied that an agreement exists with the State of Victoria or a public authority for the provision of at least 10 per cent of the total number of dwellings in the development as affordable housing and:
  - the use or development will be carried out by or on behalf of, or jointly or in partnership with, the State of Victoria or a public authority; or
  - the development will be funded, or partly funded, by the State of Victoria, the Commonwealth or a public authority; or
  - the development will be carried out on Crown land.
- The conditions corresponding to Category 3 in Table 1 are met and a contribution towards affordable housing is not proposed.

53.23-5 Exemption from review

20/09/2023
VC242

An application under any provision of this planning scheme is exempt from the decision requirements of sections 64(1), (2) and (3), and the review rights of sections 82(1) of the Act.

53.23-6 Decision guidelines

04/07/2025
VC258

Before deciding on an application the responsible authority must consider, as appropriate:

- The purpose of the clause.
- The views of the Office of the Victorian Government Architect.

53.23-7 Transitional provision

20/09/2023
VC242

Clause 53.23 does not apply to:

- An application for a permit lodged before the approval date of Amendment VC242.
- An application for an amendment of a permit under section 72 of the Act if the original permit application was lodged before the approval date of Amendment VC242.

53.24 FUTURE HOMES

22/09/2023
VC243

Purpose

To facilitate apartment developments that incorporate exemplar designs approved under the Future Homes project.

To facilitate apartment developments that increase the density and diversity of housing to respond to Victoria's population growth.

To facilitate apartment developments that are exemplary in their design, liveability and sustainability.

53.24-1 Application

28/02/2025
VC274

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

This clause applies to an application under clause 32.08-7 of the General Residential Zone or clause 32.10-5 of the Housing Choice and Transport Zone to construct two or more dwellings on a lot, or to construct a front fence in association with the construction of two or more dwellings on a lot, if all of the following requirements are met:

- The development must be an apartment development.
- The design of the apartment development must use a licenced exemplar design approved under the Future Homes project overseen by the Department of Transport and Planning.
- Any part of the land:
  - Must be within 800 metres of a passenger railway station; or
  - Must be within 800 metres of a metropolitan, major or neighbourhood activity centre in Metropolitan Melbourne; or
  - Must be within 800 metres of an activity centre outside Metropolitan Melbourne; and
  - Must not be within a Heritage Overlay or Neighbourhood Character Overlay.

For the purposes of this clause, the distance from an activity centre must be measured from:

- the boundary of the activity centre specified, shown, described or otherwise indicated in this planning scheme; or
- if the boundary of the activity centre is not specified, shown, described or otherwise indicated in this planning scheme, the boundary of any Activity Centre Zone, commercial zone, Mixed Use Zone or Precinct Zone.

For the purposes of this clause, the distance from a passenger railway station must be measured from the closest point to a station platform.

53.24-2 Meaning of terms

26/09/2023
VC246

An activity centre outside Metropolitan Melbourne means a:

- Central Activity District
- Central Business District
- City Centre
- Major Activity Centre
- Primary Activity Centre
- Principal Activity Centre
- Principal Centre

- Regional Activity Centre
- Regional Centre
- Regional Retail Centre

53.24-3 Pre-application referral requirements

25/02/2025
VC257

If an application under clause 32.08-7 or 32.10-5 is required to be referred in accordance with section 55 of the Act to a referral authority specified in clause 66, the following requirements must be met:

- The development for which the application is made must have been considered by the referral authority within the past 3 months of the application being made to the responsible authority.
- The referral authority must have stated in writing that it does not object to the granting of the permit for the development.

If the proposed development requires a permit under a provision of this planning scheme other than clause 32.08-7 of the General Residential Zone or clause 32.10-5 of the Housing Choice and Transport Zone and an application for that permit is required to be referred in accordance with section 55 of the Act to a referral authority specified in clause 66, the following requirements must be met:

- The development for which the application is made must have been considered by the referral authority within the past 3 months of the application being made to the responsible authority.
- The referral authority must have stated in writing that it does not object to the granting of the permit for the development.

53.24-4 Application requirements

03/12/2024
VC269

An application must be accompanied by:

- A neighbourhood and site description.
- A design response.
- A landscape plan.

Neighbourhood and site description

The neighbourhood and site description may use a site plan, photographs or other techniques and must include:

- Site shape, size, orientation, levels and easements.
- The location of existing buildings on the site and on surrounding properties, including the location and height of walls built to the boundary of the site.
- The use of surrounding buildings.
- The location of private open space and habitable room windows of surrounding properties that have an outlook to the site.
- Solar access to the site and adjoining properties.
- Views to and from the site.
- Street frontage features such as poles, street trees and kerb crossovers.
- The pattern of development of the neighbourhood, including the average street setback for the development site (approximately 150 metres either side).
- The location of local shops, public transport services and public open spaces within walking distance.

- Movement systems through and around the site.
- Any other notable features or characteristics of the site and area.

Design response

The design response must address the development standards of clause 53.24 and the principles, objectives, requirements and targets of the *Building future homes adaptation guide* (Department of Transport and Planning, 2023).

Landscape plan

The landscape plan must include:

- The location of significant trees existing on and adjacent to the site and any significant trees removed from the site 12 months prior to the application being made.
- The location and details of proposed vegetation, including canopy trees on the site.
- A planting schedule that demonstrates compliance with the deep soil and canopy cover requirements.
- Details of the soil type, drainage patterns and irrigation system of the site.

53.24-5 Exemption from planning scheme requirements

31/03/2025
VC267

The requirements of clauses 45.09, 52.06 and 52.34 of the planning scheme do not apply to a development under this clause.

An application is exempt from any application requirement in the General Residential Zone or any application requirements specified in a schedule to the General Residential Zone or the Housing Choice and Transport Zone.

An application is exempt from and is not required to meet the requirements of clauses 55, 57 and 58.

Matters to be considered

In deciding an application, the responsible authority must not consider, and is exempt from considering:

- The Municipal Planning Strategy and Planning Policy Framework.
- The purpose of the General Residential Zone or the Housing Choice and Transport Zone.
- Any decision guideline in the General Residential Zone, or a schedule to the General Residential Zone or the Housing Choice and Transport Zone.
- The decision guidelines in clause 65.

53.24-6 Exemption from review

25/02/2025
VC257

An application under clause 32.08-7 or 32.10-5 is exempt from the decision requirements of section 64(1), (2) and (3) and the review rights of section 82(1) of the Act.

53.24-7 Development standards

03/12/2024
VC269

A development must meet all of the following development standards.

53.24-7.1 Car parking

Car parking spaces must be provided at:

- a rate of at least 0.6 spaces per dwelling; rounded down to the closest whole number or
- if the land is in a Parking Overlay and the overlay specifies a lower car parking rate for a dwelling, the applicable rate in the overlay.

Mechanical parking may be used to meet the car parking requirement provided the dimensions of the mechanical parking system meets the standards for a B99 vehicle in Australian Standard AS/NZS 2890.1:2004, Parking facilities - Off-street car parking (Standards Australia, 2004).

53.24-7.2 Bicycle parking

Bicycle parking spaces must be provided at a rate of:

- at least 1 space per dwelling for residents.
- at least 1 space per 5 dwellings for visitors.

At least 20 percent of bicycle parking spaces for residents must be provided as horizontal spaces.

All visitor bicycle parking spaces must be provided as horizontal spaces and be located to provide convenient access from surrounding bicycle routes and main building entrances.

53.24-7.3 Communal open space

A development of 10 or more dwellings must provide a minimum area of communal outdoor open space of 30 square metres.

If a development contains 13 or more dwellings, the development must also provide an additional minimum area of communal open space of 2.5 square metres per dwelling or 220 square metres, whichever is the lesser. This additional area may be indoors or outdoors and consist of multiple separate areas of communal open space.

Each area of communal open space must be:

- Accessible to all residents.
- Of a useable size, shape and dimension.
- Capable of efficient management.
- Located to:
  - Provide passive surveillance, where appropriate.
  - Provide outlook for as many dwellings as practicable.
  - Limit overlooking into habitable rooms and private open space of new dwellings.
  - Minimise noise impacts on new and existing dwellings.

Any area of communal outdoor open space must be landscaped and where possible include canopy cover and trees.

At least 50 per cent or 125 square metres, whichever is the lesser, of the primary area of communal outdoor open space must receive a minimum of two hours of sunlight between 9am and 3pm on 21 June.

53.24-7.4 Environmentally sustainable design

A development must achieve:

- At least a 7.5 star NatHERS average (area-weighted across all dwellings).
- At least a 6.5 star NatHERS for an individual dwelling.

- An excellence, or equivalent score, in environmentally sustainable design as outlined in the Building Future Homes Adaptation Guide.
- 100 percent Stormwater Treatment Objective-Relative Measure (STORM) rating for the site.

53.24-7.5 Accessibility

At least 50 per cent of dwellings must be designed to meet all of the following accessibility design standards.

Dwelling access

- A slip resistant continuous step-free pathway must be provided from the street and car parking area to the dwelling entry door.
- The pathway must have a minimum clear width of 1.2 metres, no steps, a maximum gradient of 1:14 and a cross fall not steeper than 1:40.
- Where ramps with landings are required as part of the pathway, landings must be no less than 1.2 metres in length, and gate and door swings must not overlap this minimum landing requirements.
- Landings must be provided at the start and end of ramps.
- Where there is a change in height of 190 millimetres or less at an apartment entrance, a step ramp with a gradient not steeper than 1:10 may be used.
- Car parking spaces must provide:
  - A level surface with a gradient not exceeding 1:40 in any direction.
  - A vertical clearance over the parking space of at least 2.5 metres free of obstructions (the 2.5 m clearance is not required where mechanical parking is used).

Dwelling entrance

- The entrance to the dwelling must have:
  - A clear opening width of at least 850 millimetres.
  - A level, and step-free transition and threshold.
  - A level landing on the arrival side of the entrance door of at least 1.35 metres x 1.35 metres.

Internal doors and passageways

- Doorways to rooms must have a clear opening width of at least 850 millimetres.
- Doorways to rooms must have a level, step-free transition and threshold.
- The dwelling must have clear passageways and corridors with a minimum width of 1.2 metres.

Toilets and showers

- At least one toilet must be located on the entry level of the dwelling and must have:
  - A secure fixing surface to enable future installation of grab rails.
  - A minimum 1.2 metre x 1.2 metre circulation area located in front of the toilet that is clear of the basin and the door swing.
- The toilet must be located in:
  - the corner of the room if it is in a bathroom with the centreline of the pan 450 to 460 millimetres from the adjacent wall; or
  - a room with a minimum width of 1.2 metres if it is in a room separate to the bathroom.

- A least one bathroom must be located on the entry level of the dwelling and must have a hobless, step-free shower that:
  - Has a removable shower screen.
  - Has a minimum clear internal dimensions of 900 millimetres x 900 millimetres.
  - Has a minimum 1.2 metres x 1.2 metres clear circulation area located in front of the shower.
  - Is located in the corner of the room to enable future installation of grab rails.
- A secure fixing surface must be provided at all toilets, showers and baths to enable future installation of grab rails. This requirement may be met by either:
  - walls that are constructed of solid masonry or concrete; or
  - providing additional wall framing or structure lining behind the finished wall surface.

Kitchen laundry

- The kitchen and laundry must have a minimum 1.2 metres clear circulation area in front of appliances and benches.
- Floor finishes must extend under appliances and cabinets to allow for future modifications.

53.24-7.6 Building entry and circulation

Common corridors and passageways providing access to a dwelling entry must have a minimum width of 1.2 metres.

Entries to dwellings and buildings must:

- Be visible and easily identifiable.
- Provide shelter, a sense of personal address and a transitional space around the entry.

The layout and design of buildings must:

- Clearly distinguish entrances to residential and non-residential areas.
- Provide windows to building entrances and lift areas.
- Provide visible, safe and attractive stairs from the entry level to encourage use by residents.
- Provide common areas and corridors that:
- Include at least one source of natural light and natural ventilation.
  - Avoid obstruction from building services.
  - Maintain clear sight lines.

53.24-7.7 Storage

Each dwelling must have convenient access to usable and secure storage space.

The total minimum storage space (including kitchen, bathroom and bedroom storage) must meet the requirements specified in Table 1.

Table 1: Storage

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
Studio	8 cubic metres	5 cubic metres

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
1 bedroom dwelling	10 cubic metres	6 cubic metres
2 bedroom dwelling	14 cubic metres	9 cubic metres
3 or more bedroom dwelling	18 cubic metres	12 cubic metres

53.24-7.8 Functional layout

Bedrooms must:

- Meet the minimum internal room dimensions specified in Table 2.
- Provide an area in addition to the minimum internal room dimensions to accommodate a wardrobe.

Table 2: Bedroom dimensions

Bedroom type	Minimum width	Minimum depth
Main bedroom	3 metres	3.4 metres
All other bedrooms	3 metres	3 metres

Living areas (excluding dining and kitchen areas) must meet the minimum internal room dimensions specified in Table 3.

Table 3: Living area dimension and area

Dwelling type	Minimum width	Minimum area
Studio or 1 bedroom dwelling	3.3 metres	10 square metres
2 or more bedroom dwelling	3.6 metres	12 square metres

53.24-7.9 Room depth

Single aspect habitable rooms must not exceed a room depth of 2.5 times the ceiling height.

The depth of a single aspect, open plan, habitable room may be increased to 9 metres if all the following requirements are met:

- The room combines the living area, dining area and kitchen.
- The kitchen is located furthest from the window.
- The ceiling height is at least 2.7 metres measured from finished floor level to finished ceiling level. This excludes where services are provided above the kitchen.

The room depth must be measured from the external surface of the habitable room window to the rear wall of the room.

53.24-7.10 Windows

Habitable rooms must have a window in an external wall of the building.

A window may provide daylight to a bedroom from a smaller secondary area within the bedroom where the window is clear to the sky.

The secondary area must be:

- A minimum width of 1.2 metres.
- A maximum depth of 1.5 times the width, measured from the external surface of the window.

53.24-7.11 Natural ventilation

The design and layout of dwellings must maximise openable windows, doors or other ventilation devices in external walls of the building.

All dwellings must provide effective natural ventilation. Effective natural ventilation includes cross ventilation, single sided ventilation or mechanically assisted ventilation.

For cross ventilation:

- A maximum breeze path through the dwelling of 18 metres.
- A minimum breeze path through the dwelling of 5 metres.
- Ventilation openings with approximately the same area.

The breeze path must be measured between the ventilation openings on different orientations of the dwelling.

53.24-7.12 Deep soil and canopy cover

A development must:

- Provide the canopy cover and deep soil areas specified in Table 4 (existing trees can be used to meet the canopy cover requirements of Table 4).
- Provide canopy cover through canopy trees that are:
  - Located in an area of deep soil specified in Table 5, or where deep soil cannot be provided, located in planters specified in Table 5.
  - Consistent with the canopy diameter and height at maturity specified in Table 6.
  - Located in communal outdoor open space or common areas or street frontages.
  - Be supported by irrigation systems which utilise alternative water sources such as rainwater, stormwater and recycled water.
  - Take into account the soil type and drainage patterns of the site.

Table 4: Canopy cover and deep soil requirements

Site area	Canopy area	Deep soil
1000 square metres or less	5% of site area Include at least 1 Type A tree	5% of site area or 12 square metres whichever is the greater
1001 – 1500 square metres	50 square metres plus 20% of site area above 1,000 square metres Include at least 1 Type B tree	7.5% of site area
1501 – 2500 square metres	150 square metres plus 20% of site area above 1,500 square metres Include at least 2 Type B trees or 1 Type C tree	10% of site area

Site area	Canopy area	Deep soil
2501 square metres or more	350 square metres plus 20% of site area above 2,500 square metres Include at least 2 Type B trees or 1 Type C tree	15% of site area

Table 5: Soil requirements for trees

Tree type	Tree in deep soil Area of deep soil	Tree in planter Volume of soil planter	 Depth of soil planter
A	12 square metres (min. plan dimension 2.5 metres)	12 cubic metres (min. plan dimension of 2.5 metres)	0.8 metre
B	49 square metres (min. plan dimension 4.5 metres)	28 cubic metres (min. plan dimension of 4.5 metres)	1 metre
C	121 square metres (min. plan dimension 6.5 metres)	64 cubic metres (min. plan dimension of 6.5 metres)	1.5 metres

Note *Where multiple trees share the same section of soil the total required amount of soil can be reduced by 5% for every additional tree, up to a maximum reduction of 25%.*

Table 6: Tree types

Tree type	Minimum canopy diameter at maturity	Minimum height at maturity
A	4 metres	6 metres
B	8 metres	8 metres
C	12 metres	12 metres

53.24-8 Decision guidelines

03/12/2024
VC269

Before deciding on an application the responsible authority must consider the purpose of this clause.

53.25 GREAT DESIGN FAST TRACK

07/04/2025
VC280

Purpose

To facilitate innovative dwelling, apartment and mixed-use residential development.

To facilitate development that increases the density and diversity of dwellings to respond to Victoria's population growth.

To facilitate the development of dwellings with convenient access to public transport, and community, retail and other services.

To facilitate development that is of a high quality in its design, liveability and sustainability.

53.25-1 Application

07/04/2025
VC280

The provisions of this clause prevail over any inconsistent provision in this planning scheme.

This clause applies to an application under any provision of this planning scheme for the development of land, or the use and development of land, (other than the subdivision of land), if all of the following are met:

- The applicant submits written confirmation that the application is an application to which this clause applies.
- The application includes the construction of at least eight dwellings.
- Any proposed building contains at least two storeys and not more than eight storeys.
- The proposed development achieves a minimum NatHERS rating of:
  - 8.0 stars average, with no individual dwelling less than 6.5 stars for apartment developments.
  - 7.5 stars for all other dwellings.
- Each proposed dwelling provides effective natural ventilation, which includes cross ventilation, single sided ventilation or mechanically assisted ventilation.
- The Minister for Planning has advised in writing that they are satisfied the proposed use or development of land for accommodation (other than camping and caravan park, group accommodation, residential hotel and small second dwelling) is of significance having regard to:
  - The purpose of clause 53.25.
  - Whether the quality of the design, liveability and sustainability of the proposed development meets the design principles published by the Minister for Planning on the Department's Internet site for the purposes of clause 53.25 ('the design principles').
  - The location of the proposed development and whether it has convenient access to jobs, services, infrastructure and community facilities.
- Information demonstrating that the proposed development meets the design principles is provided to the satisfaction of the Minister for Planning. This must include written advice from the Office of the Victorian Government Architect to the satisfaction of the Minister for Planning.
- Information demonstrating the likely feasibility of the proposed development is provided to the satisfaction of the Minister for Planning. This must include written advice from the Chief Executive Officer or delegate, Invest Victoria (Department of Jobs, Skills, Industry and Regions) to the satisfaction of the Minister for Planning.

53.25-2 Planning scheme requirements

07/04/2025
VC280

The responsible authority may waive or vary any of the following in relation to an application or a proposed use or development:

- A minimum garden area requirement.
- Any building height or setback requirement.
- A condition opposite a use in Section 2 in a zone or a schedule to a zone.

A decision to waive or vary any of the matters above does not apply:

- where it would be inconsistent with an approved Statement of Planning Policy for a declared area; or
- to a requirement in clauses 45.07, 45.08 or 51.03, or in any schedule to those clauses.

The responsible authority may waive or vary any of the requirements of clauses 45.09, 52.06 and 52.34 of this planning scheme in relation to an application or a proposed use or development.

An application is exempt from an application requirement in this planning scheme if in the opinion of the responsible authority the requirement is not relevant to the assessment of the application.

Clauses 52.20, 53.20, 53.23 and 53.24 of this planning scheme do not apply to an application to which this clause applies.

53.25-3 Application requirements

07/04/2025
VC280

If the application includes a non-residential use or development, information about the purpose of the use and the types of activities proposed to be carried out must accompany the application, as appropriate.

53.25-4 Exemption from review

07/04/2025
VC280

An application under any provision of this planning scheme is exempt from the decision requirements of sections 64(1), (2) and (3), and the review rights of section 82(1) of the Act.

53.25-5 Decision guidelines

07/04/2025
VC280

Before deciding on an application, in addition to the decision guidelines elsewhere in this planning scheme including in clause 65, the responsible authority must consider, as appropriate:

- The purpose of the clause.
- The views of the Office of the Victorian Government Architect.

53.25-6 Transitional provision

07/04/2025
VC280

Clause 53.25 does not apply to:

- An application for a permit lodged before the approval date of Amendment VC280.
- An application for an amendment of a permit under section 72 of the Act if the original permit application was lodged before the approval date of Amendment VC280.

54 ONE DWELLING ON A LOT OR A SMALL SECOND DWELLING ON A LOT

08/09/2025
VC282

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To encourage residential development that provides reasonable standards of amenity for existing and new residents.

To encourage residential development that responds to the site and the surrounding area.

Application

Provisions in this clause apply to an application to the classes of applications specified in clauses:

- 32.04-5 and 32.04-6, Mixed Use Zone,
- 32.05-6 and 32.05-7, Township Zone,
- 32.07-4 and 32.07-5, Residential Growth Zone,
- 32.08-5 and 32.08-6, General Residential Zone,
- 32.09-5 and 32.09-6, Neighbourhood Residential Zone,
- 32.10-3 and 32.10-4, Housing Choice and Transport Zone.

The objectives contained in clauses 54.02-8 and 54.03-5 do not apply to one dwelling on a lot.

The objectives contained in clauses 54.02-7, 54.03-1, 54.03-3, 54.05-3 and 54.05-4 do not apply to a small second dwelling.

Operation

The provisions of this clause contain:

- **Objectives**. An objective describes the outcome to be achieved in the completed development.
- **Standards**. A standard contains the requirements to meet the corresponding objective.
  If a zone or a schedule to a zone specifies a standard that modifies the standard set out in this clause, the modified standard in the zone or a schedule to the zone applies.
  If the land is included in a Neighbourhood Character Overlay and a schedule to the overlay specifies a standard that modifies the standard set out in this clause, or a modified standard in the zone or a schedule to the zone, the modified standard in the schedule to the overlay applies.
  If the land is included in an overlay, other than a Neighbourhood Character Overlay, and a schedule to the overlay specifies a standard that modifies the standard set out in this clause, or a modified standard in the zone or a schedule to the zone, the modified standard in the schedule to the overlay applies.
- **Decision guidelines.** If a standard is not met, the decision guidelines set out the matters that the responsible authority must consider before deciding if the corresponding objective is met.

Requirements

A development must meet all of the applicable objectives contained in this clause.

If a development meets a standard:

- The corresponding objective is deemed to be met;
- The responsible authority is not required to consider the corresponding decision guidelines.

If a development does not meet a standard, the responsible authority must consider the applicable decision guidelines in determining whether the corresponding objective is met.

Exemptions

Despite any other provision of this planning scheme, in determining applications to which this clause applies, the responsible authority is exempt from and is not required to consider:

- The Municipal Planning Strategy and Planning Policy Framework, unless an applicable decision guideline specifies otherwise.
- The purpose or decision guidelines of the relevant zone, unless an applicable decision guideline specifies otherwise.
- The decision guidelines in Clause 65, unless an applicable decision guideline specifies otherwise.

If there is any inconsistency between the requirements of this clause and another provision of this planning scheme, this clause prevails.

An application to which this clause applies is exempt from the requirements of:

- Section 60(1)(b), (e), (f), (1A) and (1B) of the Act; and
- Section 84B(2)(b) to (jb) of the Act.

54.01 APPLICATION REQUIREMENTS

08/09/2025
VC282

An application to which this clause applies must be accompanied by:

- A site description.
- A design response.
- A written statement outlining which standards are met and which are not met. If a standard is not met, the written statement must include an explanation of how the development meets the corresponding objective having regard to the corresponding decision guidelines.

54.01-1 Site description

08/09/2025
VC282

The neighbourhood and site description may use a site plan, photographs or other techniques and must accurately describe:

- The built form, scale and character of surrounding development including front fencing.
- Site shape, size, orientation and easements.
- Levels of the site and the difference in levels between the site and surrounding properties.
- The location of existing buildings on the site and on surrounding properties, including the location and height of walls built to the boundary of the site.
- The use of surrounding buildings.
- The location of secluded private open space and habitable room windows of surrounding properties which have an outlook to the site within 9 metres.
- Solar access to the site and to surrounding properties.
- Location of existing trees 5 metres in height or greater, with a trunk circumference of 0.5 metres or greater at 1.4 metres above ground level, on the site.
- Any cut and filled areas of soil, where known.
- Street frontage features such as poles, services, street trees and kerb crossovers.
- The location of any existing domestic solar energy system on the roof of a dwelling, apartment development or residential building on surrounding properties.

If in the opinion of the responsible authority a requirement of the site description is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

54.01-2 Design response

08/09/2025
VC282

The design response must explain how the proposed design derives from and responds to the site description.

The design response must include correctly proportioned street elevations or photographs showing the development in the context of adjacent buildings.

The design response must include a landscape plan that details the proposed:

- Retention and planting of canopy trees,
- Planting of other vegetation including location, species, number and size at maturity of vegetation,
- Where required, areas of deep soil and root barriers,
- Irrigation system to support existing and planted vegetation including details of any alternative water supply sources,
- Selection of vegetation that responds to the site's environment and geographic factors.

If in the opinion of the responsible authority a design response requirement is not relevant to the evaluation of an application, it may waive or reduce the requirement.

54.02 NEIGHBOURHOOD CHARACTER

08/09/2025
VC282

54.02-1 Street setback objective

08/09/2025
VC282

To ensure that the setbacks of buildings from a street respond to the existing or preferred neighbourhood character and make efficient use of the site.

Standard A2-1

Walls of buildings are set back from streets:

- At least the distance specified in a schedule to the zone if the distance specified in the schedule is less than the distance specified in Table A2-1; or
- If no distance is specified in a schedule to the zone, the distance specified in Table A2-1.

Porches, pergolas and verandahs that are less than 3.6 metres high and eaves may encroach not more than 2.5 metres into the setbacks of this standard.

Table A2-1 Street setback

Development context	Minimum setback from front street	Minimum setback from a side street
There is an existing building on both the abutting allotments facing the same street, and the site is not on a corner.	The same distance as the lesser front wall setback of the existing buildings on the abutting allotments facing the front street or 6 metres, whichever is the lesser.	Not applicable
There is an existing building on one abutting allotment facing the same street and no existing building on the other abutting allotment facing the same street, and the site is not on a corner.	The same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 6 metres, whichever is the lesser.	Not applicable
There is no existing building on either of the abutting allotments facing the same street, and the site is not on a corner.	6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Not applicable
The site is on a corner.	If there is a building on the abutting allotment facing the front street, the same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 6 metres, whichever is the lesser. If there is no building on the abutting allotment facing the front street, 6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Front walls of new development fronting the side street of a corner site are setback at least the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 3 metres, whichever is the lesser. Side walls of new development on a corner site are setback the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 2 metres, whichever is the lesser.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- Whether the siting of the building is constrained by the shape, dimensions, slope or other conditions of the site.
- Whether a different setback would be more appropriate taking into account the prevailing setbacks of existing buildings on nearby lots.
- The visual impact of the building when viewed from the street and from adjoining properties.
- Whether a different setback affects the ability to retain or plant canopy trees.

54.02-2 Building height objective

08/09/2025
VC282

To ensure that the height of buildings respond to the existing or preferred neighbourhood character.

Standard A2-2

The maximum building height does not exceed the maximum height specified in the zone, schedule to the zone or an overlay that applies to the land.

If no maximum height is specified in the zone, schedule to the zone or an overlay, the maximum building height does not exceed 9 metres, unless the slope of the natural ground level at any cross section wider than 8 metres of the site of the building is 2.5 degrees or more, in which case the maximum building height does not exceed 10 metres.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- Any maximum building height specified in the zone, a schedule to the zone or an overlay applying to the land.
- The design response.
- The effect of the slope of the site on the height of the building.
- The relationship between the proposed building height and the height of existing adjacent buildings.
- The visual impact of the building when viewed from the street and from adjoining properties.

54.02-3 Side and rear setbacks objective

08/09/2025
VC282

To ensure that the height and setback of a building from a boundary responds to the existing or preferred neighbourhood character and limits the impact on the amenity of existing dwellings or small second dwellings.


Standard A2-3

A new building not on or within 200mm of a boundary is set back from side or rear boundaries at least 1 metre, plus 0.3 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres.

Sunblinds, verandahs, porches, eaves, facias, gutters, masonry chimneys, flues, pipes, domestic fuel or water tanks, and heating or cooling equipment or other services may encroach not more than 0.5 metres into the side and rear setbacks.

Landings that have an area of not more than 2 square metres and less than 1 metre high, stairways, ramps, pergolas, shade sails and carports may encroach into the side and rear setbacks.

Diagram A2-3 Side and rear setbacks



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The impact on the amenity of the habitable room windows and private open space of existing dwellings or small second dwellings.
- Whether the wall is opposite an existing or simultaneously constructed wall built to the boundary.
- Whether the wall abuts a side or rear lane.
- Whether a different setback in a rear yard affects the ability to retain or plant canopy trees.

54.02-4 Walls on boundaries objective

08/09/2025
VC282

To ensure that the location, length and height of a wall on a boundary responds to the existing or preferred neighbourhood character and limits the impact on the amenity of existing dwellings and small second dwellings.

Standard A2-4

A new wall constructed on or within 200mm of a side or rear boundary of a lot or a carport constructed on or within 1 metre of a side or rear boundary of a lot does not abut the boundary for a length that exceeds the greater of the following distances:

- 10 metres plus 25 per cent of the remaining length of the boundary of an adjoining lot, or
- The length of existing or simultaneously constructed walls or carports abutting the boundary on an abutting lot.

A new wall or carport may fully abut a side or rear boundary where slope and retaining walls or fences would result in the effective height of the wall or carport being less than 2 metres on the abutting property boundary.

A building on a boundary includes a building set back up to 200mm from a boundary.

The height of a new wall constructed on or within 200mm of a side or rear boundary or a carport constructed on or within 1 metre of a side or rear boundary does not exceed an average of 3.2 metres with no part higher than 3.6 metres unless abutting a higher existing or simultaneously constructed wall.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The extent to which walls on boundaries are part of the neighbourhood character.
- The impact on the amenity of existing dwellings or small second dwellings.
- The opportunity to minimise the length of walls on boundaries by aligning a new wall on a boundary with an existing wall on a lot of an adjoining property.
- The orientation of the boundary that the wall is being built on.
- The width of the lot.
- The extent to which the slope and retaining walls or fences reduce the effective height of the wall.
- Whether the wall abuts a side or rear lane.
- The need to increase the wall height to screen a box gutter.

54.02-5 Site coverage objective

08/09/2025
VC282

To ensure that the site coverage responds to the existing or preferred neighbourhood character and responds to the features of the site.

Standard A2-5

The site area covered by buildings does not exceed:

- The maximum site coverage specified in a schedule to the zone; or
- If no maximum site coverage is specified in a schedule to the zone, the percentage specified in Table A2-5.

If the maximum site coverage is specified in a schedule to a zone, it must be greater than the percentage specified in Table A2-5.

Table A2-5 Site coverage

Zone	Area
Neighbourhood Residential Zone Township Zone	60 per cent
General Residential Zone	65 per cent
Residential Growth Zone Mixed Use Zone Housing Choice and Transport Zone	70 per cent

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The existing site coverage and any constraints imposed by existing development or the features of the site.
- The site coverage of adjacent properties.
- The effect of the visual bulk of the building and whether this is acceptable in the neighbourhood.
- Whether a different area of site coverage affects the ability to retain or plant canopy trees.

54.02-6 Tree canopy objectives

08/09/2025
VC282

To provide tree canopy that responds to the neighbourhood character of the area and reduces the visual impact of buildings on the streetscape.

To preserve existing canopy cover and support the provision of new canopy cover.

To ensure new canopy trees are climate responsive, support biodiversity, wellbeing and amenity, and help reduce urban heat.

Standard A2-6

Provide a minimum number of trees as specified in Table A2-6.

Table A2-6 Minimum tree requirement

Site area	Tree
100 square metres or less	One tree
Above 100 square metres to 200 square metres	Two trees
Above 200 square metres to 300 square metres	Three trees

A tree must meet the following:

- Reach a height of at least 6 metres at maturity.

- Achieve a canopy width of at least 4 metres at maturity.
- Planted in a minimum deep soil area of 12 square metres with a minimum plan dimension 2.5 metres or in a planter with a minimum volume of 12 cubic metres with a minimum depth of 0.8 metres of planter soil.

Existing trees to be retained meet all of the following:

- Has a height of at least 5 metres,
- Has a trunk circumference of 0.5 metres or greater at 1.4 metres above ground level,
- Has a trunk that is located at least 4 metres from proposed buildings.

Existing trees that are retained can be used to satisfy the tree canopy requirement.

Any tree required to be planted under this standard must be of species to the satisfaction of the responsible authority, having regard to the location and relevant geographic factors.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The site context and design response.
- The extent to which the existing and proposed canopy trees contribute to a greener environment and reduce urban heat.
- Whether the growth characteristics of existing trees and proposed canopy trees will provide the required canopy cover.
- The suitability of the planting location, deep soil areas and planter soil volume for proposed canopy trees.
- Whether the species of canopy tree is suited to the soil conditions of the site.
- Whether an alternative combination of the canopy trees will provide the required canopy cover.

54.02-7 Front fences objective

08/09/2025
VC282

To encourage front fence design that responds to the existing or preferred neighbourhood character.

Standard A2-7

A front fence within 3 metres of a street is:

- The maximum height specified in a schedule to the zone, or
- If no maximum height is specified in a schedule to the zone, the maximum height specified in Table A2-7.

Table A2-7 Maximum front fence height

Street context	Maximum front fence height
Streets in a Transport Zone 2	2 metres
Other streets	1.5 metres

This standard does not apply to a small second dwelling.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.

- The design response.
- The setback, height and appearance of front fences on adjacent properties.
- The extent to which slope and retaining walls reduce the effective height of the front fence.
- Whether the fence is needed to minimise noise intrusion.

54.02-8 Building setback for small second dwellings objective

08/09/2025
VC282

To ensure that small second dwellings are sited to respond to the existing or preferred neighbourhood character.

Standard A2-8

Walls of a small second dwelling are set back behind the front wall of the existing dwelling on the lot, facing the frontage.

Porches, pergolas, verandahs, and eaves do not encroach into the setback of this standard.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The visual impact of the building when viewed from the street and from adjoining properties.

54.03 LIVEABILITY

08/09/2025
VC282

54.03-1 Street integration objective

08/09/2025
VC282

To integrate the layout of development with the street to support the safety and amenity of residents.

Standard A3-1

Where a development fronts a street, a vehicle accessway or abuts public open space, passive surveillance is provided by a direct view from a balcony or a habitable room window to each street, vehicle accessway and public open space.

This standard does not apply to a small second dwelling.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.

54.03-2 Private open space objective

08/09/2025
VC282

To provide adequate private open space for the reasonable recreation and service needs of residents.

Standard A3-2

A dwelling or small second dwelling has private open space of an area and dimensions specified in a schedule to the zone.

If no area or dimension is specified in a schedule to the zone, a dwelling has private open space with direct access from a living area, dining area or kitchen consisting of:

- An area of 20 per cent of the area of the lot, but not less than 25 square metres. At least one part of the private open space consists of secluded private open space with a minimum area of 25 square metres and a minimum dimension of 3 metres width; or
- A balcony with at least the area and dimensions specified in Table A3-2; or
- An area on a roof of at least 10 square metres, with a minimum dimension of 2 metres width.

If the area and dimensions of the private open space or secluded private open space is specified in a schedule to the zone;

- The area and dimensions specified for private open space and secluded private open space must be less than the area and dimensions specified in this standard, and
- The area and dimensions specified for a balcony or an area on a roof must be less than the area and dimensions specified in this standard.

A small second dwelling has a secluded private open space consisting of an area of 8 square metres with a minimum dimension of 1.6 metres and convenient access from a living area, dining area or kitchen.

If a cooling or heating unit is located in the secluded private open space or private open space the required area is increased by 1.5 square metres.

Where ground level private open space is provided an area for clothes drying is provided.

Table A3-2 Private open space for a balcony

Orientation of dwelling	Dwelling type	Minimum area	Minimum dimension
North (between north 20 degrees west to north 30 degrees east)	All	8 square metres	1.7 metres
South (between south 30 degrees west to south 20 degrees east)	All	8 square metres	1.2 metres
Any other orientation	1 bedroom dwelling	8 square metres	1.8 metres
	2 bedroom dwelling	8 square metres	2 metres
	3 bedroom dwelling	12 square metres	2.4 metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability of the private open space, including its size and accessibility.
- The availability of and access to public open space.
- The orientation of the lot to the street and the sun.

54.03-3 Solar access to open space objective


08/09/2025
VC282

To allow solar access into the secluded private open space of new dwellings.

Standard A3-3

The southern boundary of secluded private open space is set back from any wall on the north of the space at least (2 + 0.9h) metres, where 'h' is the height of the wall.

Diagram A3-3 Solar access to open space



This standard does not apply to a small second dwelling.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability and amenity of the secluded private open space based on the sunlight it will receive.

54.03-4 Daylight to new windows objectives

08/09/2025
VC282

To allow adequate daylight into new habitable room windows.

Standard A3-4

A window in an external wall of the building is provided to all habitable rooms.

Habitable rooms in a dwelling have a window that faces:

- An outdoor space clear to the sky or a light court with a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky, not including land on an abutting lot; or
- A verandah provided it is open for at least one third of its perimeter; or
- A carport provided it has two or more open sides and is open for at least one third of its perimeter.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which habitable rooms are provided with reasonable daylight access through the number, size, location and orientation of windows.
- The useability and amenity of the dwelling based on the layout, siting, size and orientation of habitable rooms.
- Whether there are other windows in the habitable room which have access to daylight.

54.03-5 Safety and accessibility for small second dwellings objective

08/09/2025
VC282

To ensure access to a small second dwelling is safe, convenient and meets the needs of residents.

Standard A3-5

A small second dwelling is provided with a clear and unobstructed path from the frontage that:

- Has a minimum width of at least 1 metre, with no encroachments. If the path is longer than 30 metres, the minimum width of the path is at least 1.8 metres.
- Has a minimum clear height of at least 2 metres, with no encroachments.
- Has a gradient no steeper than 1 in 14.
- Has a cross fall no steeper than 1 in 40.
- Is sealed or has an all-weather access.

Decision guidelines

Before deciding on an application, the responsible authority must consider the safety and accessibility of the small second dwelling.

54.04 EXTERNAL AMENITY

08/09/2025
VC282

54.04-1 Daylight to existing windows objective

08/09/2025
VC282

To allow adequate daylight into existing habitable room windows.


Standard A4-1

Buildings opposite an existing habitable room window provide for a light court to the existing window that has a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky. The calculation of the area may include land on the abutting lot.

Walls or carports more than 3 metres in height opposite an existing habitable room window are set back from the window at least 50 per cent of the height of the new wall if the wall is within a 55 degree arc from the centre of the existing window. The arc may be swung to within 35 degrees of the plane of the wall containing the existing window.

Where the existing window is above ground floor level, the wall height is measured from the floor level of the room containing the window.

Diagram A4-1 Daylight to existing windows



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which the existing dwelling or small second dwelling has provided for reasonable daylight access to its habitable rooms through the siting and orientation of its habitable room windows.
- The impact on the amenity of existing dwellings or small second dwellings.

54.04-2 Existing north-facing windows objective

08/09/2025
VC282


To allow adequate solar access to existing north-facing habitable room windows.

Standard A4-2

Where a north-facing habitable room window of a neighbouring dwelling or small second dwelling is within 3 metres of a boundary on an abutting lot, a new building is to be set back from the boundary by at least 1 metre, plus 0.6 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres. This setback is to be provided for a distance of at least 3 metres from the edge of each side of the window.

For this standard a north-facing window is a window with an axis perpendicular to its surface oriented from north 20 degrees west to north 30 degrees east.

Diagram A4-2 North-facing windows



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- Existing sunlight to the north-facing habitable room window of the existing dwelling or small second dwelling.
- The impact on the amenity of existing dwellings or small second dwellings.

54.04-3 Overshadowing secluded open space objective

08/09/2025
VC282

To ensure buildings do not significantly overshadow existing secluded private open space.

Standard A4-3

The area of secluded private open space that is not overshadowed by the new development is greater than 50 per cent, or 25 square metres with a minimum dimension of 3 metres, whichever is the lesser area, for a minimum of five hours between 9 am and 3 pm on 22 September.

If existing sunlight to the secluded private open space of an existing dwelling or small second dwelling is less than the requirements of this standard, the amount of sunlight will not be further reduced.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The impact on the amenity of existing dwellings or small second dwellings.
- Existing sunlight penetration to the secluded private open space of the existing dwelling or small second dwelling.
- The time of day that sunlight will be available to the secluded private open space of the existing dwelling or small second dwelling.
- The effect of a reduction in sunlight on the existing use of the existing secluded private open space.

54.04-4 Overlooking objective

08/09/2025
VC282

To limit views into existing secluded private open space and habitable room windows.

Standard A4-4

In Clause 54.04-4 a habitable room does not include a bedroom.

A habitable room window, balcony, terrace, deck or patio is located and designed to avoid direct views into the secluded private open space of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio. Views are measured within a 45 degree angle from the plane of the window or perimeter of the balcony, terrace, deck or patio, and from a height of 1.7 metres above floor level.

A habitable room window, balcony, terrace, deck or patio that is located with a direct view into a habitable room window of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio:

- Is offset a minimum of 1.5 metres from the edge of one window to the edge of the other; or
- Has sill heights of at least 1.7 metres above floor level; or
- Has fixed, obscure glazing in any part of the window below 1.7 metre above floor level; or
- Has permanently fixed external screens to at least 1.7 metres above floor level and be no more than 25 per cent transparent; or
- Has fixed elements that prevent the direct view, such as horizontal ledges or vertical fins.


Obscure glazing in any part of the window below 1.7 metres above floor level may be openable provided that there are no direct views as specified in this standard.

Screens used to obscure a view are:

- Perforated panels or trellis with a maximum of 25 per cent openings or solid translucent panels.
- Permanent, fixed and durable.
- Designed and coloured to blend in with the development.

This standard does not apply to a new habitable room window, balcony, terrace, deck or patio which faces a property boundary where there is a visual barrier at least 1.8 metres high and the floor level of the habitable room, balcony, terrace, deck or patio is less than 0.8 metres above ground level at the boundary.

Diagram A4-4 Overlooking



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The impact on the amenity of the secluded private open space or habitable room window.
- The existing extent of overlooking into the secluded private open space and habitable room windows of existing dwellings or small second dwellings.
- The internal daylight to and amenity of the proposed dwelling or small second dwelling.

54.05 SUSTAINABILITY

08/09/2025
VC282

54.05-1 Permeability objectives

08/09/2025
VC282

To reduce the impact of increased stormwater run-off on the drainage system and downstream waterways.

To facilitate on-site stormwater infiltration.

To contribute to urban cooling.

Standard A5-1

The site area covered by the pervious surfaces is at least 20 percent of the site.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The existing site coverage and any constraints imposed by existing development.
- The capacity of the drainage network to accommodate additional stormwater.
- The practicality of achieving the minimum site coverage of pervious surfaces.

54.05-2 Overshadowing domestic solar energy systems objective

08/09/2025
VC282

To ensure that the height and setback of a building from a boundary allows reasonable solar access to existing domestic solar energy systems on the roofs of buildings.

Standard A5-2

Any part of a new building that will reduce the sunlight at any time between 9 am and 4 pm on 22 September to an existing domestic solar energy system on the roof of a building on an adjoining lot be set back from the boundary to that lot by at least 1 metre at 3.6 metres above ground level, plus 0.3 metres for every metre of building height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres.

This standard applies to an existing building in a Township Zone, General Residential Zone or Neighbourhood Residential Zone.

In Clause 54.05-2 domestic solar energy system means a domestic solar energy system that existed at the date the application was lodged.

Decision guidelines

Before deciding on an application, the responsible authority must consider whether the domestic solar energy system has been sited to optimise efficiency and protection from overshadowing.

54.05-3 Rooftop solar energy generation area objective

08/09/2025
VC282

To support the future installation of appropriately sited rooftop solar energy systems for a dwelling.

Standard A5-3


In Clause 54.05-3 rooftop solar energy area means an area provided on the roof of a dwelling to enable the future installation of a solar energy system.

An area on the roof is capable of siting a rooftop solar energy area for each dwelling which:

- Has a minimum dimension of 1.7 metres.
- Has a minimum area in accordance with Table A5-3.
- Is oriented to the north, west or east.

- Is positioned on the top two thirds of a pitched roof.
- Can be a contiguous area or multiple smaller areas.
- Is free of obstructions on the roof of the dwelling within twice the height of each obstruction (H), measured horizontally (D) from the centre point of the base of the obstruction to the nearest point of the rooftop solar energy area.

Diagram A5-3 Allowable distance between obstructions and the rooftop solar energy area



Obstructions located south of all points of the rooftop solar energy area are not subject to the horizontal distance requirements.

Table A5-3 Minimum rooftop solar energy generation area

Number of bedrooms	Minimum roof area
1 bedroom dwelling	15 square metres
2 or 3 bedroom dwelling	26 square metres
4 or more bedroom dwelling	34 square metres

This standard does not apply to a small second dwelling.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size and orientation of the building.
- The availability of solar access to the rooftop.
- The extent to which the rooftop solar energy generation area is overshadowed by existing buildings, other permanent structures or equipment on the rooftop.

54.05-4 Solar protection to new north-facing windows objective

08/09/2025
VC282

To encourage external shading of north facing windows to minimise summer heat gain.

Standard A5-4

North facing windows are shaded by eaves, fixed horizontal shading devices or fixed awnings with a minimum horizontal depth of 0.25 times the window height.

This standard does not apply to a small second dwelling.

Decision guidelines

Before deciding on an application, the responsible authority considers:

- The design response.
- The size and orientation of the lot.
- The type and useability of external solar shading devices, including alternative design responses.

55 TWO OR MORE DWELLINGS ON A LOT AND RESIDENTIAL BUILDINGS

08/09/2025
VC282

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To encourage residential development that provides reasonable standards of amenity for existing and new residents.

To encourage residential development that responds to the site and the surrounding area.

Application

Provisions in this clause apply to the classes of applications specified in clauses:

- 32.04-7, Mixed Use Zone,
- 32.05-8, Township Zone,
- 32.07-6, Residential Growth Zone,
- 32.08-7, General Residential Zone,
- 32.09-7, Neighbourhood Residential Zone,
- 32.10-5, Housing Choice and Transport Zone.

The objective contained in clause 55.03-1 does not apply to a development of less than 10 dwellings.

The objective contained in clause 55.05-3 does not apply to an apartment development or residential building.

The objectives contained in clauses 55.03-12 and 55.05-7 do not apply to the construction or extension of:

- A dwelling that is not in, or does not form part of, an apartment development; or
- A residential building.

Operation

The provisions of this clause contain:

- **Objectives**. An objective describes the outcome to be achieved in the completed development.
- **Standards**. A standard contains the requirements to meet the corresponding objective.

  If a zone or a schedule to a zone specifies a standard that modifies the standard set out in this clause, the modified standard in the zone or a schedule to the zone applies.

  If the land is included in a Neighbourhood Character Overlay and a schedule to the overlay specifies a standard that modifies the standard set out in this clause, or a modified standard in the zone or a schedule to the zone, the modified standard in the schedule to the overlay applies.

  If the land is included in an overlay, other than a Neighbourhood Character Overlay, and a schedule to the overlay specifies a standard that modifies the standard set out in this clause, or a modified standard in the zone or a schedule to the zone, the modified standard in the schedule to the overlay applies.
- **Decision guidelines**. If a standard is not met, the decision guidelines set out the matters that the responsible authority must consider before deciding if the corresponding objective is met.

Requirements

A development must meet all of the applicable objectives contained in this clause.

If a development meets a standard:

- The corresponding objective is deemed to be met;
- The responsible authority is not required to consider the corresponding decision guidelines.

If a development does not meet a standard, the responsible authority must consider the applicable decision guidelines in determining whether the corresponding objective is met.

Exemptions

Despite any other provision of this planning scheme, in determining applications to which this clause applies, the responsible authority is exempt from and is not required to consider:

- The Municipal Planning Strategy and Planning Policy Framework, unless an applicable decision guideline specifies otherwise.
- The purpose or decision guidelines of the relevant zone, unless an applicable decision guideline specifies otherwise.
- The decision guidelines in Clause 65, unless an applicable decision guideline specifies otherwise.

If there is any inconsistency between the requirements of this clause and another provision of this planning scheme, this clause prevails.

An application to which this clause applies is exempt from the requirements of:

- Section 60(1)(b), (e), (f), (1A) and (1B) of the Act; and
- Section 84B(2)(b) to (jb) of the Act.

55.01 APPLICATION REQUIREMENTS

31/03/2025
VC267

An application to which this clause applies must be accompanied by:

- A site description.
- A design response.
- A written statement outlining which standards are met and which are not met. If a standard is not met, the written statement must include an explanation of how the development meets the corresponding objective having regard to the corresponding decision guidelines.

55.01-1 Site description

31/03/2025
VC267

The neighbourhood and site description may use a site plan, photographs or other techniques and must accurately describe:

- The built form, scale and character of surrounding development including front fencing.
- Site shape, size, orientation and easements.
- Levels of the site and the difference in levels between the site and surrounding properties.
- The location of existing buildings on the site and on surrounding properties, including the location and height of walls built to the boundary of the site.
- The use of surrounding buildings.
- The location of secluded private open space and habitable room windows of surrounding properties which have an outlook to the site within 9 metres.
- Solar access to the site and to surrounding properties.
- Location of existing trees 5 metres in height or greater, with a trunk circumference of 0.5 metres or greater at 1.4 metres above ground level, on the site.
- Any cut and filled areas of soil, where known.
- Street frontage features such as poles, services, street trees and kerb crossovers.
- The location of any existing domestic solar energy system on the roof of a dwelling, apartment development or residential building on surrounding properties.

If in the opinion of the responsible authority a requirement of the site description is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

55.01-2 Design response

31/03/2025
VC267

The design response must explain how the proposed design derives from and responds to the site description.

The design response must include correctly proportioned street elevations or photographs showing the development in the context of adjacent buildings.

The design response must include a landscape plan that details the proposed:

- Retention and planting of canopy trees,
- Planting of other vegetation including location, species, number and size at maturity of vegetation,
- Where required, areas of deep soil and root barriers,
- Irrigation system to support existing and planted vegetation including details of any alternative water supply sources,
- Selection of vegetation that responds to the site's environment and geographic factors,
- A plan showing the location of site services, clothes drying and storage.

If in the opinion of the responsible authority a design response requirement is not relevant to the evaluation of an application, it may waive or reduce the requirement.

55.02 NEIGHBOURHOOD CHARACTER

31/03/2025
VC267

55.02-1 Street setback objectives

31/03/2025
VC267

To ensure that the setbacks of buildings from a street respond to the existing or preferred neighbourhood character and make efficient use of the site.

Standard B2-1

Walls of buildings are set back from streets:

- At least the distance specified in a schedule to the zone if the distance specified in the schedule is less than the distance specified in Table B2-1; or
- If no distance is specified in a schedule to the zone, the distance specified in Table B2-1.

Porches, pergolas and verandahs that are less than 3.6 metres high and eaves may encroach not more than 2.5 metres into the setbacks of this standard.

Table B2-1 Street setback

Development context	Minimum setback from front street	Minimum setback from a side street
There is an existing building on both the abutting allotments facing the same street, and the site is not on a corner.	The same distance as the lesser front wall setback of the existing buildings on the abutting allotments facing the front street or 6 metres, whichever is the lesser.	Not applicable
There is an existing building on one abutting allotment facing the same street and no existing building on the other abutting allotment facing the same street, and the site is not on a corner.	The same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 6 metres, whichever is the lesser.	Not applicable
There is no existing building on either of the abutting allotments facing the same street, and the site is not on a corner.	6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Not applicable
The site is on a corner.	If there is a building on the abutting allotment facing the front street, the same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 6 metres, whichever is the lesser. If there is no building on the abutting allotment facing the front street, 6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Front walls of new development fronting the side street of a corner site are setback at least the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 3 metres, whichever is the lesser. Side walls of new development on a corner site are setback the same distance as the setback of the front wall of any existing

Development context	Minimum setback from front street	Minimum setback from a side street
		building on the abutting allotment facing the side street or 2 metres, whichever is the lesser.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- Whether the siting of the building is constrained by the shape, dimensions, slope or other conditions of the site.
- Whether a different setback would be more appropriate taking into account the prevailing setbacks of existing buildings on nearby lots.
- The visual impact of the building when viewed from the street and from adjoining properties.
- Whether a different setback affects the ability to retain or plant canopy trees.

55.02-2 Building height objective

31/03/2025
VC267

To ensure that the height of buildings respond to the existing or preferred neighbourhood character.

Standard B2-2

The maximum building height does not exceed the maximum height specified in the zone, schedule to the zone or an overlay that applies to the land.

If no maximum height is specified in the zone, schedule to the zone or an overlay, the maximum building height does not exceed 9 metres, unless the slope of the natural ground level at any cross section wider than 8 metres of the site of the building is 2.5 degrees or more, in which case the maximum building height does not exceed 10 metres.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- Any maximum building height specified in the zone, a schedule to the zone or an overlay applying to the land.
- The design response.
- The effect of the slope of the site on the height of the building.
- The relationship between the proposed building height and the height of existing adjacent buildings.
- The visual impact of the building when viewed from the street and from adjoining properties.

55.02-3 Side and rear setbacks objective

02/04/2025
VC276

To ensure that the height and setback of a building from a boundary responds to the existing or preferred neighbourhood character and limits the impact on the amenity of existing dwellings or small second dwellings.

Standard B2-3

A new building not on or within 200mm of a boundary is set back from side or rear boundaries in accordance with either B2-3.1 or B2-3.2.

Standard B2-3 is met if the building is set back in accordance with either B2-3.1 or B2-3.2, rather than needing to comply with both of these provisions:

- B2-3.1:

  The building is set back at least 1 metre, plus 0.3 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres.

- B2-3.2:

  If the boundary is not to the south of the building, the building is set back at least 3 metres up to a height not exceeding 11 metres and at least 4.5 metres for a height over 11 metres.

  If the boundary is to the south of the building, the building is set back at least 6 metres up to a height not exceeding 11 metres and at least 9 metres for a height over 11 metres between south 30 degrees west to south 30 degrees east.

Sunblinds, verandahs, porches, eaves, facias, gutters, masonry chimneys, flues, pipes, domestic fuel or water tanks, and heating or cooling equipment or other services may encroach not more than 0.5 metres into the side and rear setbacks.

Landings that have an area of not more than 2 square metres and less than 1 metre high, stairways, ramps, pergolas, shade sails and carports may encroach into the side and rear setbacks.

Diagram B2-3.1 Side and rear setbacks





Diagram B2-3.2 Side and rear setbacks



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The impact on the amenity of the habitable room windows and private open space of existing dwellings or small second dwellings.
- Whether the wall is opposite an existing or simultaneously constructed wall built to the boundary.
- Whether the wall abuts a side or rear lane.
- Whether a different setback in a rear yard affects the ability to retain or plant canopy trees.

55.02-4 Walls on boundaries objectives

31/03/2025
VC267

To ensure that the location, length and height of a wall on a boundary responds to the existing or preferred neighbourhood character and limits the impact on the amenity of existing dwellings and small second dwellings.

Standard B2-4

A new wall constructed on or within 200mm of a side or rear boundary of a lot or a carport constructed on or within 1 metre of a side or rear boundary of a lot does not abut the boundary for a length that exceeds the greater of the following distances:

- 10 metres plus 25 per cent of the remaining length of the boundary of an adjoining lot, or
- The length of existing or simultaneously constructed walls or carports abutting the boundary on an abutting lot.

A new wall or carport may fully abut a side or rear boundary where slope and retaining walls or fences would result in the effective height of the wall or carport being less than 2 metres on the abutting property boundary.

A building on a boundary includes a building set back up to 200mm from a boundary.

The height of a new wall constructed on or within 200mm of a side or rear boundary or a carport constructed on or within 1 metre of a side or rear boundary does not exceed an average of 3.2 metres with no part higher than 3.6 metres unless abutting a higher existing or simultaneously constructed wall.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The extent to which walls on boundaries are part of the neighbourhood character.
- The impact on the amenity of existing dwellings or small second dwellings.
- The opportunity to minimise the length of walls on boundaries by aligning a new wall on a boundary with an existing wall on a lot of an adjoining property.
- The orientation of the boundary that the wall is being built on.
- The width of the lot.
- The extent to which the slope and retaining walls or fences reduce the effective height of the wall.

- Whether the wall abuts a side or rear lane.
- The need to increase the wall height to screen a box gutter.

55.02-5 Site coverage objective

31/03/2025
VC267

To ensure that the site coverage responds to the existing or preferred neighbourhood character and responds to the features of the site.

Standard B2-5

The site area covered by buildings does not exceed:

- The maximum site coverage specified in a schedule to the zone; or
- If no maximum site coverage is specified in a schedule to the zone, the percentage specified in Table B2-5.

If the maximum site coverage is specified in a schedule to a zone, it must be greater than the percentage specified in Table B2-5.

Table B2-5 Site coverage

Zone	Area
Neighbourhood Residential Zone Township Zone	60 per cent
General Residential Zone	65 per cent
Residential Growth Zone Mixed Use Zone Housing Choice and Transport Zone	70 per cent

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The existing site coverage and any constraints imposed by existing development or the features of the site.
- The site coverage of adjacent properties.
- The effect of the visual bulk of the building and whether this is acceptable in the neighbourhood.
- Whether a different area of site coverage affects the ability to retain or plant canopy trees.

55.02-6 Access objective

31/03/2025
VC267

To ensure the number and design of vehicle crossovers responds to the neighbourhood character.

Standard B2-6

The width of accessways or car spaces (other than to a rear lane) does not exceed:

- 33 per cent of the street frontage; or
- 40 per cent of the street frontage if the width of the street frontage is less than 20 metres.

The number of access points to a road in a Transport Zone 2 or a Transport Zone 3 is not increased.

The location of a vehicle crossover or accessway does not encroach the tree protection zone of an existing tree, that is proposed to be retained in a road by more than 10 per cent.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The reduction of on-street car parking spaces.
- Whether a different accessway width, number of access points or encroachment of an existing tree affects the ability to retain or plant canopy trees on the site or footpath.

55.02-7 Tree canopy objectives

31/03/2025
VC267

To provide tree canopy that responds to the neighbourhood character of the area and reduces the visual impact of buildings on the streetscape.

To preserve existing canopy cover and support the provision of new canopy cover.

To ensure new canopy trees are climate responsive, support biodiversity, wellbeing and amenity, and help reduce urban heat.

Standard B2-7

Provide a minimum canopy cover as specified in Table B2-7.1.

Table B2-7.1 Canopy cover

Site area	Canopy cover
1000 square metres or less	10% of site area
More than 1000 square metres	20% of site area

Existing trees to be retained meet all of the following:

- Has a height of at least 5 metres,
- Has a trunk circumference of 0.5 metres or greater at 1.4 metres above ground level,
- Has a trunk that is located at least 4 metres from proposed buildings.

The minimum canopy cover is met using any combination of trees specified in Table B2-7.2.

Existing trees that are retained can be used in calculating canopy cover.

Table B2-7.2 Tree type, canopy cover, deep soil and planter requirements

Tree type	Minimum canopy diameter at maturity	Minimum height at maturity	Minimum mature canopy cover	Tree in deep soil Area of deep soil	Tree in planter Volume of planter	Minimum depth of planter soil
A	4 metres	6 metres	12.6 sqm	12 square metres (min. plan dimension 2.5 metres)	12 cubic metres (min. plan dimension 2.5 metres)	0.8 metre

Tree type	Minimum canopy diameter at maturity	Minimum height at maturity	Minimum mature canopy cover	Tree in deep soil Area of deep soil	Tree in planter Volume of planter	Minimum depth of planter soil
B	8 metres	8 metres	50.3 sqm	49 square metres (min. plan dimension 4.5 metres)	28 cubic metres (min. plan dimension 4.5 metres)	1 metre
C	12 metres	12 metres	113.1 sqm	121 square metres (min. plan dimension 6.5 metres)	64 cubic metres (min. plan dimension 6.5 metres)	1.5 metre

Provide at least one new or retained tree in the front setback and the rear setback.

Trees are located in either:

- An area of deep soil as specified in Table B2-7.2; or
- A planter as specified in Table B2-7.2.

Any tree required to be planted under this standard must be of species to the satisfaction of the responsible authority, having regard to the location and relevant geographic factors.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The site context and design response.
- The extent to which the existing and proposed canopy trees contribute to a greener environment and reduce urban heat.
- Whether the growth characteristics of existing trees and proposed canopy trees will provide the required canopy cover.
- The suitability of the planting location, deep soil areas and planter soil volume for proposed canopy trees.
- Whether the species of canopy tree is suited to the soil conditions of the site.

55.02-8 Front fences objective

31/03/2025
VC267

To encourage front fence design that responds to the existing or preferred neighbourhood character.

Standard B2-8

A front fence within 3 metres of a street is:

- The maximum height specified in a schedule to the zone, or
- If no maximum height is specified in a schedule to the zone, the maximum height specified in Table B2-8.

Table B2-8 Maximum front fence height

Street context	Maximum front fence height
Streets in a Transport Zone 2	2 metres
Other streets	1.5 metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The setback, height and appearance of front fences on adjacent properties.
- The extent to which slope and retaining walls reduce the effective height of the front fence.
- Whether the fence is needed to minimise noise intrusion.

55.03 LIVEABILITY

31/03/2025
VC267

55.03-1 Dwelling diversity objective

31/03/2025
VC267

To encourage a range of dwelling sizes and types in developments of ten or more dwellings.

Standard B3-1

Developments include at least:

- One dwelling that contains a kitchen, bath or shower, bedroom and a toilet and wash basin at ground floor level for every 10 dwellings.
- One dwelling that includes no more and no less than 2 bedrooms for every 10 dwellings.
- One dwelling that includes no more and no less than 3 bedrooms for every 10 dwellings.

Decision guidelines

Before deciding on an application, the responsible authority must consider whether the development provides a range of dwelling sizes and types to meet diverse household needs.

55.03-2 Parking location objective

31/03/2025
VC267

To minimise the impact of vehicular noise within developments on residents.

Standard B3-2

Habitable room windows with sill heights of less than 3 metres above ground level are setback from accessways and car parks by at least:

- 1.5 metres; or
- If there is a solid fence with a height of at least 1.5 metres between the accessway or car park and the window, 1 metre; or
- 1 metre where window sills are at least 1.5 metres above ground level.

This standard is met if an accessway or relevant car parking space is used exclusively by the resident of the building with the habitable room.

Decision guidelines

Before deciding on an application, the responsible authority must consider the design response.

55.03-3 Street integration objective

31/03/2025
VC267

To integrate the layout of development with the street to support the safety and amenity of residents.

Standard B3-3

Where a development fronts a street, a vehicle accessway or abuts public open space:

- Passive surveillance is provided by a direct view from a balcony or a habitable room window to each street, vehicle accessway and public open space.
- The total cumulative width of all site services to be located within 3 metres of a street, do not take up more than 20 per cent of the width of the frontage and are screened from view from the street or located behind a fence. Screens or fences are to provide no more than 25 per cent transparency.

Lighting is provided to all external accessways and paths.

Mailboxes are provided for each dwelling and can be communally located.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.

55.03-4 Entry objectives

31/03/2025
VC267

To provide each dwelling, apartment development or residential building with its own sense of identity.

To provide entries with weather protection, safe design, natural light and ventilation.

Standard B3-4

Dwellings (other than a dwelling in or forming part of an apartment development) and residential buildings

Each dwelling and each residential building has a ground level entry door that:

- Has a direct line of sight from a street, accessway or shared walkway.
- Is not accessed through a garage.
- Has an external covered area of at least 1.44 square metres with a minimum dimension of least 1.2 metres over the entry door.

Apartment development and residential building with a shared entry

An apartment development and each residential building has:

- A ground level entry door, gate or walkway with a direct line of sight from a street, accessway or shared walkway.
- An external covered area of at least 1.44 square metres with a minimum dimension of least 1.2 metres over the entry door to the building.
- Shared corridors and common areas have at least one source of natural light and natural ventilation.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Whether the entry is visible and easily identifiable from streets and other public areas.
- Whether the entry provides shelter, a sense of address and a transitional space around the entry.

55.03-5 Private open space objectives

31/03/2025
VC267

To provide adequate private open space for the reasonable recreation and service needs of residents.

Standard B3-5

A dwelling or residential building has private open space of an area and dimensions specified in a schedule to the zone.

If no area or dimension is specified in a schedule to the zone, a dwelling or residential building has private open space with direct access from a living area, dining area or kitchen consisting of:

- An area of 25 square metres of secluded private open space, with a minimum dimension of 3 metres width; or
- A balcony with at least the area and dimensions specified in Table B3-5; or

- An area on a podium or similar of at least 15 square metres, with a minimum dimension of 3 metres width; or
- An area on a roof of at least 10 square metres, with a minimum dimension of 2 metres width.

If the area and dimensions of the private open space or secluded private open space is specified in a schedule to the zone;

- The area and dimensions specified in the schedule must be 25 square metres or less; and
- The area and dimensions specified for a podium, balcony or an area on a roof must be less than the area and dimensions specified in this standard.

If a cooling or heating unit is located in the secluded private open space or private open space the required area is increased by 1.5 square metres.

Where ground level private open space is provided an area for clothes drying is provided.

Table B3-5 Private open space for a balcony

Orientation of dwelling	Dwelling type	Minimum area	Minimum dimension
North (between north 20 degrees west to north 30 degrees east)	All	8 square metres	1.7 metres
South (between south 30 degrees west to south 20 degrees east)	All	8 square metres	1.2 metres
Any other orientation	Studio or 1 bedroom dwelling	8 square metres	1.8 metres
	2 bedroom dwelling	8 square metres	2 metres
	3 bedroom dwelling	12 square metres	2.4 metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability of the private open space, including its size and accessibility.
- The availability of and access to public or communal open space.
- The orientation of the lot to the street and the sun.

55.03-6 Solar access to open space objective


31/03/2025
VC267

To allow solar access into the secluded private open space of new dwellings and residential buildings.

Standard B3-6

The southern boundary of secluded private open space is set back from any wall on the north of the space at least (2 + 0.9h) metres, where ‘h’ is the height of the wall.

Diagram B3-6 Solar access to open space



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability and amenity of the secluded private open space based on the sunlight it will receive.

55.03-7 Functional layout objective

02/04/2025
VC276

To ensure dwellings provide functional areas that meet the needs of residents.

Standard B3-7

Bedrooms:

- Meet the minimum internal room dimensions specified in Table B3-7.1; and
- Provide an additional area of at least 0.8 square metres to accommodate a wardrobe.

Table B3-7.1 Bedroom dimensions

Bedroom type	Minimum width	Minimum depth
Main bedroom	3 metres	3.4 metres
All other bedrooms	3 metres	3 metres

Living areas (excluding dining and kitchen areas) meet the minimum internal room dimensions specified in Table B3-7.2.

Table B3-7.2 Living area dimensions

Dwelling type	Minimum width	Minimum area
Studio and 1 bedroom dwelling	3.3 metres	10 sqm
2 or more bedroom dwelling	3.6 metres	12 sqm

Decision guideline

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability and amenity of habitable rooms.

55.03-8 Room depth objective

31/03/2025
VC267

To allow adequate daylight into single aspect habitable rooms.

Standard B3-8

The depth of a single aspect habitable room does not exceed 2.5 times the ceiling height measured from the external surface of the habitable room window to the rear wall of the room.

The depth of a single aspect, open plan, habitable room may be increased to 9 metres if all the following requirements are met:

- The room combines the living area, dining area and kitchen; and
- The kitchen is located furthest from the window; and
- The ceiling height is at least 2.7 metres measured from finished floor level to finished ceiling level, this excludes where services are provided above the kitchen; and
- An overhang extends no more than 2m beyond the window of the single aspect habitable room.

In Clause 55.03-8 a single aspect habitable room is a habitable room with windows on only one wall.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which the habitable room is provided with reasonable daylight access through the number, size, location and orientation of windows.
- The useability, functionality and amenity of the dwelling based on the layout, siting, size and orientation of habitable rooms.
- Any overhang above habitable room windows that limits daylight access.

55.03-9 Daylight to new windows objective

31/03/2025
VC267

To allow adequate daylight into new habitable room windows.

Standard B3-9

Dwelling (other than a dwelling in or forming part of an apartment development)

A window in an external wall of the building is provided to all habitable rooms.

Habitable rooms in a dwelling have a window that faces:

- An outdoor space clear to the sky or a light court with a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky, not including land on an abutting lot; or
- A verandah provided it is open for at least one third of its perimeter; or
- A carport provided it has two or more open sides and is open for at least one third of its perimeter.

Dwelling in or forming part of an apartment development

A window in an external wall of the building is provided to all habitable rooms.

Where daylight to a bedroom is provided from a smaller secondary area within the bedroom, the secondary area is to have:

- A minimum width of 1.2 metres.
- A maximum depth of 1.5 times the width, measured from the external surface of the window.
- A window clear to the sky.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which habitable rooms are provided with reasonable daylight access through the number, size, location and orientation of windows.
- The useability and amenity of the dwelling based on the layout, siting, size and orientation of habitable rooms.
- Whether there are other windows in the habitable room which have access to daylight.

55.03-10 Natural ventilation objectives

31/03/2025
VC267

To encourage natural ventilation of dwellings.

To allow occupants to effectively manage natural ventilation of dwellings.

Standard B3-10

Dwelling (other than a dwelling in or forming part of an apartment development)

Dwellings have openable windows, doors or other ventilation devices in external walls of the building that provide:

- A maximum breeze path through the dwelling of 18 metres.
- A minimum breeze path through the dwelling of 5 metres.
- Ventilation openings with approximately the same size.

The breeze path is measured between the ventilation openings on different orientations of the dwelling.

Dwelling in or forming part of an apartment development

At least 40 per cent of dwellings have openable windows, doors or other ventilation devices in external walls of the building that provide:

- A maximum breeze path through the dwelling of 18 metres.
- A minimum breeze path through the dwelling of 5 metres.
- Ventilation openings with approximately the same size.

The breeze path is measured between the ventilation openings on different orientations of the dwelling.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size, orientation, slope and wind exposure of the site.

- The extent to which the orientation and layout of the dwelling maximises opportunities for cross ventilation.
- Whether an alternative design meets the relevant objectives having regard to the amenity of the dwelling and site context.

55.03-11 Storage objective

31/03/2025
VC267

To provide adequate storage facilities for each dwelling.

Standard B3-11

Dwelling (other than a dwelling in or forming part of an apartment development)

Each dwelling has exclusive access to at least 6 cubic metres of externally accessible storage space.

Dwelling in or forming part of an apartment development

Each dwelling has exclusive access to storage at least the total minimum storage volume that is specified in Table B3-11.

Table B3-11 Storage

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
Studio	8 cubic metres	5 cubic metres
1 bedroom dwelling	10 cubic metres	6 cubic metres
2 bedroom dwelling	14 cubic metres	9 cubic metres
3 or more bedroom dwelling	18 cubic metres	12 cubic metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability, functionality and location of storage facilities provided for the dwelling.

55.03-12 Accessibility for apartment developments objective

31/03/2025
VC267

To ensure the design of dwellings meets the needs of people with limited mobility.

Standard B3-12

At least 50 per cent of dwellings in or forming part of an apartment development have:

- A clear opening width of at least 850mm at the entrance to the dwelling and main bedroom.
- A clear path with a minimum width of 1.2 metres that connects the dwelling entrance to the main bedroom, an adaptable bathroom and the living area.
- A main bedroom with access to an adaptable bathroom.
- At least one adaptable bathroom that meets all of the requirements of either Design A or Design B specified in Table B3-12.

Table B3-12 Bathroom design

	Design option A	Design option B
Door opening	A clear 850mm wide door opening.	A clear 820mm wide door opening located opposite the shower.
Door design	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards that is clear of the circulation area and has readily removable hinges.	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards and has readily removable hinges.
Circulation area	A clear circulation area that is: ▪ A minimum area of 1.2 metres by 1.2 metres. ▪ Located in front of the shower and the toilet. ▪ Clear of the toilet, basin and the door swing. The circulation area for the toilet and shower can overlap.	A clear circulation area that is: ▪ A minimum width of 1 metre. ▪ The full length of the bathroom and a minimum length of 2.7 metres. ▪ Clear of the toilet and basin. The circulation area can include a shower area.
Path to circulation area	A clear path with a minimum width of 900mm from the door opening to the circulation area.	Not applicable.
Shower	A hobless (step-free) shower.	A hobless (step-free) shower that has a removable shower screen and is located on the furthest wall from the door opening.
Toilet	A toilet located in the corner of the room.	A toilet located closest to the door opening and clear of the circulation area.

55.04 EXTERNAL AMENITY

31/03/2025
VC267

55.04-1 Daylight to existing windows objective

31/03/2025
VC267

To allow adequate daylight into existing habitable room windows.


Standard B4-1

Buildings opposite an existing habitable room window provide for a light court to the existing window that has a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky. The calculation of the area may include land on the abutting lot.

Walls or carports more than 3 metres in height opposite an existing habitable room window are set back from the window at least 50 per cent of the height of the new wall if the wall is within a 55 degree arc from the centre of the existing window. The arc may be swung to within 35 degrees of the plane of the wall containing the existing window.

Where the existing window is above ground floor level, the wall height is measured from the floor level of the room containing the window.

Diagram B4-1 Daylight to existing windows



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which the existing dwelling or small second dwelling has provided for reasonable daylight access to its habitable rooms through the siting and orientation of its habitable room windows.
- The impact on the amenity of existing dwellings or small second dwellings.

55.04-2 Existing north-facing windows objective

02/04/2025
VC276

To allow adequate solar access to existing north-facing habitable room windows.

Standard B4-2

Where a north-facing habitable room window of a neighbouring dwelling or small second dwelling is within 3 metres of a boundary on an abutting lot:

- A new building is to be set back from the boundary by at least 1 metre, plus 0.6 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres. This setback is to be provided for a distance of at least 3 metres from the edge of each side of the window.
- For new buildings that meet the Standard B2-3.2 setback, the building is set back from the boundary by at least 6 metres up to a height not exceeding 11 metres and at least 9 metres for a height over 11 metres between south 30 degrees west to south 30 degrees east. This setback is to be provided for a distance of at least 3 metres from the edge of each side of the window.

For this standard a north-facing window is a window with an axis perpendicular to its surface oriented from north 20 degrees west to north 30 degrees east.

Diagram B4-2.1 North-facing windows





Diagram B4-2.2 North-facing windows



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- Existing sunlight to the north-facing habitable room window of the existing dwelling or small second dwelling.
- The impact on the amenity of existing dwellings or small second dwellings.

55.04-3 Overshadowing secluded open space objective

02/04/2025
VC276

To ensure buildings do not significantly overshadow existing secluded private open space.

Standard B4-3

The area of secluded private open space that is not overshadowed by the new development is greater than 50 per cent, or 25 square metres with a minimum dimension of 3 metres, whichever is the lesser area, for a minimum of five hours between 9 am and 3 pm on 22 September.

If existing sunlight to the secluded private open space of an existing dwelling or small second dwelling is less than the requirements of this standard, the amount of sunlight will not be further reduced.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The impact on the amenity of existing dwellings or small second dwellings.
- Existing sunlight penetration to the secluded private open space of the existing dwelling or small second dwelling.
- The time of day that sunlight will be available to the secluded private open space of the existing dwelling or small second dwelling.
- The effect of a reduction in sunlight on the existing use of the existing secluded private open space.

55.04-4 Overlooking objective

31/03/2025
VC267

To limit views into existing secluded private open space and habitable room windows.

Standard B4-4

In Clause 55.04-4 a habitable room does not include a bedroom.

A habitable room window, balcony, podium, terrace, deck or patio is located and designed to avoid direct views into the secluded private open space of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio. Views are measured within a 45 degree angle from the plane of the window or perimeter of the balcony, terrace, deck or patio, and from a height of 1.7 metres above floor level.

A habitable room window, balcony, terrace, deck or patio that is located with a direct view into a habitable room window of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio:

- Is offset a minimum of 1.5 metres from the edge of one window to the edge of the other; or
- Has sill heights of at least 1.7 metres above floor level; or
- Has fixed, obscure glazing in any part of the window below 1.7 metre above floor level; or
- Has permanently fixed external screens to at least 1.7 metres above floor level and be no more than 25 per cent transparent; or
- Has fixed elements that prevent the direct view, such as horizontal ledges or vertical fins.


Obscure glazing in any part of the window below 1.7 metres above floor level may be openable provided that there are no direct views as specified in this standard.

Screens used to obscure a view are:

- Perforated panels or trellis with a maximum of 25 per cent openings or solid translucent panels.
- Permanent, fixed and durable.
- Designed and coloured to blend in with the development.

This standard does not apply to a new habitable room window, balcony, terrace, deck or patio which faces a property boundary where there is a visual barrier at least 1.8 metres high and the floor level of the habitable room, balcony, terrace, deck or patio is less than 0.8 metres above ground level at the boundary.

Diagram B4-4 Overlooking



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The impact on the amenity of the secluded private open space or habitable room window.

- The existing extent of overlooking into the secluded private open space and habitable room windows of existing dwellings or small second dwellings.
- The internal daylight to and amenity of the proposed dwelling, residential building or small second dwelling.

55.04-5 Internal views objective

31/03/2025
VC267

To limit views into the secluded private open space and habitable room windows of dwellings and residential buildings within a development.

Standard B4-5

In Clause 55.04-5 a habitable room does not include a bedroom.

Within the development, a habitable room window, balcony, terrace, deck or patio that is located with a direct view into the secluded private open space of another dwelling:

- Is offset a minimum of 1.5 metres from the edge of the secluded private open space; or
- Has a sill height of at least 1.7 metres above floor level; or
- Has a fixed, visually obscure balustrade to at least 1.7 metre above floor level; or
- Has permanently fixed external screens to at least 1.7 metres above floor level; or.
- Has fixed elements that prevent the direct view, such as horizontal ledges or vertical fins.

Direct views are measured at a height of 1.7 metres above floor level and within:

- A 45 degree horizontal angle from the edge of the new window or balcony.
- A 45 degree angle in the downward direction.

Screens provided for overlooking are no more than 25 per cent transparent. Screens may be openable provided that this does not allow direct views as specified in this standard.

Decision guideline

Before deciding on an application, the responsible authority must consider the design response.

55.05 SUSTAINABILITY

31/03/2025
VC267

55.05-1 Permeability and stormwater management objective

31/03/2025
VC267

To reduce the impact of increased stormwater run-off on the drainage system and downstream waterways.

To facilitate on-site stormwater infiltration.

To encourage stormwater management that maximises the retention and reuse of stormwater.

To contribute to urban cooling.

Standard B5-1

The site area covered by the pervious surfaces is at least 20 percent of the site.

The development includes a stormwater management system designed to:

- Meet the best practice quantitative performance objectives for stormwater quality specified in the Urban stormwater management guidance (EPA Publication 1739.1, 2021) of:
  - Suspended solids 80% reduction in mean annual load.
  - Total phosphorus and Total Nitrogen 45% reduction in mean annual load.
  - Litter 70% reduction of mean annual load.

  Note:

  A certificate generated from a stormwater assessment tool including Stormwater Treatment Objective - Relative Measurement (STORM), Model for Urban Stormwater Improvement Conceptualisation (MUSIC) or an equivalent product accepted by the responsible authority may be used to demonstrate the performance objectives for stormwater quality are met.

- Direct flows of stormwater into treatment areas, garden areas, tree pits and permeable surfaces, with drainage of residual flows to the legal point of discharge.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The capacity of the site to incorporate stormwater retention and reuse.
- The existing site coverage and any constraints imposed by existing development.
- The capacity of the drainage network to accommodate additional stormwater.

55.05-2 Overshadowing domestic solar energy systems objective

31/03/2025
VC267

To ensure that the height and setback of a building from a boundary allows reasonable solar access to existing domestic solar energy systems on the roofs of buildings.

Standard B5-2

Any part of a new building that will reduce the sunlight at any time between 9am and 4 pm on 22 September to an existing domestic solar energy system on the roof of a building on an adjoining lot be set back from the boundary to that lot by at least 1 metre at 3.6 metres above ground level, plus 0.3 metres for every metre of building height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres.

This standard applies to an existing building in a Township Zone, General Residential Zone or Neighbourhood Residential Zone.

In Clause 55.05-2 domestic solar energy system means a domestic solar energy system that existed at the date the application was lodged.

Decision guidelines

Before deciding on an application, the responsible authority must consider whether the domestic solar energy system has been sited to optimise efficiency and protection from overshadowing.

55.05-3 Rooftop solar energy generation area objective

31/03/2025
VC267

To support the future installation of appropriately sited rooftop solar energy systems for a dwelling.


Standard B5-3

In Clause 55.05-3 rooftop solar energy area means an area provided on the roof of a dwelling to enable the future installation of a solar energy system.

An area on the roof is capable of siting a rooftop solar energy area for each dwelling which:

- Has a minimum dimension of 1.7 metres.
- Has a minimum area in accordance with Table B5-3.
- Is oriented to the north, west or east.
- Is positioned on the top two thirds of a pitched roof.
- Can be a contiguous area or multiple smaller areas.
- Is free of obstructions on the roof of the dwelling within twice the height of each obstruction (H), measured horizontally (D) from the centre point of the base of the obstruction to the nearest point of the rooftop solar energy area.

Diagram B5-3 Allowable distance between obstructions and the rooftop solar energy area



Obstructions located south of all points of the rooftop solar energy area are not subject to the horizontal distance requirements.

Table B5-3 Minimum rooftop solar energy generation area

Number of bedrooms	Minimum roof area
1 bedroom dwelling	15 square metres
2 or 3 bedroom dwelling	26 square metres

Number of bedrooms	Minimum roof area
4 or more bedroom dwelling	34 square metres

This standard does not apply to apartments and residential buildings.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size and orientation of the building.
- The availability of solar access to the rooftop.
- The extent to which the rooftop solar energy generation area is overshadowed by existing buildings, other permanent structures or equipment on the rooftop.

55.05-4 Solar protection to new north-facing windows objective

31/03/2025
VC267

To encourage external shading of north facing windows to minimise summer heat gain.

Standard B5-4

North facing windows are shaded by eaves, fixed horizontal shading devices or fixed awnings with a minimum horizontal depth of 0.25 times the window height.

Decision Guidelines

Before deciding on an application, the responsible authority considers:

- The design response.
- The size and orientation of the lot.
- The type and useability of external solar shading devices, including alternative design responses.

55.05-5 Waste and recycling objectives

31/03/2025
VC267

To ensure dwellings are designed to facilitate waste recycling.

To ensure that waste and recycling facilities are accessible and are of sufficient size to manage organic and general waste, and mixed and glass recycling.

To ensure that waste and recycling facilities are designed and managed to minimise impacts on residential amenity.

Standard B5-5

Dwelling (other than a dwelling in or forming part of an apartment development)

The development includes an individual bin storage area for each dwelling, or a shared bin storage area for use by each dwelling, of at least the applicable area, depth and height specified in Table B5-5.1.

Table B5-5.1 Bin storage

Type of bin storage area	Minimum area	Minimum depth	Minimum height
Individual bin storage area for a dwelling.	1.8 square metres	0.8 metre	1.8 metres

Type of bin storage area	Minimum area	Minimum depth	Minimum height
Shared bin storage area for 3 dwellings or less.	5.4 square metres	0.8 metre	1.8 metres
Shared bin storage area for 4 or more dwellings.	1 square metre per dwelling plus 4 square metres	0.8 metre	1.8 metres

If the development includes a shared bin storage area:

- The shared bin storage area:
  - Is located within 40 metres of a kerbside collection point.
  - Includes a tap for bin washing.
- There is a continuous path of travel free of steps and obstructions from dwellings to the bin storage area.

Where access is provided for private bin collection on the land the design of access ways must allow the vehicle to enter and exit in a forward direction.

Each dwelling includes an internal waste and recycling storage space of at least 0.07 cubic metres with a minimum depth of 250 millimetres.

Dwelling in or forming part of an apartment development

The development includes a shared bin storage area for use by each dwelling of at least the applicable area, depth and height specified in Table B5-5.2.

Table B5-5.2 Apartment bin storage

Number of dwellings	Minimum area	Minimum depth	Minimum height
15 or less dwellings	0.7 square metres per dwelling in a shared waste storage area	0.8 metres	2.7 metres
16 to 55 dwellings	0.5 square metres per dwelling, plus 5 square metres in a shared waste storage area.	1 metre	2.7 metres
56 or more dwellings	0.5 square metres per dwelling in a shared waste storage area.	1 metre	2.7 metres

Enclosed bin storage areas are ventilated by:

- Natural ventilation openings to the external air with an area of at least 5 per cent of the area for bin storage area; or
- A mechanical exhaust ventilation system.

A tap and drain is provided to wash bins.

A continuous path of travel is provided from each dwelling to bin storage areas.

Each dwelling includes an internal waste and recycling storage space of at least 0.07 cubic metres with a minimum depth of 250 millimetres.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response, including a Waste Management Plan.
- Any relevant waste and recycling objective, policy or statement set out in this planning scheme.
- The functionality and accessibility of waste and recycling facilities, including for people with limited mobility.
- Whether facilities are provided for on-site reuse or management of food and garden organics through composting or other waste recovery.
- Whether waste and recycling facilities are designed to meet the better practice design options specified in Waste management and recycling in multi-unit developments (Sustainability Victoria, 2019).

55.05-6 Noise impacts objective

31/03/2025
VC267

To minimise the impact of mechanical plant noise located in the development.

Standard B5-6

Mechanical plant, including mechanical car storage and lift facilities are not located immediately adjacent to bedrooms of new or existing dwellings or small second dwellings, unless a solid barrier is in place to provide a line of sight barrier to transmission of noise and the location of all relevant bedrooms.

Decision guideline

Before deciding on an application, the responsible authority must consider:

- The design response.
- Whether the impact of potential noise sources within a development have been mitigated through design, location and siting.
- Whether an alternative design meets the relevant objectives having regard to the amenity of the dwelling or small second dwelling and the site context.

55.05-7 Energy efficiency for apartment developments objectives

31/03/2025
VC267

To achieve energy efficient dwellings and buildings.

To ensure dwellings achieve adequate thermal efficiency.

Standard B5-7

Dwellings in or forming part of an apartment development located in a climate zone identified in Table B5-7 do not exceed the maximum NatHERS annual cooling load.

NatHERS climate zone	NatHERS maximum cooling load MJ/M^2 per annum
Climate zone 21 Melbourne	30
Climate zone 22 East Sale	22
Climate zone 27 Mildura	69
Climate zone 60 Tullamarine	22
Climate zone 62 Moorabbin	21

NatHERS climate zone	NatHERS maximum cooling load MJ/M^2 per annum
Climate zone 63 Warrnambool	21
Climate zone 64 Cape Otway	19
Climate zone 66 Ballarat	23

Note:

Refer to NatHERS zone map, Nationwide House Energy Rating Scheme (Commonwealth Department of Environment and Energy).

Decision Guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size, orientation and layout of the site.
- The availability of solar access to north-facing windows on the site.
- The annual cooling load for each dwelling.

56
25/02/2025
VC257

RESIDENTIAL SUBDIVISION

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To create liveable and sustainable neighbourhoods and urban places with character and identity.

To achieve residential subdivision outcomes that appropriately respond to the site and its context for:

- Metropolitan Melbourne growth areas.
- Infill sites within established residential areas.
- Regional cities and towns.

To ensure residential subdivision design appropriately provides for:

- Policy implementation.
- Liveable and sustainable communities.
- Residential lot design.
- Urban landscape.
- Access and mobility management.
- Integrated water management.
- Site management.
- Utilities.

Application

These provisions apply to an application to subdivide land in the Neighbourhood Residential Zone, General Residential Zone, Residential Growth Zone, Housing Choice and Transport Zone, Mixed Use Zone or Township Zone and any Comprehensive Development Zone or Priority Development Zone that provides for residential development.

These provisions do not apply to an application to subdivide land into lots each containing an existing dwelling or car parking space.

Operation

The provisions of this clause contain:

- **Objectives.** An objective describes the desired outcome to be achieved in the completed subdivision.
- **Standards.** A standard contains the requirements to meet the objective.

A standard should normally be met. However, if the responsible authority is satisfied that an application for an alternative design solution meets the objective, the alternative design solution may be considered.

Requirement

An application to subdivide land:

- Must be accompanied by a site and context description and a design response.
- Must meet all of the objectives included in the clauses specified in the zone.
- Should meet all of the standards included in the clauses specified in the zone.

Certification of standards

A subdivision may be certified by a person authorised by the Minister for Planning as meeting the requirements of a standard in this clause.

A standard that is certified as met is deemed to have met the objective of that standard.

56.01 SUBDIVISION SITE AND CONTEXT DESCRIPTION AND DESIGN RESPONSE

16/01/2018
VC142

56.01-1 Subdivision site and context description

16/01/2018
VC142

The site and context description may use a site plan, photographs or other techniques and must accurately describe:

- In relation to the site:
  - Site shape, size, dimensions and orientation.
  - Levels and contours of the site.
  - Natural features including trees and other significant vegetation, drainage lines, water courses, wetlands, ridgelines and hill tops.
  - The siting and use of existing buildings and structures.
  - Street frontage features such as poles, street trees and kerb crossovers.
  - Access points.
  - Location of drainage and other utilities.
  - Easements.
  - Any identified natural or cultural features of the site.
  - Significant views to and from the site.
  - Noise and odour sources or other external influences.
  - Soil conditions, including any land affected by contamination, erosion, salinity, acid sulphate soils or fill.
  - Any other notable features or characteristics of the site.
  - Adjacent uses.
  - Any other factor affecting the capacity to develop the site including whether the site is affected by inundation.
- An application for subdivision of 3 or more lots must also describe in relation to the surrounding area:
  - The pattern of subdivision.
  - Existing land uses.
  - The location and use of existing buildings on adjacent land.
  - Abutting street and path widths, materials and detailing.
  - The location and type of significant vegetation.
- An application for subdivision of 60 or more lots must also describe in relation to the surrounding area:
  - Location, distance and type of any nearby public open space and recreational facilities.
  - Direction and distances to local shops and community facilities.
  - Directions and walking distances to public transport routes and stops.
  - Direction and walking distances to existing neighbourhood, major and principal activity centres and major employment areas.

- Existing transport routes, including freeways, arterial roads and streets connecting neighbourhoods.
- Local street network including potential connections to adjacent subdivisions.
- Traffic volumes and movements on adjacent roads and streets.
- Pedestrian, bicycle and shared paths identifying whether their primary role is neighbourhood or regional access.
- Any places of cultural significance.
- Natural features including trees and other significant vegetation, drainage lines, water courses, wetlands, ridgelines and hill tops.
- Proximity of any fire threats.
- Pattern of ownership of adjoining lots.

If in the opinion of the responsible authority a requirement of the site and context description is not relevant to the assessment of an application, the responsible authority may waive or reduce the requirement.

Satisfactory subdivision site and context description

If the responsible authority decides that the site and context description is not satisfactory, it may require more information from the applicant under Section 54 of the Act.

The responsible authority must not require notice of an application to be given or decide an application until it is satisfied that the site and context description meets the requirements of Clause 56.01-1 and is satisfactory.

This does not apply if the responsible authority refuses an application under Section 52(1A) of the Act.

56.01-2 Subdivision design response

09/10/2006
VC42

The design response must explain how the proposed design:

- Derives from and responds to the site and context description.
- Responds to any site and context features for the area identified in a local planning policy or a Neighbourhood Character Overlay.
- Responds to any relevant objective, policy, strategy or plan set out for the area in this scheme.
- Meets the relevant objectives of Clause 56.

The design response must include a dimensioned plan to scale showing the layout of the subdivision in context with the surrounding area. If in the opinion of the responsible authority this requirement is not relevant to the assessment of an application, it may waive or reduce the requirement.

An application for subdivision of 60 or more lots must also include a plan that meets the requirements of Standard C2. The plan must also show the:

- Proposed uses of each part of the site.
- Natural features of the site and identify any features proposed to be altered.
- Proposed integrated water management system.
- Proposed staging of the subdivision.

56.02 POLICY IMPLEMENTATION

09/10/2006
VC42

56.02-1 Strategic implementation objective

09/10/2006
VC42

To ensure that the layout and design of a subdivision is consistent with and implements any objective, policy, strategy or plan for the area set out in this scheme.

Standard C1

An application must be accompanied by a written statement that describes how the subdivision is consistent with and implements any relevant growth area, activity centre, housing, access and mobility, community facilities, open space and recreation, landscape (including any native vegetation precinct plan) and urban design objective, policy, strategy or plan for the area set out in this scheme.

56.03 LIVEABLE AND SUSTAINABLE COMMUNITIES

19/09/2017
VC132

56.03-1 Compact and walkable neighbourhoods objectives

09/10/2006
VC42

To create compact neighbourhoods that are oriented around easy walking distances to activity centres, schools and community facilities, public open space and public transport.

To allow easy movement through and between neighbourhoods for all people.

Standard C2

A subdivision should implement any relevant growth area or any approved land-use and development strategy, plan or policy for the area set out in this scheme.

An application for subdivision must include a plan of the layout of the subdivision that:

- Meets the objectives (if relevant to the class of subdivision specified in the zone) of:
  - Clause 56.03-2 Activity centres
  - Clause 56.03-3 Planning for community facilities
  - Clause 56.04-1 Lot diversity and distribution
  - Clause 56.06-2 Walking and cycling network
  - Clause 56.06-3 Public transport network
  - Clause 56.06-4 Neighbourhood street network
- Shows the 400 metre street walking distance around each existing or proposed bus stop, 600 metres street walking distance around each existing or proposed tram stop and 800 metres street walking distance around each existing or proposed railway station and shows the estimated number of dwellings within those distances.
- Shows the layout of the subdivision in relation to the surrounding area.
- Is designed to be accessible for people with disabilities.

56.03-2 Activity centre objective

09/10/2006
VC42

To provide for mixed-use activity centres, including neighbourhood activity centres, of appropriate area and location.

Standard C3

A subdivision should implement any relevant activity centre strategy, plan or policy for the area set out in this scheme.

Subdivision should be supported by activity centres that are:

- Accessible by neighbourhood and regional walking and cycling networks.
- Served by public transport that is connected to the regional public transport network.
- Located at public transport interchange points for the convenience of passengers and easy connections between public transport services.
- Located on arterial roads or connector streets.
- Of appropriate size to accommodate a mix of uses that meet local community needs.
- Oriented to support active street frontages, support street-based community interaction and pedestrian safety.

56.03-3 Planning for community facilities objective

20/03/2023
VC229

To provide appropriately located sites for community facilities including schools, libraries, preschools and childcare, health services, police and fire stations, recreation and sports facilities.

Standard C4

A subdivision should:

- Implement any relevant regional and local community facility strategy, plan or policy for the area set out in this scheme.
- Locate community facilities on sites that are in or near activity centres and public transport.

School sites should:

- Be integrated with the neighbourhood and located near activity centres.
- Be located on walking and cycling networks.
- Have a bus stop located along the school site boundary.
- Have student drop-off zones, bus parking and on-street parking in addition to other street functions in abutting streets.
- Adjoin the public open space network and community sporting and other recreation facilities.
- Be integrated with community facilities.
- Be located on land that is not affected by physical, environmental or other constraints.

Schools should be accessible by the Principal Public Transport Network in Metropolitan Melbourne and on the regional public transport network outside Metropolitan Melbourne.

Primary schools should be located on connector streets and not on arterial roads.

New State Government school sites must meet the requirements of the Department of Education and abut at least two streets with sufficient widths to provide student drop-off zones, bus parking and on-street parking in addition to other street functions.

56.03-4 Built environment objective

09/10/2006
VC42

To create urban places with identity and character.

Standard C5

The built environment should:

- Implement any relevant urban design strategy, plan or policy for the area set out in this scheme.
- Provide living and working environments that are functional, safe and attractive.
- Provide an integrated layout, built form and urban landscape.
- Contribute to a sense of place and cultural identity.

An application should describe the identity and character to be achieved and the elements that contribute to that identity and character.

56.03-5 Neighbourhood character objective

09/10/2006
VC42

To design subdivisions that respond to neighbourhood character.

Standard C6

Subdivision should:

- Respect the existing neighbourhood character or achieve a preferred neighbourhood character consistent with any relevant neighbourhood character objective, policy or statement set out in this scheme.
- Respond to and integrate with the surrounding urban environment.
- Protect significant vegetation and site features.

56.04 LOT DESIGN

09/10/2006
VC42

56.04-1 Lot diversity and distribution objectives

09/10/2006
VC42

To achieve housing densities that support compact and walkable neighbourhoods and the efficient provision of public transport services.

To provide higher housing densities within walking distance of activity centres.

To achieve increased housing densities in designated growth areas.

To provide a range of lot sizes to suit a variety of dwelling and household types.

Standard C7

A subdivision should implement any relevant housing strategy, plan or policy for the area set out in this scheme.

Lot sizes and mix should achieve the average net residential density specified in any zone or overlay that applies to the land or in any relevant policy for the area set out in this scheme.

A range and mix of lot sizes should be provided including lots suitable for the development of:

- Single dwellings.
- Two dwellings or more.
- Higher density housing.
- Residential buildings and Retirement villages.

Unless the site is constrained by topography or other site conditions, lot distribution should provide for 95 per cent of dwellings to be located no more than 400 metre street walking distance from the nearest existing or proposed bus stop, 600 metres street walking distance from the nearest existing or proposed tram stop and 800 metres street walking distance from the nearest existing or proposed railway station.

Lots of 300 square metres or less in area, lots suitable for the development of two dwellings or more, lots suitable for higher density housing and lots suitable for Residential buildings and Retirement villages should be located in and within 400 metres street walking distance of an activity centre.

56.04-2 Lot area and building envelopes objective

08/09/2025
VC282

To provide lots with areas and dimensions that enable the appropriate siting and construction of a dwelling, solar access, private open space, vehicle access and parking, water management, easements and the retention of significant vegetation and site features.

Standard C8

An application to subdivide land that creates lots of less than 300 square metres should be accompanied by information that shows:

- That the lots are consistent or contain building envelope that is consistent with a development approved under this scheme, or
- That a dwelling may be constructed on each lot in accordance with the requirements of this scheme.

Lots of between 300 square metres and 500 square metres should:

- Contain a building envelope that is consistent with a development of the lot approved under this scheme, or
- If no development of the lot has been approved under this scheme, contain a building envelope and be able to contain a rectangle measuring 10 metres by 15 metres, or 9 metres by 15 metres if a boundary wall is nominated as part of the building envelope.

If lots of between 300 square metres and 500 square metres are proposed to contain dwellings that are built to the boundary, the long axis of the lots should be within 30 degrees east and 20 degrees west of north unless there are significant physical constraints that make this difficult to achieve.

Lots greater than 500 square metres should be able to contain a rectangle measuring 10 metres by 15 metres, and may contain a building envelope.

A building envelope may specify or incorporate any relevant siting and design requirement. Any requirement should meet the relevant standards of Clause 54, unless:

- The objectives of the relevant standards are met, and
- The building envelope is shown as a restriction on a plan of subdivision registered under the *Subdivision Act 1988*, or is specified as a covenant in an agreement under Section 173 of the Act.

Where a lot with a building envelope adjoins a lot that is not on the same plan of subdivision or is not subject to the same agreement relating to the relevant building envelope:

- The building envelope must meet Standards A2-3 and A2-4 of Clause 54 in relation to the adjoining lot, and
- The building envelope must not regulate siting matters covered by Standards A4-1 to A4-4 (inclusive) of Clause 54 in relation to the adjoining lot. This should be specified in the relevant plan of subdivision or agreement.

Lot dimensions and building envelopes should protect:

- Solar access for future dwellings and support the siting and design of dwellings that achieve the energy rating requirements of the Building Regulations.
- Existing or proposed easements on lots.
- Significant vegetation and site features.

56.04-3 Solar orientation of lots objective

09/10/2006
VC42

To provide good solar orientation of lots and solar access for future dwellings.

Standard C9

Unless the site is constrained by topography or other site conditions, at least 70 percent of lots should have appropriate solar orientation.

Lots have appropriate solar orientation when:

- The long axis of lots are within the range north 20 degrees west to north 30 degrees east, or east 20 degrees north to east 30 degrees south.
- Lots between 300 square metres and 500 square metres are proposed to contain dwellings that are built to the boundary, the long axis of the lots should be within 30 degrees east and 20 degrees west of north.
- Dimensions of lots are adequate to protect solar access to the lot, taking into account likely dwelling size and the relationship of each lot to the street.

56.04-4 Street orientation objective

09/10/2006
VC42

To provide a lot layout that contributes to community social interaction, personal safety and property security.

Standard C10

Subdivision should increase visibility and surveillance by:

- Ensuring lots front all roads and streets and avoid the side or rear of lots being oriented to connector streets and arterial roads.
- Providing lots of 300 square metres or less in area and lots for 2 or more dwellings around activity centres and public open space.
- Ensuring streets and houses look onto public open space and avoiding sides and rears of lots along public open space boundaries.
- Providing roads and streets along public open space boundaries.

56.04-5 Common area objectives

09/10/2006
VC42

To identify common areas and the purpose for which the area is commonly held.

To ensure the provision of common area is appropriate and that necessary management arrangements are in place.

To maintain direct public access throughout the neighbourhood street network.

Standard C11

An application to subdivide land that creates common land must be accompanied by a plan and a report identifying:

- The common area to be owned by the body corporate, including any streets and open space.
- The reasons why the area should be commonly held.
- Lots participating in the body corporate.
- The proposed management arrangements including maintenance standards for streets and open spaces to be commonly held.

56.05 URBAN LANDSCAPE

01/10/2009
VC58

56.05-1 Integrated urban landscape objectives

09/10/2006
VC42

To provide attractive and continuous landscaping in streets and public open spaces that contribute to the character and identity of new neighbourhoods and urban places or to existing or preferred neighbourhood character in existing urban areas.

To incorporate natural and cultural features in the design of streets and public open space where appropriate.

To protect and enhance native habitat and discourage the planting and spread of noxious weeds.

To provide for integrated water management systems and contribute to drinking water conservation.

Standard C12

An application for subdivision that creates streets or public open space should be accompanied by a landscape design.

The landscape design should:

- Implement any relevant streetscape, landscape, urban design or native vegetation precinct plan, strategy or policy for the area set out in this scheme.
- Create attractive landscapes that visually emphasise streets and public open spaces.
- Respond to the site and context description for the site and surrounding area.
- Maintain significant vegetation where possible within an urban context.
- Take account of the physical features of the land including landform, soil and climate.
- Protect and enhance any significant natural and cultural features.
- Protect and link areas of significant local habitat where appropriate.
- Support integrated water management systems with appropriate landscape design techniques for managing urban run-off including wetlands and other water sensitive urban design features in streets and public open space.
- Promote the use of drought tolerant and low maintenance plants and avoid species that are likely to spread into the surrounding environment.
- Ensure landscaping supports surveillance and provides shade in streets, parks and public open space.
- Develop appropriate landscapes for the intended use of public open space including areas for passive and active recreation, the exercising of pets, playgrounds and shaded areas.
- Provide for walking and cycling networks that link with community facilities.
- Provide appropriate pathways, signage, fencing, public lighting and street furniture.
- Create low maintenance, durable landscapes that are capable of a long life.
- The landscape design must include a maintenance plan that sets out maintenance responsibilities, requirements and costs.

56.05-2 Public open space provision objectives

01/10/2009
VC58

To provide a network of quality, well-distributed, multi-functional and cost-effective public open space that includes local parks, active open space, linear parks and trails, and links to regional open space.

To provide a network of public open space that caters for a broad range of users.

To encourage healthy and active communities.

To provide adequate unencumbered land for public open space and integrate any encumbered land with the open space network.

To ensure land provided for public open space can be managed in an environmentally sustainable way and contributes to the development of sustainable neighbourhoods.

Standard C13

The provision of public open space should:

- Implement any relevant objective, policy, strategy or plan (including any growth area precinct structure plan) for open space set out in this scheme.
- Provide a network of well-distributed neighbourhood public open space that includes:
- Local parks within 400 metres safe walking distance of at least 95 percent of all dwellings. Where not designed to include active open space, local parks should be generally 1 hectare in area and suitably dimensioned and designed to provide for their intended use and to allow easy adaptation in response to changing community preferences.
- Additional small local parks or public squares in activity centres and higher density residential areas.
- Active open space of a least 8 hectares in area within 1 kilometre of 95 percent of all dwellings that is:
- Suitably dimensioned and designed to provide for the intended use, buffer areas around sporting fields and passive open space
- Sufficient to incorporate two football/cricket ovals
- Appropriate for the intended use in terms of quality and orientation
- Located on flat land (which can be cost effectively graded)
- Located with access to, or making provision for, a recycled or sustainable water supply
- Adjoin schools and other community facilities where practical
- Designed to achieve sharing of space between sports.
- Linear parks and trails along waterways, vegetation corridors and road reserves within 1 kilometre of 95 percent of all dwellings.

Public open space should:

- Be provided along foreshores, streams and permanent water bodies.
- Be linked to existing or proposed future public open spaces where appropriate.
- Be integrated with floodways and encumbered land that is accessible for public recreation.
- Be suitable for the intended use.
- Be of an area and dimensions to allow easy adaptation to different uses in response to changing community active and passive recreational preferences.
- Maximise passive surveillance.
- Be integrated with urban water management systems, waterways and other water bodies.
- Incorporate natural and cultural features where appropriate.

56.06 ACCESS AND MOBILITY MANAGEMENT

18/06/2010
VC62

56.06-1 Integrated mobility objectives

18/06/2010
VC62

To achieve an urban structure where compact and walkable neighbourhoods are clustered to support larger activity centres on the Principal Public Transport Network in Metropolitan Melbourne and on the regional public transport network outside Metropolitan Melbourne.

To provide for walking (including persons with impaired mobility), cycling, public transport and other motor vehicles in an integrated manner.

To contribute to reduced car dependence, improved energy efficiency, improved transport efficiency, reduced greenhouse gas emissions and reduced air pollution.

Standard C14

An application for a subdivision must include a plan of the layout of the neighbourhood that meets the objectives of:

- Clause 56.06-2 Walking and cycling network.
- Clause 56.06-3 Public transport network.
- Clause 56.06-4 Neighbourhood street network.

56.06-2 Walking and cycling network objectives

09/10/2006
VC42

To contribute to community health and well being by encouraging walking and cycling as part of the daily lives of residents, employees and visitors.

To provide safe and direct movement through and between neighbourhoods by pedestrians and cyclists.

To reduce car use, greenhouse gas emissions and air pollution.

Standard C15

The walking and cycling network should be designed to:

- Implement any relevant regional and local walking and cycling strategy, plan or policy for the area set out in this scheme.
- Link to any existing pedestrian and cycling networks.
- Provide safe walkable distances to activity centres, community facilities, public transport stops and public open spaces.
- Provide an interconnected and continuous network of safe, efficient and convenient footpaths, shared paths, cycle paths and cycle lanes based primarily on the network of arterial roads, neighbourhood streets and regional public open spaces.
- Provide direct cycling routes for regional journeys to major activity centres, community facilities, public transport and other regional activities and for regional recreational cycling.
- Ensure safe street and road crossings including the provision of traffic controls where required.
- Provide an appropriate level of priority for pedestrians and cyclists.
- Have natural surveillance along streets and from abutting dwellings and be designed for personal safety and security particularly at night.
- Be accessible to people with disabilities.

56.06-3 Public transport network objectives

09/10/2006
VC42

To provide an arterial road and neighbourhood street network that supports a direct, efficient and safe public transport system.

To encourage maximum use of public transport.

Standard C16

The public transport network should be designed to:

- Implement any relevant public transport strategy, plan or policy for the area set out in this scheme.
- Connect new public transport routes to existing and proposed routes to the satisfaction of the relevant public transport authority.
- Provide for public transport links between activity centres and other locations that attract people using the Principal Public Transport Network in Metropolitan Melbourne and the regional public transport network outside Metropolitan Melbourne.
- Locate regional bus routes principally on arterial roads and locate local bus services principally on connector streets to provide:
  - Safe and direct movement between activity centres without complicated turning manoeuvres.
  - Direct travel between neighbourhoods and neighbourhood activity centres.
  - A short and safe walk to a public transport stop from most dwellings.

56.06-4 Neighbourhood street network objective

14/05/2021
VC198

To provide for direct, safe and easy movement through and between neighbourhoods for pedestrians, cyclists, public transport and other motor vehicles using the neighbourhood street network.

Standard C17

The neighbourhood street network must:

- Take account of the existing mobility network of arterial roads, neighbourhood streets, cycle paths, shared paths, footpaths and public transport routes.
- Provide clear physical distinctions between arterial roads and neighbourhood street types.
- Comply with the Head, Transport for Victoria's arterial road access management policies.
- Provide an appropriate speed environment and movement priority for the safe and easy movement of pedestrians and cyclists and for accessing public transport.
- Provide safe and efficient access to activity centres for commercial and freight vehicles.
- Provide safe and efficient access to all lots for service and emergency vehicles.
- Provide safe movement for all vehicles.
- Incorporate any necessary traffic control measures and traffic management infrastructure.

The neighbourhood street network should be designed to:

- Implement any relevant transport strategy, plan or policy for the area set out in this scheme.
- Include arterial roads at intervals of approximately 1.6 kilometres that have adequate reservation widths to accommodate long term movement demand.
- Include connector streets approximately halfway between arterial roads and provide adequate reservation widths to accommodate long term movement demand.
- Ensure connector streets align between neighbourhoods for direct and efficient movement of pedestrians, cyclists, public transport and other motor vehicles.
- Provide an interconnected and continuous network of streets within and between neighbourhoods for use by pedestrians, cyclists, public transport and other vehicles.
- Provide an appropriate level of local traffic dispersal.

- Indicate the appropriate street type.
- Provide a speed environment that is appropriate to the street type.
- Provide a street environment that appropriately manages movement demand (volume, type and mix of pedestrians, cyclists, public transport and other motor vehicles).
- Encourage appropriate and safe pedestrian, cyclist and driver behaviour.
- Provide safe sharing of access lanes and access places by pedestrians, cyclists and vehicles.
- Minimise the provision of culs-de-sac.
- Provide for service and emergency vehicles to safely turn at the end of a dead-end street.
- Facilitate solar orientation of lots.
- Facilitate the provision of the walking and cycling network, integrated water management systems, utilities and planting of trees.
- Contribute to the area's character and identity.
- Take account of any identified significant features.

56.06-5 Walking and cycling network detail objectives

09/10/2006
VC42

To design and construct footpaths, shared path and cycle path networks that are safe, comfortable, well constructed and accessible for people with disabilities.

To design footpaths to accommodate wheelchairs, prams, scooters and other footpath bound vehicles.

Standard C18

Footpaths, shared paths, cycle paths and cycle lanes should be designed to:

- Be part of a comprehensive design of the road or street reservation.
- Be continuous and connect.
- Provide for public transport stops, street crossings for pedestrians and cyclists and kerb crossovers for access to lots.
- Accommodate projected user volumes and mix.
- Meet the requirements of Table C1.
- Provide pavement edge, kerb, channel and crossover details that support safe travel for pedestrians, footpath bound vehicles and cyclists, perform required drainage functions and are structurally sound.
- Provide appropriate signage.
- Be constructed to allow access to lots without damage to the footpath or shared path surfaces.
- Be constructed with a durable, non-skid surface.
- Be of a quality and durability to ensure:
  - Safe passage for pedestrians, cyclists, footpath bound vehicles and vehicles.
  - Discharge of urban run-off.
  - Preservation of all-weather access.
  - Maintenance of a reasonable, comfortable riding quality.
  - A minimum 20 year life span.

- Be accessible to people with disabilities and include tactile ground surface indicators, audible signals and kerb ramps required for the movement of people with disabilities.

56.06-6 Public transport network detail objectives

09/10/2006
VC42

To provide for the safe, efficient operation of public transport and the comfort and convenience of public transport users.

To provide public transport stops that are accessible to people with disabilities.

Standard C19

Bus priority measures must be provided along arterial roads forming part of the existing or proposed Principal Public Transport Network in Metropolitan Melbourne and the regional public transport network outside Metropolitan Melbourne to the requirements of the relevant roads authority.

Road alignment and geometry along bus routes should provide for the efficient, unimpeded movement of buses and the safety and comfort of passengers.

The design of public transport stops should not impede the movement of pedestrians.

Bus and tram stops should have:

- Surveillance from streets and adjacent lots.
- Safe street crossing conditions for pedestrians and cyclists.

Safe pedestrian crossings on arterial roads and at schools including the provision of traffic controls as required by the roads authority.

- Continuous hard pavement from the footpath to the kerb.
- Sufficient lighting and paved, sheltered waiting areas for forecast user volume at neighbourhood centres, schools and other locations with expected high patronage.
- Appropriate signage.

Public transport stops and associated waiting areas should be accessible to people with disabilities and include tactile ground surface indicators, audible signals and kerb ramps required for the movement of people with physical disabilities.

56.06-7 Neighbourhood street network detail objective

15/09/2008
VC49

To design and construct street carriageways and verges so that the street geometry and traffic speeds provide an accessible and safe neighbourhood street system for all users.

Standard C20

The design of streets and roads should:

- Meet the requirements of Table C1. Where the widths of access lanes, access places, and access streets do not comply with the requirements of Table C1, the requirements of the relevant fire authority and roads authority must be met.
- Provide street blocks that are generally between 120 metres and 240 metres in length and generally between 60 metres to 120 metres in width to facilitate pedestrian movement and control traffic speed.
- Have verges of sufficient width to accommodate footpaths, shared paths, cycle paths, integrated water management, street tree planting, lighting and utility needs.
- Have street geometry appropriate to the street type and function, the physical land characteristics and achieve a safe environment for all users.
- Provide a low-speed environment while allowing all road users to proceed without unreasonable inconvenience or delay.

- Provide a safe environment for all street users applying speed control measures where appropriate.
- Ensure intersection layouts clearly indicate the travel path and priority of movement for pedestrians, cyclists and vehicles.
- Provide a minimum 5 metre by 5 metre corner splay at junctions with arterial roads and a minimum 3 metre by 3 metre corner splay at other junctions unless site conditions justify a variation to achieve safe sight lines across corners.
- Ensure streets are of sufficient strength to:
  - Enable the carriage of vehicles.
  - Avoid damage by construction vehicles and equipment.
- Ensure street pavements are of sufficient quality and durability for the:
  - Safe passage of pedestrians, cyclists and vehicles.
  - Discharge of urban run-off.
  - Preservation of all-weather access and maintenance of a reasonable, comfortable riding quality.
- Ensure carriageways of planned arterial roads are designed to the requirements of the relevant road authority.
- Ensure carriageways of neighbourhood streets are designed for a minimum 20 year life span.
- Provide pavement edges, kerbs, channel and crossover details designed to:
  - Perform the required integrated water management functions.
  - Delineate the edge of the carriageway for all street users.
  - Provide efficient and comfortable access to abutting lots at appropriate locations.
  - Contribute to streetscape design.
- Provide for the safe and efficient collection of waste and recycling materials from lots.
- Be accessible to people with disabilities.
- Meet the requirements of Table C1. Where the widths of access lanes, access places, and access streets do not comply with the requirements of Table C1, the requirements of the relevant fire authority and roads authority must be met. Where the widths of connector streets do not comply with the requirements of Table C1, the requirements of the relevant public transport authority must be met.

A street detail plan should be prepared that shows, as appropriate:

- The street hierarchy and typical cross-sections for all street types.
- Location of carriageway pavement, parking, bus stops, kerbs, crossovers, footpaths, tactile surface indicators, cycle paths and speed control and traffic management devices.
- Water sensitive urban design features.
- Location and species of proposed street trees and other vegetation.
- Location of existing vegetation to be retained and proposed treatment to ensure its health.
- Any relevant details for the design and location of street furniture, lighting, seats, bus stops, telephone boxes and mailboxes.

56.06-8 Lot access objective

18/06/2010
VC62

To provide for safe vehicle access between roads and lots.

Standard C21

Vehicle access to lots abutting arterial roads should be provided from service roads, side or rear access lanes, access places or access streets where appropriate and in accordance with the access management requirements of the relevant roads authority.

Vehicle access to lots of 300 square metres or less in area and lots with a frontage of 7.5 metres or less should be provided via rear or side access lanes, places or streets.

The design and construction of a crossover should meet the requirements of the relevant road authority.

Table C1 Design of roads and neighbourhood streets

Access Lane

A side or rear lane principally providing access to parking on lots with another street frontage.

Traffic volume[1]	300vpd
Target speed[2]	10kph
Carriageway width[3] **& parking provision within street reservation**	5.5m[6] wide with no parking spaces to be provided. Appropriately signed.
Verge width[4]	No verge required.
Kerbing[5]	
Footpath provision	None Carriageway designed as a shared zone and appropriately signed.
Cycle path provision	None

Access Place

A minor street providing local residential access with shared traffic, pedestrian and recreation use, but with pedestrian priority.

Traffic volume[1]	300vpd to1000vpd
Target speed[2]	15kph
Carriageway width[3] **& parking provision within street reservation**	5.5m wide with 1 hard standing verge parking space per 2 lots. or 5.5m wide with parking on carriageway - one side. Appropriately signed.
Verge width[4]	7.5m minimum total width. For services provide a minimum of 3.5m on one side and a minimum of 2.5m on the other.

Kerbing[5]	Semi-mountable rollover or flush and swale or other water sensitive urban design treatment area.
Footpath provision	Not required if serving 5 dwellings or less and the carriageway is designed as a shared zone and appropriately signed. or 1.5m wide footpath offset a minimum distance of 1m from the kerb.
Cycle path provision	None

Access Street - Level 1

A street providing local residential access where traffic is subservient, speed and volume are low and pedestrian and bicycle movements are facilitated.

Traffic volume[1]	1000vpd to 2000vpd
Target speed[2]	30kph
Carriageway width[3] **& parking provision within street reservation**	5.5m wide with1 hard standing verge parking space per 2 lots.
Verge width[4]	4m minimum each side
Kerbing[5]	Semi-mountable rollover or flush and swale or other water sensitive urban design treatment area.
Footpath provision	1.5m wide footpaths on both sides. Footpaths should be widened to 2.0m in vicinity of a school, shop or other activity centre. Be offset a minimum distance of 1m from the kerb.
Cycle path provision	Carriageway designed as a shared zone and appropriately signed.

Access Street - Level 2

A street providing local residential access where traffic is subservient, speed and volume are low and pedestrian and bicycle movements are facilitated.

Traffic volume[1]	2000vpd to 3000vpd
Target speed[2]	40kph
Carriageway width[3] **& parking provision within street reservation**	7m-7.5m wide with parking on both sides of carriageway
Verge width[4]	4.5m minimum each side
Kerbing[5]	Semi-mountable rollover or flush and swale or other water sensitive urban design treatment area.
Footpath provision	1.5m wide footpaths on both sides. Footpaths should be widened to 2.0m in vicinity of a school, shop or other activity centre.

	Be offset a minimum distance of 1m from the kerb.
Cycle path provision	Carriageway designed as a shared zone and appropriately signed.

Connector Street - Level 1

A street that carries higher volumes of traffic. It connects access places and access streets through and between neighbourhoods.

Traffic volume[1]	3000 vpd
Target speed[2]	50 kph[7] reduced to 40 kph at schools and 20 kph at pedestrian and cycle crossing points.
Carriageway width[3]**, cycle lane provision, parking provision and bus stops within street reservation**	▪ 3.5m minimum lane width in each direction of travel. ▪ 4.0m minimum lane width at approaches to and departures from roundabouts and T-intersections. ▪ For on-street cycling, increase the minimum clear carriageway in each direction by: – 0.7m where the trafficable carriageway is shared by cyclists but no dedicated bicycle lane is marked on the carriageway; or – 1.5m where a trafficable carriageway is shared by cyclists but no dedicated bicycle lane is marked on the carriageway and there is a single lane in each direction separated by a raised trafficable median of at least 2.0m in width with mountable kerbs; or – 1.7m where a dedicated 1.7m wide bicycle lane is marked on the carriageway. ▪ An additional dedicated parking lane or indented parking within the verge must be provided where street parking is required. A parking lane width of 2.3m is required where parallel parking is provided. ▪ Bus stops at the kerbside, not indented within the verge.
Verge width[4]	4.5m minimum each side.
Kerbing[5]	Semi-mountable rollover or flush and swale or other water sensitive urban design treatment area.
Footpath provision	▪ 1.5m wide footpaths on both sides. ▪ Footpath widened to a minimum 2.0m in the vicinity of a school, shop, public transport stop or other activity centre. ▪ Footpaths offset a minimum distance of 1m from the kerb.

Connector Street - Level 2

A street that carries higher volumes of traffic. It connects access places and access streets through and between neighbourhoods.

Traffic volume[1]	3,000 vpd to 7,000 vpd
Target speed[2]	60 kph[8] or 50km/h reduced to 40kph at schools.

Carriageway width[3], cycle lane provision, parking provision and bus stops within street reservation	▪ 3.5m minimum lane width in each direction of travel. ▪ 4.0m minimum lane width at approaches to and departures from roundabouts and T-intersections. ▪ 7.0m minimum carriageway width in each direction of travel where there are two lanes in each direction separated by a non-trafficable central medium. ▪ 8.0m minimum carriageway width at approaches to and departures from roundabouts and T-intersections where there are two lanes in each direction separated by an non-trafficable central medium. ▪ For on-street cycling, increase the minimum clear carriageway in each direction by: – 0.7m where the trafficable carriageway is shared by cyclists but no dedicated bicycle lane is marked on the carriageway; or – 1.7m where a dedicated 1.7m wide dedicated bicycle lane is marked on the carriageway – 0.3m where there are two trafficable lanes in each direction separated by a non-trafficable central median and the carriageways are shared by cyclists but no dedicated bicycle lane is marked on the carriageway; or – 0.5m where there are two trafficable lanes in each direction separated by a non-trafficable central median and a 1.7m wide dedicated bicycle lane is marked on the carriageway. ▪ An additional dedicated parking lane or indented parking within the verge must be provided where street parking is required. A parking lane width of 2.3m is required where parallel parking is provided. ▪ Bus stops located at the kerbside, not indented within the verge.
Verge width[4]	▪ 6m minimum each side (plus central median).
Kerbing[5]	▪ Semi-mountable rollover or flush and swale or other water sensitive urban design treatment area.
Footpath and cycle path provision	▪ 1.5m wide footpath on each side and 1.7m bicycle lanes on the carriageway; or ▪ 2.5m wide shared foot and cycle path on both sides and no dedicate bicycle lanes marked on the carriageway. ▪ Footpaths widened to a minimum of 2.0m in the vicinity of a school, shop, public transport stop or other activity centre. ▪ Footpaths or shared foot and cycle paths offset a minimum distance of 1m from the kerb.

Arterial Road

Traffic volume[1]	Greater than 7000vpd
Target speed[2]	Arterial road design as required by the relevant roads authority.
Carriageway width[3] & parking provision within street reservation	Arterial road design as required by the relevant roads authority.

Verge width[4]	Arterial road design as required by the relevant roads authority.
Kerbing[5]	Arterial road design as required by the relevant roads authority.
Footpath & cycle path provision	3m wide shared path on each side or as otherwise required by the relevant roads authority.

Key to Table C1

1. Indicative maximum traffic volume for 24-hour period. These volumes depend upon location. Generation rates may vary between existing and newly developing areas.
2. Target speed is the desired speed at which motorists should travel. This is not necessarily the design speed and is not greater than the marked legal speed limit.
3. Width is measured from kerb invert to kerb invert. Widening may be required at bends to allow for wider vehicle paths using appropriate Australian Standards for on street and off-street parking but should not negate the function of bends serving as slow points.
4. Verge width includes footpaths. Additional width may be required to accommodate a bicycle path.
5. Where drainage is not required a flush pavement edge treatment can be used. Layback kerbs are preferred for safety reasons. Upright kerbs may be considered for drainage purposes or in locations where on-street parking should be clearly defined and parking within the verge is not desired.
6. Turning requirements to access and egress parking on abutting lots may require additional carriageway width. The recommended carriageway width of 5.5m will provide adequate access to a standard 3.5m wide single garage built to the property line.
7. 50kph is the default urban speed limit in Victoria.
8. Target speed must not exceed the legal speed limit.

56.07 INTEGRATED WATER MANAGEMENT

29/10/2015
VC101

56.07-1 Drinking water supply objectives

09/10/2006
VC42

To reduce the use of drinking water.

To provide an adequate, cost-effective supply of drinking water.

Standard C22

The supply of drinking water must be:

- Designed and constructed in accordance with the requirements and to the satisfaction of the relevant water authority.
- Provided to the boundary of all lots in the subdivision to the satisfaction of the relevant water authority.

56.07-2 Reused and recycled water objective

20/03/2023
VC229

To provide for the substitution of drinking water for non-drinking purposes with reused and recycled water.

Standard C23

Reused and recycled water supply systems must be:

- Designed, constructed and managed in accordance with the requirements and to the satisfaction of the relevant water authority, Environment Protection Authority and Department of Health.
- Provided to the boundary of all lots in the subdivision where required by the relevant water authority.

56.07-3 Waste water management objective

01/07/2021
VC203

To provide a waste water system that is adequate for the maintenance of public health and the management of effluent in an environmentally friendly manner.

Standard C24

Waste water systems must be:

- Designed, constructed and managed in accordance with the requirements and to the satisfaction of the relevant water authority and the Environment Protection Authority.
- Consistent with a domestic waste water management plan adopted by the relevant council.

Reticulated waste water systems must be provided to the boundary of all lots in the subdivision where required by the relevant water authority.

56.07-4 Stormwater management objectives

26/10/2018
VC154

To minimise damage to properties and inconvenience to residents from stormwater.

To ensure that the street operates adequately during major storm events and provides for public safety.

To minimise increases in stormwater and protect the environmental values and physical characteristics of receiving waters from degradation by stormwater.

To encourage stormwater management that maximises the retention and reuse of stormwater.

To encourage stormwater management that contributes to cooling, local habitat improvements and provision of attractive and enjoyable spaces.

Standard C25

The stormwater management system must be:

- Designed and managed in accordance with the requirements and to the satisfaction of the relevant drainage authority.
- Designed and managed in accordance with the requirements and to the satisfaction of the water authority where reuse of stormwater is proposed.
- Designed to meet the current best practice performance objectives for stormwater quality as contained in the *Urban Stormwater - Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999).
- Designed to ensure that flows downstream of the subdivision site are restricted to pre-development levels unless increased flows are approved by the relevant drainage authority and there are no detrimental downstream impacts.
- Designed to contribute to cooling, improving local habitat and providing attractive and enjoyable spaces.

The stormwater management system should be integrated with the overall development plan including the street and public open space networks and landscape design.

For all storm events up to and including the 20% Average Exceedence Probability (AEP) standard:

- Stormwater flows should be contained within the drainage system to the requirements of the relevant authority.
- Ponding on roads should not occur for longer than 1 hour after the cessation of rainfall.

For storm events greater than 20% AEP and up to and including 1% AEP standard:

- Provision must be made for the safe and effective passage of stormwater flows.
- All new lots should be free from inundation or to a lesser standard of flood protection where agreed by the relevant floodplain management authority.
- Ensure that streets, footpaths and cycle paths that are subject to flooding meet the safety criteria $d_a V_{ave} < 0.35\ m^2/s$ (where, d_a = average depth in metres and V_{ave} = average velocity in metres per second).

The design of the local drainage network should:

- Ensure stormwater is retarded to a standard required by the responsible drainage authority.
- Ensure every lot is provided with drainage to a standard acceptable to the relevant drainage authority. Wherever possible, stormwater should be directed to the front of the lot and discharged into the street drainage system or legal point of discharge.
- Ensure that inlet and outlet structures take into account the effects of obstructions and debris build up. Any surcharge drainage pit should discharge into an overland flow in a safe and predetermined manner.
- Include water sensitive urban design features to manage stormwater in streets and public open space. Where such features are provided, an application must describe maintenance responsibilities, requirements and costs.

Any flood mitigation works must be designed and constructed in accordance with the requirements of the relevant floodplain management authority.

56.08 SITE MANAGEMENT

09/10/2006
VC42

56.08-1 Site management objectives

09/10/2006
VC42

To protect drainage infrastructure and receiving waters from sedimentation and contamination.

To protect the site and surrounding area from environmental degradation or nuisance prior to and during construction of subdivision works.

To encourage the re-use of materials from the site and recycled materials in the construction of subdivisions where practicable.

Standard C26

A subdivision application must describe how the site will be managed prior to and during the construction period and may set out requirements for managing:

- Erosion and sediment.
- Dust.
- Run-off.
- Litter, concrete and other construction wastes.
- Chemical contamination.
- Vegetation and natural features planned for retention.

Recycled material should be used for the construction of streets, shared paths and other infrastructure where practicable.

56.09 UTILITIES

22/08/2014
VC118

56.09-1 Shared trenching objectives

22/08/2014
VC118

To maximise the opportunities for shared trenching.

To minimise constraints on landscaping within street reserves.

Standard C27

Reticulated services for water, gas, electricity and telecommunications should be provided in shared trenching to minimise construction costs and land allocation for underground services.

56.09-2 Electricity and telecommunications objectives

01/01/2024
VC250

To provide public utilities to each lot in a timely, efficient and cost effective manner.

To reduce greenhouse gas emissions by supporting generation and use of electricity from renewable sources.

Standard C28

The electricity supply system must be designed in accordance with the requirements of the relevant electricity supply agency and be provided to the boundary of all lots in the subdivision to the satisfaction of the relevant electricity authority.

Arrangements that support the generation or use of renewable energy at a lot or neighbourhood level are encouraged.

The telecommunication system must be designed in accordance with the requirements of the relevant telecommunications servicing agency and should be consistent with any approved strategy, policy or plan for the provision of advanced telecommunications infrastructure, including fibre optic technology. The telecommunications system must be provided to the boundary of all lots in the subdivision to the satisfaction of the relevant telecommunications servicing authority.

56.09-3 Fire hydrants objective

15/09/2008
VC49

To provide fire hydrants and fire plugs in positions that enable fire fighters to access water safely, effectively and efficiently.

Standard C29

Fire hydrants should be provided:

- A maximum distance of 120 metres from the rear of the each lot.
- No more than 200 metres apart.

Hydrants and fire plugs must be compatible with the relevant fire service equipment. Where the provision of fire hydrants and fire plugs does not comply with the requirements of standard C29, fire hydrants must be provided to the satisfaction of the relevant fire authority.

56.09-4 Public lighting objective

09/10/2006
VC42

To provide public lighting to ensure the safety of pedestrians, cyclists and vehicles.

To provide pedestrians with a sense of personal safety at night.

To contribute to reducing greenhouse gas emissions and to saving energy.

Standard C30

Public lighting should be provided to streets, footpaths, public telephones, public transport stops and to major pedestrian and cycle paths including public open spaces that are likely to be well used at night to assist in providing safe passage for pedestrians, cyclists and vehicles.

Public lighting should be designed in accordance with the relevant Australian Standards.

Public lighting should be consistent with any strategy, policy or plan for the use of renewable energy and energy efficient fittings.

57 TWO OR MORE DWELLINGS ON A LOT AND RESIDENTIAL BUILDINGS OF FOUR STOREYS

08/09/2025
VC282

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To encourage residential development that provides reasonable standards of amenity for existing and new residents.

To encourage residential development that responds to the site and the surrounding area.

Application

Provisions in this clause apply to the classes of applications specified in clauses:

- 32.04-7, Mixed Use Zone,
- 32.05-8, Township Zone,
- 32.07-6, Residential Growth Zone,
- 32.08-7, General Residential Zone,
- 32.09-7, Neighbourhood Residential Zone,
- 32.10-5, Housing Choice and Transport Zone.

The objective contained in clause 57.03-1 does not apply to a development of less than 10 dwellings.

The objective contained in clause 57.05-3 does not apply to an apartment development or residential building.

The objectives contained in clauses 57.03-12 and 57.05-7 do not apply to the construction or extension of:

- A dwelling that is not in, or does not form part of, an apartment development; or
- A residential building.

Operation

The provisions of this clause contain:

- **Objectives.** An objective describes the outcome to be achieved in the completed development.
- **Standards.** A standard contains the requirements to meet the corresponding objective.

  If a zone or a schedule to a zone specifies a standard that modifies the standard set out in this clause, the modified standard, as specified in the zone or schedule to the zone applies for the purpose of this clause.

  If the land is included in a Neighbourhood Character Overlay and a schedule to the overlay specifies a standard that modifies the standard set out in this clause, or a modified standard in the zone or a schedule to the zone, the modified standard in the schedule to the overlay applies.

  If the land is included in an overlay, other than a Neighbourhood Character Overlay, and a schedule to the overlay specifies a standard that modifies the standard set out in this clause, or a modified standard in the zone or a schedule to the zone, the modified standard in the schedule to the overlay applies.
- **Decision guidelines.** The decision guidelines set out the matters that the responsible authority must consider before deciding if the corresponding objective is met.

Requirements

A development must meet all of the applicable objectives contained in this clause.

A development should meet all of the applicable standards of this clause that apply to the application.

The responsible authority must consider the applicable decision guidelines in determining whether the corresponding objective is met.

57.01 APPLICATION REQUIREMENTS

31/03/2025
VC267

An application to which this clause applies must be accompanied by:

- A site description.
- A design response.

57.01-1 Site description

31/03/2025
VC267

The site description may use a site plan, photographs or other techniques and must accurately describe:

- The built form, scale and character of surrounding development including front fencing.
- Site shape, size, orientation and easements.
- Levels of the site and the difference in levels between the site and surrounding properties.
- The location of existing buildings on the site and on surrounding properties, including the location and height of walls built to the boundary of the site.
- The use of surrounding buildings.
- The location of secluded private open space and habitable room windows of surrounding properties which have an outlook to the site within 9 metres.
- Solar access to the site and to surrounding properties.
- Location of existing trees 5 metres in height or greater, with a trunk circumference of 0.5 metres or greater at 1.4 metres above ground level, on the site.
- Any cut and filled areas of soil, where known.
- Street frontage features such as poles, services, street trees and kerb crossovers.
- The location of any existing domestic solar energy system on the roof of a dwelling, apartment development or residential building on surrounding properties.

If in the opinion of the responsible authority a requirement of the site description is not relevant to the evaluation of an application, the responsible authority may waive or reduce the requirement.

57.01-2 Design response

31/03/2025
VC267

The design response must explain how the proposed design:

- Derives from and responds to the site description.
- Meets the objectives of Clause 57.

The design response must include correctly proportioned street elevations or photographs showing the development in the context of adjacent buildings.

The design response must include a landscape plan that details the proposed:

- Retention and planting of canopy trees,
- Planting of other vegetation including location, species, number and size at maturity of vegetation,
- Where required, areas of deep soil and root barriers,
- Irrigation system to support existing and planted vegetation including details of any alternative water supply sources,
- Selection of vegetation that responds to the site's environment and geographic factors,
- A plan showing the location of site services, clothes drying and storage.

If in the opinion of the responsible authority a design response requirement is not relevant to the evaluation of an application, it may waive or reduce the requirement.

57.02 NEIGHBOURHOOD CHARACTER

31/03/2025
VC267

57.02-1 Street setback objective

08/09/2025
VC282

To ensure that the setbacks of buildings from a street respond to the existing or preferred neighbourhood character and make efficient use of the site.

Standard E2-1

Walls of buildings should be set back from streets the distance specified in Table E2-1.

Porches, pergolas and verandahs that are less than 3.6 metres high and eaves should not encroach more than 2.5 metres into the setbacks of this standard.

Table E2-1 Street setback

Development context	Minimum setback from front street	Minimum setback from a side street
There is an existing building on both the abutting allotments facing the same street, and the site is not on a corner.	The same distance as the lesser front wall setback of an existing building on the abutting allotments facing the front street or 6 metres, whichever is the lesser.	Not applicable
There is an existing building on one abutting allotment facing the same street and no existing building on the other abutting allotment facing the same street, and the site is not on a corner.	The same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 6 metres, whichever is the lesser.	Not applicable
There is no existing building on either of the abutting allotments facing the same street, and the site is not on a corner.	6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Not applicable
The site is on a corner.	If there is a building on the abutting allotment facing the front street, the same distance as the setback of the front wall of the existing building on the abutting allotment facing the front street or 6 metres, whichever is the lesser. If there is no building on the abutting allotment facing the front street, 6 metres for streets in a Transport Zone 2 and 4 metres for other streets.	Front walls of new development fronting the side street of a corner site is set back at least the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 3 metres, whichever is the lesser. Side walls of new development on a corner site is set back the same distance as the setback of the front wall of any existing building on the abutting allotment facing the side street or 2 metres, whichever is the lesser.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.

- The design response.
- Whether the siting of the building is constrained by the shape, dimensions, slope or other conditions of the site.
- Whether a different setback would be more appropriate taking into account the prevailing setbacks of existing buildings on nearby lots.
- The visual impact of the building when viewed from the street and from adjoining properties.
- Whether a different setback affects the ability to retain or plant canopy trees.

57.02-2 Building height objective

31/03/2025
VC267

To ensure that the height of buildings respond to the existing or preferred neighbourhood character.

Standard E2-2

The maximum building height should not exceed the maximum height specified in the zone, schedule to the zone or an overlay that applies to the land.

If no maximum height is specified in the zone, schedule to the zone or an overlay, the maximum building height should not exceed 9 metres, unless the slope of the natural ground level at any cross section wider than 8 metres of the site of the building is 2.5 degrees or more, in which case the maximum building height should not exceed 10 metres.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- Any maximum building height specified in the zone, a schedule to the zone or an overlay applying to the land.
- The design response.
- The effect of the slope of the site on the height of the building.
- The relationship between the proposed building height and the height of existing adjacent buildings.
- The visual impact of the building when viewed from the street and from adjoining properties.

57.02-3 Side and rear setbacks objective

02/04/2025
VC276

To ensure that the height and setback of a building from a boundary responds to the existing or preferred neighbourhood character and limits the impact on the amenity of existing dwellings or small second dwellings.

Standard E2-3

A new building not on or within 200mm of a boundary should be set back from side or rear boundaries in accordance with either E2-3.1 or E2-3.2.

Either standard E2-3.1 or E2-3.2 should apply rather than applying both in full or part:

- E2-3.1:
  The building is set back at least 1 metre, plus 0.3 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres.
- E2-3.2:
  If the boundary is not to the south of the building, the building is set back at least 3 metres up to a height not exceeding 11 metres and at least 4.5 metres for a height over 11 metres.

If the boundary is to the south of the building, the building is set back at least 6 metres up to a height not exceeding 11 metres and at least 9 metres for a height over 11 metres between south 30 degrees west to south 30 degrees east.

Sunblinds, verandahs, porches, eaves, facias, gutters, masonry chimneys, flues, pipes, domestic fuel or water tanks, and heating or cooling equipment or other services should not encroach more than 0.5 metres into the side and rear setbacks.

Landings that have an area of not more than 2 square metres and less than 1 metre high, stairways, ramps, pergolas, shade sails and carports may encroach into the side and rear setbacks.

Diagram E2-3.1 Side and rear setbacks





Diagram E2-3.2 Side and rear setbacks



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The impact on the amenity of the habitable room windows and private open space of existing dwellings or small second dwellings.
- Whether the wall is opposite an existing or simultaneously constructed wall built to the boundary.
- Whether the wall abuts a side or rear lane.
- Whether a different setback in a rear yard affects the ability to retain or plant canopy trees.

57.02-4 Walls on boundaries objective

31/03/2025
VC267

To ensure that the location, length and height of a wall on a boundary responds to the existing or preferred neighbourhood character and limits the impact on the amenity of existing dwellings and small second dwellings.

Standard E2-4

A new wall constructed on or within 200mm of a side or rear boundary of a lot or a carport constructed on or within 1 metre of a side or rear boundary of a lot should not abut the boundary for a length that exceeds the greater of the following distances:

- 10 metres plus 25 per cent of the remaining length of the boundary of an adjoining lot, or
- The length of existing or simultaneously constructed walls or carports abutting the boundary on an abutting lot.

A new wall or carport may fully abut a side or rear boundary where slope and retaining walls or fences would result in the effective height of the wall or carport being less than 2 metres on the abutting property boundary.

A building on a boundary includes a building set back up to 200mm from a boundary.

The height of a new wall constructed on or within 200mm of a side or rear boundary or a carport constructed on or within 1 metre of a side or rear boundary should not exceed an average of 3.2 metres with no part higher than 3.6 metres unless abutting a higher existing or simultaneously constructed wall.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The extent to which walls on boundaries are part of the neighbourhood character.
- The impact on the amenity of existing dwellings or small second dwellings.
- The opportunity to minimise the length of walls on boundaries by aligning a new wall on a boundary with an existing wall on a lot of an adjoining property.
- The orientation of the boundary that the wall is being built on.
- The width of the lot.
- The extent to which the slope and retaining walls or fences reduce the effective height of the wall.
- Whether the wall abuts a side or rear lane.
- The need to increase the wall height to screen a box gutter.

57.02-5 Site coverage objective

08/09/2025
VC282

To ensure that the site coverage responds to the existing or preferred neighbourhood character and responds to the features of the site.

Standard E2-5

The site area covered by buildings should not exceed the percentage specified in Table E2-5.

Table E2-5 Site coverage

Zone	Area of site covered by buildings
Neighbourhood Residential Zone Township Zone	60 per cent
General Residential Zone	65 per cent
Residential Growth Zone Mixed Use Zone Housing Choice and Transport Zone	70 per cent

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The existing site coverage and any constraints imposed by existing development or the features of the site.
- The site coverage of adjacent properties.

- The effect of the visual bulk of the building and whether this is acceptable in the neighbourhood.
- Whether a different area of site coverage affects the ability to retain or plant canopy trees.

57.02-6 Access objective

31/03/2025
VC267

To ensure the number and design of vehicle crossovers responds to the neighbourhood character.

Standard E2-6

The width of accessways or car spaces (other than to a rear lane) should not exceed:

- 33 per cent of the street frontage; or
- 40 per cent of the street frontage if the width of the street frontage is less than 20 metres.

The number of access points to a road in a Transport Zone 2 or a Transport Zone 3 should not be increased.

The location of a vehicle crossover or accessway should not encroach the tree protection zone of an existing tree, that is proposed to be retained in a road by more than 10 per cent.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The reduction of on-street car parking spaces.
- Whether a different accessway width, number of access points or encroachment of an existing tree affects the ability to retain or plant canopy trees on the site or footpath.

57.02-7 Tree canopy objectives

08/09/2025
VC282

To provide tree canopy that responds to the neighbourhood character of the area and reduces the visual impact of buildings on the streetscape.

To preserve existing canopy cover and support the provision of new canopy cover.

To ensure new canopy trees are climate responsive, support biodiversity, wellbeing and amenity, and help reduce urban heat.

Standard E2-7

A minimum canopy cover as specified in Table E2-7.1 should be provided.

Table E2-7.1 Canopy cover

Site area	Canopy cover
1000 square metres or less	10% of site area
More than 1000 square metres	20% of site area

Existing trees to be retained meet all of the following:

- Have a height of at least 5 metres,
- Have a trunk circumference of 0.5 metres or greater at 1.4 metres above ground level,
- Have a trunk that is located at least 4 metres from proposed buildings.

The minimum canopy cover is met using any combination of trees specified in Table E2-7.2.

Existing trees that are retained can be used in calculating canopy cover.

Table E2-7.2 Tree type, canopy cover, deep soil and planter requirements

Tree type	Minimum canopy diameter at maturity	Minimum height at maturity	Minimum mature canopy cover	Tree in deep soil Area of deep soil	Tree in planter Volume of planter	Minimum depth of planter soil
A	4 metres	6 metres	12.6 sqm	12 square metres (min. plan dimension 2.5 metres)	12 cubic metres (min. plan dimension 2.5 metres)	0.8 metre
B	8 metres	8 metres	50.3 sqm	49 square metres (min. plan dimension 4.5 metres)	28 cubic metres (min. plan dimension 4.5 metres)	1 metre
C	12 metres	12 metres	113.1 sqm	121 square metres (min. plan dimension 6.5 metres)	64 cubic metres (min. plan dimension 6.5 metres)	1.5 metre

Provide at least one new or retained tree in the front setback and the rear setback.

Trees are located in either:

- An area of deep soil as specified in Table E2-7.2; or
- A planter as specified in Table E2-7.2.

Any trees proposed to be planted should be of species to the satisfaction of the responsible authority, having regard to the location and relevant geographic factors.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The site context and design response.
- The extent to which the existing and proposed canopy trees contribute to a greener environment and reduce urban heat.
- Whether the growth characteristics of existing trees and proposed canopy trees will provide the required canopy cover.
- The suitability of the planting location, deep soil areas and planter soil volume for proposed canopy trees.
- Whether the species of canopy tree is suited to the soil conditions of the site.

57.02-8 Front fences objective

08/09/2025
VC282

To encourage front fence design that responds to the existing or preferred neighbourhood character.

Standard E2-8

A front fence within 3 metres of a street should not exceed the maximum height specified in Table E2-8.

Table E2-8 Maximum front fence height

Street context	Maximum front fence height
Streets in a Transport Zone 2	2 metres
Other streets	1.5 metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character objective, policy or statement set out in this scheme.
- The design response.
- The setback, height and appearance of front fences on adjacent properties.
- The extent to which slope and retaining walls reduce the effective height of the front fence.
- Whether the fence is needed to minimise noise intrusion.

57.03 LIVEABILITY

31/03/2025
VC267

57.03-1 Dwelling diversity objective

31/03/2025
VC267

To encourage a range of dwelling sizes and types in developments of ten or more dwellings.

Standard E3-1

Developments should include at least:

- One dwelling that contains a kitchen, bath or shower, bedroom and a toilet and wash basin at ground floor level for every 10 dwellings.
- One dwelling that includes no more and no less than 2 bedrooms for every 10 dwellings.
- One dwelling that includes no more and no less than 3 bedrooms for every 10 dwellings.

Decision Guidelines

Before deciding on an application, the responsible authority must consider whether the development provides a range of dwelling sizes and types to meet diverse household needs.

57.03-2 Parking location objective

08/09/2025
VC282

To minimise the impact of vehicular noise within developments on residents.

Standard E3-2

Habitable room windows with sill heights of less than 3 metres above ground level should be setback from accessways and car parks by at least:

- 1.5 metres; or
- If there is a solid fence with a height of at least 1.5 metres between the accessway or car park and the window, 1 metre; or
- 1 metre where window sills are at least 1.5 metres above ground level.

This standard is met in respect to any accessway or relevant car parking space that is used exclusively by the resident of the building with the habitable room.

Decision Guidelines

Before deciding on an application, the responsible authority must consider the design response.

57.03-3 Street integration objective

31/03/2025
VC267

To integrate the layout of development with the street to support the safety and amenity of residents.

Standard E3-3

Where a development fronts a street, a vehicle accessway or abuts public open space:

- Passive surveillance should be provided by a direct view from a balcony or a habitable room window to each street, vehicle accessway and public open space.
- The total cumulative width of all site services should be located within 3 metres of a street, do not take up more than 20 per cent of the width of the frontage and are screened from view from the street or located behind a fence Screens or fences are to provide no more than 25 per cent transparency.

Lighting should be provided to all external accessways and paths.

Mailboxes should be provided for each dwelling and can be communally located.

Decision guidelines

Before deciding on an application, the responsible authority must consider the design response.

57.03-4 Entry objective

31/03/2025
VC267

To provide each dwelling, apartment development or residential building with its own sense of identity.

To provide entries with weather protection, safe design, natural light and ventilation.

Standard E3-4

Dwellings (other than a dwelling in or forming part of an apartment development) and residential buildings

Each dwelling and each residential building should have a ground level entry door that:

- Has a direct line of sight from a street, accessway or shared walkway.
- Is not accessed through a garage.
- Has an external covered area of at least 1.44 square metres with a minimum dimension of least 1.2 metres over the entry door.

Apartment development and residential building with a shared entry

An apartment development and each residential building should have:

- A ground level entry door, gate or walkway with a direct line of sight from a street, accessway or shared walkway.
- An external covered area of at least 1.44 square metres with a minimum dimension of least 1.2 metres over the entry door to the building.
- Shared corridors and common areas should have at least one source of natural light and natural ventilation.

Decision guidelines

Whether the entry is visible and easily identifiable from streets and other public areas.

Whether the entry provides shelter, a sense of address and a transitional space around the entry.

57.03-5 Private open space objective

08/09/2025
VC282

To provide adequate private open space for the reasonable recreation and service needs of residents.

Standard E3-5

A dwelling or residential building should have private open space with direct access from a living area, dining area or kitchen consisting of:

- An area of 25 square metres of secluded private open space, with a minimum dimension of 3 metres width; or
- An area on a podium or similar of at least 15 square metres, with a minimum dimension of 3 metres width; or
- A balcony with at least the area and dimensions specified in Table E3-5; or
- An area on a roof of at least 10 square metres, with a minimum dimension of 2 metres width.

If a cooling or heating unit is located in the secluded private open space or private open space the required area should increase by 1.5 square metres.

Where ground level private open space is provided an area for clothes drying should be provided.

Table E3-5 Private open space for a balcony

Orientation of dwelling	Dwelling type	Minimum area	Minimum dimension
North (between north 20 degrees west to north 30 degrees east)	All	8 square metres	1.7 metres
South (between south 30 degrees west to south 20 degrees east)	All	8 square metres	1.2 metres
Any other orientation	Studio or 1 bedroom dwelling	8 square metres	1.8 metres
	2 bedroom dwelling	8 square metres	2 metres
	3 bedroom dwelling	12 square metres	2.4 metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability of the private open space, including its size and accessibility.
- The availability of and access to public or communal open space.
- The orientation of the lot to the street and the sun.

57.03-6 Solar access to open space objective


31/03/2025
VC267

To allow solar access into the secluded private open space of new dwellings and residential buildings.

Standard E3-6

The southern boundary of secluded private open space should be set back from any wall on the north of the space at least (2 + 0.9h) metres, where 'h' is the height of the wall.

Diagram E3-6 Solar access to open space



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability and amenity of the secluded private open space based on the sunlight it will receive.

57.03-7 Functional layout objective

02/04/2025
VC276

To ensure dwellings provide functional areas that meet the needs of residents.

Standard E3-7

Bedrooms should:

- Meet the minimum internal room dimensions specified in Table E3-7.1; and
- Provide an additional area of at least 0.8 square metres to accommodate a wardrobe.

Table E3-7.1 Bedroom dimensions

Bedroom type	Minimum width	Minimum depth
Main bedroom	3 metres	3.4 metres
All other bedrooms	3 metres	3 metres

Living areas (excluding dining and kitchen areas) should meet the minimum internal room dimensions specified in Table E3-7.2.

Table E3-7.2 Living area dimensions

Dwelling type	Minimum width	Minimum area
Studio and 1 bedroom dwelling	3.3 metres	10 sqm
2 or more bedroom dwelling	3.6 metres	12 sqm

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability and amenity of habitable rooms.

57.03-8 Room depth objective

31/03/2025
VC267

To allow adequate daylight into single aspect habitable rooms.

Standard E3-8

The depth of a single aspect habitable room should not exceed 2.5 times the ceiling height measured from the external surface of the habitable room window to the rear wall of the room.

The depth of a single aspect, open plan, habitable room may be increased to 9 metres if all the following requirements are met:

- The room combines the living area, dining area and kitchen; and
- The kitchen is located furthest from the window; and

- The ceiling height is at least 2.7 metres measured from finished floor level to finished ceiling level, this excludes where services are provided above the kitchen; and
- An overhang extends no more than 2m beyond the window of the single aspect habitable room.

In Clause 57.03-8 a single aspect habitable room is a habitable room with windows on only one wall.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which the habitable room is provided with reasonable daylight access through the number, size, location and orientation of windows.
- The useability, functionality and amenity of the dwelling based on the layout, siting, size and orientation of habitable rooms.
- Any overhang above habitable room windows that limits daylight access.

57.03-9 Daylight to new windows objective

31/03/2025
VC267

To allow adequate daylight into new habitable room windows.

Standard E3-9

Dwelling (other than a dwelling in or forming part of an apartment development)

A window in an external wall of the building should be provided to all habitable rooms.

Habitable rooms in a dwelling should have a window that faces:

- An outdoor space clear to the sky or a light court with a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky, not including land on an abutting lot; or
- A verandah provided it is open for at least one third of its perimeter; or
- A carport provided it has two or more open sides and is open for at least one third of its perimeter.

Dwelling in or forming part of an apartment development

A window in an external wall of the building should be provided to all habitable rooms.

Where daylight to a bedroom is provided from a smaller secondary area within the bedroom, the secondary area should have:

- A minimum width of 1.2 metres.
- A maximum depth of 1.5 times the width, measured from the external surface of the window.
- A window clear to the sky.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which habitable rooms are provided with reasonable daylight access through the number, size, location and orientation of windows.
- The useability and amenity of the dwelling based on the layout, siting, size and orientation of habitable rooms.
- Whether there are other windows in the habitable room which have access to daylight.

57.03-10 Natural ventilation objectives

31/03/2025
VC267

To encourage natural ventilation of dwellings.

To allow occupants to effectively manage natural ventilation of dwellings.

Standard E3-10

Dwelling (other than a dwelling in or forming part of an apartment development)

Dwellings should have openable windows, doors or other ventilation devices in external walls of the building that provide:

- A maximum breeze path through the dwelling of 18 metres.
- A minimum breeze path through the dwelling of 5 metres.
- Ventilation openings with approximately the same size.

The breeze path is measured between the ventilation openings on different orientations of the dwelling.

Dwelling in or forming part of an apartment development

At least 40 per cent of dwellings should have openable windows, doors or other ventilation devices in external walls of the building that provide:

- A maximum breeze path through the dwelling of 18 metres.
- A minimum breeze path through the dwelling of 5 metres.
- Ventilation openings with approximately the same size.

The breeze path is measured between the ventilation openings on different orientations of the dwelling.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size, orientation, slope and wind exposure of the site.
- The extent to which the orientation and layout of the dwelling maximises opportunities for cross ventilation.
- Whether an alternative design meets the relevant objectives having regard to the amenity of the dwelling and site context.

57.03-11 Storage objective

31/03/2025
VC267

To provide adequate storage facilities for each dwelling.

Standard E3-11

Dwelling (other than a dwelling in or forming part of an apartment development)

Each dwelling should have exclusive access to at least 6 cubic metres of externally accessible storage space.

Dwelling in or forming part of an apartment development

Each dwelling should have exclusive access to storage at least the total minimum storage volume that is specified in Table E3-11.

Table E3-11 Storage

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
Studio	8 cubic metres	5 cubic metres
1 bedroom dwelling	10 cubic metres	6 cubic metres
2 bedroom dwelling	14 cubic metres	9 cubic metres
3 or more bedroom dwelling	18 cubic metres	12 cubic metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability, functionality and location of storage facilities provided for the dwelling.

57.03-12 Accessibility for apartment developments objective

31/03/2025
VC267

To ensure the design of dwellings meets the needs of people with limited mobility.

Standard E3-12

At least 50 per cent of dwellings should have:

- A clear opening width of at least 850mm at the entrance to the dwelling and main bedroom.
- A clear path with a minimum width of 1.2 metres that connects the dwelling entrance to the main bedroom, an adaptable bathroom and the living area.
- A main bedroom with access to an adaptable bathroom.
- At least one adaptable bathroom that meets all of the requirements of either Design A or Design B specified in Table E3-12.

Table E3-12 Bathroom design

	Design option A	Design option B
Door opening	A clear 850mm wide door opening.	
Door design	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards that is clear of the circulation area and has readily removable hinges.	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards and has readily removable hinges.
Circulation area	A clear circulation area that is: ▪ A minimum area of 1.2 metres by 1.2 metres.	A clear circulation area that is: ▪ A minimum width of 1 metre.

	Design option A	Design option B
	▪ Located in front of the shower and the toilet. ▪ Clear of the toilet, basin and the door swing. The circulation area for the toilet and shower can overlap.	▪ The full length of the bathroom and a minimum length of 2.7 metres. ▪ Clear of the toilet and basin. The circulation area can include a shower area.
Path to circulation area	A clear path with a minimum width of 900mm from the door opening to the circulation area.	Not applicable.
Shower	A hobless (step-free) shower.	A hobless (step-free) shower that has a removable shower screen and is located on the furthest wall from the door opening.
Toilet	A toilet located in the corner of the room.	A toilet located closest to the door opening and clear of the circulation area.

57.04 EXTERNAL AMENITY

31/03/2025
VC267

57.04-1 Daylight to existing windows objective

31/03/2025
VC267

To allow adequate daylight into existing habitable room windows.


Standard E4-1

Buildings opposite an existing habitable room window should provide for a light court to the existing window that has a minimum area of 3 square metres and minimum dimension of 1 metre clear to the sky. The calculation of the area may include land on the abutting lot.

Walls or carports more than 3 metres in height opposite an existing habitable room window should be set back from the window at least 50 per cent of the height of the new wall if the wall is within a 55 degree arc from the centre of the existing window. The arc may be swung to within 35 degrees of the plane of the wall containing the existing window.

Where the existing window is above ground floor level, the wall height is measured from the floor level of the room containing the window.

Diagram E4-1 Daylight to existing windows



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which the existing dwelling or small second dwelling has provided for reasonable daylight access to its habitable rooms through the siting and orientation of its habitable room windows.
- The impact on the amenity of existing dwellings or small second dwellings.

57.04-2 Existing north-facing windows objective

02/04/2025
VC276

To allow adequate solar access to existing north-facing habitable room windows.

Standard E4-2

Where a north-facing habitable room window of a neighbouring dwelling or small second dwelling is within 3 metres of a boundary on an abutting lot:

- A new building should be set back from the boundary by at least 1 metre, plus 0.6 metres for every metre of height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres. This setback is to be provided for a distance of at least 3 metres from the edge of each side of the window.
- For new buildings that meet the Standard E2-3.2 setback, the building should be set back from the boundary by at least 6 metres up to a height not exceeding 11 metres and at least 9 metres for a height over 11 metres between south 30 degrees west to south 30 degrees east. This setback is to be provided for a distance of at least 3 metres from the edge of each side of the window.

For this standard a north-facing window is a window with an axis perpendicular to its surface oriented from north 20 degrees west to north 30 degrees east.

Diagram E4-2.1 North-facing windows





Diagram E4-2.2 North-facing windows



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- Existing sunlight to the north-facing habitable room window of the existing dwelling or small second dwelling.
- The impact on the amenity of existing dwellings or small second dwellings.

57.04-3 Overshadowing secluded open space objective

02/04/2025
VC276

To ensure buildings do not significantly overshadow existing secluded private open space.

Standard E4-3

The area of secluded private open space that is not overshadowed by the new development should be greater than 50 per cent, or 25 square metres with a minimum dimension of 3 metres, whichever is the lesser area, for a minimum of five hours between 9 am and 3 pm on 22 September.

If existing sunlight to the secluded private open space of an existing dwelling or small second dwelling is less than the requirements of this standard, the amount of sunlight should not be further reduced.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The impact on the amenity of existing dwellings or small second dwellings.
- Existing sunlight penetration to the secluded private open space of the existing dwelling or small second dwelling.
- The time of day that sunlight will be available to the secluded private open space of the existing dwelling or small second dwelling.
- The effect of a reduction in sunlight on the existing use of the existing secluded private open space.

57.04-4 Overlooking objective

08/09/2025
VC282

To limit views into existing secluded private open space and habitable room windows.

Standard E4-4

In Clause 57.04-4 a habitable room does not include a bedroom.

A habitable room window, balcony, podium, terrace, deck or patio should be located and designed to avoid direct views into the secluded private open space of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio. Views are measured within a 45 degree angle from the plane of the window or perimeter of the balcony, terrace, deck or patio, and from a height of 1.7 metres above floor level.

A habitable room window, balcony, terrace, deck or patio located with a direct view into a habitable room window of an existing dwelling or small second dwelling within a horizontal distance of 9 metres (measured at ground level) of the window, balcony, terrace, deck or patio should:

- Be offset a minimum of 1.5 metres from the edge of one window to the edge of the other; or
- Have sill heights of at least 1.7 metres above floor level; or
- Have fixed, obscure glazing in any part of the window below 1.7 metre above floor level; or
- Have permanently fixed external screens to at least 1.7 metres above floor level and be no more than 25 per cent transparent; or
- Have fixed elements that prevent the direct view, such as horizontal ledges or vertical fins.


Obscure glazing in any part of the window below 1.7 metres above floor level may be openable provided that there are no direct views as specified in this standard.

Screens used to obscure a view should be:

- Perforated panels or trellis with a maximum of 25 per cent openings or solid translucent panels.
- Permanent, fixed and durable.
- Designed and coloured to blend in with the development.

This standard does not apply to a new habitable room window, balcony, terrace, deck or patio which faces a property boundary where there is a visual barrier at least 1.8 metres high and the floor level of the habitable room, balcony, terrace, deck or patio is less than 0.8 metres above ground level at the boundary.

Diagram E4-4 Overlooking



Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The impact on the amenity of the secluded private open space or habitable room window.

- The existing extent of overlooking into the secluded private open space and habitable room windows of existing dwellings or small second dwellings.
- The internal daylight to and amenity of the proposed dwelling, residential building or small second dwelling.

57.04-5 Internal views objective

31/03/2025
VC267

To limit views into the secluded private open space and habitable room windows of dwellings and residential buildings within a development.

Standard E4-5

In Clause 57.04-5 a habitable room does not include a bedroom.

Within the development, a habitable room window, balcony, terrace, deck or patio that is located with a direct view into the secluded private open space of another dwelling should:

- be offset a minimum of 1.5 metres from the edge of the secluded private open space; or
- have a sill height of at least 1.7 metres above floor level; or
- have a fixed, visually obscure balustrade to at least 1.7 metre above floor level; or
- have permanently fixed external screens to at least 1.7 metres above floor level; or.
- have fixed elements that prevent the direct view, such as horizontal ledges or vertical fins.

Direct views are measured at a height of 1.7 metres above floor level and within:

- A 45 degree horizontal angle from the edge of the new window or balcony.
- A 45 degree angle in the downward direction.

Screens provided for overlooking should be no more than 25 per cent transparent. Screens may be openable provided that this does not allow direct views as specified in this standard.

Decision guideline

Before deciding on an application, the responsible authority must consider the design response.

57.05 SUSTAINABILITY

31/03/2025
VC267

57.05-1 Permeability and stormwater management objectives

08/09/2025
VC282

To reduce the impact of increased stormwater run-off on the drainage system and downstream waterways.

To facilitate on-site stormwater infiltration.

To encourage stormwater management that maximises the retention and reuse of stormwater.

To contribute to urban cooling.

Standard E5-1

The site area covered by the pervious surfaces should be at least 20 percent of the site.

The development should include a stormwater management system designed to:

- Meet the best practice quantitative performance objectives for stormwater quality specified in the Urban stormwater management guidance (EPA Publication 1739.1, 2021) of:
  - Suspended solids 80% reduction in mean annual load.
  - Total phosphorus and Total Nitrogen 45% reduction in mean annual load.
  - Litter 70% reduction of mean annual load.

    Note: A certificate generated from a stormwater assessment tool including STORM, MUSIC or an equivalent product accepted by the responsible authority may be used to demonstrate the performance objectives for stormwater quality are met.

- Direct flows of stormwater into treatment areas, garden areas, tree pits and permeable surfaces, with drainage of residual flows to the legal point of discharge.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The capacity of the site to incorporate stormwater retention and reuse.
- The existing site coverage and any constraints imposed by existing development.
- The capacity of the drainage network to accommodate additional stormwater.

57.05-2 Overshadowing domestic solar energy systems objective

31/03/2025
VC267

To ensure that the height and setback of a building from a boundary allows reasonable solar access to existing domestic solar energy systems on the roofs of buildings.

Standard E5-2

Any part of a new building that will reduce the sunlight at any time between 9am and 4 pm on 22 September to an existing domestic solar energy system on the roof of a building on an adjoining lot should be set back from the boundary to that lot by at least 1 metre at 3.6 metres above ground level, plus 0.3 metres for every metre of building height over 3.6 metres up to 6.9 metres, plus 1 metre for every metre of height over 6.9 metres.

This standard applies to an existing building in a Township Zone, General Residential Zone or Neighbourhood Residential Zone.

In Clause 57.05-2 domestic solar energy system means a domestic solar energy system that existed at the date the application was lodged.

Decision guidelines

Before deciding on an application, the responsible authority must consider whether the domestic solar energy system has been sited to optimise efficiency and protection from overshadowing.

57.05-3 Rooftop solar energy generation area objective

08/09/2025
VC282

To support the future installation of appropriately sited rooftop solar energy systems for a dwelling.


Standard E5-3

In Clause 57.05-3 rooftop solar energy area means an area provided on the roof of a dwelling to enable the future installation of a solar energy system.

An area on the roof capable of siting a rooftop solar energy area for each dwelling should be provided and:

- Have a minimum dimension of 1.7 metres.
- Have a minimum area in accordance with Table E5-3.
- Is oriented to the north, west or east.
- Is positioned on the top two thirds of a pitched roof.
- Can be a contiguous area or multiple smaller areas.
- Is free of obstructions on the roof of the dwelling within twice the height of each obstruction (H), measured horizontally (D) from the centre point of the base of the obstruction to the nearest point of the rooftop solar energy area.

Diagram E5-3 Space should be provided between obstructions and the rooftop solar energy area



Obstructions located south of all points of the rooftop solar energy area are not subject to the horizontal distance requirements.

Table E5-3 Minimum rooftop solar energy generation area

Number of bedrooms	Minimum roof area
1 bedroom dwelling	15 square metres
2 or 3 bedroom dwelling	26 square metres
4 or more bedroom dwelling	34 square metres

This standard does not apply to apartments and residential buildings.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size and orientation of the building.
- The availability of solar access to the rooftop.
- The extent to which the rooftop solar energy generation area is overshadowed by existing buildings, other permanent structures or equipment on the rooftop.

57.05-4 Solar access protection to new north-facing windows objectives

31/03/2025
VC267

To encourage external shading of north facing windows to minimise summer heat gain.

Standard E5-4

North facing windows should be shaded by eaves, fixed horizontal shading devices or fixed awnings with a minimum horizontal depth of 0.25 times the window height.

Decision Guidelines

Before deciding on an application, the responsible authority considers:

- The design response.
- The size and orientation of the lot.
- The type and useability of external solar shading devices, including alternative design responses.

57.05-5 Waste and recycling objectives

31/03/2025
VC267

To ensure dwellings are designed to facilitate waste recycling.

To ensure that waste and recycling facilities are accessible and are of sufficient size to manage organic and general waste, and mixed and glass recycling.

To ensure that waste and recycling facilities are designed and managed to minimise impacts on residential amenity.

Standard E5-5

Dwelling (other than a dwelling in or forming part of an apartment development)

The development should include an individual bin storage area for each dwelling, or a shared bin storage area for use by each dwelling, of at least the applicable area, depth and height specified in Table E5-5.1.

Table E5-5.1 Bin storage

Type of bin storage area	Minimum area	Minimum depth	Minimum height
Individual bin storage area for a dwelling.	1.8 square metres	0.8 metre	1.8 metres
Shared bin storage area for 3 dwellings or less.	5.4 square metres	0.8 metre	1.8 metres
Shared bin storage area for 4 or more dwellings.	1 square metre per dwelling plus 4 square metres	0.8 metre	1.8 metres

If the development includes a shared bin storage area:

- The shared bin storage area should be:
  - Located within 40 metres of a kerbside collection point.
  - Include a tap for bin washing.
- A continuous path of travel free of steps and obstructions from dwellings to the bin storage area should be provided.

Where access is provided for private bin collection on the land the design of access ways should allow the vehicle to enter and exit in a forward direction.

Each dwelling should include an internal waste and recycling storage space of at least 0.07 cubic metres with a minimum depth of 250 millimetres.

Dwelling in or forming part of an apartment development

The development should include a shared bin storage area for use by each dwelling of at least the applicable area, depth and height specified in Table E5-5.2.

Table E5-5.2 Apartment bin storage

Number of dwellings	Minimum area	Minimum depth	Minimum height
15 or less dwellings	0.7 square metres per dwelling in a shared waste storage area	0.8 metres	2.7 metres
16 to 55 dwellings	0.5 square metres per dwelling, plus 5 square metres in a shared waste storage area.	1 metre	2.7 metres
56 or more dwellings	0.5 square metres per dwelling in a shared waste storage area.	1 metre	2.7 metres

Enclosed bin storage areas should be ventilated by:

- Natural ventilation openings to the external air with an area of at least 5 per cent of the area for bin storage area; or
- A mechanical exhaust ventilation system.

A tap and drain should be provided to wash bins.

A continuous path of travel should be provided from each dwelling to bin storage areas.

Each dwelling should include an internal waste and recycling storage space of at least 0.07 cubic metres with a minimum depth of 250 millimetres.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response, including a Waste Management Plan.
- Any relevant waste and recycling objective, policy or statement set out in this planning scheme.
- The functionality and accessibility of waste and recycling facilities, including for people with limited mobility.

- Whether facilities are provided for on-site reuse or management of food and garden organics through composting or other waste recovery.
- Whether waste and recycling facilities are designed to meet the better practice design options specified in *Waste management and recycling in multi-unit developments* (Sustainability Victoria, 2019).

57.05-6 Noise impacts objectives

31/03/2025
VC267

To minimise the impact of mechanical plant noise located in the development.

Standard E5-6

Mechanical plant, including mechanical car storage and lift facilities should not be located immediately adjacent to bedrooms of new or existing dwellings or small second dwellings, unless a solid barrier is in place to provide a line of sight barrier to transmission of noise and the location of all relevant bedrooms.

Decision guideline

Before deciding on an application, the responsible authority must consider:

- The design response.
- Whether the impact of potential noise sources within a development have been mitigated through design, location and siting.
- Whether an alternative design meets the relevant objectives having regard to the amenity of the dwelling or small second dwelling and the site context.

57.05-7 Energy efficiency for apartment developments objectives

08/09/2025
VC282

To achieve energy efficient dwellings and buildings.

To ensure dwellings achieve adequate thermal efficiency.

Standard E5-7

Dwellings located in a climate zone identified in Table E5-7 should not exceed the maximum NatHERS annual cooling load.

Table E5-7 Cooling load

NatHERS climate zone	NatHERS maximum cooling load MJ/M^2 per annum
Climate zone 21 Melbourne	30
Climate zone 22 East Sale	22
Climate zone 27 Mildura	69
Climate zone 60 Tullamarine	22
Climate zone 62 Moorabbin	21
Climate zone 63 Warrnambool	21
Climate zone 64 Cape Otway	19
Climate zone 66 Ballarat	23

Note: Refer to NatHERS zone map, Nationwide House Energy Rating Scheme (Commonwealth Department of Environment and Energy).

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size, orientation and layout of the site.
- The availability of solar access to north-facing windows on the site.
- The annual cooling load for each dwelling.

58 APARTMENT DEVELOPMENTS

28/02/2025
VC274

Purpose

To implement the Municipal Planning Strategy and the Planning Policy Framework.

To encourage apartment development that provides reasonable standards of amenity for existing and new residents.

To encourage apartment development that is responsive to the site and the surrounding area.

Application

Provisions in this clause apply to an application to construct or extend an apartment development, or to construct or extend a dwelling in or forming part of an apartment development, if:

- The apartment development is five or more storeys, excluding a basement, and is in the General Residential Zone, Residential Growth Zone, Housing Choice and Transport Zone, Mixed Use Zone or Township Zone, or
- The apartment development is in the Commercial 1 Zone, Commercial 3 Zone, Special Use Zone, Comprehensive Development Zone, Capital City Zone, Docklands Zone, Priority Development Zone, Activity Centre Zone or Precinct Zone.

Operation

The provisions of this clause contain:

- **Objectives**. An objective describes the desired outcome to be achieved in the completed development.
- **Standards**. A standard contains the requirements to meet the objective.
  A standard should normally be met. However, if the responsible authority is satisfied that an application for an alternative design solution meets the objective, the alternative design solution may be considered.
- **Decision guidelines**. The decision guidelines set out the matters that the responsible authority must consider before deciding if an application meets the objectives.

Requirements

A development:

- Must meet all of the objectives of this clause.
- Should meet all of the standards of this clause.

If a zone or a schedule to a zone, or a schedule to an overlay specifies a requirement different from a requirement of a standard set out in Clause 58 (excluding Clause 58.04-1), the requirement in Clause 58 applies.

For Clause 58.04-1 (Building setback):

- If a zone or a schedule to a zone specifies a building setback requirement different from a requirement set out in Clause 58.04-1, the building setback requirement in the zone or a schedule to the zone applies.
- If the land is included in an overlay and a schedule to the overlay specifies a building setback requirement different from the requirement set out Clause 58.04-1 or a requirement set out in the zone or a schedule to the zone, the requirement for building setback in the overlay applies.

58.01 URBAN CONTEXT REPORT AND DESIGN RESPONSE

16/01/2018
VC142

58.01-1 Application requirements

13/04/2017
VC136

An application must be accompanied by:

- An urban context report.
- A design response.

58.01-2 Urban context report

16/01/2018
VC142

The urban context report may use a site plan, photographs or other techniques and must include:

An accurate description of:

- Site shape, size, orientation and easements.
- Levels and contours of the site and the difference in levels between the site and surrounding properties.
- The location and height of existing buildings on the site and surrounding properties.
- The use of surrounding buildings.
- The location of private open space of surrounding properties and the location of trees, fences and other landscape elements.
- Solar access to the site and to surrounding properties.
- Views to and from the site.
- Street frontage features such as poles, street trees and kerb crossovers.
- The location of local shops, public transport services and public open spaces within walking distance.
- Movement systems through and around the site.
- Any other notable feature or characteristic of the site.

An assessment of the characteristics of the area including:

- Any environmental features such as vegetation, topography and significant views.
- The pattern of subdivision.
- Street design and landscape.
- The pattern of development.
- Building form, scale and rhythm.
- Connection to the public realm.
- Architectural style, building details and materials.
- Off-site noise sources.
- The relevant NatHERS climate zones (as identified in Clause 58.03-1).
- Social and economic activity.
- Any other notable or cultural characteristics of the area.

Satisfactory urban context report

If the responsible authority decides that the urban context report is not satisfactory, it may require more information from the applicant under Section 54 of the Act.

The responsible authority must not require notice of an application to be given or decide an application until it is satisfied that the urban context report meets the requirements of Clause 58.01-2 and is satisfactory.

This does not apply if the responsible authority refuses an application under Section 52(1A) of the Act.

58.01-3 Design response

20/12/2021
VC174

The design response must explain how the proposed design:

- Responds to any relevant planning provision that applies to the land.
- Meets the objectives of Clause 58.
- Responds to any relevant housing, urban design and landscape plan, strategy or policy set out in this scheme.
- Selects materials and finishes for the external walls.
- Derives from and responds to the urban context report.

The design response must include correctly proportioned street elevations or photographs showing the development in the context of adjacent buildings. If in the opinion of the responsible authority this requirement is not relevant to the evaluation of an application, it may waive or reduce the requirement.

58.02 URBAN CONTEXT

31/07/2018
VC148

58.02-1 Urban context objectives

13/04/2017
VC136

To ensure that the design responds to the existing urban context or contributes to the preferred future development of the area.

To ensure that development responds to the features of the site and the surrounding area.

Standard D1

The design response must be appropriate to the urban context and the site.

The proposed design must respect the existing or preferred urban context and respond to the features of the site.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant urban design objective, policy or statement set out in this scheme.
- The urban context report.
- The design response.

58.02-2 Residential policy objectives

31/07/2018
VC148

To ensure that residential development is provided in accordance with any policy for housing in the Municipal Planning Strategy and the Planning Policy Framework.

To support higher density residential development where development can take advantage of public and community infrastructure and services.

Standard D2

An application must be accompanied by a written statement to the satisfaction of the responsible authority that describes how the development is consistent with any relevant policy for housing in the Municipal Planning Strategy and the Planning Policy Framework.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The Municipal Planning Strategy and the Planning Policy Framework.
- The design response.

58.02-3 Dwelling diversity objective

13/04/2017
VC136

To encourage a range of dwelling sizes and types in developments of ten or more dwellings.

Standard D3

Developments of ten or more dwellings should provide a range of dwelling sizes and types, including dwellings with a different number of bedrooms.

58.02-4 Infrastructure objectives

01/01/2024
VC250

To ensure development is provided with appropriate utility services and infrastructure.

To ensure development does not unreasonably overload the capacity of utility services and infrastructure.

Standard D4

Development should be connected to reticulated services, including reticulated sewerage, drainage and electricity, if available.

Development should not unreasonably exceed the capacity of utility services and infrastructure, including reticulated services and roads.

In areas where utility services or infrastructure have little or no spare capacity, developments should provide for the upgrading of or mitigation of the impact on services or infrastructure.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The capacity of the existing infrastructure.
- In the absence of reticulated sewerage, a Land Capability Assessment on the risks to human health and the environment of an on-site wastewater management system constructed, installed or altered on the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017*.
- If the drainage system has little or no spare capacity, the capacity of the development to provide for stormwater drainage mitigation or upgrading of the local drainage system.

58.02-5 Integration with the street objective

20/12/2021
VC174

To integrate the layout of development with the street.

To support development that activates street frontage.

Standard D5

Development should be oriented to front existing and proposed streets.

Along street frontage, development should:

- Incorporate pedestrian entries, windows, balconies or other active spaces.
- Limit blank walls.
- Limit high front fencing, unless consistent with the existing urban context.
- Provide low and visually permeable front fences, where proposed.
- Conceal car parking and internal waste collection areas from the street.

Development next to existing public open space should be designed to complement the open space and facilitate passive surveillance.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant urban design objective, policy or statement set out in this scheme.
- The design response.

58.03 SITE LAYOUT

31/07/2018
VC148

58.03-1 Energy efficiency objectives

14/12/2023
VC253

To achieve and protect energy efficient dwellings and buildings.

To ensure the orientation and layout of development reduce fossil fuel energy use and make appropriate use of daylight and solar energy.

To ensure dwellings achieve adequate thermal efficiency.

Standard D6

Buildings should be:

- Oriented to make appropriate use of solar energy.
- Sited and designed to ensure that the energy efficiency of existing dwellings or small second dwellings on adjoining lots is not unreasonably reduced.

Living areas and private open space should be located on the north side of the development, if practicable.

Developments should be designed so that solar access to north-facing windows is optimised.

Dwellings located in a climate zone identified in Table D1 should not exceed the maximum NatHERS annual cooling load specified in the following table.

Table D1 Cooling load

NatHERS climate zone	NatHERS maximum cooling load MJ/M² per annum
Climate zone 21 Melbourne	30
Climate zone 22 East Sale	22
Climate zone 27 Mildura	69
Climate zone 60 Tullamarine	22
Climate zone 62 Moorabbin	21
Climate zone 63 Warrnambool	21
Climate zone 64 Cape Otway	19
Climate zone 66 Ballarat	23

Note: Refer to NatHERS zone map, Nationwide House Energy Rating Scheme (Commonwealth Department of Environment and Energy).

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size, orientation and layout of the site.
- The existing amount of solar access to abutting properties.
- The availability of solar access to north-facing windows on the site.
- The annual cooling load for each dwelling.

58.03-2 Communal open space objective

14/12/2023
VC253

To provide communal open space that meets the recreation and amenity needs of residents.

To ensure that communal open space is accessible, practical, attractive, easily maintained.

To ensure that communal open space is integrated with the layout of the development and enhances resident amenity.

Standard D7

A development of 10 or more dwellings should provide a minimum area of communal outdoor open space of 30 square metres.

If a development contains 13 or more dwellings, the development should also provide an additional minimum area of communal open space of 2.5 square metres per dwelling or 220 square metres, whichever is the lesser. This additional area may be indoors or outdoors and may consist of multiple separate areas of communal open space.

Each area of communal open space should be:

- Accessible to all residents.
- A useable size, shape and dimension.
- Capable of efficient management.
- Located to:
  - Provide passive surveillance opportunities, where appropriate.
  - Provide outlook for as many dwellings as practicable.
  - Avoid overlooking into habitable rooms and private open space of new dwellings.
  - Minimise noise impacts to new and existing dwellings and existing small second dwellings.

Any area of communal outdoor open space should be landscaped and include canopy cover and trees.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant urban design objective, policy or statement set out in this scheme.
- The design response.
- The availability of and access to public open space.

58.03-3 Solar access to communal outdoor open space objective

13/04/2017
VC136

To allow solar access into communal outdoor open space.

Standard D8

The communal outdoor open space should be located on the north side of a building, if appropriate.

At least 50 per cent or 125 square metres, whichever is the lesser, of the primary communal outdoor open space should receive a minimum of two hours of sunlight between 9am and 3pm on 21 June.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.

- The useability and amenity of the primary communal outdoor open space areas based on the urban context, the orientation of the building, the layout of dwellings and the sunlight it will receive.

58.03-4 Safety objective

13/04/2017
VC136

To ensure the layout of development provides for the safety and security of residents and property.

Standard D9

Entrances to dwellings should not be obscured or isolated from the street and internal accessways.

Planting which creates unsafe spaces along streets and accessways should be avoided.

Developments should be designed to provide good lighting, visibility and surveillance of car parks and internal accessways.

Private spaces within developments should be protected from inappropriate use as public thoroughfares.

Decision guideline

Before deciding on an application, the responsible authority must consider the design response.

58.03-5 Landscaping objectives

15/03/2024
VC256

To provide landscaping that supports the existing or preferred urban context of the area and reduces the visual impact of buildings on the streetscape.

To preserve existing canopy cover and support the provision of new canopy cover.

To ensure landscaping is climate responsive, supports biodiversity, wellbeing and amenity and reduces urban heat.

Standard D10

Development should retain existing trees and canopy cover.

Development should provide for the replacement of any significant trees that have been removed in the 12 months prior to the application being made.

Development should:

- Provide the canopy cover and deep soil areas specified in Table D2. Existing trees can be used to meet the canopy cover requirements of Table D2.
- Provide canopy cover through canopy trees that are:
  - Located in an area of deep soil specified in Table D3. Where deep soil cannot be provided trees should be provided in planters specified in Table D3.
  - Consistent with the canopy diameter and height at maturity specified in Table D4.
  - Located in communal outdoor open space or common areas or street frontages.
- Comprise smaller trees, shrubs and ground cover, including flowering native species.
- Include landscaping, such as climbing plants or smaller plants in planters, in the street frontage and in outdoor areas, including communal outdoor open space.
- Shade outdoor areas exposed to summer sun through landscaping or shade structures and use paving and surface materials that lower surface temperatures and reduce heat absorption.
- Be supported by irrigation systems which utilise alternative water sources such as rainwater, stormwater and recycled water.
- Protect any predominant landscape features of the area.

- Take into account the soil type and drainage patterns of the site.
- Provide a safe, attractive and functional environment for residents.
- Specify landscape themes, vegetation (location and species), irrigation systems, paving and lighting.

Table D2 Canopy cover and deep soil requirements

Site area	Canopy cover	Deep soil
1000 square metres or less	5% of site area Include at least 1 Type A tree	5% of site area or 12 square metres whichever is the greater
1001 - 1500 square metres	50 square metres plus 20% of site area above 1,000 square metres Include at least 1 Type B tree	7.5% of site area
1501 - 2500 square metres	150 square metres plus 20% of site area above 1,500 square metres Include at least 2 Type B trees or 1 Type C tree	10% of site area
2501 square metres or more	350 square metres plus 20% of site area above 2,500 square metres Include at least 2 Type B trees or 1 Type C tree	15% of site area

Table D3 Soil requirements for trees

Tree type	Tree in deep soil Area of deep soil	Tree in planter Volume of planter soil	Depth of planter soil
A	12 square metres (min. plan dimension 2.5 metres)	12 cubic metres (min. plan dimension of 2.5 metres)	0.8 metre
B	49 square metres (min. plan dimension 4.5 metres)	28 cubic metres (min. plan dimension of 4.5 metres)	1 metre
C	121 square metres (min. plan dimension 6.5 metres)	64 cubic metres (min. plan dimension of 6.5 metres)	1.5 metre

Note: Where multiple trees share the same section of soil the total required amount of soil can be reduced by 5% for every additional tree, up to a maximum reduction of 25%.

Table D4 Tree type

Tree type	Minimum canopy diameter at maturity	Minimum height at maturity
A	4 metres	6 metres
B	8 metres	8 metres
C	12 metres	12 metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant neighbourhood character, landscaping or environmental policy, objective, strategy or statement set out in this planning scheme.
- The design response.
- The health of any trees to be removed.
- The suitability of the proposed location, deep soil area and planter volume for canopy trees.
- The suitability of the proposed landscaping in communal outdoor open space.
- The type and quantity of canopy cover, including any alternatives to trees.
- The soil type and drainage patterns of the site.
- The ongoing management of landscaping, including any irrigation systems.

58.03-6 Access objective

20/12/2021
VC174

To ensure that vehicle crossovers are designed and located to provide safe access for pedestrians, cyclists and other vehicles.

To ensure the vehicle crossovers are designed and located to minimise visual impact.

Standard D11

Vehicle crossovers should be minimised.

Car parking entries should be consolidated, minimised in size, integrated with the façade and where practicable located at the side or rear of the building.

Pedestrian and cyclist access should be clearly delineated from vehicle access.

The location of crossovers should maximise pedestrian safety and the retention of on-street car parking spaces and street trees.

Developments must provide for access for service, emergency and delivery vehicles.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The impact on the street.
- The impact on the safety of pedestrians or cyclists.
- The reduction of on-street car parking spaces.
- The effect on any significant vegetation on the site and road reserve.

58.03-7 Parking location objectives

13/04/2017
VC136

To provide convenient parking for resident and visitor vehicles.

To protect residents from vehicular noise within developments.

Standard D12

Car parking facilities should:

- Be reasonably close and convenient to dwellings.
- Be secure.
- Be well ventilated if enclosed.

Shared accessways or car parks of other dwellings should be located at least 1.5 metres from the windows of habitable rooms. This setback may be reduced to 1 metre where there is a fence at least 1.5 metres high or where window sills are at least 1.4 metres above the accessway.

Decision guideline

Before deciding on an application, the responsible authority must consider the design response.

58.03-8 Integrated water and stormwater management objectives

26/10/2018
VC154

To encourage the use of alternative water sources such as rainwater, stormwater and recycled water.

To facilitate stormwater collection, utilisation and infiltration within the development.

To encourage development that reduces the impact of stormwater run-off on the drainage system and filters sediment and waste from stormwater prior to discharge from the site.

Standard D13

Buildings should be designed to collect rainwater for non-drinking purposes such as flushing toilets, laundry appliances and garden use.

Buildings should be connected to a non-potable dual pipe reticulated water supply, where available from the water authority.

The stormwater management system should be:

- Designed to meet the current best practice performance objectives for stormwater quality as contained in the *Urban Stormwater - Best Practice Environmental Management Guidelines* (Victorian Stormwater Committee, 1999).
- Designed to maximise infiltration of stormwater, water and drainage of residual flows into permeable surfaces, tree pits and treatment areas.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant water and stormwater management objective, policy or statement set out in this scheme.
- The design response.
- Whether the development has utilised alternative water sources and/or incorporated water sensitive urban design.
- Whether stormwater discharge from the site will adversely affect water quality entering the drainage system.
- The capacity of the drainage network to accommodate additional stormwater.
- Whether the stormwater treatment areas can be effectively maintained.
- Whether the owner has entered into an agreement to contribute to off-site stormwater management in lieu of providing an on-site stormwater management system.

58.04 AMENITY IMPACTS

13/04/2017
VC136

58.04-1 Building setback objectives

14/12/2023
VC253

To ensure the setback of a building from a boundary appropriately responds to the existing urban context or contributes to the preferred future development of the area.

To allow adequate daylight into new dwellings.

To limit views into habitable room windows and private open space of new and existing dwellings.

To provide a reasonable outlook from new dwellings and existing small second dwellings.

To ensure the building setbacks provide appropriate internal amenity to meet the needs of residents.

Standard D14

The built form of the development must respect the existing or preferred urban context and respond to the features of the site.

Buildings should be set back from side and rear boundaries, and other buildings within the site to:

- Ensure adequate daylight into new habitable room windows.
- Avoid direct views into habitable room windows and private open space of new and existing dwellings and existing small second dwellings. Developments should avoid relying on screening to reduce views.
- Provide an outlook from dwellings that creates a reasonable visual connection to the external environment.
- Ensure the dwellings are designed to meet the objectives of Clause 58.

Decision Guidelines

Before deciding on an application, the responsible authority must consider:

- The purpose of the zone and/or overlay that applies to the land.
- Any relevant urban design objective, policy or statement set out in this scheme.
- The urban context report.
- The design response.
- The relationship between the proposed building setback and the building setbacks of existing adjacent buildings, including the interface with laneways.
- The extent to which the proposed dwellings are provided with reasonable daylight access through the layout of rooms and the number, size, location and orientation of windows.
- The impact of overlooking on the amenity of existing and proposed dwellings and existing small second dwellings.
- The existing extent of overlooking into existing dwellings or small second dwellings and private open space.
- Whether the development meets the objectives of Clause 58.

58.04-2 Internal views objective

13/04/2017
VC136

To limit views into the private open space and habitable room windows of dwellings within a development.

Standard D15

Windows and balconies should be designed to prevent overlooking of more than 50 per cent of the private open space of a lower-level dwelling directly below and within the same development.

Decision guideline

Before deciding on an application, the responsible authority must consider the design response.

58.04-3 Noise impacts objectives

14/12/2023
VC253

To contain noise sources in developments that may affect existing dwellings or small second dwellings.

To protect residents from external and internal noise sources.

Standard D16

Noise sources, such as mechanical plants should not be located near bedrooms of immediately adjacent existing dwellings or small second dwellings.

The layout of new dwellings and buildings should minimise noise transmission within the site.

Noise sensitive rooms (such as living areas and bedrooms) should be located to avoid noise impacts from mechanical plants, lifts, building services, non-residential uses, car parking, communal areas and other dwellings.

New dwellings should be designed and constructed to include acoustic attenuation measures to reduce noise levels from off-site noise sources.

Buildings within a noise influence area specified in Table D5 should be designed and constructed to achieve the following noise levels:

- Not greater than 35dB(A) for bedrooms, assessed as an LAeq,8h from 10pm to 6am.
- Not greater than 40dB(A) for living areas, assessed LAeq,16h from 6am to 10pm.

Buildings, or part of a building screened from a noise source by an existing solid structure, or the natural topography of the land, do not need to meet the specified noise level requirements.

Noise levels should be assessed in unfurnished rooms with a finished floor and the windows closed.

Table D5 Noise influence area

Noise source	Noise influence area
Zone interface	
Industry	300 metres from the Industrial 1, 2 and 3 zone boundary
Roads	
Freeways, tollways and other roads carrying 40,000 Annual Average Daily Traffic Volume	300 metres from the nearest trafficable lane
Railways	
Railway servicing passengers in Victoria	80 metres from the centre of the nearest track
Railway servicing freight outside Metropolitan Melbourne	80 metres from the centre of the nearest track
Railway servicing freight in Metropolitan Melbourne	135 metres from the centre of the nearest track

Note: The noise influence area should be measured from the closest part of the building to the noise source.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.

- Whether it can be demonstrated that the design treatment incorporated into the development meets the specified noise levels or an acoustic report by a suitably qualified consultant submitted with the application.
- Whether the impact of potential noise sources within a development have been mitigated through design, location and siting.
- Whether the layout of rooms within a dwelling mitigates noise transfer within and between dwellings.
- Whether an alternative design meets the relevant objectives having regard to the amenity of the dwelling or small second dwelling and the site context.

58.04-4 Wind impacts objective

04/05/2022
VC210

To ensure the built form, design and layout of development does not generate unacceptable wind impacts within the site or on surrounding land.

Standard D17

Development of five or more storeys, excluding a basement should:

- not cause unsafe wind conditions specified in Table D6 in public land, publicly accessible areas on private land, private open space and communal open space; and
- achieve comfortable wind conditions specified in Table D6 in public land and publicly accessible areas on private land

within a distance of half the greatest length of the building, or half the total height of the building measured outwards on the horizontal plane from the ground floor building façade, whichever is greater.

Trees and landscaping should not be used to mitigate wind impacts. This does not apply to sitting areas, where trees and landscaping may be used to supplement fixed wind mitigation elements.

Wind mitigation elements, such as awnings and screens should be located within the site boundary, unless consistent with the existing urban context or preferred future development of the area.

Table D6 Wind conditions

Unsafe	Comfortable
Annual maximum 3 second gust wind speed exceeding 20 metres per second with a probability of exceedance of 0.1% considering at least 16 wind directions.	Hourly mean wind speed or gust equivalent mean speed (3 second gust wind speed divided by 1.85), from all wind directions combined with probability of exceedance less than 20% of the time, equal to or less than: ▪ 3 metres per second for sitting areas, ▪ 4 metres per second for standing areas, ▪ 5 metres per second for walking areas.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The urban context report.
- The design response.

- The safety, functionality and amenity of public, private and communal open space areas.
- Whether it has been demonstrated by a suitably qualified specialist that the development will not generate unacceptable wind impacts within the site or on surrounding land.

58.05 ON-SITE AMENITY AND FACILITIES

13/04/2017
VC136

58.05-1 Accessibility objective

04/05/2022
VC210

To ensure the design of dwellings meets the needs of people with limited mobility.

Standard D18

At least 50 per cent of dwellings should have:

- A clear opening width of at least 850mm at the entrance to the dwelling and main bedroom.
- A clear path with a minimum width of 1.2 metres that connects the dwelling entrance to the main bedroom, an adaptable bathroom and the living area.
- A main bedroom with access to an adaptable bathroom.
- At least one adaptable bathroom that meets all of the requirements of either Design A or Design B specified in Table D7.

Table D7 Bathroom design

	Design option A	Design option B
Door opening	A clear 850mm wide door opening.	A clear 820mm wide door opening located opposite the shower.
Door design	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards that is clear of the circulation area and has readily removable hinges.	Either: ▪ A slide door, or ▪ A door that opens outwards, or ▪ A door that opens inwards and has readily removable hinges.
Circulation area	A clear circulation area that is: ▪ A minimum area of 1.2 metres by 1.2 metres. ▪ Located in front of the shower and the toilet. ▪ Clear of the toilet, basin and the door swing. The circulation area for the toilet and shower can overlap.	A clear circulation area that is: ▪ A minimum width of 1 metre. ▪ The full length of the bathroom and a minimum length of 2.7 metres. ▪ Clear of the toilet and basin. The circulation area can include a shower area.
Path to circulation area	A clear path with a minimum width of 900mm from the door opening to the circulation area.	Not applicable.
Shower	A hobless (step-free) shower.	A hobless (step-free) shower that has a removable shower screen and is located on the furthest wall from the door opening.
Toilet	A toilet located in the corner of the room.	A toilet located closest to the door opening and clear of the circulation area.

58.05-2 Building entry and circulation objectives

04/05/2022
VC210

To provide each dwelling and building with its own sense of identity.

To ensure the internal layout of buildings provide for the safe, functional and efficient movement of residents.

To ensure internal communal areas provide adequate access to daylight and natural ventilation.

Standard D19

Entries to dwellings and buildings should:

- Be visible and easily identifiable.
- Provide shelter, a sense of personal address and a transitional space around the entry.

The layout and design of buildings should:

- Clearly distinguish entrances to residential and non-residential areas.
- Provide windows to building entrances and lift areas.
- Provide visible, safe and attractive stairs from the entry level to encourage use by residents.
- Provide common areas and corridors that:
  - Include at least one source of natural light and natural ventilation.
  - Avoid obstruction from building services.
  - Maintain clear sight lines.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability and amenity of internal communal areas based on daylight access and the natural ventilation it will receive.

58.05-3 Private open space objective

04/05/2022
VC210

To provide adequate private open space for the reasonable recreation and service needs of residents.

Standard D20

A dwelling should have private open space consisting of at least one of the following:

- An area at ground level of at least 25 square metres, with a minimum dimension of 3 metres and convenient access from a living room.
- A balcony with at least the area and dimensions specified in Table D8 and convenient access from a living room.
- An area on a podium or other similar base of at least 15 square metres, with a minimum dimension of 3 metres and convenient access from a living room.
- An area on a roof of 10 square metres, with a minimum dimension of 2 metres and convenient access from a living room.

If a cooling or heating unit is located on a balcony, the minimum balcony area specified in Table D8 should be increased by at least 1.5 square metres.

If the finished floor level of a dwelling is 40 metres or more above ground level, the requirements of Table D8 do not apply if at least the area specified in Table D9 is provided as living area or bedroom area in addition to the minimum area specified in Table D11 or Table D12 in Standard D25.

Table D8 Balcony size

Orientation of dwelling	Dwelling type	Minimum area	Minimum dimension
North (between north 20 degrees west to north 30 degrees east)	All	8 square metres	1.7 metres
South (between south 30 degrees west to south 30 degrees east)	All	8 square metres	1.2 metres
Any other orientation	Studio or 1 bedroom dwelling	8 square metres	1.8 metres
	2 bedroom dwelling	8 square metres	2 metres
	3 or more bedroom dwelling	12 square metres	2.4 metres

Table D9 Additional living area or bedroom area

Dwelling type	Additional area
Studio or 1 bedroom dwelling	8 square metres
2 bedroom dwelling	8 square metres
3 or more bedroom dwelling	12 square metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability and functionality of the private open space, including its size and accessibility.
- The amenity of the private open space based on the orientation of the lot, noise exposure, the wind conditions and the sunlight it will receive.
- The availability of and access to public or communal open space.
- The useability and functionality of any additional living area or bedroom area, including its size and layout.

58.05-4 Storage objective

04/05/2022
VC210

To provide adequate storage facilities for each dwelling.

Standard D21

Each dwelling should have convenient access to usable and secure storage space.

The total minimum storage space (including kitchen, bathroom and bedroom storage) should meet the requirements specified in Table D10.

Table D10 Storage

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
Studio	8 cubic metres	5 cubic metres
1 bedroom dwelling	10 cubic metres	6 cubic metres

Dwelling type	Total minimum storage volume	Minimum storage volume within the dwelling
2 bedroom dwelling	14 cubic metres	9 cubic metres
3 or more bedroom dwelling	18 cubic metres	12 cubic metres

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability, functionality and location of storage facilities provided for the dwelling.

58.06 DETAILED DESIGN

13/04/2017
VC136

58.06-1 Common property objectives

04/05/2022
VC210

To ensure that communal open space, car parking, access areas and site facilities are practical, attractive and easily maintained.

To avoid future management difficulties in areas of common ownership.

Standard D22

Developments should clearly delineate public, communal and private areas.

Common property, where provided, should be functional and capable of efficient management.

58.06-2 Site services objectives

04/05/2022
VC210

To ensure that site services are accessible and can be installed and maintained.

To ensure that site services and facilities are visually integrated into the building design or landscape.

Standard D23

Development should provide adequate space (including easements where required) for site services to be installed and maintained efficiently and economically.

Meters and utility services should be designed as an integrated component of the building or landscape.

Mailboxes and other site facilities should be adequate in size, durable, water-protected, located for convenient access and integrated into the overall design of the development.

Decision guideline

Before deciding on an application, the responsible authority must consider:

- Any relevant urban design objective, policy or statement set out in this scheme.
- The design response.

58.06-3 Waste and recycling objectives

04/05/2022
VC210

To ensure dwellings are designed to encourage waste recycling.

To ensure that waste and recycling facilities are accessible, adequate and attractive.

To ensure that waste and recycling facilities are designed and managed to minimise impacts on residential amenity, health and the public realm.

Standard D24

Developments should include dedicated areas for:

- Waste and recycling enclosures which are:
  - Adequate in size, durable, waterproof and blend in with the development.
  - Adequately ventilated.
  - Located and designed for convenient access by residents and made easily accessible to people with limited mobility.
- Adequate facilities for bin washing. These areas should be adequately ventilated.
- Collection, separation and storage of waste and recyclables, including where appropriate opportunities for on-site management of food waste through composting or other waste recovery as appropriate.

- Collection, storage and reuse of garden waste, including opportunities for on-site treatment, where appropriate, or off-site removal for reprocessing.
- Adequate circulation to allow waste and recycling collection vehicles to enter and leave the site without reversing.
- Adequate internal storage space within each dwelling to enable the separation of waste, recyclables and food waste where appropriate.

Waste and recycling management facilities should be designed and managed in accordance with a Waste Management Plan approved by the responsible authority and:

- Be designed to meet the better practice design options specified in *Waste Management and Recycling in Multi-unit Developments* (Sustainability Victoria, 2019).
- Protect public health and amenity of residents and adjoining premises from the impacts of odour, noise and hazards associated with waste collection vehicle movements.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- Any relevant waste and recycling objective, policy or statement set out in this scheme.

58.06-4 External walls and materials objective

04/05/2022
VC210

To ensure external walls use materials appropriate to the existing urban context or preferred future development of the area.

To ensure external walls endure and retain their attractiveness.

Standard D25

External walls should be finished with materials that:

- Do not easily deteriorate or stain.
- Weather well over time.
- Are resilient to the wear and tear from their intended use.

External wall design should facilitate safe and convenient access for maintenance.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- Any relevant building design and urban design objective, policy or statement set out in this scheme.
- The urban context report.
- The design response.

58.07 INTERNAL AMENITY

13/04/2017
VC136

58.07-1 Functional layout objective

04/05/2022
VC210

To ensure dwellings provide functional areas that meet the needs of residents.

Standard D26

Bedrooms should:

- Meet the minimum internal room dimensions specified in Table D11.
- Provide an area in addition to the minimum internal room dimensions to accommodate a wardrobe.

Table D11 Bedroom dimensions

Bedroom type	Minimum width	Minimum depth
Main bedroom	3 metres	3.4 metres
All other bedrooms	3 metres	3 metres

Living areas (excluding dining and kitchen areas) should meet the minimum internal room dimensions specified in Table D12.

Table D12 Living area dimensions

Dwelling type	Minimum width	Minimum area
Studio and 1 bedroom dwelling	3.3 metres	10 sqm
2 or more bedroom dwelling	3.6 metres	12 sqm

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The useability, functionality and amenity of habitable rooms.

58.07-2 Room depth objective

04/05/2022
VC210

To allow adequate daylight into single aspect habitable rooms.

Standard D27

Single aspect habitable rooms should not exceed a room depth of 2.5 times the ceiling height.

The depth of a single aspect, open plan, habitable room may be increased to 9 metres if all the following requirements are met:

- The room combines the living area, dining area and kitchen.
- The kitchen is located furthest from the window.
- The ceiling height is at least 2.7 metres measured from finished floor level to finished ceiling level. This excludes where services are provided above the kitchen.

The room depth should be measured from the external surface of the habitable room window to the rear wall of the room.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which the habitable room is provided with reasonable daylight access through the number, size, location and orientation of windows.
- The useability, functionality and amenity of the dwelling based on layout, siting, size and orientation of habitable rooms.
- Any overhang above habitable room windows that limits daylight access.

58.07-3 Windows objective

04/05/2022
VC210

To allow adequate daylight into new habitable room windows.

Standard D28

Habitable rooms should have a window in an external wall of the building.

A window may provide daylight to a bedroom from a smaller secondary area within the bedroom where the window is clear to the sky.

The secondary area should be:

- A minimum width of 1.2 metres.
- A maximum depth of 1.5 times the width, measured from the external surface of the window.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The extent to which the habitable room is provided with reasonable daylight access through the number, size, location and orientation of windows.
- The useability and amenity of the dwelling based on the layout, siting, size and orientation of habitable rooms.

58.07-4 Natural ventilation objectives

04/05/2022
VC210

To encourage natural ventilation of dwellings.

To allow occupants to effectively manage natural ventilation of dwellings.

Standard D29

The design and layout of dwellings should maximise openable windows, doors or other ventilation devices in external walls of the building, where appropriate.

At least 40 per cent of dwellings should provide effective cross ventilation that has:

- A maximum breeze path through the dwelling of 18 metres.
- A minimum breeze path through the dwelling of 5 metres.
- Ventilation openings with approximately the same area.

The breeze path is measured between the ventilation openings on different orientations of the dwelling.

Decision guidelines

Before deciding on an application, the responsible authority must consider:

- The design response.
- The size, orientation, slope and wind exposure of the site.

- The extent to which the orientation of the building and the layout of dwellings maximises opportunities for cross ventilation.
- Whether an alternative design meets the relevant objectives having regard to the amenity of the dwelling and the site context.

59 VICSMART APPLICATIONS AND REQUIREMENTS

31/07/2018
VC148

59.01 REALIGN THE COMMON BOUNDARY BETWEEN TWO LOTS

31/07/2018
VC148

59.01-1 Information requirements

01/07/2021
VC203

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A layout plan, drawn to scale and fully dimensioned showing:
  - The location, shape and size of the site.
  - The location of any existing buildings, car parking area, driveways, storage areas, loading areas and private open space.
  - The location of any easements on the subject land.
  - The location of the approved stormwater discharge point.
  - The location and details of any significant vegetation.
  - The location of any street trees, poles, pits or other street furniture.
  - Existing and proposed vehicle access to the lots.
  - Any abutting roads.
  - The location of the existing and proposed common boundary between the lots and the proposed size and shape of the realigned lots.
  - Any proposed common property to be owned by a body corporate and the lots participating in the body corporate.
- If the land is in more than one ownership, the consent of the owners of the land.
- If common property is proposed, an explanation of why the common property is required.
- A written statement that describes:
  - The existing use of the land and its possible future development.
  - The reason for the realignment of the common boundary.
  - For land in an overlay, how the proposal responds to any statement of significance, objectives or requirements specified in the schedule to the overlay.
- If the land is in an area where reticulated sewerage is not provided, a plan which shows the location of any existing effluent disposal area for each lot or a Land Capability Assessment which demonstrates that each lot is capable of treating and retaining all wastewater and the risks to human health and the environment of a on-site wastewater management system constructed, installed or altered on the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017*.
- If the land is in a residential zone and the realignment of the common boundary will result in a vacant lot, information that shows that the vacant lot meets the requirements of Standard C8 of Clause 56.

59.01-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- The suitability of the subdivision including how the layout and dimensions of the subdivision:
  - Respond to and integrate with the surrounding urban or rural environment.
  - Protect significant vegetation.

  - Appropriately accommodate any existing or proposed easements on the lots.
  - Protect solar access for existing and any future dwellings on the lots.
  - Appropriately accommodate any existing waste storage areas, loading bays and vehicle standing areas on the site.
  - Appropriately accommodate private open space.
  - Appropriately accommodate the provision of utility services to each lot.
  - If the land is in an area where reticulated sewerage is not provided to each lot, whether the layout of the subdivision accommodates the effluent disposal area for each lot.
  - Appropriately accommodate the siting of buildings having regard to the risk of spread of fire.
  - Appropriately accommodate the existing use and possible future development of the land.
- Whether the provision of common property is appropriate for the purpose for which the land is to be commonly held.
- If the land is in a residential zone and the realignment of the common boundary will result in a vacant lot, the objective and standard of Clause 56.04-2.
- The statement of significance and the objectives contained in the schedule to the overlay and whether the subdivision will adversely affect that significance or the objectives.
- Whether the proposal meets any requirements specified in the overlay or the schedule to the overlay.

59.02 SUBDIVISION OF BUILDINGS AND CAR PARKING SPACES

31/07/2018
VC148

59.02-1 Information requirements

01/07/2021
VC203

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A copy of the relevant planning permit and approved plans for the development.
- A layout plan, drawn to scale and fully dimensioned showing:
  - The location, shape and size of the site.
  - The location of any existing buildings, car parking areas and private open space.
  - The location, shape and size of the proposed lots to be created.
  - The location of any easements on the subject land.
  - The location and details of any significant vegetation.
  - The location of the approved stormwater discharge point.
  - Any abutting roads.
  - The location of any street trees, poles, pits and other street furniture.
  - Existing and proposed vehicle access to the lots.
  - Any loading bays and vehicle standing areas.
  - Any waste storage areas.
  - Any proposed common property to be owned by a body corporate and the lots participating in the body corporate.
- For the subdivision of existing buildings and car parking spaces, a copy of the occupancy permit or a certificate of final inspection for the development.
- For the subdivision of land into two lots with an approved development currently under construction, evidence that the construction has commenced.
- If common property is proposed, an explanation of why the common property is required.
- If the land is in an area where reticulated sewerage is not provided, a plan which shows the location of any existing effluent disposal area for each lot or a Land Capability Assessment which demonstrates that each lot is capable of treating and retaining all wastewater and manage the risks to human health and the environment of an on-site wastewater management system constructed, installed or altered on the lot in accordance with the requirements of the Environment Protection Regulations under the *Environment Protection Act 2017*.
- For land in an overlay, a written statement that describes how the proposal responds to any statement of significance, objectives or requirements specified in the schedule to the overlay.

59.02-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- The suitability of the subdivision including how the layout and dimensions of the subdivision:
  - Are consistent with the approved plans and conditions of any relevant planning permit for the development.
  - Are consistent with the layout of existing buildings and car parking spaces on the land.
  - Appropriately accommodate any existing waste storage areas.

  - Appropriately accommodate any existing loading bay and vehicle storage area.
  - Appropriately accommodate significant vegetation.
  - Appropriately accommodate existing or proposed easements on the lots.
  - Appropriately accommodate the provision of utility services to each lot.
  - Appropriately accommodate the siting of buildings having regard to safety and the risk of spread of fire.
- If the land is in an area where reticulated sewerage is not provided to each lot, whether the layout of the subdivision accommodates the effluent disposal area for each lot.
- For the subdivision of existing buildings and car parking spaces, whether each new lot, other than common property, contains an existing building, part of an existing building or a car parking space.
- Whether the provision and location of common property is appropriate for the purpose for which the land is to be commonly held.
- Whether any public open space contribution is required under Clause 53.01 of this scheme or under Section 18 of the *Subdivision Act 1988*.
- The statement of significance and the objectives contained in the schedule to the overlay and whether the subdivision will adversely affect that significance or the objectives.
- Whether the proposal meets any requirements specified in the overlay or the schedule to the overlay.

59.03 FRONT FENCE IN A RESIDENTIAL ZONE

31/07/2018
VC148

59.03-1 Information requirements

31/07/2018
VC148

An application must be accompanied by the following information as appropriate:

- A copy of the title for the subject land and a copy of any registered restrictive covenant.
- A plan drawn to scale and fully dimensioned showing:
  - The location, shape and size of the site.
  - The location, length, height and design of the proposed fence including details of materials.
  - The location, height and design of any existing front fence on adjoining and nearby properties including details of materials.
- A photograph of the site and adjoining and nearby properties along the street frontage.
- The reason for the proposed height.

59.03-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- Whether the setback, height and design of the proposed fence are:
  - Appropriate to the neighbourhood character and the site.
  - Consistent with any relevant neighbourhood character objective or policy set out in the scheme.
  - Appropriate with the setback, height and appearance of front fences on adjoining and nearby properties.
  - Complement the design of the dwelling.
- The extent to which slope and retaining walls reduce the effective height of the proposed fence.
- Whether the proposed fence is needed to minimise noise intrusion.
- The reason for the proposed height.

59.04 BUILDINGS AND WORKS IN A ZONE (EXCEPT A RURAL ZONE)

31/07/2018
VC148

59.04-1 Information requirements

08/09/2025
VC282

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A description of the use of the land and the proposed buildings and works.
- A layout plan, drawn to scale and fully dimensioned showing:
  - The boundaries and dimensions of the site.
  - Adjoining roads.
  - The location, height and use of buildings and works on adjoining land.
  - Relevant ground levels.
  - Any contaminated soils and filled areas, where known.
  - The layout of existing and proposed buildings and works.
  - All existing and proposed driveways, car parking, bicycle parking and loading areas.
  - Existing and proposed landscape areas.
  - All external storage and waste treatment areas.
  - The location of easements and services.
- Elevation drawings to scale showing the height, colour and materials of all proposed buildings and works.
- A photograph of the building or area affected by the proposal.
- A written statement describing the proposal and if relevant:
  - The built form and character of adjoining and nearby buildings.
  - The heritage character of any adjoining heritage places.
  - Ground floor street frontages, including visual impacts and pedestrian safety.
- A written statement describing whether the proposed buildings and works meet:
  - The number of car parking spaces required under Clause 52.06 or in the schedule to Clause 45.09.
  - Any development requirement specified in the zone or the schedule to the zone.
- Any relevant requirement in an approved development plan or incorporated plan for the land.
- Any other information specified in the schedule to the zone.
- For land in a residential zone, a written statement, plan or diagram showing how the proposal meets:
  - The requirements in the following standards of Clause 54:
    - A2-3 Side and rear setbacks.
    - A2-4 Walls on boundaries.
    - A4-1 Daylight to existing windows.
    - A4-2 Existing north-facing windows.
    - A4-3 Overshadowing secluded open space.

- A4-4 Overlooking.
- A5-2 Overshadowing domestic solar energy systems.

If a schedule to the zone specifies a requirement of a standard different from a requirement set out in the Clause 54 standard the schedule to the zone applies.

59.04-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- Whether the proposal is consistent with any relevant urban design and built form policy set out in the scheme.
- Whether the movement of pedestrians and cyclists, and vehicles providing for supplies and waste removal are appropriately accommodated.
- Whether the design complements the built form of the surrounding properties and the streetscape, including the conservation of buildings, the design of verandahs, access from the street front, protecting active frontages to pedestrian areas, the treatment of the fronts and backs of buildings and their appurtenances, illumination of buildings or their immediate spaces and the landscaping of land adjoining a road.
- Whether the land and building have availability of and connection to services.
- Whether the proposed development adversely impacts the amenity of the land and the locality including existing dwellings on adjoining sites.
- Whether the proposed development appropriately provides for landscaping.
- Whether the proposed development adversely affects solar access to existing open spaces and public places.
- Whether the proposal meets the car parking requirements specified in Clause 52.06 or in the schedule to the Parking Overlay.
- Whether the proposal meets the maximum building height specified in the schedule to the zone.
- Whether the proposal meets any relevant requirements specified in the zone or the schedule to the zone.
- Whether the proposal is consistent with any relevant approved development plan or incorporated plan.
- The objectives set out in the schedule to the zone.
- Whether the proposal provides adequate vehicle loading and unloading facilities.
- For land in a residential zone:
  - Whether the proposed development is consistent with any neighbourhood character objectives set out in the schedule to the zone.
  - Whether the development is compatible with residential use.
  - The scale and intensity of the development.
  - The design, height, setback and appearance of the proposed buildings and works.

59.05 BUILDINGS AND WORKS IN AN OVERLAY

31/07/2018
VC148

59.05-1 Information requirements

08/09/2025
VC282

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A plan, drawn to scale and fully dimensioned showing:
  - The location, shape and size of the site.
  - The location, height and design of the proposed buildings and works including details of materials.
  - The location of any existing buildings, including fences and trees.
  - For land in a Neighbourhood Character Overlay, any buildings proposed to be demolished.
- For land in a Significant Landscape Overlay, a written description of the proposal including:
  - How the proposal responds to the landscape significance and objectives specified in a schedule to the overlay.
  - The impact of the proposed buildings and works on the significance of the landscape.
- For land in a Neighbourhood Character Overlay, a written description of the proposal including:
  - The built form and character of adjoining and nearby buildings.
  - How the proposal responds to the key features and objectives specified in the schedule to the overlay.
  - If demolition is proposed, the reason for the demolition.
  - How the proposal meets the requirements of Clauses 54.02-1, 54.02-2, 54.02-3, 54.02-4, 54.02-5, 54.02-7, 54.03-1, 54.04-1, 54.04-2, 54.05-1, including any Clause 54 modification specified in the schedule to the overlay.
- For land in a Design and Development Overlay, a written description of the proposal including:
  - How the proposal responds to the design objectives specified in a schedule to the overlay.
  - How the proposal meets the requirements specified in a schedule to the overlay.
  - The built form and character of adjoining and nearby buildings.
- A photograph of the building or area affected by the proposal.
- For land in an Erosion Management Overlay, information showing:
  - The extent of any proposed earthworks.
  - The means proposed to stabilise disturbed areas.
- For an application under the Salinity Management Overlay, written advice including plan references and any conditions from the referral authority demonstrating that the referral authority has considered the proposal for which the application is made within the past three months and does not object to the granting of the permit for the proposal.

59.05-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- The statement of significance and the objectives contained in the schedule to the overlay and whether the buildings and works will adversely affect that significance or the objectives.

- Whether the proposal meets any requirements specified in the overlay or the schedule to the overlay.
- For an application in a Salinity Management Overlay, any comments from the relevant referral authority.
- For an application in a Neighbourhood Character Overlay, the relevant objectives, standards and decision guidelines of Clause 54.
- Any relevant decision guideline specified in the overlay and the schedule to the overlay.

59.06 REMOVE, DESTROY OR LOP ONE TREE

20/03/2023
VC229

59.06-1 Information requirements

31/07/2018
VC148

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- If the tree to be removed, destroyed or lopped is identified as a significant tree in a schedule to the overlay, a report prepared by an arborist.
- A layout plan, drawn to scale and fully dimensioned showing:
  - The location, shape, size and slope of the site.
  - The location of the tree to be removed, destroyed or lopped.
  - The location and type of other significant vegetation on the site.
  - The location, species and height of any significant trees on the site that have been removed or approved to be removed in the past 3 years.
- A written statement that describes:
  - The species, height and trunk girth of the tree to be removed, destroyed or lopped.
  - The reason the tree is to be removed, destroyed or lopped.
  - If provision is to be made to replace the tree elsewhere on the land.
  - If the tree is to be lopped, the extent of lopping proposed.
  - Any impacts on the significance of the area.
- A photograph of the tree to be removed, destroyed or lopped.

59.06-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- The statement of significance and the objectives contained in the schedule to the overlay and whether the proposal will adversely affect that significance or the objectives.
- Whether the tree proposed to be removed, destroyed or lopped contributes to the significance of the area and whether the proposal will adversely affect that significance.
- Whether the removal or lopping of the tree is needed because of the health of the tree.
- Whether the lopping of the tree will adversely affect the health, appearance or significance of the tree.
- Whether the removal of the tree will contribute to soil erosion, slippage or salinisation.
- Whether the removal or lopping of the tree is needed to create a defendable space to reduce the risk of bushfire to life and property.
- If the tree is a native tree, its role in conserving flora and fauna and whether the proposal will adversely affect the conservation of flora and fauna of the area.
- Whether provision is made to plant a new tree elsewhere on the land.
- The reasons for removing the tree including the health of the tree to be removed.
- The cumulative impact of the number of trees that have been removed or been approved for removal in the past 3 years.
- Any relevant decision guideline specified in the overlay or the schedule to the overlay.

59.07 APPLICATIONS UNDER A HERITAGE OVERLAY

31/07/2018
VC148

59.07-1 Information requirements

04/11/2022
VC226

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A plan, drawn to scale and fully dimensioned showing:
  - The location, shape and size of the site.
  - The location of any existing buildings, including fences and trees.
  - The location, height and design of the proposed building or works including details of proposed materials.
  - Any buildings to be demolished.
  - An elevation of the proposed building.
  - The size and design of any proposed sign, including details of the supporting structure and any proposed illumination.
  - The location, style, size, colour and materials of any proposed solar energy system (that is visible from the street frontage or any nearby public park), including details of the supporting structure.
- A written description of the proposal including:
  - Any impacts on the significance of the heritage place.
  - How the proposal responds to any relevant local heritage policy set out in the planning scheme.
  - If lopping of a tree is proposed, the reason for the lopping, the extent of lopping and an arborist report.
- The proposed colour schedule and nature of any materials and finishes.
- A photograph of the area affected by the proposal including any building, outbuilding, fence or tree which may be affected by the proposal.
- A photograph of the subject site and adjoining properties along the street frontage.
- If subdivision is proposed, the location, shape and size of the proposed lots to be created.
- If a sign is proposed:
  - The location, size and design of the proposed sign on the site or building.
  - The location and size of existing signage on the site including details of any signs to be retained or removed.
- If a solar energy system is proposed that is visible from a street (other than a lane) or public park, measures proposed to minimise the visibility of the system and protect the structural integrity of heritage features.

59.07-2 Decision guidelines

04/11/2022
VC226

In assessing an application the responsible authority must consider as appropriate:

General

- The significance of the heritage place and whether the proposal will adversely affect that significance.

- Any applicable statement of significance, heritage study and any applicable conservation policy.
- Whether the proposal will adversely affect the character or appearance of the building or heritage place.
- Any relevant local heritage policy set out in the planning scheme.

Demolition

- Whether the outbuilding to be demolished contributes to the significance, character or appearance of the building or heritage place.

Buildings and works

- Whether the location, bulk, form and appearance of the proposed building or works will adversely affect the significance of the building or heritage place.
- Whether the proposed building or works will affect the health or appearance of a tree which is the subject of a Heritage Overlay.

Alterations

- Whether the proposed alterations will restore or reconstruct original fabric which has been removed or damaged.
- Whether the proposed alterations will adversely affect the significance, character and appearance of the heritage place.

Fences

- Whether the fence proposed to be demolished contributes to the significance, character and appearance of the building or heritage place.
- Whether the proposed fence, including its style, height and materials, is appropriate to the building or heritage place.

Trees

- Whether the proposed lopping will adversely affect the health, appearance or significance of the tree.

Subdivision

- Whether the proposed subdivision retains the significant setting (landscapes, landscape features and views) of the heritage place.
- Whether the proposed subdivision respects the rhythm and spacing of buildings in the streetscape.
- Whether the proposed subdivision will result in a new boundary fence, wall or structure that adversely affects the setting of the heritage place.

Signage

- Whether the proposed sign will adversely affect the significance, character or appearance of the heritage place.

Solar energy systems

- Any relevant building design or energy policy set out in the Planning Policy Framework.
- Whether the proposed solar energy system can be sited to minimise visibility from a street or public park without significantly impacting its performance.
- Whether the proposed solar energy system can be designed to minimise the impact on the significance, character or appearance of the heritage place.

59.08 APPLICATIONS UNDER A SPECIAL BUILDING OVERLAY

31/07/2018
VC148

59.08-1 Information requirements

31/07/2018
VC148

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A plan, drawn to scale and fully dimensioned showing:
  - The boundaries and dimensions of the site.
  - The layout, size and use of existing and proposed buildings and works, including floor plan layout and vehicle parking areas.
  - Setbacks between existing and proposed buildings and site boundaries.
  - Natural surface levels of the site to Australian Height Datum.
  - Floor and surface levels of any existing and proposed buildings and works to Australian Height Datum.
  - Cross sectional details of any basement entry ramps and other basement entries to Australian Height Datum, showing floor levels of entry and exit areas and drainage details.
  - If subdivision is proposed, the location, shape and size of the proposed lots to be created.
- If a referral to the floodplain management authority is required, written advice, including endorsed plans of the proposal and any conditions, from the relevant floodplain management authority demonstrating that the floodplain management authority has considered the proposal for which the application is made within the past three months and does not object to the granting of the permit for the proposal.

59.08-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- Clauses 13.01 and 13.03 of the Planning Policy Framework.
- Whether the proposal is consistent with any local floodplain development plan for the area incorporated into this scheme.
- If a referral to the floodplain management authority is required, any comments from the relevant floodplain management authority.
- The existing use and development of the land.
- Whether the proposed use or development could be located on flood-free land or land with a lesser flood hazard outside this overlay.
- The susceptibility of the development to flooding and flood damage.
- The flood risk including:
  - The frequency, duration, extent, depth and velocity of flooding of the site and accessways.
  - The flood warning time available.
  - The danger to the occupants of the development, other floodplain residents and emergency personnel if the site or accessway is flooded.
- The effect of the development redirecting or obstructing floodwater, stormwater or drainage water and the effect of the development on reducing flood storage and increasing flood levels and flow velocities.

59.09 SIGNS

31/07/2018
VC148

59.09-1 Information requirements

31/07/2018
VC148

An application must be accompanied by the following information, as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A site context report, using a site plan, photographs or other methods to accurately describe:
  - The location of the proposed sign on the site or building and distance from property boundaries.
  - The location and size of existing signs on the site including details of any signs to be retained or removed.
  - The location and form of existing signs on adjoining properties and in the locality.
  - The location of closest traffic control signs.
  - Identification of any view lines or vistas that could be affected by the proposed sign.
- The dimensions, height above ground level and extent of projection of the proposed sign.
- The height, width and depth of the total sign structure including the method of support and any associated structures such as safety devices and service platforms.
- The colour, lettering style and materials of the proposed sign.
- The size of the proposed display (total display area including all sides of a multi-sided sign).

59.09-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- Whether the proposal is consistent with any relevant local advertising policy set out in the scheme.
- Whether the proposal will impact the character of the area including:
  - Natural environment, heritage, waterway, open space and rural landscape values.
  - The desired future character of the area.
  - The cumulative impact of signs on the character of an area.
  - The need to avoid visual disorder or clutter of signs.
- Whether the proposal will impact views and vistas including:
  - Important views from the public realm.
  - Significant public views.
  - Views to existing signs.
- Whether the proportion, scale and form of the proposed sign relates to the site, building, streetscape, setting or landscape including:
  - The position of the proposed sign, including if it protrudes above existing buildings or landscape and natural elements.
  - Screening of unsightly elements.
  - The number, scale and location of existing signs.
  - The ability to rationalise or simplify the number of signs.
  - The ability to include landscaping to reduce the visual impact of the proposed sign structure.

  - The extent to which the proposed sign requires the removal of vegetation.

- Whether the proposed sign is consistent with any outdoor advertising theme.
- Whether there is a need for identification and the opportunities for adequate identification on the site or locality.
- Whether the proposed sign will adversely impact road safety.

59.10 CAR PARKING

31/07/2018
VC148

59.10-1 Information requirements

31/07/2018
VC148

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A plan, drawn to scale and fully dimensioned showing:
  - The boundaries and dimensions of the site.
  - The location of existing buildings.
  - All car parking spaces and access lanes.
  - Allocation of car parking spaces to different uses or tenancies, if applicable.
  - Landscaping and sensitive water design treatments.
- A written statement that describes:
  - The proposed use of the site, number of employees and patrons and hours of operation.
  - The previous use of the site.
  - The site and floor area to be occupied.
  - The number of car parking spaces required under Clause 52.06-5 or in a schedule to the Parking Overlay.
  - The total number of car parking spaces provided.
  - The likely impact of a reduction in car parking on the amenity of the area and on the area's existing car parking.

59.10-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- Whether the reduction of the car parking requirement is consistent with any relevant local planning policy or incorporated plan.
- The objectives contained in the schedule to the Parking Overlay.
- Whether there is availability of alternative car parking in the locality including:
  - Efficiencies gained from the consolidation of shared car parking spaces.
  - Public car parks intended to serve the land.
  - On street parking in non-residential zones.
  - Streets in residential zones specifically managed for non-residential parking.
- The practicality of providing car parking on the site, particularly for lots of less than 300 square metres.
- Whether there is any car parking deficiency associated with the existing use of the land.
- Whether there is any credit that should be allowed for car parking spaces provided on common land or by a Special Charge Scheme or cash-in-lieu payment.
- Whether fewer car parking spaces will impact local amenity, including pedestrian amenity and the amenity of nearby residential areas.
- Whether there is a need to create safe, functional and attractive parking areas.
- The availability of public transport in the locality of the land.

- The convenience of pedestrian and cyclist access to the land.
- The likelihood of multi-purpose trips within the locality which are likely to be combined with a trip to the land in connection with the use.
- The equity of reducing the car parking requirement having regard to any historic contributions by existing businesses.
- On street parking in residential zones in the locality of the land that is intended to be for residential use.
- The future growth and development of any nearby activity centre.
- Local traffic management in the locality of the land.
- Access to or provision of alternative transport modes to and from the land.
- Whether any car parking spaces to be provided meet the design standards of Clause 52.06.
- Any relevant decision guideline specified in a schedule to the Parking Overlay.

59.11 [NO CONTENT]

31/07/2018
VC148

59.12 TWO LOT SUBDIVISION IN A RURAL ZONE

31/07/2018
VC148

59.12-1 Information requirements

31/07/2018
VC148

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A layout plan, drawn to scale and fully dimensioned showing:
  - The location, shape and size of the site.
  - The location of any existing buildings and associated works.
  - The location, shape and size of the proposed lots to be created.
  - The location of any easements on the subject land.
  - The location of any significant vegetation, waterways and wetlands.
  - The location of the approved stormwater discharge point and effluent disposal areas.
  - Any abutting roads.
  - Existing and proposed vehicle access to the lots.

59.12-2 Decision guidelines

31/07/2018
VC148

In assessing an application the responsible authority must consider as appropriate:

- The suitability of the subdivision including how the layout and dimensions of the subdivision:
  - Are consistent with the layout of existing buildings and associated works on the land.
  - Appropriately accommodate significant vegetation.
  - Appropriately accommodate existing or proposed easements on the lots.
  - Appropriately accommodate the provision of utility services to each lot.
  - Appropriately accommodate existing and proposed vehicle access to the lots.
- If the land is in an area where reticulated sewerage is not provided to each lot, whether the layout of the subdivision accommodates the effluent disposal area for each lot.
- The location and design of existing and proposed infrastructure including roads, gas, water, drainage, telecommunications and sewerage facilities.
- Any Regional Catchment Strategy applying to the land.
- If the land is in an overlay, statement of significance and the objectives contained in the schedule to the overlay and whether the subdivision will adversely affect that significance or the objectives.
- Whether any public open space contribution is required under Clause 53.01 of this scheme or under Section 18 of the *Subdivision Act 1988*.

59.13 BUILDINGS AND WORKS IN A RURAL ZONE

31/07/2018
VC148

59.13-1 Information requirements

31/07/2018
VC148

An application must be accompanied by the following information as appropriate:

- A copy of title for the subject land and a copy of any registered restrictive covenant.
- A description of the use of the land and the proposed buildings and works.
- A layout plan, drawn to scale and fully dimensioned showing:
  - The boundaries and dimensions of the site.
  - Adjoining roads.
  - The location of any waterway or wetlands.
  - The location and use of buildings and works on adjoining land.
  - Relevant ground levels.
  - The layout of existing and proposed buildings and works.
  - All existing and proposed driveways, car parking and loading areas.
  - Existing and proposed landscape areas.
  - All external storage and waste treatment areas.
- Elevation drawings to scale showing the height, colour and materials of all proposed buildings and works.
- A photograph of the building or area affected by the proposal.

59.13-2 Decision guidelines

03/02/2022
VC199

In assessing an application the responsible authority must consider as appropriate:

- The impact of the siting, design, height, bulk, colours and materials to be used, on the natural environment, character and appearance of the area, landscape features, major roads, vistas and water features and the measures to be undertaken to minimise any adverse impacts.
- Whether the proposal will have an adverse impact on adjoining and nearby land uses.
- The need to protect amenity of existing residents.
- The need to locate buildings in one area to avoid any adverse impacts on surrounding agricultural uses.
- The likely environmental impact on the natural physical features and biodiversity of the area, including the need to retain vegetation and faunal habitat and the need to revegetate land including riparian buffers along waterways, gullies, ridgelines, property boundaries and saline discharge and recharge areas.
- The capability of the land to accommodate the proposed development.
- Whether the development will support and enhance agricultural production.
- The location of on-site effluent disposal areas to minimise the impact of nutrient loads on waterways and native vegetation.
- Any Regional Catchment Strategy and associated plan applying to the land.
- The impact of the proposal on any wetlands or waterways.
- Any integrated land management plan prepared for the site.

- Whether the development will require traffic management measures.
- For buildings and works associated with a dwelling:
  - Whether the dwelling will result in the loss or fragmentation of productive agricultural land.
  - Whether the dwelling will be adversely affected by agricultural activities on adjacent and nearby land due to dust, noise, odour, use of chemicals and farm machinery, traffic and hours of operation.
  - Whether the dwelling will adversely affect the operation and expansion of adjoining and nearby agricultural uses.
  - The potential for the proposal to lead to a concentration or proliferation of dwellings in the area and the impact of this on the use of the land for agriculture.

59.14 [NO CONTENT]

08/09/2025
VC282

59.15 LOCAL VICSMART APPLICATIONS

31/07/2018
VC148

The schedule to this clause may specify classes of application that are VicSmart applications to which Clause 71.06 applies. A class of application specified must not be a class of VicSmart application specified in another provision of this planning scheme.

The classes of VicSmart application are specified in three tables:

- Table 1 specifies classes VicSmart application under a zone.
- Table 2 specifies classes VicSmart application under an overlay.
- Table 3 specifies classes VicSmart application under a particular provision.

Each table in the schedule is divided into four columns:

- Column 1 specifies the name or class of zone or overlay or name of particular provision.
- Column 2 specifies the development.
- Column 3 specifies the provision of the planning scheme that contains the permit requirement applicable to the development.
- Column 4 specifies the information requirements and decision guidelines in Clauses 59.01 to 59.14 or the schedule to Clause 59.16 applicable to the class of VicSmart application.

Subject to Clause 71.06, an application under a provision specified in Column 3 for a use or development specified in Column 2 is a class of VicSmart application and must be assessed against the provision specified in Column 4.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 59.15 LOCAL VICSMART APPLICATIONS

1.0

08/07/2021
C211brim

Table 1 Classes of VicSmart application under zone provisions

Name of zone or class of zone	Class of application	Permit requirement provision	Information requirements and decision guidelines
None specified			

2.0

08/07/2021
C211brim

Table 2 Classes of VicSmart application under overlay provisions

Name of overlay or class of overlay	Class of application	Permit requirement provision	Information requirements and decision guidelines
None specified			

3.0

08/07/2021
C211brim

Table 3 Classes of VicSmart application under particular provisions

Name of particular provision	Class of application	Permit requirement provision	Information requirements and decision guidelines
None specified			

59.16 INFORMATION REQUIREMENTS AND DECISION GUIDELINES FOR LOCAL VICSMART APPLICATIONS

31/07/2018
VC148

A schedule to this clause may set out information requirements and decision guidelines for a class of VicSmart application specified in the Schedule to Clause 59.15.

08/07/2021
C211brim

SCHEDULE 1 TO CLAUSE 59.16 INFORMATION REQUIREMENTS AND DECISION GUIDELINES FOR LOCAL VICSMART APPLICATIONS

1.0 Information requirements

08/07/2021
C211brim

None specified.

2.0 Decision guidelines

08/07/2021
C211brim

None specified.

60 GENERAL PROVISIONS

31/07/2018
VC148

This section sets out provisions about existing uses, decision guidelines, referral of applications and other matters.

61 [NO CONTENT]

31/07/2018
VC148

62 GENERAL EXEMPTIONS

31/07/2018
VC148

62.01 USES NOT REQUIRING A PERMIT

14/12/2023
VC253

Any requirement in this scheme relating to the use of land, other than a requirement in the Public Conservation and Resource Zone, does not apply to:

- The use of land for a Road except within the Urban Floodway Zone and a Public Conservation and Resource Zone.
- The use of land for Natural systems.
- The use of land in a road if the use is associated with the use of adjoining land and is authorised by the Council under a local law.
- The use of land in a road to trade from a stall, stand, motor vehicle, trailer, barrow or other similar device.
- The use of land for wind measurement by an anemometer for three years or less.
- The use of land for earth and energy resources industry if the conditions of Clause 52.08 are met.
- The use of land for a carnival or circus if the requirements of A 'Good Neighbour' Code of Practice for a Circus or Carnival, October 1997 are met.
- The use of land for apiculture if the requirements of the Apiary Code of Practice, May 2011 are met.
- The use of land for temporary portable land sales office located on the land for sale.
- The use of land for a telecommunications facility.
- The use of land for a helicopter landing site if the use meets the requirements of Clause 52.15-1.
- The use of land for a minor utility installation.
- The use of land to display a sign.
- The use of land for power lines and electrical sub-stations associated with an energy generation facility or geothermal energy extraction if a permit was issued for such use or development prior to the approval date of Amendment VC157.
- The use of land for environmental monitoring (including monitoring groundwater, noise or air quality) carried out by or on behalf of the Head, Transport for Victoria.
- The use of land for an Electorate office.
- The use of land for a moveable unit as defined in the *Housing Act 1983*, carried out by or on behalf of the Chief Executive Officer, Homes Victoria.

62.02 BUILDINGS AND WORKS

15/03/2019
VC157

Clauses 62.02-1 and 62.02-2 set out exemptions from permit requirements in this scheme relating to the construction of a building or the construction or carrying out of works. These exemptions do not apply to the removal, destruction or lopping of trees and the removal of vegetation. Exemptions for vegetation removal are set out in Clause 62.02-3.

62.02-1 Buildings and works not requiring a permit

14/12/2023
VC253

Any requirement in this scheme relating to the construction of a building or the construction or carrying out of works, other than a requirement in the Public Conservation and Resource Zone, does not apply to:

- Buildings or works which provide for fire protection under relevant legislation.
- Emergency works undertaken by, or on behalf of, a municipality, public authority or utility service provider in the exercise of any power conferred on them under any Act.
- Buildings or works with an estimated cost of $1,000,000 or less carried out by or on behalf of a municipality.
- Maintenance works carried out by a municipality or public authority to prevent or alleviate flood damage.
- An anemometer located on a site for three years or less.
- Buildings and works associated with a use on adjoining land or street trading if authorised under a local law.
- Gardening.
- Buildings and works associated with a minor utility installation.
- Power lines and electrical sub-stations associated with an Energy generation facility or Geothermal energy extraction if a permit was issued for such use or development prior to the approval date of Amendment VC157.
- Buildings or works which are a modification necessary to comply with a direction under the *Dangerous Goods Act 1985* or the *Occupational Health and Safety Act 2004* or a Development Licence, Operating Licence or notice under the *Environment Protection Act 2017*.
- Buildings and works for a telecommunications facility exempt from a permit under clause 52.19-1.
- Buildings and works associated with a dam if a licence is required to construct the dam or to take and use water from the dam under the *Water Act 1989*.
- Buildings and works associated with a carnival or circus if the requirements of A 'Good Neighbour' Code of Practice for a Circus or Carnival, October 1997 are met.
- Buildings and works associated with apiculture if the requirements of the Apiary Code of Practice, May 2011 are met.
- A temporary portable classroom associated with an education centre located on a site for three years or less.
- A temporary shed or temporary structure for construction purposes, or a temporary portable land sales office located on the land for sale.
- A children's cubbyhouse.
- External lighting normal to a dwelling or small second dwelling.
- The construction, alteration, removal or demolition of an observational bore where a licence has been issued for those works under Part 5 of the *Water Act 1989*.

- Any works associated with the use of land for earth and energy resources industry if the conditions of Clause 52.08 are met.
- A crop support or protection structure associated with horticulture, including a trellis, cloche, net and shadecloth. It does not include a structure with a solid roof or solid wall such as a glass house or igloo.
- An annexe attached to a movable caravan located on land used for a camping and caravan park.
- Works associated with geotechnical testing or service proving.
- Buildings and works associated with the use of land in a road to trade from a stall, stand, motor vehicle, trailer, barrow or other similar device.
- The construction of or putting up for display a sign consistent with the requirements of Clause 52.05-10.
- Temporary buildings and works associated with environmental monitoring (including monitoring groundwater, noise or air quality) constructed or carried out by or on behalf of the Head, Transport for Victoria.

62.02-2 Buildings and works not requiring a permit unless specifically required by the planning scheme

14/12/2023
VC253

Any requirement in this scheme relating to the construction of a building or the construction or carrying out of works, other than a requirement in the Public Conservation and Resource Zone, does not apply to:

- A fence.
- The construction of or putting up for display a sign (except for a sign consistent with the requirements of Clause 52.05-10 which is provided for in Clause 62.02-1).
- Roadworks.
- Buildings and works associated with a railway, railway station or tramway constructed or carried out by or on behalf of the Head, Transport for Victoria. If the buildings or works are on land in an Urban Floodway Zone, Floodway Overlay, Land Subject to Inundation Overlay, Special Building Overlay and will redirect or obstruct the water flow path, they must be constructed and carried out to the satisfaction of the relevant floodplain management authority.
- Street furniture including post boxes, telephone booths, fire hydrants, bus shelters, shade sails, traffic control devices and public toilets.
- Park furniture including seating, tables, shelters, rubbish bins, playground equipment, barbeques, shade sails, drinking fountains and public toilets.
- Furniture and works normally associated with an education centre including, but not limited to, outdoor furniture, playground equipment, art works, drinking fountains, rubbish bins and landscaping.
- Disability access and disability facilities associated with an education centre (not including a lift external to a building).
- Art work that is carried out by or on behalf of a public land manager.
- Oil pipelines.
- Buildings and works associated with a moveable unit as defined in the *Housing Act 1983*, carried out by or on behalf of the Chief Executive Officer, Homes Victoria.
- The internal rearrangement of a building or works provided the gross floor area of the building, or the size of the works, is not increased and the number of dwellings is not increased.
- Repairs and routine maintenance to an existing building or works.

- Domestic services normal to a dwelling or small second dwelling.
- A rainwater tank with a capacity of not more than 10,000 litres.
- Bicycle pathways and trails.
- A television antenna.
- A flagpole.
- A domestic swimming pool or spa and associated mechanical and safety equipment if associated with one dwelling on a lot.
- An open-sided pergola or verandah to a dwelling or small second dwelling with a finished floor level not more than 800 mm above ground level and a maximum building height of three metres above ground level.
- A deck to a dwelling or small second dwelling with a finished floor level not more than 800 mm above ground level.
- A disabled access ramp.
- Any works necessary to prevent soil erosion, or to ensure soil conservation or reclamation.
- A solar energy system attached to a building that primarily services the land on which it is situated.
- Buildings and works associated with cat cages and runs, bird cages, dog houses, and other domestic animal enclosures associated with the use of the land as a dwelling.
- Services normal to a building other than a dwelling or small second dwelling, including chimneys, flues, skylights, heating and cooling systems, hot water systems, security systems and cameras, downpipes, window shading devices, or similar.
- An electric vehicle charging station.

This does not apply if a permit is specifically required for any of these matters.

62.02-3 Vegetation removal

30/08/2006
VC40

Any requirement in this scheme relating to the construction or carrying out of works does not apply to the removal, destruction or lopping of trees and the removal of vegetation.

This does not apply if a permit is specifically required to remove, destroy or lop trees or to remove vegetation.

62.03 EVENTS AND OUTDOOR DINING ON PUBLIC LAND

27/06/2025
VC275

62.03-1 Events

27/06/2025
VC275

Any requirement in this scheme relating to the use of land or the construction of a building or the construction or carrying out of works does not apply to:

- an event on public land; or
- temporary buildings or works required for the event;

where that event has been authorised by the public land manager or by the council under a local law.

An event includes land used to provide temporary cultural or community activities and entertainment such as a concert, festival or exhibition.

This does not apply to public land where a local provision of this scheme specifically regulates an event for a particular site.

62.03-2 Outdoor dining

27/06/2025
VC275

In this clause:

Dining means the consumption of food or drink, including liquor. It includes the preparation or sale of food or drink, including liquor, for immediate consumption on, or off, the land.

Exemption from planning scheme requirements

Any requirement in this scheme relating to the use of land, the construction of a building, the construction or carrying out of works, or provision of car parking, including preparation of a car parking plan under Clause 52.06, does not apply to:

- The use of a road or other public land for outdoor dining if the use is associated with the use of adjoining land and is authorised under a local law or by the public land manager.
- Street and park furniture including, seats, tables, marquees, covered and uncovered pergolas or similar shade sails, bollards, traffic control devices and platforms associated with outdoor dining in a road or other public land on adjoining land and is authorised under a local law or by the public land manager.

62.04 SUBDIVISIONS NOT REQUIRING A PERMIT

28/03/2018
VC145

Any requirement in this scheme relating to the subdivision of land does not apply to:

- A subdivision by an authority acquiring the land which does not create an additional lot.
- A subdivision by a public authority or utility service provider which does not create an additional lot other than for the sole purpose of a minor utility installation. This does not apply if a permit is required to subdivide land under any overlay.
- A subdivision by an authority acquiring the land which creates additional lots if the additional lots are severed parcels of land without legal access to an existing road and the additional lots are retained by the acquiring authority or sold to an abutting land owner on the condition that the lot be consolidated with abutting land.
- A subdivision which realigns the common boundary between two lots if all the land is in one urban zone and any of the following apply:
  - Any lot that is reduced in area meets the minimum lot area and minimum dimensions (if any) specified for the zone. This does not apply if the area of the smaller lot is limited by a provision of this scheme, or by a condition of a planning permit.
  - There is no minimum lot area specified for the zone, the area of the smaller lot is more than 230 square metres, and the area of either lot is reduced by less than 30 square metres.
  - There is no minimum lot area specified for the zone, the area of the smaller lot is 230 square metres or less, and the area of either lot is reduced by less than 5 percent or by less than 30 square metres, which ever is lesser.
  - The new boundary coincides with a boundary fence that is more than five years old. This does not apply if all the land is in one ownership.
- A subdivision which realigns the common boundary between two lots if all the land is in one non-urban zone, the re-subdivision does not allow the number of dwellings the whole of the land could be used for under this scheme to increase, and any of the following apply:
  - Any lot that is reduced in area meets the minimum lot area and minimum dimensions (if any) specified for the zone. This does not apply if the area of the smaller lot is limited by a provision of this scheme, or by a condition of a planning permit.
  - There is no minimum lot area specified for the zone, and no part of the boundary is moved more than 1 metre. This does not apply if the area of the smaller lot would be less than the area specified by a condition of a planning permit.
  - There is no minimum lot area specified for the zone, the new boundary coincides with the location of a fence that is more than 5 years old, and no part of the boundary is moved more than three metres.

62.05 DEMOLITION

17/02/2022
VC200

A permit is not required for the demolition or removal of a building or works unless a permit is specifically required for demolition or removal.

Any requirement in this planning scheme (other than a requirement in a Heritage Overlay) relating to the demolition or removal of a building or works does not apply to the demolition of removal of a building or works associated with a car park, railway, railway station or tramway carried out by or on behalf of the Head, Transport for Victoria.

62.06 DELIVERY OF ESSENTIAL GOODS PERMIT CONDITION EXEMPTION

28/10/2022
VC224

The purpose of this exemption is to enable additional flexibility for deliveries of essential goods if the time within which a delivery may be carried out is regulated by a permit condition.

In this exemption, ***delivery*** includes loading, dispatching and unloading.

This exemption applies to the delivery of food, drink, groceries, medicine, or cleaning, sanitising, health, hygiene, medical or personal protection equipment, supplies, or products, or the like.

Despite any condition of a permit that specifies a period of time within which a delivery may be carried out, a delivery may be carried out for up to 1 hour before the start of the specified period and 1 hour after the end of the specified period.

Example: *If a condition of a permit only allows deliveries between the hours of 7am and 10pm, the delivery may be carried out under this exemption after 6am and up until 11pm.*

63 EXISTING USES

28/03/2018
VC145

63.01 EXTENT OF EXISTING USE RIGHTS

28/03/2018
VC145

An existing use right is established in relation to use of land under this scheme if any of the following apply:

- The use was lawfully carried out immediately before the approval date.
- A permit for the use had been granted immediately before the approval date and the use commences before the permit expires.
- A permit for the use has been granted under Clause 63.08 and the use commences before the permit expires.
- Proof of continuous use for 15 years is established under Clause 63.11.
- The use is a lawful continuation by a utility service provider or other private body of a use previously carried on by a Minister, government department or public authority, even where the continuation of the use is no longer for a public purpose.

63.02 CHARACTERISATION OF USE

31/07/2018
VC148

If a use of land is being characterised to assess the extent of any existing use right, the use is to be characterised by the purpose of the actual use at the relevant date, subject to any conditions or restrictions applying to the use at that date, and not by the classification in the table to Clause 73.03 or in Section 1, 2 or 3 of any zone.

63.03 EFFECT OF DEFINITIONS ON EXISTING USE RIGHTS

28/03/2018
VC145

The definition of a term in this scheme, or the amendment of any definition, does not increase or restrict the extent of any existing use right established prior to the inclusion of the definition or amendment.

63.04 SECTION 1 USES

28/03/2018
VC145

A use in Section 1 of a zone for which an existing use right is established may continue provided any condition or restriction to which the use was subject and which applies to the use in Section 1 of the zone continues to be met.

63.05 SECTIONS 2 AND 3 USES

28/03/2018
VC145

A use in Section 2 or 3 of a zone for which an existing use right is established may continue provided:

- No building or works are constructed or carried out without a permit. A permit must not be granted unless the building or works complies with any other building or works requirement in this scheme.
- Any condition or restriction to which the use was subject continues to be met. This includes any implied restriction on the extent of the land subject to the existing use right or the extent of activities within the use.
- The amenity of the area is not damaged or further damaged by a change in the activities beyond the limited purpose of the use preserved by the existing use right.

63.06 EXPIRATION OF EXISTING USE RIGHTS

28/03/2018
VC145

An existing use right expires if either:

- The use has stopped for a continuous period of 2 years, or has stopped for two or more periods which together total 2 years in any period of 3 years.
- In the case of a use which is seasonal in nature, the use does not take place for 2 years in succession.

63.07 COMPLIANCE WITH CODES OF PRACTICE

28/03/2018
VC145

A use for which an existing use right is established must comply with any relevant code of practice incorporated in this scheme if either:

- The code of practice has been incorporated or adopted in accordance with Section 39 of the Conservation Forests and *Lands Act 1987*.
- The code of practice is approved or ratified by Parliament under an Act.

63.08 ALTERNATIVE USE

28/03/2018
VC145

If land is used for a use in Section 3 of a zone for which an existing use right is established, a permit may be granted to use the land for an alternative use which does not comply with this scheme. The responsible authority must be satisfied that the use of the land for the alternative use will be less detrimental to the amenity of the locality.

63.09 SHOP CONDITIONS

28/03/2018
VC145

A permit must not be granted to:

- Construct or carry out a building or works under Clause 63.05 for a shop with a leasable floor area exceeding 500 square metres.
- Use land under Clause 63.08 for a shop with a leasable floor area exceeding 500 square metres.

63.10 DAMAGED OR DESTROYED BUILDINGS OR WORKS

28/03/2018
VC145

If at least 50 percent of the gross floor area of a building or at least 50 percent of the area of any works is damaged or destroyed so that the use cannot continue without the building or works being reconstructed, the land must be used in conformity with this scheme, unless a permit is granted to continue the use, and to construct or carry out buildings or works.

63.11 PROOF OF CONTINUOUS USE

12/02/2024
VC254

If, in relation to an application or proceeding under the Act or this scheme, including an application for a certificate of compliance under Section 97N of the Act, the extent of any existing use right for a period in excess of 15 years is in question, it is sufficient proof of the establishment of the existing use right if the use has been carried out continuously for a period of 15 years at any time before the date of the application or proceeding.

An existing use right may be established under this clause even if the use did not comply with the scheme immediately before or during the 15 year period, unless any of the following apply:

- At any time before or after commencement of the 15 year period the use has been held to be unlawful by a decision of a court or tribunal.
- During the 15 year period, the responsible authority has clearly and unambiguously given a written direction for the use to cease by reason of its non-compliance with the scheme.
- The use ceased between the end of the 15 year period and the date of the application or proceeding.

63.12 DECISION GUIDELINES

28/03/2018
VC145

Before deciding on an application under Clause 63.05, 63.08 or 63.10, in addition to the decision guidelines in Clause 65 and any other requirements of the Act, the responsible authority must consider the extent to which compliance can be achieved with all scheme requirements that can reasonably be met.

64 GENERAL PROVISIONS FOR USE AND DEVELOPMENT OF LAND

28/03/2018
VC145

64.01 LAND USED FOR MORE THAN ONE USE

28/03/2018
VC145

If land is used for more than one use and one is not ancillary to the other, each use must comply with this scheme.

64.02 LAND USED IN CONJUNCTION WITH ANOTHER USE

28/03/2018
VC145

If a provision of this scheme provides that a use of land must be used 'in conjunction with' another use of the land:

- there must be an essential association between the two uses; and
- the use must have a genuine, close and continuing functional relationship in its operation with the other use.

64.03 SUBDIVISION OF LAND IN MORE THAN ONE ZONE

28/03/2018
VC145

If a provision of this scheme provides that a permit is required to subdivide land and the land is in more than one zone a permit may be granted even if one of the lots does not comply with the minimum lot size requirements of a zone.

Permit Requirement

A permit may be granted to create one lot smaller than specified in the scheme if all of the following are met:

- The lot to be subdivided is in more than one zone and cannot comply with the minimum lot area specified in the scheme.
- The proposed subdivision does not create lots where any lot extends into more than one zone. This does not apply to any lots created for the following purposes:
  - To comply with the requirements of the Urban Floodway Zone.
  - To provide access to a road.
- The remainder of the proposed lots must comply with the minimum lot area specified in the scheme.

65 DECISION GUIDELINES

28/03/2018
VC145

Because a permit can be granted does not imply that a permit should or will be granted. The responsible authority must decide whether the proposal will produce acceptable outcomes in terms of the decision guidelines of this clause.

65.01 APPROVAL OF AN APPLICATION OR PLAN

09/12/2021
VC204

Before deciding on an application or approval of a plan, the responsible authority must consider, as appropriate:

- The matters set out in section 60 of the Act.
- Any significant effects the environment, including the contamination of land, may have on the use or development.
- The Municipal Planning Strategy and the Planning Policy Framework.
- The purpose of the zone, overlay or other provision.
- Any matter required to be considered in the zone, overlay or other provision.
- The orderly planning of the area.
- The effect on the environment, human health and amenity of the area.
- The proximity of the land to any public land.
- Factors likely to cause or contribute to land degradation, salinity or reduce water quality.
- Whether the proposed development is designed to maintain or improve the quality of stormwater within and exiting the site.
- The extent and character of native vegetation and the likelihood of its destruction.
- Whether native vegetation is to be or can be protected, planted or allowed to regenerate.
- The degree of flood, erosion or fire hazard associated with the location of the land and the use, development or management of the land so as to minimise any such hazard.
- The adequacy of loading and unloading facilities and any associated amenity, traffic flow and road safety impacts.
- The impact the use or development will have on the current and future development and operation of the transport system.

This clause does not apply to a VicSmart application.

65.02 APPROVAL OF AN APPLICATION TO SUBDIVIDE LAND

15/03/2024
VC256

Before deciding on an application to subdivide land, the responsible authority must also consider, as appropriate:

- The suitability of the land for subdivision.
- The existing use and possible future development of the land and nearby land.
- The availability of subdivided land in the locality, and the need for the creation of further lots.
- The effect of development on the use or development of other land which has a common means of drainage.
- The subdivision pattern having regard to the physical characteristics of the land including existing vegetation.
- The density of the proposed development.
- The area and dimensions of each lot in the subdivision.
- The layout of roads having regard to their function and relationship to existing roads.
- The movement of pedestrians and vehicles throughout the subdivision and the ease of access to all lots.
- The provision and location of reserves for public open space and other community facilities.
- The staging of the subdivision.
- The design and siting of buildings having regard to safety and the risk of spread of fire.
- The provision of off-street parking.
- The provision and location of common property.
- The functions of any owners corporation.
- The availability and provision of utility services, including water, sewerage, drainage, electricity, and, where the subdivision is not a residential subdivision, gas.
- If the land is not sewered and no provision has been made for the land to be sewered, the capacity of the land to treat and retain all sewage and sullage within the boundaries of each lot.
- Whether, in relation to subdivision plans, native vegetation can be protected through subdivision and siting of open space areas.
- The impact the development will have on the current and future development and operation of the transport system.

This clause does not apply to a VicSmart application.

66
14/05/2021
VC198

REFERRAL AND NOTICE PROVISIONS

Scope

These provisions set out the kinds of applications which must be referred under section 55 of the Act or for which notice must be given under section 52(1)(c) of the Act. The provisions do not apply to the seeking of advice about an application or where a responsible authority may choose to give notice under another sub-section of section 52(1) of the Act.

These provisions also specify when a plan must be referred under section 8(1)(a) of the *Subdivision Act 1988*.

Referrals

Applications of the kind listed in Clauses 66.01, 66.02, 66.03 and 66.04 must be referred to the person or body specified as a referral authority in accordance with section 55 of the Act.

Any requirement for referral under this or another clause does not apply if:

- In the opinion of the responsible authority, the proposal satisfies requirements or conditions previously agreed in writing between the responsible authority and the referral authority, or the referral authority has considered the proposal for which the application is made within the past three months and has stated in writing that it does not object to the granting of the permit for the proposal; or
- The application is for the use or development of land for extractive industry or mining and a copy of a work plan or variation to an approved work plan accompanying the application was given to the referral authority (other than the Head, Transport for Victoria) under section 77TE of the *Mineral Resources (Sustainable Development) Act 1990.*

Notice

Notice of an application of the kind listed in Clauses 66.05 and 66.06 must be given in accordance with section 52(1)(c) of the Act to the person or body specified as a person or body to be notified.

Any requirement for notice under this or another clause does not apply if, in the opinion of the responsible authority, the proposal satisfies requirements or conditions previously agreed in writing between the responsible authority and the person or body to be notified.

66.01 SUBDIVISION REFERRALS

04/08/2022
VC221

An application of the kind listed in the table below must be referred to the person or body specified as the referral authority. The table below specifies whether the referral authority is a determining referral authority or a recommending referral authority.

Kind of application	Referral authority	Type of referral authority
To subdivide land other than: ▪ A boundary realignment. ▪ The subdivision of an existing building already connected to services. ▪ A two lot subdivision. ▪ The subdivision of land into lots each containing an existing dwelling or car parking space.	The relevant water, drainage or sewerage authority The relevant electricity supply or distribution authority The relevant gas supply authority only where the subdivision is proposed to connect a lot to a reticulated gas supply system.	Determining referral authority Determining referral authority Determining referral authority
To subdivide land outside the metropolitan fire district which creates a road, where the requirements of Clause 56.09-3 are not met.	Country Fire Authority	Determining referral authority
To subdivide land if the only access to a lot is over Crown land which has not been reserved or proclaimed as a road.	Minister administering the *Land Act 1958*	Determining referral authority
To subdivide land crossed by a gas transmission pipeline or a gas transmission pipeline easement.	The relevant gas supply authority	Determining referral authority
To subdivide land within 60 metres of a major electricity transmission line (220 Kilovolts or more) or an electricity transmission easement.	The relevant electricity transmission authority	Determining referral authority
To subdivide a heritage place of which all or part is included in the Victorian Heritage Register.	The Executive Director specified in the *Heritage Act 2017*	Determining referral authority

Note: A subdivision which does not require referral under Clause 66.01 must be referred if it is listed as a requirement under any other provision of Clause 66.

66.01-1 Mandatory conditions for subdivision permits

04/08/2022
VC221

A permit for subdivision must contain the following conditions:

The owner of the land must enter into an agreement with:

- a telecommunications network or service provider for the provision of telecommunication services to each lot shown on the endorsed plan in accordance with the provider's requirements and relevant legislation at the time; and
- a suitably qualified person for the provision of fibre ready telecommunication facilities to each lot shown on the endorsed plan in accordance with any industry specifications or any standards set by the Australian Communications and Media Authority, unless the applicant can demonstrate that the land is in an area where the National Broadband Network will not be provided by optical fibre.

Before the issue of a Statement of Compliance for any stage of the subdivision under the *Subdivision Act 1988*, the owner of the land must provide written confirmation from:

- a telecommunications network or service provider that all lots are connected to or are ready for connection to telecommunications services in accordance with the provider's requirements and relevant legislation at the time; and
- a suitably qualified person that fibre ready telecommunication facilities have been provided in accordance with any industry specifications or any standards set by the Australian Communications and Media Authority, unless the applicant can demonstrate that the land is in an area where the National Broadband Network will not be provided by optical fibre.

This requirement does not apply to a permit granted to:

- Subdivide land in a rural zone, public land zone, Urban Floodway Zone or Special Use Zone if the responsible authority is satisfied that connection to telecommunication services is not warranted.
- Realign the common boundary between two lots (boundary realignment).
- Subdivide an existing building already connected to telecommunication services.

A permit granted to subdivide land in a manner that does not require referral under Clause 66.01 must contain the following conditions:

- The owner of the land must enter into agreements with the relevant authorities for the provision of water supply, drainage, sewerage facilities, electricity and gas (where it is proposed to be connected) services to each lot shown on the endorsed plan in accordance with the authority's requirements and relevant legislation at the time.
- All existing and proposed easements and sites for existing or required utility services and roads on the land must be set aside in the plan of subdivision submitted for certification in favour of the relevant authority for which the easement or site is to be created.
- The plan of subdivision submitted for certification under the *Subdivision Act 1988* must be referred to the relevant authority in accordance with Section 8 of that Act.

This requirement does not apply to a permit granted to subdivide land into lots each containing an existing dwelling or car parking space.

66.01-2 Referrals under the Subdivision Act – certification of plans

15/09/2008
VC49

For the purpose of Section 8(1)(a) of the *Subdivision Act 1988* referral of a plan is required if:

- A referral is required by a permit issued under this scheme. The plan must be referred to the relevant referral authority.
- A plan creates, varies or removes an easement or restriction likely to be of interest to a referral authority. The plan must be referred to the relevant referral authority.
- The only access to a lot on a plan is over Crown land and the Minister administering the *Land Act 1958* has not consented or provision has not been made for a road to be reserved or proclaimed. The plan must be referred to that Minister.
- In the opinion of the Council the plan may affect existing sewerage, water, drainage or other works. The plan must be referred to the referral authority responsible for those works.

66.02 USE AND DEVELOPMENT REFERRALS

31/07/2018
VC148

An application of the kind listed in the tables below must be referred to the person or body specified as the referral authority. The tables below specify whether the referral authority is a determining referral authority or a recommending referral authority.

66.02-1 Environment Protection Authority Licence

04/05/2022
VC210

Kind of application	Referral authority	Type of referral authority
For a use or development requiring any of the following: ▪ A Development Licence or Operating Licence in accordance with Part 4.4 of the *Environment Protection Act 2017*. ▪ Amendment of a licence in accordance with Part 4.3 of the *Environment Protection Act 2017*.	Environment Protection Authority	Determining referral authority

66.02-2 Native vegetation

12/12/2017
VC138

Kind of application	Referral authority	Type of referral authority
▪ To remove, destroy or lop native vegetation in the Detailed Assessment Pathway as defined in the *Guidelines for the removal, destruction or lopping of native vegetation* (Department of Environment, Land, Water and Planning, 2017). ▪ To remove, destroy or lop native vegetation if a property vegetation plan applies to the site. ▪ To remove, destroy or lop native vegetation on Crown land which is occupied or managed by the responsible authority.	Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*)	Recommending referral authority

66.02-3 Cattle feedlot

25/05/2017
VC133

Kind of application	Referral authority	Type of referral authority
To use or develop land for a cattle feedlot.	Minister for Agriculture	Determining referral authority
	If the site is located within a special water supply catchment area under the *Catchment and Land Protection Act 1994*, the relevant water authority under the *Water Act 1989* and the Secretary to the Department administering the *Catchment and Land Protection Act 1994*	Determining referral authority
	If the number of cattle is 5000 or more, the Environment Protection Authority	Determining referral authority

66.02-4 Major electricity line or easement

25/05/2017
VC133

Kind of application	Referral authority	Type of referral authority
To construct a building or construct or carry out works on land within 60 metres of a major electricity transmission line (220 Kilovolts or more) or an electricity transmission easement.	The relevant electricity transmission authority	Determining referral authority

66.02-5 Special water supply catchment area

22/11/2024
VC263

Kind of application	Referral authority	Type of referral authority
To use, subdivide or consolidate land, to construct a building or construct or carry out works, or to demolish a building or works that are within a declared Special Area classified as a Special Water Supply Catchment Area under the *Catchment and Land Protection Act 1994* and which provides water to a domestic supply. This does not apply to an application for a sign, fence, roadworks or unenclosed building or works ancillary to a dwelling.	The relevant water board or water supply authority	Determining referral authority

66.02-6 Timber production

25/05/2017
VC133

Kind of application	Referral authority	Type of referral authority
▪ To use or develop land for timber production by establishing a plantation. ▪ To use or develop land for timber production by harvesting timber from native forest, including thinning, if the area of native forest to be subjected to timber production operations is 10 hectares or greater.	Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*)	Determining referral authority

66.02-7 Industry, utility installation or warehouse

14/01/2025
VC237

Kind of application	Referral authority	Type of referral authority
▪ To use land for an industry, utility installation or warehouse for a purpose listed in the table to Clause 53.10 with no threshold distance specified or if the threshold distance is not to be met.	Environment Protection Authority	Determining referral authority
▪ To use land for an industry, utility installation or warehouse if any of the following apply: – A fire protection quantity is exceeded under the Dangerous Goods (Storage and Handling) Regulations 2022.	The Victorian WorkCover Authority	Determining referral authority

Kind of application	Referral authority	Type of referral authority
– A notification is required under the Occupational Health and Safety Regulations 2017. – A licence is required under the Dangerous Goods (Explosives) Regulations 2011. – A licence is required under Dangerous Goods (HCDG) Regulations 2016 and the use is not associated with agriculture.		
▪ To construct a building or construct or carry out works on land used for an industry, utility installation or warehouse if the area of the buildings and works will increase by more than 25 per cent and any of the following apply: – A fire protection quantity is exceeded under the Dangerous Goods (Storage and Handling) Regulations 2022. – A notification is required under the Occupational Health and Safety Regulations 2017. – A licence is required under the Dangerous Goods (Explosives) Regulations 2011. – A licence is required under the Dangerous Goods (HCDG) Regulations 2016 and the use is not associated with agriculture.	The Victorian WorkCover Authority	Determining referral authority

66.02-8 Extractive industry

22/03/2022
VC219

Kind of application	Referral authority	Type of referral authority
▪ To use or develop land for extractive industry.	Secretary to the Department administering the *Heritage Act 2017*. Secretary to the Department administering the *Mineral Resources (Sustainable Development) Act 1990*	Determining referral authority
▪ To use or develop land for accommodation in a rural zone if the building or works associated with the accommodation is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.	Secretary to the Department administering the *Mineral Resources (Sustainable Development) Act 1990*	Recommending referral authority
▪ To use or develop land for extractive industry on Crown land or land abutting Crown land, other than a government road.	Secretary to the Department administering the *Land Act 1958*, *Crown Land (Reserves) Act 1978*, *National Parks Act 1975* and *Forests Act 1958*	Determining referral authority

Kind of application	Referral authority	Type of referral authority
▪ To use or develop land for extractive industry: – In Special Areas declared under Section 27 of the *Catchment and Land Protection Act 1994*. – On land where the use or development involves the removal or destruction of native vegetation if the total area to be cleared is 10 hectares or greater. – On land which has been identified in this scheme as being subject to high erosion risk or areas identified as being subject to salinity management.	Secretary to the Department administering the *Catchment and Land Protection Act 1994*	Determining referral authority
▪ To use or develop land for extractive industry: – In areas with communities or taxa listed or critical habitat determined under the *Flora and Fauna Guarantee Act 1988*. – On land which has been identified in this scheme as containing sites of flora or fauna significance.	Secretary to the Department administering the *Flora and Fauna Guarantee Act 1988*	Determining referral authority
▪ To use or develop land for extractive industry on land which has been identified in this scheme as flood prone.	Secretary to the Department administering Section 201 of the *Water Act 1989*	Determining referral authority
▪ To use or develop land for extractive industry if the land is intended to be used for land fill at a future date.	Environment Protection Authority	Determining referral authority
▪ To use or develop land for extractive industry: – On land which abuts a local road which intersects with a road declared as a freeway or an arterial road under the *Road Management Act 2004* and if the development is expected to increase traffic movement at the intersection of the local road and the declared road by ten percent or more. – On land which abuts a road declared as a freeway or an arterial road under the *Road Management Act 2004*. This does not apply to a development which generates less than one hundred commercial trips per day, with roadworks at the entrance to the site built in accordance with the requirements of the Head, Transport for Victoria and the declared road is not a freeway.	Head, Transport for Victoria	Determining referral authority

66.02-9 Geothermal energy extraction

25/05/2017
VC133

Kind of application	Referral authority	Type of referral authority
To use or develop land for geothermal energy extraction.	Secretary to the Department administering the *Geothermal Energy Resources Act 2005*	Determining referral authority

66.02-10 Greenhouse gas sequestration

25/05/2017
VC133

Kind of application	Referral authority	Type of referral authority
To use or develop land for greenhouse gas sequestration.	Secretary to the Department administering the *Greenhouse Gas Geological Sequestration Act 2008*	Determining referral authority

66.02-11 Land use and transport integration

09/12/2021
VC204

Kind of application	Referral authority	Type of referral authority
An application to subdivide land, to construct a building or to construct or carry out works for any of the following: ▪ A residential development comprising 60 or more dwellings or lots. ▪ A residential building comprising 60 or more lodging rooms. ▪ A residential village comprising 60 or more dwellings. ▪ A retirement village comprising 60 or more dwellings or lots. ▪ A new retail premises of 4000 or more square metres of leasable floor area. ▪ An increase of more than 1000 square metres to the leasable floor area of an existing retail premises which is 4000 or more square metres leasable floor area. ▪ An office development of 10,000 or more square metres of leasable floor area. ▪ A place of assembly comprising 400 or more seats or 600 or more square metres of gross floor area. ▪ An education centre. ▪ A major sports and recreation facility. ▪ Any alteration or development of public transport infrastructure or stops, unless undertaken for the Head, Transport for Victoria. This does not apply to: ▪ Buildings and works associated with an existing place of assembly, education centre, major sports and recreation facility or retirement village. ▪ A development consistent with an adopted Structure Plan that has been prepared in consultation with and endorsed by the Head, Transport for Victoria.	Head, Transport for Victoria	Determining referral authority

66.02-12 Declared irrigation districts

17/09/2019
VC161

Kind of application	Referral authority	Type of referral authority
An application to use or develop land for a renewable energy facility located within an irrigation district declared under Part 6A of the *Water Act 1989.*	Secretary to the Department administering the *Water Act 1989.*	Recommending referral authority

66.02-13 State transport projects

17/02/2022
VC200

Kind of application	Referral authority	Type of referral authority
An application to which clause 53.21 applies.	The municipal council for the municipal district within which the proposed use or development will be carried out.	Recommending referral authority.

66.02-14 Freeway service centre

20/03/2023
VC229

Kind of application	Referral authority	Type of referral authority
To use or develop land for a Freeway service centre.	Head, Transport for Victoria	Determining referral authority

66.03
01/07/2025
VC286

REFERRAL OF PERMIT APPLICATIONS UNDER OTHER STATE STANDARD PROVISIONS

An application of the kind listed in the table below, where the planning scheme includes the specified clause, must be referred to the person or body specified as the referral authority. The table below specifies whether the referral authority is a determining referral authority or a recommending referral authority.

Clause	Kind of application	Referral authority	Type of referral authority
Clause 36.03-5 (PCRZ)	An application for the use or development of an Emergency services facility.	Secretary to the Department of Energy, Environment and Climate Action	Determining referral authority
Clause 37.03-5 (UFZ)	An application under the zone within the waterway management district of Melbourne Water Corporation.	Melbourne Water Corporation	Determining referral authority
	An application under the zone outside the waterway management district of Melbourne Water Corporation.	Relevant floodplain management authority	Recommending referral authority
Clause 37.07-5 (UGZ)	An application under the zone within Metropolitan Melbourne.	Victorian Planning Authority	Determining referral authority
	An application under the zone outside Metropolitan Melbourne.	Secretary to the Department administering the *Planning and Environment Act 1987*	Determining referral authority
Clause 44.02-8 (SMO)	An application under the overlay and any site capability report.	Secretary to the Department of Energy, Environment and Climate Action	Determining referral authority
Clause 44.03-6 (FO)	An application under the overlay within the waterway management district of Melbourne Water Corporation.	Melbourne Water Corporation	Determining referral authority
	An application under the overlay outside the waterway management district of Melbourne Water Corporation.	Relevant floodplain management authority	Recommending referral authority
Clause 44.04-7 (LSIO)	An application under the overlay within the waterway management district of Melbourne Water Corporation.	Melbourne Water Corporation	Determining referral authority
	An application under the overlay outside the waterway management district of Melbourne Water Corporation.	Relevant floodplain management authority	Recommending referral authority
Clause 44.05-6 (SBO)	An application under the overlay within the waterway management district of Melbourne Water Corporation.	Melbourne Water Corporation	Determining referral authority

Clause	Kind of application	Referral authority	Type of referral authority
	An application under the overlay outside the waterway management district of Melbourne Water Corporation.	Relevant floodplain management authority	Recommending referral authority
Clause 44.06-6 (BMO)	An application to construct a building or carry out works associated with a dwelling. This does not apply to a non habitable outbuilding that meets the following requirements: ▪ The outbuilding is ancillary to a dwelling, ▪ 10 metres of defendable space is provided around the outbuilding in accordance with the vegetation management requirements at Table 6 of Clause 53.02, ▪ The canopy of each tree within the defendable space is separated by at least 2 metres, and ▪ Where the outbuilding is located less than 10 metres from a dwelling the outbuilding construction requirements at Table 7 of Clause 53.02 are met.	Relevant fire authority	Recommending referral authority
	An application to subdivide land.	Relevant fire authority	Recommending referral authority
	An application under the overlay other than an application to construct a building or carry out works associated with a dwelling or an application to subdivide land.	Relevant fire authority	Determining referral authority
Clause 44.07-6 (SRO)	An application of the kind specified in a schedule to the overlay.	Referral authority specified in a schedule to the overlay	Determining referral authority
Clause 45.01-3 (PAO)	An application under the overlay.	Acquiring authority specified in the schedule to the overlay	Determining referral authority
Clause 45.07-6 (CLPO)	An application under the overlay.	Head, Transport for Victoria	Determining referral authority
Clause 52.05-3	An application to display an animated or electronic sign within 60 metres of a freeway or arterial road declared under the *Road Management Act 2004.*	Head, Transport for Victoria	Determining referral authority
Clause 52.29-4	An application to create or alter access to, or to subdivide land adjacent to, a road declared as a freeway or an arterial road	Head, Transport for Victoria	Determining referral authority

Clause	Kind of application	Referral authority	Type of referral authority
	under the *Road Management Act 2004*, land owned by the Head, Transport for Victoria for the purpose of a road, or land in a Public Acquisition Overlay if the Head, Transport for Victoria is the acquiring authority and the acquisition is for the purpose of a road.		
	Any other application under the Clause.	Owner of, or the acquiring authority for, the adjacent land in the Transport Zone 2 or the Public Acquisition Overlay	Determining referral authority
Clause 52.32	An application to amend a permit under section 72 or 97I of the *Planning and Environment Act 1987* for a wind energy facility if the application amends or removes conditions or requirements for operational wind turbine noise.	Environment Protection Authority Victoria	Recommending referral authority
Clause 53.24	An application to which Clause 53.24 applies.	Secretary to the Department of Transport and Planning	Determining referral authority

66.04 REFERRAL OF PERMIT APPLICATIONS UNDER LOCAL PROVISIONS

28/03/2018
VC145

In addition to the referral requirements of Clause 66.01, 66.02 and 66.03, an application of the kind listed in the schedule to this clause must be referred to the referral authority specified in the schedule. The table below specifies whether the referral authority is a determining referral authority or a recommending referral authority.

If a local provision of the scheme specifies a person or body as a referral authority for a kind of application or contains a referral requirement, and that specification or requirement is not included in the schedule to this clause, it is not a referral requirement under section 55 of the Act.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 66.04 REFERRAL OF PERMIT APPLICATIONS UNDER LOCAL PROVISIONS

1.0 Referral of permit applications under local provisions

08/07/2021
C211brim

Clause	Kind of application	Referral authority	Referral authority type
None specified			

66.05 NOTICE OF PERMIT APPLICATIONS UNDER STATE STANDARD PROVISIONS

01/07/2025
VC286

Notice of an application of the kind listed in the table below must be given to the person or body specified as a person or body to be notified.

Clause	Kind of application	Person or body to be notified
Clause 35.07	An application to use or develop land for accommodation within one kilometre from the nearest title boundary of land subject to: ▪ A permit for a wind energy facility; or ▪ An application for a permit for a wind energy facility; or ▪ An incorporated document approving a wind energy facility; or ▪ A proposed wind energy facility for which an action has been taken under section 8(1), 8(2), 8(3) or 8(4) of the *Environment Effects Act 1978*.	The owners and occupiers of land subject to: ▪ A permit for a wind energy facility; or ▪ An application for a permit for a wind energy facility; or ▪ An incorporated document approving a wind energy facility; or ▪ A proposed wind energy facility for which an action has been taken under section 8(1), 8(2), 8(3) or 8(4) of the *Environment Effects Act 1978*.
Clause 45.08-6	An application to use or subdivide land, or to construct a building or construct or carry out works.	The airport lessee company of Melbourne Airport in accordance with the Commonwealth *Airports Act 1996*
Clause 52.09-7	An application to use or subdivide land or construct a building for accommodation, education centre or hospital: ▪ Within an Extractive Industry Interest Area. ▪ On land which is within 500 metres of land on which a work plan has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*. An application to construct a building or construct or carry out works on land for which a work plan has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*. These requirements do not apply to: ▪ An application to extend a building or works. ▪ An application that is required to be referred to the Secretary of the Department administering the *Mineral Resources (Sustainable Development) Act 1990* under section 55 of the Act.	The Secretary of the Department administering the *Mineral Resources (Sustainable Development) Act 1990*
Clause 52.09-7	An application to use or develop land for accommodation in a rural zone if the building or works associated with the accommodation is located within 500 metres from the nearest title boundary of land on which a work authority has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.	The owners and occupiers of land subject to a work authority that has been applied for or granted under the *Mineral Resources (Sustainable Development) Act 1990*.

Clause	Kind of application	Person or body to be notified
Clause 52.21	An application to construct, use or illuminate a private tennis court under any provision of this scheme.	The owners and occupiers of adjoining and opposite properties
Clause 53.09	An application to use or develop land to establish a new broiler farm, or to increase the farm capacity of an existing broiler farm, that meets the requirements of a Special Class Broiler Farm or Farm Cluster as specified in the Victorian Code for Broiler Farms 2009.	Environment Protection Authority
Clause 67.02-2	An application which except for the provisions of clause 67.01, would be made to the Minister in accordance with section 96 of the Act. This does not apply to an application: ▪ To which the exemption from notice and review in clause 52.31-2 applies. ▪ To construct or put up for display a sign. ▪ To remove, destroy or lop native vegetation under clause 52.17. ▪ If a permit is only required under the Bushfire Management Overlay, Floodway Overlay, Land Subject to Inundation Overlay, Salinity Management Overlay or Special Building Overlay.	The owners and occupiers of adjoining land The National Trust of Australia (Victoria), if the application relates to land on which there is a building classified by the Trust
Clause 67.02-2	An application to remove, destroy or lop native vegetation under clause 52.17 which, except for the provisions of clause 67.01, would be made to the Minister in accordance with section 96 of the Act. This does not apply if the application must be referred to the Secretary under section 55 of the Act.	Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*)

66.06 NOTICE OF PERMIT APPLICATIONS UNDER LOCAL PROVISIONS

28/03/2018
VC145

In addition to the notice requirements of Clause 66.05, notice of an application of the kind specified in the schedule to this clause must be given to the person or body specified in the schedule. If a local provision of the scheme specifies a notice requirement and that requirement is not included in the schedule to this clause, it is not a notice requirement under Section 52(1)(c) of the Act.

08/07/2021
C211brim

SCHEDULE TO CLAUSE 66.06 NOTICE OF PERMIT APPLICATIONS UNDER LOCAL PROVISIONS

1.0 Notice of permit applications under local provisions

08/07/2021
C211brim

Clause	Kind of application	Person or body to be notified
37.02 Schedule 2 – Clause 7.0	To use land or construct a building or to construct or carry out works.	Secretary to the Department of Environment, Land, Water and Planning
37.02 Schedule 2 – Clause 7.0	To use land or construct a building or to construct or carry out works.	Melbourne Water
37.02 Schedule 2 – Clause 7.0	To use land or construct a building or to construct or carry out works.	VicRoads
43.04 Schedule 16 – Clause 3.0	To use land or construct a building or to construct or carry out works.	Environment Protection Authority
43.04 Schedule 16 – Clause 3.0	To use land or construct a building or to construct or carry out works.	WorkSafe Victoria

67 LAND OWNED OR PERMIT REQUIRED BY RESPONSIBLE AUTHORITIES

14/09/2021
VC211

67.01 EXEMPTIONS FROM SECTION 96(1) AND 96(2) OF THE ACT

24/01/2020
VC160

In accordance with section 6(2)(ka) of the Act, the following classes of use and development are exempted from section 96(1) and 96(2) of the Act:

Class 1

Use of land for:

Car park, camping and caravan park, community facility (including child care centre, maternal and infant welfare centre, neighbourhood house, place of assembly and toilet block), dwelling, extractive industry, hospital, industry, leisure and recreation, office, residential village, retail premises or service station.

Class 2

Development of land for:

A Class 1 use, demolition of a building or works, lighting and floodlighting of a recreation facility or building, sign or advertisement or subdivision.

Class 3

Any other use or development.

67.02 NOTICE REQUIREMENTS AND EXEMPTION

14/09/2021
VC211

67.02-1 Application

14/09/2021
VC211

This clause applies to an application which, except for the provisions of clause 67.01, would be made to the Minister in accordance with section 96 of the Act.

67.02-2 Notice requirements

14/09/2021
VC211

In accordance with section 52(1)(c) of the Act, notice of an application must be given to:

- The owners and occupiers of adjoining land.
- The National Trust of Australia (Victoria), if the application relates to land on which there is a building classified by the Trust.

This does not apply to an application:

- To which the exemption from notice and review in clause 52.31-2 applies.
- To construct or put up for display a sign.
- To remove, destroy or lop native vegetation under clause 52.17.
- If a permit is only required under the Bushfire Management Overlay, Floodway Overlay, Land Subject to Inundation Overlay, Salinity Management Overlay or Special Building Overlay.

In accordance with section 52(1)(c) of the Act, notice of an application to remove, destroy or lop native vegetation under clause 52.17 must be given to the Secretary to the Department of Environment, Land, Water and Planning (as constituted under Part 2 of the *Conservation, Forests and Lands Act 1987*).

This does not apply if the application must be referred to the Secretary under section 55 of the Act.

67.02-3 Exemption from notice

14/09/2021
VC211

An application to construct or put up for display a sign on land managed, occupied or owned by the responsible authority is exempt from the notice requirement of section 52(1)(a) of the Act.

70 OPERATIONAL PROVISIONS

31/07/2018
VC148

This section sets out provisions about the operation, administration and enforcement of this planning scheme, the meaning of terms used in this planning scheme, and other matters.

71 OPERATION OF THIS PLANNING SCHEME

31/07/2018
VC148

71.01 OPERATION OF THE MUNICIPAL PLANNING STRATEGY

31/07/2018
VC148

71.01-1 Municipal Planning Strategy

24/01/2020
VC160

The Municipal Planning Strategy at Clause 02 provides an overview of important local planning issues in an introductory context, sets out the vision for future use and development in the municipality and establishes strategic directions about how the municipality is expected to change through the implementation of planning policy and the planning scheme.

A planning authority must take into account the Municipal Planning Strategy when it prepares an amendment to this planning scheme.

A responsible authority must take into account and give effect to the Municipal Planning Strategy when it makes a decision under this planning scheme.

71.01-2 Transitional

03/02/2022
VC199

If this planning scheme includes a Municipal Strategic Statement at Clause 21, the provisions of Clauses 23.01 and 23.02 apply.

71.02 OPERATION OF THE PLANNING POLICY FRAMEWORK

31/07/2018
VC148

71.02-1 Purpose of the Planning Policy Framework

31/07/2018
VC148

The Planning Policy Framework provides a context for spatial planning and decision making by planning and responsible authorities. The Planning Policy Framework is dynamic and will be built upon as planning policy is developed and refined, and changed as the needs of the community change.

The Planning Policy Framework seeks to ensure that the objectives of planning in Victoria (as set out in section 4 of the Act) are fostered through appropriate land use and development planning policies and practices that integrate relevant environmental, social and economic factors in the interests of net community benefit and sustainable development.

71.02-2 Operation

24/01/2020
VC160

The Planning Policy Framework sets out the planning policies that form part of this planning scheme. It comprises Clauses 10 to 19.

A planning policy applies to all land subject to this planning scheme unless the policy specifies otherwise.

A planning policy provides guidance for decision making and can help the community to understand how the responsible authority will consider a proposal.

The consistent application of planning policy over time should achieve a desired outcome.

A planning authority must take into account the Planning Policy Framework when it prepares an amendment to this planning scheme.

A responsible authority must take into account and give effect to the Planning Policy Framework when it makes a decision under this planning scheme. This does not apply to policy guidelines and policy documents.

Policy guidelines

A planning policy may include policy guidelines. Policy guidelines indicate how objectives can be met and how strategies can be implemented.

A responsible authority must take a relevant policy guideline into account when it makes a decision under this planning scheme, but is not required to give effect to it. If the responsible authority is satisfied that an alternative approach meets the objective, the alternative may be considered.

Policy documents

A planning policy may include reference to a policy document. A policy document may be an incorporated, background and other document.

A background document listed in the table or the schedule to Clause 72.08 that applies to Clauses 10 to 19 is a policy document for applicable planning policies.

71.02-3 Integrated decision making

03/02/2022
VC199

Victorians have various needs and expectations such as land for settlement, protection of the environment, economic wellbeing, various social needs, proper management of resources and infrastructure. Planning aims to meet these needs and expectations by addressing aspects of economic, environmental and social wellbeing affected by land use and development.

The Planning Policy Framework operates together with the remainder of the scheme to deliver integrated decision making. Planning and responsible authorities should endeavour to integrate the range of planning policies relevant to the issues to be determined and balance conflicting

objectives in favour of net community benefit and sustainable development for the benefit of present and future generations. However, in bushfire affected areas, planning and responsible authorities must prioritise the protection of human life over all other policy considerations.

Planning authorities should identify the potential for regional impacts in their decision making and coordinate strategic planning with their neighbours and other public bodies to achieve sustainable development and effective and efficient use of resources.

71.02-4 Transitional

31/07/2018
VC148

If this planning scheme includes a Municipal Strategic Statement at Clause 21 and local planning policies at Clause 22, the provisions of Clauses 23.01, 23.02 and 23.03 apply. To the extent of any inconsistency, Clauses 23.02 and 23.03 prevail over this clause.

71.03 OPERATION OF ZONES

31/07/2018
VC148

In each zone and schedule to a zone which contains a table of uses, the controls over the use of land are divided into three sections.

71.03-1 Section 1 uses

31/07/2018
VC148

A use in Section 1 does not require a permit. Any condition opposite the use must be met. If the condition is not met, the use is in Section 2 and requires a permit unless the use is specifically included in Section 3 as a use that does not meet the Section 1 condition.

71.03-2 Section 2 uses

31/07/2018
VC148

A use in Section 2 requires a permit. Any condition opposite the use must be met. If the condition is not met, the use is prohibited.

Making decisions about Section 2 uses

Because a use is in Section 2 does not imply that a permit should or will be granted. The responsible authority must decide whether the proposal will produce acceptable outcomes in terms of the Municipal Planning Strategy, the Planning Policy Framework, the purpose and decision guidelines of the zone and any of the other decision guidelines in Clause 65.

71.03-3 Section 3 uses

31/07/2018
VC148

A use in Section 3 is prohibited.

71.04 OPERATION OF OVERLAYS

31/07/2018
VC148

If an overlay is shown on the planning scheme map, the provisions of the overlay apply in addition to the provisions of the zone and any other provision of this scheme.

Because a permit can be granted does not imply that a permit should or will be granted. The responsible authority must decide whether the proposal will produce acceptable outcomes in terms of the Municipal Planning Strategy, the Planning Policy Framework, the purpose and decision guidelines of the overlay and any of the other decision guidelines in Clause 65.

71.05 OPERATION OF PARTICULAR PROVISIONS

31/07/2018
VC148

The requirements of particular provisions apply to the specified categories of use and development and other matters in addition to any provisions which apply due to any other provision of this planning scheme.

71.06 OPERATION OF VICSMART APPLICATIONS AND PROCESS

31/07/2018
VC148

71.06-1 VicSmart applications

08/09/2025
VC282

Any provision of this planning scheme may specify:

- Classes of application that are VicSmart applications to which Clause 71.06 applies.
- Information and other requirements for each class of VicSmart application.
- Decision guidelines for each class of VicSmart application.

An application is a VicSmart application if all of the following requirements are met:

- The application is in a class or classes specified in a provision of this planning scheme.
- A permit is required only under the provisions of this planning scheme that are specified as a VicSmart application, and not under any other provision of this planning scheme.
- Nothing authorised by the grant of a permit would result in a breach of a registered restrictive covenant.
- If the application requires referral to a referral authority under Clause 66, the referral requirements in Clause 71.06-2 are met.

71.06-2 VicSmart process

08/09/2025
VC282

Despite any other provision of this planning scheme:

- A VicSmart application is exempt from the requirements of the Act and planning scheme specified in this clause.
- The responsible authority must assess a VicSmart application in accordance with the requirements of this clause.

If there is any inconsistency between the requirements of this clause and another provision of this planning scheme, this clause prevails.

Referral requirements

If an application requires referral to a referral authority under Clause 66:

- The application must have been considered by the referral authority within the past 3 months of the application being made to the responsible authority.
- The referral authority must have stated in writing that it does not object to the granting of the permit for the proposal.

Information requirements

A VicSmart application must be accompanied by the information requirements specified for the relevant class of application. The information requirements of the relevant zone, overlay or particular provision, other than those specified for VicSmart applications, do not apply unless the information requirements for the relevant class of application specify otherwise.

If in the opinion of the responsible authority an information requirement is not relevant to the evaluation of a VicSmart application, the responsible authority may waive or reduce the information requirement.

Exemption from notice and review

A VicSmart application is exempt from:

- The notice requirements of section 52(1)(a), (b), (c) and (d) of the Act.
- The decision requirements of section 64(1), (2) and (3) of the Act.
- The review rights of section 82(1) of the Act.

Matters to be considered

In deciding a VicSmart application, the responsible authority:

- Must only consider the decision guidelines and requirements specified for the relevant class of application.
- Is exempt from considering the following matters:
  - The requirements of section 60(1)(b), (c), (e) and (f) and (1A) (b) to (h) and (j) of the Act.
  - The Municipal Planning Strategy and Planning Policy Framework unless the decision guidelines for the relevant class of application specify otherwise.
  - The decision guidelines of the relevant zone, overlay or particular provision, other than those specified for VicSmart applications, unless the decision guidelines for the relevant class of application specify otherwise.
  - The decision guidelines in Clause 65.
- In deciding an application for review in relation to a VicSmart application, the Tribunal is exempt from the matters specified in section 84B(2)(b) to (g) and (i) to (ja) of the Act.

Decision guidelines

Before deciding a VicSmart application, the responsible authority must consider the decision guidelines specified for the relevant class of application unless in the opinion of the responsible authority a decision guideline is not relevant to the evaluation of the application.

Before deciding a VicSmart application to which clause 54 applies, the responsible authority must, if a standard in clause 54 is not met, consider the decision guidelines for the corresponding objective.

72 ADMINISTRATION AND ENFORCEMENT OF THIS PLANNING SCHEME

31/07/2018
VC148

72.01 RESPONSIBLE AUTHORITY FOR THIS PLANNING SCHEME

17/09/2019
VC161

The responsible authority for the administration and enforcement of this planning scheme or a provision of this planning scheme is specified in this clause and the schedule to this clause.

The person nominated under section 198(1)(a) of the Act or the responsible authority under section 198(1)(b) of the Act, to whom a person may apply for a planning certificate, is specified in the schedule to this clause.

72.01-1 Minister is responsible authority

04/07/2025
VC258

The Minister for Planning is the responsible authority for matters under Divisions 1, 1A, 2 and 3 of Part 4 of the Act, and endorsement of, approval of or being satisfied with matters required by a permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority, in relation to the use and development of land for a:

- Energy generation facility with an installed capacity of 1 megawatt or greater.
- Utility installation used to:
  - Transmit or distribute electricity.
  - Store electricity if the installed capacity is 1 megawatt or greater.
- Industry to manufacture hydrogen gas with a minimum production capacity of 410 kilograms of hydrogen per day, and any land use or development in conjunction with this use.
- Primary school or secondary school, or education centre that is ancillary to, carried out in conjunction with, and on the same land or contiguous land in the same ownership as, a primary school or secondary school, if any of the following apply:
  - There is no existing primary school or secondary school on the land.
  - The estimated cost of development is $3 million or greater.
- Primary school or secondary school for which an application was made to the Minister for Planning prior to the approval date of Amendment VC180.
- A use or development, other than the subdivision of land, carried out by or on behalf of the Head, Transport for Victoria or the Secretary to the Department of Transport and Planning.
- Use and development to which clause 52.20 applies.
- Development of 10 or more dwellings to which clause 53.20 applies.
- Construction or extension of an apartment development to which clause 53.20 applies.
- Construction or extension of a dwelling in or forming part of an apartment development to which clause 53.20 applies.
- Use or development to which clause 53.25 applies.

with the exception of the following:

- in relation to applications lodged, or permits issued, for the use and development of land for an energy generation facility (other than a renewable energy facility) or a utility installation (other than a utility installation used to store, transmit or distribute electricity generated by a renewable energy facility with an installed capacity of 1 megawatt or greater), under Division 1 of Part 4 of the Act prior to the approval date of Amendment VC192 , the Council is the responsible authority for matters under Divisions 1, 1A, 2 and 3 of Part 4 of the Act, and for matters required by the permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority.

- in relation to permits for the use and development of land for a wind energy facility issued prior to 2 April 2015 under Division 1 of Part 4 of the Act, the Council is the responsible authority for matters under Divisions 1, 1A, 2 and 3 of Part 4 of the Act, and for matters required by the permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority.
- in relation to permits for the use and development of land for a wind energy facility issued prior to 2 April 2015 under Division 6 of Part 4 of the Act, the Council is the responsible authority for matters required by the permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority, subject to the operation of section 97H of the Act.
- in relation to applications lodged, or permits issued, for the use and development of land for a renewable energy facility (other than a wind energy facility) under Division 1 of Part 4 of the Act prior to the approval date of Amendment VC161, the Council is the responsible authority for matters under Divisions 1, 1A, 2 and 3 of Part 4 of the Act, and for matters required by the permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority.
- in relation to applications lodged, or permits issued, for the use and development of land for a utility installation used to store, transmit or distribute electricity generated by a renewable energy facility, under Division 1 of Part 4 of the Act prior to the approval date of Amendment VC161, the Council is the responsible authority for matters under Divisions 1, 1A, 2 and 3 of Part 4 of the Act, and for matters required by the permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority.
- in relation to an application made, or permit issued, for the use or development of land by the Head, Transport for Victoria or the Secretary to the Department of Transport and Planning, under Division 1 of Part 4 of the Act prior to the approval date of Amendment VC200, the Council is the responsible authority for matters under Divisions 1, 1A, 2 and 3 of Part 4 of the Act, and for matters required by the permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority.
- in relation to an application made, or permit issued, under Division 1 of Part 4 of the Act for the use and development of land for a primary school, secondary school, or education centre that is ancillary to, carried out in conjunction with, and on the same land or contiguous land in the same ownership as, a primary school or secondary school:
  - prior to the approval date of Amendment VC180; and
  - where clause 53.19 immediately in force before the approval date of Amendment VC180 did not apply,

  the Council is the responsible authority for matters under Divisions 1, 1A, 2 and 3 of Part 4 of the Act, and for matters required by the permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority.
- in relation to the use and development of land for a primary school, secondary school, or education centre that is ancillary to, carried out in conjunction with, and on the same land or contiguous land in the same ownership as, a primary school or secondary school, the Council is the responsible authority for matters required:
  - by clause 43.04 Development Plan Overlay to be done to the satisfaction of the responsible authority;
  - under Part 6 of the Act.

The Minister for Planning is the responsible authority for the following matters where clause 53.22 or 53.23 applies:

- matters under Divisions 1, 1A, 2 and 3 of Part 4 of the Act;

- matters under Division 2 of Part 9 of the Act where required under a permit in relation to the provision of the affordable housing contribution; and
- endorsement of, approval of or being satisfied with matters required by a permit or the scheme to be endorsed, approved or done to the satisfaction of the responsible authority.

11/10/2018
GC96

SCHEDULE TO CLAUSE 72.01 RESPONSIBLE AUTHORITY FOR THIS PLANNING SCHEME

1.0 Responsible authority for administering and enforcing this planning scheme:

31/07/2018
VC148

The Brimbank City Council is the responsible authority for administering and enforcing the planning scheme, except for matters specified in Clause 72.01-1 and matters listed in this schedule.

2.0 Responsible authority for administering and enforcing a provision of this planning scheme

22/05/2025
C241brim

The Minister for Planning is the responsible authority for administering and enforcing the planning scheme for the land at 147A Cairnlea Drive and 26S Glenbrook Avenue, Cairnlea.

The Minister for Planning is the responsible authority for administering and enforcing:

- Clause 51.01 of the planning scheme in respect of the "Regional Rail Link Project Section 1 Incorporated Document, March 2015" .
- Any other provision of the planning scheme as it applies to the use or development of land authorised by the Victorian Government for the Regional Rail Link Project.
- Clause 51.01 of the planning scheme in respect of the "Palmers Road Upgrade Project (Western Freeway to Calder Freeway) Incorporated Document, June 2017".
- Clause 51.01 of the planning scheme in respect of the "West Gate Tunnel Project Incorporated Document, December 2017".
- Any other provision of the planning scheme as it applies to the use or development of land for the West Gate Tunnel Project.
- Clause 51.01 of the scheme in respect of the "Melbourne Metro Rail Project: Upgrades to the Rail Network Incorporated Document, May 2018".
- Any other provision of the scheme as it applies to the use or development of land for the Melbourne Metro Rail Project: Upgrades to the Rail Network.

3.0 Person or responsible authority for issuing planning certificates:

31/07/2018
VC148

Minister for Planning.

4.0 Responsible authority for VicSmart and other specified applications:

22/09/2023
VC243

The Chief Executive Officer of the Brimbank City Council is the responsible authority for considering and determining VicSmart applications to which Clause 71.06 applies, in accordance with Divisions 1, 1A, 2 and 3 of Part 4 of the Act.

The Chief Executive Officer of the Brimbank City Council is the responsible authority for considering and determining applications to which Clause 53.24 applies, in accordance with Divisions 1, 1A, 2 and 3 of Part 4 of the Act.

The Chief Executive Officer of the Brimbank City Council is the responsible authority for considering and determining any application that the notice and review exemption in Clause 52.10-2 applies to, in accordance with Divisions 1, 1A, 2 and 3 of Part 4 of the Act.

72.02 WHAT AREA IS COVERED BY THIS PLANNING SCHEME?

31/07/2018
VC148

This planning scheme applies to the municipal district or other area specified in the schedule to this clause.

31/07/2018
VC148

SCHEDULE TO CLAUSE 72.02 WHAT AREA IS COVERED BY THIS PLANNING SCHEME?

1.0 Area covered by this planning scheme:

31/07/2018
VC148

City of Brimbank.

72.03 WHAT DOES THIS PLANNING SCHEME CONSIST OF?

31/07/2018
VC148

This planning scheme consists of this document, any maps specified in the schedule to this clause, and any document incorporated in the scheme in accordance with the Act. A document is not incorporated in this scheme by reason only that it is referred to in the scheme.

This document consists of State standard provisions and local provisions. Local provisions are:

- If included in this planning scheme:
  - Clause 02 (Municipal Planning Strategy).
  - Clause 21 (Municipal Strategic Statement).
  - Clause 22 (Local Planning Policies).
- All clauses in the Planning Policy Framework that include the letter 'L' in the clause number.
- All schedules to zones, overlays, particular provisions, general provisions and operational provisions.

All other provisions are State standard provisions.

Maps specified in the schedule to this clause show how land is zoned and whether land is affected by an overlay. This information is indicated by a letter and/or number code that is explained on each map.

Note: A clause numbered '11.01-1L' would be an example of a local provision in the Planning Policy Framework. 'C1Z' is an example of a code on a map that may be specified in the schedule to this clause. It stands for 'Commercial 1 Zone'.

31/07/2018
VC148

SCHEDULE TO CLAUSE 72.03 WHAT DOES THIS PLANNING SCHEME CONSIST OF?

1.0

14/04/2023
C216brim

Maps comprising part of this planning scheme:

- 1, 1DCPO, 1DPO, 1ESO, 1HO, 1LSIO, 1MAEO, 1PAO, 1SBO
- 2, 2DCPO, 2ESO, 2HO, 2LSIO, 2MAEO, 2PAO
- 3, 3DCPO, 3EAO,3ESO, 3HO, 3LSIO, 3PAO, 3SBO
- 4, 4DCPO, 4DDO, 4DPO, 4EAO, 4ESO, 4HO, 4LSIO, 4MAEO, 4PAO, 4PO, 4SBO
- 5, 5DCPO, 5DDO, 5DPO, 5EAO, 5ESO, 5HO, 5LSIO, 5MAEO, 5PAO, 5SBO, 5SLO
- 6, 6DCPO, 6ESO, 6HO
- 7, 7DCPO, 7DPO, 7EAO, 7ESO, 7HO, 7LSIO, 7PAO, 7SBO
- 8, 8DCPO, 8DDO, 8DPO, 8EAO, 8ESO, 8HO, 8LSIO, 8PAO, 8PO, 8SBO, 8SCO
- 9, 9DCPO, 9DDO, 9DPO, 9EAO, 9ESO, 9HO, 9LSIO, 9MAEO, 9PAO, 9PO, 9SBO, 9SLO
- 10, 10DCPO, 10DPO, 10ESO, 10HO, 10PAO
- 11, 11DCPO, 11DDO, 11DPO, 11EAO, 11ESO, 11HO, 11LSIO, 11PAO, 11SBO
- 12, 12DCPO, 12DDO, 12EAO, 12ESO, 12HO, 12LSIO, 12PAO, 12PO, 12SBO

72.04 INCORPORATED DOCUMENTS

02/09/2025
VC283

The documents listed in the table and the schedule to this clause are incorporated documents under section 6(2)(j) of the *Planning and Environment Act 1987*.

An incorporated document forms part of this planning scheme.

If a document is not listed in the table or the schedule, it is not an incorporated document.

A document is not incorporated in this planning scheme by reason only that it is referred to in the scheme.

Note: Clause 72.08 contains a list of background documents relevant to this planning scheme. A background document does not form part of the planning scheme.

Table to Clause 72.04

Name of document	Introduced by:
A 'Good Neighbour' Code of Practice for a Circus or Carnival (Department of Infrastructure, October 1997)	NPS1
Apiary Code of Practice (Department of Planning and Community Development, May 2011)	VC81
Australian Standard AS/NZS 2890.1:2004, Parking Facilities - Off-street Car Parking (Standards Australia, 2004)	VC26
Australian Standard AS2890.3:2015, Parking Facilities Part 3: Bicycle Parking (Standards Australia, 2015)	VC237
Building in Bushfire-Prone Areas (Publication SAA HB36-1993, CSIRO & Standards Australia, May 1993)	NPS1
Code of Practice for Bushfire Management on Public Land (Department of Sustainability and Environment, June 2012)	VC101
Code of Practice for Timber Production 2014 (as amended 2022) (Department of Environment, Land, Water and Planning, 2022)	VC229
Design Vehicles and Turning Path Templates (Publication AP-34/95, Austroads, 1995)	VC12
Guide to Residential Streets and Paths (Publication C&CCA T51-2004, Cement and Concrete Association of Australia, 2004)	VC26
Guide to Road Design, Part 6A: Pedestrian and Cycle Paths (Austroads, 2021)	VC77
Guidelines for the Removal, Destruction or Lopping of Native Vegetation (Department of Environment, Land, Water and Planning 2017)	VC138
Industrial and Commercial Land Classifications (Department of Transport and Planning, July 2025)	VC283
North Growth Corridor Plan (Victorian Planning Authority, August 2012)	VC283
Local Government Planning Guide for Dry Land Salinity(Department Conservation and Natural Resources, October 1995)	NPS1
Pavement Design - A Guide to the Structural Design of Road Pavements (Austroads, 1992)	VC12
Planning Requirements for Racing Dog Keeping and Training (Department of Environment, Land, Water and Planning, August 2017)	VC139
Principal Public Transport Network 2017 (Victorian Government, 2017)	VC132
Principal Public Transport Network Area Maps (Victorian Government, August 2018)	VC151
Private Tennis Court Development Code of Practice (Revision 1, Department of Infrastructure, March 1999)	VC5

Name of document	Introduced by:
South East Growth Corridor Plan (Victorian Planning Authority, August 2012)	VC283
Sunbury Growth Corridor Plan (Victorian Planning Authority, June 2012)	VC283
Victorian Code for Broiler Farms 2009 - Plus 2018 amendments (Department of Primary Industries, 1999)	VC60
Victorian Code for Cattle Feedlots (Department of Agriculture, Energy and Minerals, August 1995)	NPS1
Victorian Low Density Mobile Outdoor Poultry Farm Planning Permit Guidelines (Department of Economic Development, Jobs, Transport and Resources, June 2018)	VC150
Victorian Low Density Mobile Outdoor Pig Farm Planning Permit Guidelines (Department of Economic Development, Jobs, Transport and Resources, June 2018)	VC150
West Growth Corridor Plan (Victorian Planning Authority, August 2012)	VC283

15/01/2024
VC249

SCHEDULE TO CLAUSE 72.04 INCORPORATED DOCUMENTS

1.0 Incorporated documents

29/05/2025
C244brim

Name of document	Introduced by:
Australian Standard AS2021-2015, Acoustics – Aircraft Noise Intrusion – Building Siting and Construction (Standards Australia, 2015)	VC107
Brimbank Development Contributions Plan (Brimbank City Council, December 2023)	VC249
Furlong Road, St Albans Level Crossing Removal Project Incorporated Document (August 2015)	C181
Grand Junction Estate and Matthew's Hill Precinct Statement of Significance (Brimbank City Council, May 2025)	C244brim
Keilor Cemetery Incorporated Plan (November 2007)	C84(Part1)
Keilor Reserve Incorporated Plan (November 2007)	C84(Part1)
Main Road, St Albans Level Crossing Removal Project Incorporated Document (May 2014)	C160
Maribyrnong River Valley Design Guidelines (April 2010)	C141
Melbourne Metro Rail Project: Upgrades to the Rail Network Incorporated Document (May 2018)	GC96
Melton Highway, Sydenham Level Crossing Removal Project, Incorporated Document (October 2016)	C191
Mental Health Beds Expansion Program Incorporated Document (November 2020)	GC176
Outer Suburban Arterial Roads - Western Package Incorporated Document (June 2017)	GC74
Overnewton Anglican Community College Keilor Campus Master Plan (March 2006)	C81
Palmers Road and Robinsons Road Upgrade (Sayers Road to Western Freeway, Truganina) Incorporated Document (July 2012)	C152
Palmers Road Upgrade Project (Western Freeway to Calder Freeway) Incorporated Document (June 2017)	C194
Sunshine Barley Terminal Silos Statement of Significance (Brimbank City Council, October 2022)	C227brim
Sunshine Town Centre Development Contributions Plan (Brimbank City Council, December 2023)	VC249
Sydenham Regional Activity Centre Structure Plan, April 1999 (Revised August 2015)	C179(Part 1)
Water for a Growing West Project Incorporated Document (July 2014)	GC18
Watergardens Town Centre Framework Plan (March 2009)	C117
West Gate Tunnel Project Incorporated Document (December 2017)	GC93

72.05 WHEN DID THIS PLANNING SCHEME BEGIN?

31/07/2018
VC148

This planning scheme began on the date specified in the schedule to this clause.

31/07/2018
VC148

SCHEDULE TO CLAUSE 72.05 WHEN DID THIS PLANNING SCHEME BEGIN?

1.0 Date this planning scheme began:

31/07/2018
VC148

29 July 1999

72.06 EFFECT OF THIS PLANNING SCHEME

31/07/2018
VC148

Land may be used or developed only in accordance with this planning scheme.

Land must not be developed unless the land as developed can be used in accordance with this planning scheme.

If this planning scheme allows a particular use of land, it may be developed for that use provided all requirements of the scheme are met.

72.07 DETERMINATION OF BOUNDARIES

31/07/2018
VC148

If a boundary in this planning scheme is not precisely shown on a planning scheme map or is not otherwise defined, the certificate issuing authority must determine the boundary if asked to do so and must notify the applicant within 60 days.

72.08 BACKGROUND DOCUMENTS

02/09/2025
VC283

The documents listed in the table and the schedule to this clause are background documents.

A background document may:

- Have informed the preparation of, or an amendment to, this planning scheme.
- Provide information to explain the context within which a provision has been framed.
- Assist the understanding of this planning scheme.

A background document does not form part of this planning scheme.

Table to Clause 72.08

Name of background document	Amendment number - clause reference
Central Highlands Regional Growth Plan (Victorian Government, 2014)	VC106 Clauses 10 to 19
G21 Regional Growth Plan (Geelong Region Alliance, 2013)	VC106 Clauses 10 to 19
Gippsland Regional Growth Plan (Victorian Government, 2014)	VC106 Clauses 10 to 19
Great South Coast Regional Growth Plan (Victorian Government, 2014)	VC106 Clauses 10 to 19
Hume Regional Growth Plan (Victorian Government, 2014)	VC106 Clauses 10 to 19
Loddon Mallee North Regional Growth Plan (Victorian Government, 2014)	VC106 Clauses 10 to 19
Loddon Mallee South Regional Growth Plan (Victorian Government, 2014)	VC106 Clauses 10 to 19
Plan for Victoria (Department of Transport and Planning, February 2025)	VC283 Clauses 10 to 19
Wimmera Southern Mallee Regional Growth Plan (Victorian Government, 2014)	VC106 Clauses 10 to 19

31/07/2018
VC148

SCHEDULE TO CLAUSE 72.08 BACKGROUND DOCUMENTS

1.0
27/06/2024
C225brim

Background documents

Name of background document	Amendment number - clause reference
Albion Neighbourhood Plan (Brimbank City Council, 2013)	C225brim
Brimbank Aboriginal Cultural Heritage Strategy 2018 - 2023 (Brimbank City Council, 2018)	C225brim
Brimbank Activity Centres Strategy (Brimbank City Council, 2018)	C225brim
Brimbank Age Friendly City Plan 2018 - 2022 (Brimbank City Council, 2018)	C225brim
Brimbank Biodiversity Strategy 2012 - 2022 (Brimbank City Council, 2012)	C225brim
Brimbank City Council Post-Contact Cultural Heritage Study, Version 2 (Gary Vines, Olwen Ford, Graeme Butler & Francine Gilfedder, 2013)	C84 (Part 1)
Brimbank Climate Change Action Plan 2020 - 2025 (Brimbank City Council 2020)	C225brim
Brimbank Community Vision 2040 (Brimbank City Council, 2018)	C225brim
Brimbank Council Plan 2017 – 2021 (Brimbank City Council, 2017)	C225brim
Brimbank Cultural Strategy 2018 – 2022 (Brimbank City Council, 2018)	C225brim
Brimbank Cycling and Walking Strategy (Brimbank City Council, 2016)	C225brim
Brimbank Economic Development Strategy 2016 - 2020 (Brimbank City Council, 2016)	C225brim
Brimbank Electronic Gambling Policy (Brimbank City Council, 2019)	C225brim
Brimbank Green Wedge Management Plan (Brimbank City Council, August 2010)	C93
Brimbank Habitat Connectivity Plan 2018 - 2023 (Brimbank City Council, 2018)	C225brim
Brimbank Heritage Design Guidelines, Parts 1 – 9 (Brimbank City Council, 2009)	C84 (Part 1)
Brimbank Heritage Strategy 2018 - 2023 (Brimbank City Council, 2018)	C225brim
Brimbank Housing Strategy, Home and Housed (Brimbank City Council, 2014)	C158
Brimbank Industrial Land Strategy 2018 – 2030 (Brimbank City Council, 2018)	C225brim
Brimbank Landscape Guidelines (Brimbank City Council, Updated 2004)	C225brim
Brimbank Lifelong Learning Strategy 2024 - 2029 (Brimbank City Council, 2023)	C225brim
Brimbank Native Vegetation Review: Site Assessments (Abzeco Pty Ltd, 2007)	C93
Brimbank Parking Strategy 2019 - 2029 (Brimbank City Council, 2019)	C225brim
Brimbank Public Art Policy and Plan 2018 – 2023 (Brimbank City Council, 2018)	C225brim
Brimbank Reconciliation Action Plan (Brimbank City Council, 2019)	C225brim
Brimbank Response Strategy, Western Rail Plan, including Melbourne Airport Rail Link and Sunshine Super Hub (Brimbank City Council, 2019)	C225brim
Brimbank Settlement Action Plan (Brimbank City Council, 2019)	C225brim
Brooklyn Evolution (Brimbank City Council, 2016)	C177

Name of background document	Amendment number - clause reference
Central Sunshine Urban Design Framework (Brimbank City Council, 2009)	C179 (Part 1)
Community Services and Infrastructure Plan 2018 - 2038 (Brimbank City Council, 2018)	C225brim
Creating Better Parks Policy and Plan (Brimbank City Council, 2016)	C225brim
Deer Park Urban Design Framework (Brimbank City Council, 2009)	C225brim
Disability Action Plan 2022 – 2026 (Brimbank City Council, 2022)	C225brim
Guidelines for the Assessment of Heritage Planning Applications, Public Draft (Heritage Victoria, 2007)	C84 (Part 1)
Industrial Estate Guidelines:	C93
Derrimut Park, Part 1, November 2004	C93
Derrimut Park, Part 2, November 2004	C93
Gilberton's Industrial Estate, November 1997	C93
Glengala Estate, October 2000	C93
Glengala Estate, Stage 2, October 2008	C93
North Sunshine Industrial Estate Guidelines, 2007	C93
Paramount Estate, Release 1, March 2006	C93
Paramount Estate, Release 2, October 2006	C93
Paramount Estate, Release 3a, November 2006	C93
Paramount Estate, Release 3b, November 2007	C93
Paramount Estate, Release 4a, July 2007	C93
Paramount Estate, Release 4b, August 2008	C93
Paramount Estate, Release 5a, November 2007	C93
Paramount Estate, Release 5b, September 2009	C179 (Part 1)
Paramount Estate, Release 5c, October 2010	C179 (Part 1)
Paramount Estate, Release 5d, November 2011	C179 (Part 1)
Paramount Estate, Release 5e, April 2013	C179 (Part 1)
Proximity Fairbairn Road, August 2005	C179 (Part 1)
Translink Business Park, Stage 3, May 2006	C93
Translink Business Park, March 2004	C93
West Park, May 2004, amended February 2005	C93
West Park, Stage 5-8, January 2006	C93
West Park, Stage 9, March 2009	C93
Keilor Downs Urban Design Framework (Brimbank City Council, 2018)	C225brim
Keilor Village Vision Document (Brimbank City Council, 2014)	C162
Kororoit Creek Regional Strategy 2005 - 2030 (Department of Sustainability, 2006)	C93
Port Phillip and Western Port Native Vegetation Plan (Port Phillip and Western Port Catchment Management Authority, 2006)	C93

Name of background document	Amendment number - clause reference
Revised Greenhouse Reduction Strategy 2013 - 2023 (Brimbank City Council, 2018)	C225brim
Safe and Inclusive Brimbank 2020 - 2024 (Brimbank City Council, 2020)	C225brim
Southern Sunshine Urban Design Framework (SJB Urban, 2014)	C225brim
Sports Facility Development Plan (Brimbank City Council, 2018)	C225brim
St Albans Activity Centre Precinct Structure Plan (Brimbank City Council, 2015)	C150
St Albans Major Activity Centre Car Parking Plan (GTA, now Stantec 2021)	C216brim
Stand Alone Food and Drink Premises Policy (Brimbank City Council, 2013)	C141
Sunshine Activity Centre Northern Precinct Urban Design Framework (David Lock Associates, 2013)	C225brim
Sunshine Metropolitan Activity Centre Car Parking Plan (GTA, now Stantec 2021)	C216brim
Sunshine Town Centre Structure Plan (Brimbank City Council, Revised 2014)	C105
Sustainable Water Management Strategy 2013 - 2023 (Brimbank City Council, Revised 2018)	C225brim
Transport Priorities Paper (Brimbank City Council, 2018)	C225brim
Urban Forest Strategy 2016 – 2046 (Brimbank City Council, 2016)	C225brim
Victoria in Future (Department of Transport and Planning, 2023)	C225brim
Waste, Recycling, and Litter Strategy (Brimbank City Council, 2018)	C225brim

73 MEANING OF TERMS

11/04/2019
VC156

A term used in this planning scheme has its ordinary meaning unless that term is defined:

- In this planning scheme; or
- In the *Planning and Environment Act 1987* or the *Interpretation of Legislation Act 1984*, in which case the term has the meaning given to it in those Acts unless it is defined differently in this scheme.

73.01 GENERAL TERMS

02/09/2025
VC283

The following table lists general terms which may be used in this planning scheme. A term listed in the first column, under the heading "General term", has the meaning set out beside that term in the second column, under the heading "Definition".

General term	Definition
Act	The *Planning and Environment Act 1987*.
Agricultural production	Any form of primary production of renewable commodities. It does not include extractive industry, Mineral extraction, or timber production from native forest.
Anemometer	A wind measuring device.
Apartment	A dwelling located above the ceiling level or below the floor level of another dwelling and is part of a building containing two or more dwellings.
Approval date	The date this scheme began, or the date of notice in the Victoria Government Gazette of approval of an amendment to this scheme.
Basement	A storey below ground level, or that projects no more than 1.2 metres above ground level.
Building height	The vertical distance from natural ground level to the roof or parapet at any point.
Building Regulations	The *Building Regulations 1994*.
Carriageway	The area of a street reserve which is provided for the movement or parking of vehicles. It is determined by the invert of a kerb and channel and the point adjacent to the pavement edge for kerb (only) and edge strips.
Central Highlands region	The area covered by the Ararat, Ballarat, Golden Plains, Hepburn, Moorabool and Pyrenees planning schemes.
Clear to the sky	An unroofed area or area roofed with material that transmits 90 per cent of light.
Defendable space	An area of land around a building where vegetation is modified and managed to reduce the effects of flame contact and radiant heat associated with bushfire.
Deflection angle	The angle between two tangent sections of a carriageway.
Design speed	The speed fixed for the design and correlation of the geometric features of a carriageway that influence vehicle operation. It is the speed which is not exceeded by 85 per cent of vehicles.
Domestic services normal to a dwelling or small second dwelling	A domestic appliance or apparatus that is normal to and services a dwelling or small second dwelling. It includes disabled access ramps and handrails, an air conditioner, cooling or heating system, a hot water service, security systems and cameras, shade sails, a barbeque, downpipes and flues, a skylight, security screens, and the like.
Earthworks	Land forming, laser grading, levee banks, raised access roads and tracks, building pads, storage embankments, channel banks and drain banks and associated structures.
Employment and innovation areas	Dandenong, Fishermans Bend, La Trobe, Monash, Parkville, Sunshine and Werribee.

General term	Definition
Frontage	The road alignment at the front of a lot. If a lot abuts two or more roads, the one to which the building, or proposed building, faces.
Gaming	The playing of a gaming machine.
Gaming machine	Has the same meaning as it has in the *Gambling Regulation Act 2003.*
Garden area	Any area on a lot with a minimum dimension of 1 metre that does not include: a) a dwelling, small second dwelling or residential building, except for: ▪ an eave, fascia or gutter that does not exceed a total width of 600mm; ▪ a pergola; ▪ unroofed terraces, patios, decks, steps or landings less than 800mm in height; ▪ a basement that does not project above ground level; ▪ any outbuilding that does not exceed a gross floor area of 10 square metres; and ▪ domestic services normal to a dwelling, small second dwelling or residential building; b) a driveway; or c) an area set aside for car parking.
Geelong G21 region	The area covered by the Colac Otway, Golden Plains, Greater Geelong, Queenscliffe and Surf Coast planning schemes.
Gippsland region	The area covered by the Bass Coast, Baw Baw, East Gippsland, Latrobe, South Gippsland and Wellington planning schemes.
Great South Coast region	The area covered by the Corangamite, Glenelg, Moyne, Southern Grampians and Warrnambool planning schemes
Gross floor area	The total floor area of a building, measured from the outside of external walls or the centre of party walls, and includes all roofed areas.
Ground level	The natural level of a site at any point.
Habitable room	Any room of a dwelling, small second dwelling or residential building other than a bathroom, laundry, toilet, pantry, walk-in wardrobe, corridor, stair, lobby, photographic darkroom, clothes drying room and other space of a specialised nature occupied neither frequently nor for extended periods.
High quality productive agricultural land	Land which is used for animal husbandry or crop raising, and is capable of continuing to sustain agricultural production, and: a) is of prime, or very good, agricultural quality, having regard to soil type, growing season, and availability of infrastructure, and is of sufficient extent to support agricultural activities on an economically viable scale; or b) has been identified through a regional, sub-regional, or local study as being of particularly good quality and strategic significance for agriculture in the regional or local context.

General term	Definition
Hume region	The area covered by the Alpine, Benalla, Greater Shepparton, Indigo, Mansfield, Mitchell, Moira, Murrindindi, Strathbogie, Towong, Wangaratta and Wodonga planning schemes.
Land capability assessment	The assessment of the physical ability of the land to sustain specific uses having regard to its management, and without long term on-site detriment to the environment.
Leasable floor area	That part of the net floor area able to be leased. It does not include public or common tenancy areas, such as malls, verandahs, or public conveniences.
Loddon Mallee North region	The area covered by the Buloke, Campaspe, Gannawarra, Mildura and Swan Hill planning schemes.
Loddon Mallee South region	The area covered by the Central Goldfields, Greater Bendigo, Loddon, Macedon Ranges and Mount Alexander planning schemes.
Lot	A part (consisting of one or more pieces) of any land (except a road, a reserve, or common property) shown on a plan, which can be disposed of separately and includes a unit or accessory unit on a registered plan of strata subdivision and a lot or accessory lot on a registered cluster plan.
Mean building height	The vertical distance between the mean ground level and the finished roof height at its highest point.
Mean ground level	One half the sum of the highest and lowest levels along ground level of the outer surface of all external building walls.
Metropolitan activity centres	Box Hill (Suburban Rail Loop East Precinct), Broadmeadows, Cloverton (future), Cobblebank (future), Dandenong, Epping, Footscray, Fountain Gate-Narre Warren, Frankston, Ringwood and Sunshine.
Metropolitan Melbourne	The area covered by the Banyule, Bayside, Boroondara, Brimbank, Cardinia, Casey, Darebin, Frankston, Glen Eira, Greater Dandenong, Hobsons Bay, Hume, Kingston, Knox, Manningham, Maribyrnong, Maroondah, Melbourne, Melton, Merri-bek, Monash, Moonee Valley, Mornington Peninsula, Nillumbik, Port of Melbourne, Port Phillip, Stonnington, Whitehorse, Whittlesea, Wyndham, Yarra and Yarra Ranges Planning Schemes and the area within the urban growth boundary in the Mitchell Planning Scheme.
Mineral	Any substance which occurs naturally as part of the earth's crust, including: a) oil shale and coal; and b) hydrocarbons and mineral oils contained in oil shale or coal, or extracted from oil shale or coal by chemical or industrial processes. It does not include water, stone, or petroleum.
Minister for Planning	A Minister for the time being administering the Act.
Movable building	A structure, other than a tent, caravan, or vehicle, which is designed to be moved from place to place on more than one occasion.
Native vegetation	Plants that are indigenous to Victoria, including trees, shrubs, herbs, and grasses.

General term	Definition
Net floor area	The total floor area of all floors of all buildings on a site. It includes half the width of any party wall and the full width of all other walls. It does not include the area of stairs, loading bays, accessways, or car parking areas, or any area occupied by machinery required for air conditioning, heating, power supply, or lifts.
Plot ratio	The gross floor area of all buildings on a site, divided by the area of the site.
Potentially contaminated land	Land: a) used or known to have been used for industry or mining; b) used or known to have been used for the storage of chemicals, gas, waste or liquid fuel (other than minor above-ground storage that is ancillary to another use of the land); or c) where a known past or present activity or event (occurring on or off the land) may have cause contamination of the land.
Priority precincts	Arden, Docklands, East Werribee, Fishermans Bend, Footscray, La Trobe, Parkville, Richmond to Flinders, and Sunshine, and the SRL East Precincts at Box Hill, Burwood, Clayton, Cheltenham, Glen Waverley and Monash.
Private open space	An outdoor area of a dwelling, small second dwelling or residential building or land for the exclusive use of the occupants.
Property vegetation plan	A plan which relates to the management of native vegetation within a property, and which is contained within an agreement made pursuant to section 69 of the *Conservation, Forests and Lands Act 1987*.
Public land manager	The Minister, government department, public authority or municipal council having responsibility for the care or management of public land. In relation to Crown land reserved under an Act and managed or controlled by a committee of management, other than Parks Victoria, the Great Ocean Road Coast and Parks Authority or a municipal council, it means the Minister administering that Act and does not include the committee of management.
Radio mast	A mast, for radio transmission or reception in a dwelling or small second dwelling, that is: a) with antenna, more than 14 metres above the ground; b) if attached to a building, with antenna, more than 5 metres above the roof line; c) including antenna, wider than 6 metres; or d) excluding antenna, wider than 50 centimetres at any point exceeding 3 metres above the ground.
Retail	The sale of goods or materials, in any quantity or manner, other than by wholesale.
Secluded private open space	That part of private open space primarily intended for outdoor living activities which enjoys a reasonable amount of privacy.
Setback	The minimum distance from any allotment boundary to a building.
Site coverage	The proportion of a site covered by buildings.

General term	Definition
Stone	Basalt, freestone, granite, limestone, sandstone, or other building stone, or rock, ordinarily used for building, manufacturing, road making, or construction; or clay (not fine clay, bentonite, or kaolin), earth, gravel, quartz (not quartz crystals), sand, soil, slate, or other similar material.
Storey	That part of a building between floor levels. If there is no floor above, it is the part between the floor level and ceiling. It may include an attic, basement, built over car parking area, and mezzanine.
Stormwater	The net increase in run-off from urban development due to water not being able to seep into the ground because of impervious surfaces, such as roofs and roads.
Street leg length	The distance between street intersections or junctions, or points and locations where vehicles must slow down, usually to a maximum speed of 20 kilometres per hour.
Street reserve	Land set aside for a street pavement and verge.
Sustainable agriculture	The use of farming practices and systems which maintain or enhance: a) the economic viability of agricultural production; b) the natural resource base; and c) other ecosystems which are influenced by agricultural activities.
Telecommunications line	A wire, cable, optic fibre, tube, conduit, waveguide or other physical medium used, or to be used, as a continuous artificial guide for or in connection with carrying communications by means of guided electromagnetic energy.
Telecommunications network	A system or series of systems that carries, or is capable of carrying, communications by means of guided and unguided electromagnetic energy.
Telecommunications tower	A free-standing tower, pole or mast used as part of a telecommunications network that is not mounted on, or affixed to, any other structure.
Tenement	Land comprised in: a) a lot which does not adjoin another lot in the same ownership; or b) lots in the same ownership and which adjoin each other. Lots are considered to adjoin each other if they are separated only by a stream, stream reserve, or unmade or unused government road or rail reserve.
Transport manager	(a) a Minister; or (b) government department; or (c) Administrative Office under the *Public Administration Act 2004*; or (d) public authority; or (e) any person - that has responsibility under an Act for the care or management of land that forms part of Victoria's transport system.
Transport system	All of the components that make up the system for the movement and transport of people and goods including:

General term	Definition
	▪ Movement networks including cycling paths, footpaths, roads, railways, shipping lanes, tramways and water transport routes. ▪ Transport interchanges for accessing, disembarking, unloading and interchange of people and goods, and for the storage of freight and vehicles. This includes transport terminals and public transport stops. ▪ Infrastructure required to operate movement networks and transport interchanges. ▪ Land reserved for the future development of movement networks and transport interchanges.
Utility service provider	A person, other than a public authority or municipal council, having responsibility under an Act for the generation, transmission, distribution or supply of electricity, gas, power, telecommunications, water supply, drainage or sewerage services.
Verge	The part of the street reserve between the carriageway and the boundary of adjacent lots or other limit to the street reserve. It may accommodate public utilities, a footpath, indented parking, stormwater flows, street lighting poles and planting.
Wall height	The vertical distance between the top of the eaves at the wall line, parapet or flat roof (not including a chimney), whichever is the highest, and the natural ground level.
Wholesale	The sale of goods or materials, to be sold by others.
Wimmera Southern Mallee region	The area covered by the Hindmarsh, Horsham, Northern Grampians, West Wimmera and Yarriambiack planning schemes.

73.02
31/07/2018
VC148

SIGN TERMS

The following table lists terms which may be used in this planning scheme in relation to signs. A term listed in the first column, under the heading "Sign term", has the meaning set out beside that term in the second column, under the heading "Definition".

Sign term	Definition
Above-verandah sign	A sign above a verandah or, if no verandah, that is more than 3.7 metres above pavement level, and which projects more than 0.3 metre outside the site.
Display area	The area of that part of a sign used to display its content, including borders, surrounds and logo boxes. It does not include safety devices, platforms and lighting structures. If the sign does not move or rotate, the area is one side only.
Animated sign	A sign that can move, contains moving or scrolling parts, changes its message, flashes, or has a moving or flashing border.
Bed and breakfast sign	A sign at a dwelling that advertises bed and breakfast accommodation in the dwelling.
Bunting sign	An advertisement that consists of bunting, streamers, flags, windvanes, or the like.
Business identification sign	A sign that provides business identification information about a business or industry on the land where it is displayed. The information may include the name of the business or building, the street number of the business premises, the nature of the business, a business logo or other business identification information.
Direction sign	A sign not exceeding 0.3 square metre that directs vehicles or pedestrians. It does not include a sign that contains commercial information.
Electronic sign	A sign that can be updated electronically. It includes screens broadcasting still or moving images.
Floodlit sign	A sign illuminated by external lighting provided for that purpose.
High-wall sign	A sign on the wall of a building so that part of it is more than 10 metres above the ground.
Home based business sign	A sign at a dwelling that advertises a home based business carried on in the dwelling, or on the land around the dwelling.
Internally illuminated sign	A sign illuminated by internal lighting or which contains lights or illuminated tubes arranged as an advertisement.
Major promotion sign	A sign which is 18 square metres or greater that promotes goods, services, an event or any other matter, whether or not provided, undertaken or sold or for hire on the land or in the building on which the sign is sited.
Panel sign	A sign with an advertisement area exceeding 10 square metres.
Pole sign	A sign: a) on a pole or pylon that is not part of a building or another structure; b) that is no more than 7 metres above the ground;

Sign term	Definition
	c) with an advertisement area not exceeding 6 square metres; and d) that has a clearance under it of at least 2.7 metres.
Promotion sign	A sign of less than 18 square metres that promotes goods, services, an event or any other matter, whether or not provided, undertaken or sold or for hire on the land or in the building on which the sign is sited.
Reflective sign	A sign finished with material specifically made to reflect external light.
Sign	Includes a structure specifically built to support or illuminate a sign.
Sky sign	A sign: a) on or above the roof of a building, but not a verandah; b) fixed to the wall of a building and which projects above the wall; or c) fixed to a structure (not a building) so that part of it is more than 7 metres above the ground.

73.03 LAND USE TERMS

21/08/2025
VC279

The table to this clause lists terms which may be used in this planning scheme in relation to the use of land. A term describing a use or activity in relation to land which is not listed in the table must not be characterised as a separate use of land if the term is obviously or commonly included within one or more of the terms listed in the table.

Meaning of terms

A term listed in the first column, under the heading "Land use term", has the meaning set out beside that term in the second column, under the heading "Definition".

No definition of listed term indicates ordinary meaning

A term listed in the first column, under the heading "Land use term", which does not have a meaning set out beside that term in the second column, under the heading "Definition", has its ordinary meaning.

Terms which specifically include other listed terms

A term listed in the first column, under the heading "Land use term", which has other terms listed beside it in the third column, under the heading "Includes", includes any term so listed in the third column and any term included within that term in the third column, but does not include any other term listed in the first column.

A term listed in the first column which has other terms listed beside it in the third column may also include other terms which are not listed in the first column.

All terms listed in the third column are also listed in the first column.

Terms which do not specifically include other listed terms

If a term listed in the first column, under the heading "Land use term", does not have any term listed beside it in the third column, under the heading "Includes", that term does not include any term listed in the first column.

However, a term listed in the first column which does not have any term listed beside it in the third column may include other terms which are not listed in the first column.

Terms which are included within other listed terms

A term listed in the first column, under the heading "Land use term", which has a term listed beside it in the fourth column, under the heading "Included in", is included within the term so listed in the fourth column and any term which includes that term in the fourth column.

All terms listed in the fourth column are also listed in the first column.

Terms which are not included within other listed terms

If a term listed in the first column, under the heading "Land use term", does not have a term listed beside it in the fourth column, under the heading "Included in", that term is not included within any other term listed in the first column.

Table to Clause 73.03

Land use term	Definition	Includes	Included in
Abattoir	Land used to slaughter animals, including birds. It may include the processing of animal products.		**Rural industry**
Accommodation	Land used to accommodate persons.	**Camping and caravan park**	

Land use term	Definition	Includes	Included in
		Corrective institution **Dwelling** **Group accommodation** **Host farm** **Residential aged care facility** **Residential building** **Residential village** **Retirement village** **Small second dwelling**	
Adult sex product shop	Land used to sell or hire sexually explicit material, including: a) publications classified as restricted under the *Classification (Publications, Films and Computer Games) (Enforcement) Act 1995*; and b) materials and devices (other than contraceptives and medical treatments) used in conjunction with sexual behaviour.		**Shop**
Agriculture	Land used to: a) propagate, cultivate or harvest plants, including cereals, flowers, fruit, seeds, trees, turf, and vegetables; b) keep, breed, board, or train animals, including livestock, and birds; or c) propagate, cultivate, rear, or harvest living resources of the sea or inland waters.	**Animal husbandry** **Aquaculture** **Crop raising**	
Airport			**Transport terminal**
Amusement park			**Outdoor recreation facility**
Amusement parlour	A building that contains: a) three or more coin, card, or token operated amusement machines;		**Place of assembly**

Land use term	Definition	Includes	Included in
	b) one or more coin, card, or token operated amusement machines with more than one screen or console that can be played by three or more people simultaneously; or c) two or more coin, card, or token operated billiard, snooker, or pool tables. It does not include coin, card, or token operated children's rides, amusement machines if there is the ability to receive a monetary reward, or premises used for a Bar or Hotel.		
Animal husbandry	Land used to keep, breed, board, or train animals, including birds.	**Animal production** **Animal training** **Apiculture** **Domestic animal husbandry** **Horse husbandry** **Racing dog husbandry**	**Agriculture**
Animal production	Land used to keep or breed farm animals for the production of livestock, eggs, fibre, meat, milk or other animal products.	**Grazing animal production** **Intensive animal production** **Pig farm** **Poultry farm** **Poultry hatchery**	**Animal husbandry**
Animal training	Land used to train animals, other than domestic animals, horses, or racing dogs.		**Animal husbandry**
Apiculture	Land used to keep honeybee hives and to extract honey or other bee hive products.		**Animal husbandry**
Aquaculture	Land used to keep or breed aquatic animals, or cultivate or propagate aquatic plants.		**Agriculture**
Art and craft centre	Land used to manufacture, display, and sell, works of art or craft, such as handicrafts, paintings, and sculptures.		

Land use term	Definition	Includes	Included in
Art gallery	Land used to display works of art, including ceramics, furniture, glass, paintings, screen based art, sculptures, and textiles.		**Exhibition centre**
Automated collection point	A building with a gross floor area of no more than 100 square metres, used as an automated collection point as defined in the *Circular Economy (Waste Reduction and Recycling) Act 2021*.		**Transfer station**
Bank			**Office**
Bar	Land used to sell liquor for consumption on the premises. It may include accommodation, food for consumption on the premises, entertainment, dancing, amusement machines, and gambling.		**Food and drink premises**
Beauty salon			**Shop**
Bed and breakfast	A dwelling used, by a resident of the dwelling, to provide accommodation for persons away from their normal place of residence.		**Dwelling**
Betting agency	Land used for gambling by wagering, and where there is the ability to receive a monetary reward.		**Gambling premises**
Boat and caravan storage	Land used to store boats, caravans, or vehicle-towed boat trailers.		**Store**
Boat launching facility	Land used to launch boats into the water and to retrieve boats from the water.	**Boat ramp slipway**	**Recreational boat facility**
Boat ramp			**Boat launching facility**
Bottle shop	Land used to sell packaged liquor for consumption off the premises.		**Shop**
Broiler farm	Land used to keep broiler chickens for the production of meat.		**Poultry farm**
Bus terminal			**Transport terminal**
Camping and caravan park	Land used to allow accommodation in caravans, cabins, tents, or the like.		**Accommodation**

Land use term	Definition	Includes	Included in
Caretaker's house	A dwelling on the same site as a building, operation, or plant, and occupied by a supervisor of that building, operation, or plant.		**Dwelling**
Carnival	Land, other than an Exhibition centre or trade fair, used for a temporary fair or amusements which provide entertainment such as side shows, merry-go-rounds, and stalls for games or snacks.		**Place of assembly**
Car park	Land used to park motor vehicles. It may include charging of electric vehicles.		
Car sales			**Motor vehicle, boat, or caravan sales**
Car wash			**Service industry**
Cattle feedlot	Land used for a cattle feedlot as defined by the Victorian Code for Cattle Feedlots 1995.		**Intensive animal production**
Cemetery	Land used to dispose of human remains by burial. It may include funeral chapels or the like.		
Child care centre	Land used to care for five or more children who are not permanently resident on the land.	**Kindergarten**	**Education centre**
Cinema	Land used to provide screen based entertainment or information to the public.		**Place of assembly**
Cinema based entertainment facility	Land used to provide screen based entertainment or information to the public, in association with the provision of meals or sporting, amusement, entertainment, leisure or retail facilities.		**Place of assembly**
Circus	Land used, by performers, to provide entertainment such as acrobatic feats, tricks of skill, and exhibiting animals.		**Place of assembly**
Commercial display area	Land used only to display goods.		**Warehouse**
Community care accommodation	Land used to provide accommodation and care services. It includes permanent, temporary		**Residential building**

Land use term	Definition	Includes	Included in
	and emergency accommodation. It may include supervisory staff and support services for residents and visitors.		
Conference centre			**Function centre**
Container deposit scheme centre	Land used to collect, consolidate, temporarily store, sort or recover materials under Victoria's Container Deposit Scheme by a network or collection point operator in accordance with the *Circular Economy (Waste Reduction and Recycling) Act 2021*. The centre may incorporate a reverse vending machine, automated collection point, drop off point and over the counter refunds.		**Transfer station**
Convenience restaurant	Land used to prepare and sell food and drink for immediate consumption, where substantial provision is made for consumption both on and off the premises.		**Food and drink premises**
Convenience shop	A building with a leasable floor area of no more than 240 square metres, used to sell food, drinks, and other convenience goods. It may also be used to hire convenience goods.		**Shop**
Corrective institution	Land used to hold and reform persons committed to it by the courts, such as a prison, remand centre, and other type of detention facility.		**Accommodation**
Crematorium	Land used to cremate human remains. It may include funeral chapels or the like.		
Crop raising	Land used to propagate, cultivate or harvest plants, including cereals, flowers, fruit, seeds, trees, turf, and vegetables.	**Horticulture** **Rice growing** **Timber production**	**Agriculture**
Dance studio			**Indoor recreation facility**
Data centre			**Utility installation**
Department store			**Shop**

Land use term	Definition	Includes	Included in
Display home centre	One or more buildings constructed as a dwelling, but used for display, to encourage people to buy or construct similar dwellings. It may include a sales office.		
Dog breeding			**Domestic animal husbandry**
Domestic animal boarding	Land used to board domestic animals, such as boarding kennels and a cattery. It includes domestic animal day care.		**Domestic animal husbandry**
Domestic animal husbandry	Land used to keep, breed, board or train domestic animals.	**Dog breeding** **Domestic animal boarding**	**Animal husbandry**
Drive-in theatre			**Place of assembly**
Dry cleaner	Land used to professionally clean or launder clothing or household articles. It may include the use of dry cleaning processes.		**Service industry**
Dry cleaning agent	Land used to arrange for professional cleaning or laundering of clothing or household articles predominantly at another location. It does not include the use of dry cleaning processes on the land.		**Shop**
Dwelling	A building used as a self-contained residence which must include: a) a kitchen sink; b) food preparation facilities; c) a bath or shower; and d) a toilet and wash basin. It includes outbuildings and works normal to a dwelling.	**Bed and breakfast** **Caretaker's house**	**Accommodation**
Education centre	Land used for education.	**Child care centre** **Employment training centre** **Primary school** **Secondary school** **Tertiary institution**	

Land use term	Definition	Includes	Included in
Earth and energy resources industry	Land used for the exploration, removal or processing of natural earth or energy resources. It includes any activity incidental to this purpose including the construction and use of temporary accommodation.	**Extractive industry** **Greenhouse gas sequestration** **Greenhouse gas sequestration exploration** **Geothermal energy exploration** **Geothermal energy extraction** **Mining** **Mineral exploration** **Petroleum exploration** **Petroleum production** **Stone exploration**	
Electoral office	An office used for electioneering by a candidate in a local, State, or Federal Government election.		**Office**
Electorate office	An office used by a State or Federal Member of Parliament to conduct their representative duties.		**Office**
Emergency services facility	Land used to provide facilities for emergency services, such as fire prevention and ambulance services. It may include administrative, operational or storage facilities associated with the provision of emergency services.		
Employment training centre			**Education centre**
Energy generation facility	Land used to generate energy for use off site other than geothermal energy extraction. It includes any building or other structure or thing used in or in connection with the generation of energy.	**Renewable energy facility** **Waste-to-energy facility**	
Equestrian supplies			**Restricted retail premises**
Exhibition centre	Land used to display works of art, artefacts, or historical, cultural, or other like works or artefacts.	**Art gallery** **Museum**	**Place of assembly**

Land use term	Definition	Includes	Included in
Extractive industry	Land used for the extraction or removal of stone from land for commercial use, or to use the stone for building, construction, road or manufacturing works. It includes: ▪ the rehabilitation of the land; and ▪ the treatment of stone (such as crushing and processing) or the manufacture of bricks, tiles, pottery, or cement or asphalt products on, or adjacent to, the land from which the stone is extracted or removed.		**Earth and energy resources industry**
Food and drink premises	Land used to prepare and sell food and drink for immediate consumption on, or off, the premises.	**Bar** **Convenience restaurant** **Hotel** **Restaurant** **Take away food premises**	**Retail premises**
Freeway service centre	Land which has direct access to a freeway and is used to provide essential services and facilities which encourage drivers to stop and take an effective break in the interests of driver safety.		
Freezing and cool storage			**Store**
Fuel depot	Land used to store, sell, and distribute fuel.	**Liquid fuel depot** **Solid fuel depot**	**Warehouse**
Function centre	Land used, by arrangement, to cater for conferences, private functions, and in which food and drink may be served. It may include entertainment and dancing.	**Conference centre** **Reception centre**	**Place of assembly**
Funeral parlour	Land used to organise and conduct funerals, memorial services, or the like. It includes the storage and preparation of bodies for burial or cremation.		
Gambling premises	Land used for gambling by gaming or wagering, and where there is the ability to receive a monetary reward.	**Betting agency** **Gaming premises**	**Retail premises**

Land use term	Definition	Includes	Included in
Gaming premises	Land used for gambling by gaming, and where there is the ability to receive a monetary reward.		**Gambling premises**
Garden supplies	Land used to sell and distribute garden supplies such as sand, soil, railway sleepers, screenings, rock, and the like.		**Landscape gardening supplies**
Geothermal energy exploration	Land used for geothermal energy exploration as defined in the Geothermal *Energy Resources Act 2005.*		**Earth and energy resources industry**
Geothermal energy extraction	Land used for geothermal energy extraction as defined in the Geothermal *Energy Resources Act 2005.*		**Earth and energy resources industry**
Golf course			**Outdoor recreation facility**
Golf driving range			**Outdoor recreation facility**
Grazing animal production	Land used for animal production where the animals' food is obtained by directly grazing, browsing or foraging plants growing on the land. It includes: ▪ emergency, seasonal and supplementary feeding; ▪ the incidental penning, feeding and housing of animals for weaning or other husbandry purposes. In this definition: *Emergency feeding* means providing feed to animals when an emergency event such as a flood, bushfire or biosecurity event, restricts or prevents the animals from grazing, browsing or foraging plants growing on the land; *Seasonal feeding* means providing feed to animals when seasonal conditions, including drought, restrict or prevent the animals from grazing, browsing or foraging plants growing on the land;		**Animal production**

Land use term	Definition	Includes	Included in
	Supplementary feeding means providing feed to animals to supplement the food the animals obtain by directly grazing, browsing or foraging plants growing on the land.		
Greenhouse gas sequestration	Land used for greenhouse gas substance injection and monitoring as defined in the *Greenhouse Gas Geological Sequestration Act 2008.*		**Earth and energy resources industry**
Greenhouse gas sequestration exploration	Land used for greenhouse gas sequestration formation exploration as defined in the *Greenhouse Gas Geological Sequestration Act 2008.*		**Earth and energy resources industry**
Group accommodation	Land, in one ownership, containing a number of dwellings used to accommodate persons away from their normal place of residence.		**Accommodation**
Hairdresser			**Shop**
Hall			**Place of assembly**
Helicopter landing site	Land used for the take-off and landing of a helicopter, with or without a permanent landing pad, but without permanent facilities for the assembly and distribution of goods or passengers.		
Heliport			**Transport terminal**
Home based business	An occupation carried on in a dwelling, or on the land around a dwelling, by a resident of the dwelling. It may include a use defined elsewhere.		
Horse husbandry	Land used to keep, breed, board or train horses.	**Horse riding school** **Horse stables**	**Animal husbandry**
Horse riding school			**Horse husbandry**
Horse stables			**Horse husbandry**
Horticulture	Land used to propagate, cultivate, or harvest flowers, fruit, vegetables, vines, or the like.	**Market garden**	**Crop raising**

Land use term	Definition	Includes	Included in
Hospital	Land used to provide health services (including preventative care, diagnosis, medical and surgical treatment, and counselling) to persons admitted as in-patients. It may include the care or treatment of out-patients.		
Host farm	An agricultural property used to provide accommodation for persons, away from their normal place of residence, to experience living on land used for agricultural purposes.		**Accommodation**
Hotel	Land used to sell liquor for consumption on and off the premises. It may include accommodation, food for consumption on the premises, entertainment, dancing, amusement machines, and gambling.		**Food and drink premises**
Indoor recreation facility	A building used for indoor leisure, recreation, or sport.	**Dancing studio**	**Minor sports and recreation facility**
Industry	Land used for any of the following operations: a) any process of manufacture; b) dismantling or breaking up of any article; c) treating waste materials; d) winning clay, gravel, rock, sand, soil, stone, or other materials; e) laundering, repairing, servicing or washing any article, machinery, or vehicle, other than on-site work on a building, works, or land; or f) any process of testing or analysis. If on the same land as any of these operations, it also includes: a) storing goods used in the operation or resulting from it; b) providing amenities for people engaged in the operation; c) selling by wholesale, goods resulting from the operation; and d) accounting or administration in connection with the operation.	**Materials recycling** **Refuse disposal** **Transfer station** **Research and development centre** **Rural industry** **Service industry**	

Land use term	Definition	Includes	Included in
	If Materials recycling, goods resulting from the operation may be sold by retail.		
Informal outdoor recreation	Land open to the public and used by non-paying persons for leisure or recreation, such as a cycle track, park, picnic or barbecue area, playground, plaza, and walking or jogging track.		**Minor sports and recreation facility**
Intensive animal production	Land used for animal production where the animals' food is imported from outside the immediate building, enclosure, paddock or pen. It does not include: ▪ an abattoir or sale yard; or ▪ grazing animal production, pig farm, poultry farm or poultry hatchery.	**Cattle feedlot** **Intensive dairy farm**	**Animal production**
Intensive dairy farm	Land used for intensive animal production where cattle are kept or bred for the production of milk.		**Intensive animal production**
Interpretation centre	A facility that assists in the public understanding of the natural or cultural environment.		
Jetty			**Marina**
Kindergarten			**Child care centre**
Landscape gardening supplies	Land used to propagate, grow, and sell plants, or sell and distribute garden supplies.	**Garden supplies** **Plant nursery**	**Retail premises**
Laundromat	Land used to clean or launder clothing or household items using self-service machines.		**Shop**
Leisure and recreation	Land used for leisure, recreation, or sport.	**Major sports and recreation facility** **Minor sports and recreation facility** **Motor racing track**	
Library			**Place of assembly**
Liquid fuel depot	Land used to store, sell by wholesale, and distribute fuel.		**Fuel depot**

Land use term	Definition	Includes	Included in
Mail centre	Land used to sort mail for distribution.		**Warehouse**
Major sports and recreation facility	Land used for leisure, recreation or sport, and where there is substantial provision made for spectators, such as a grandstand, and to which spectators are usually charged admission.	**Race course**	**Leisure and recreation**
Manufacturing sales	Land used, as an incidental part of an industry, to retail goods made materially different on the land by that industry.		**Retail premises**
Marina	Land used to moor boats, or store boats above or adjacent to the water. It may include boat recovery facilities, and facilities to repair, fuel, and maintain boats and boat accessories.	**Jetty** **Mooring pole** **Pier** **Pontoon**	**Recreational boat facility**
Market	Land used to sell goods, including foodstuffs, from stalls.		**Retail premises**
Market garden			**Horticulture**
Materials recycling	Land used to dismantle, treat, process, store, recycle, or sell refuse, used or surplus materials.		**Industry**
Medical centre	Land used to provide health or surgical services (including preventative care, diagnosis, medical and surgical treatment, pathology services, and counselling) to out-patients only.		**Office**
Milk depot	Land used to receive milk and milk products for distribution to consumers, but where milk is not processed or pasteurised.		**Warehouse**
Mineral exploration	Land used for exploration as defined in the *Mineral Resources (Sustainable Development) Act 1990.*		**Earth and energy resources industry**
Mining	Land used for mining as defined in the *Mineral Resources (Sustainable Development) Act 1990.*		**Earth and energy resources industry**
Minor sports and recreation facility	Land used for leisure, recreation, or sport, without substantial provision for spectators, and which is usually open to non-paying spectators.	**Indoor recreation facility**	**Leisure and recreation**

Land use term	Definition	Includes	Included in
		Informal outdoor recreation **Open sports ground** **Outdoor recreation facility** **Restricted recreation facility**	
Minor utility installation	Land used for a utility installation comprising any of the following: a) sewerage or water mains; b) storm or flood water drains or retarding basins; c) flow measurement device or a structure to gauge waterway flow; d) siphons, water storage tanks, disinfection booster stations and channels; e) gas mains providing gas directly to consumers; f) a sewerage treatment plant, and any associated disposal works, required to serve a neighbourhood; g) a pumping station required to serve a neighbourhood; h) power lines designed to operate at less than 220,000 volts but excluding any power lines directly associated with an Energy generation facility or Geothermal energy extraction; i) an electrical sub-station designed to operate at no more than 66,000 volts but excluding any sub-station directly associated with an Energy generation facility or Geothermal energy extraction; or j) a battery with a storage capacity of no more than 5 megawatts.	**Water retarding basin**	**Utility installation**
Mooring pole			**Marina**
Motel	Land used to provide accommodation in serviced rooms for persons away from their normal place of residence, and where provision is made for parking guests' vehicles convenient to the rooms.		**Residential hotel**

Land use term	Definition	Includes	Included in
Motor racing track	Land used to race, rally, scramble, or test, vehicles, including go-karts, motor boats, and motorcycles, and includes other competitive motor sports. It may include training.		**Leisure and recreation**
Motor repairs	Land used to repair or service motor vehicles, and includes the fitting of accessories.	**Panel beating**	**Service industry**
Motor vehicle, boat, or caravan sales	Land used to sell or hire motor vehicles, boats, or caravans. It may include the minor repair or servicing of motor vehicles, boats, or caravans, and the sale or fitting of accessories.	**Car sales**	**Retail premises**
Museum	Land used to display archaeological, biological, cultural, geographical, geological, historical, scientific, or other like works or artefacts.		**Exhibition centre**
Natural systems	Land in substantially its natural state which is used to maintain ecological systems, or to preserve an area of historic, scientific, aesthetic, or cultural significance.		
Nightclub	A building used to provide entertainment and dancing. It may include the provision of food and drink for consumption on the premises. It does not include the sale of packaged liquor, or gaming.		**Place of assembly**
Office	Land used for administration, or clerical, technical, professional or other like business activity. No goods or materials intended for manufacture, sale, or hire may be stored on the land. Other than electoral office and medical centre, it does not include any other defined use.	**Bank** **Electoral office** **Electorate office** **Medical centre** **Real estate agency** **Travel agency**	
Open sports ground	Land used for organised games of sport, but which is available for informal outdoor leisure or recreation when not being used or prepared for an organised game. It may include lights, change rooms, pavilions, and shelters.		**Minor sports and recreation facility**

Land use term	Definition	Includes	Included in
Outdoor recreation facility	Land used for outdoor leisure, recreation, or sport. It does not include an Open sports ground or Informal outdoor recreation.	**Amusement park** **Golf course** **Golf driving range** **Paintball games facility** **Zoo**	**Minor sports and recreation facility**
Paintball games facility			**Outdoor recreation facility**
Panel beating	Land used to repair or replace damaged motor vehicle bodies and panels, and carry out any associated mechanical work or spray painting.		**Motor repairs**
Party supplies			**Restricted retail premises**
Petroleum exploration	Land used for petroleum exploration as defined in the *Petroleum Act 1998.*		**Earth and energy resources industry**
Petroleum production	Land used for petroleum production as defined in the *Petroleum Act 1998.*		**Earth and energy resources industry**
Pier			**Marina**
Pig farm	Land used to keep or breed pigs.		**Animal production**
Place of assembly	Land where people congregate for religious, spiritual or cultural activities, entertainment, or meetings.	**Amusement parlour** **Carnival** **Cinema** **Cinema-based entertainment facility** **Circus** **Drive-in theatre** **Exhibition centre** **Function centre** **Hall** **Library** **Nightclub** **Place of worship** **Restricted place of assembly**	

Land use term	Definition	Includes	Included in
Place of worship	Land used for religious activities, such as a church, chapel, mosque, synagogue, and temple.		**Place of assembly**
Plant nursery	Land used to propagate, grow, and sell plants. It may include the sale of gardening equipment and horticultural products.		**Landscape gardening supplies**
Pontoon			**Marina**
Postal agency			**Retail premises**
Poultry farm	Land used to keep or breed poultry.	**Broiler farm**	**Animal production**
Poultry hatchery	Land used to incubate and hatch poultry eggs.		**Animal production**
Primary produce sales	Land used to display and sell primary produce, grown on the land or adjacent land. It may include processed goods made substantially from the primary produce.		**Retail premises**
Primary school			**Education centre**
Race course			**Major sports and recreation facility**
Racing dog husbandry	Land used to keep, breed, board or train racing dogs.	**Racing dog training**	**Animal husbandry**
Racing dog training			**Racing dog husbandry**
Railway station	Land used to assemble and distribute goods and passengers and includes facilities to park and manoeuvre vehicles. It may include the selling of food, drinks and other convenience goods and services.		**Transport terminal**
Real estate agency			**Office**
Reception centre			**Function centre**
Recreational boat facility	Land used to provide facilities for boats operated primarily for pleasure or recreation, including boats operated commercially for pleasure or recreation.	**Boat launching facility** **Marina**	
Refuse disposal	Land used to dispose of refuse, by landfill, incineration, or other means.		**Industry**

Land use term	Definition	Includes	Included in
Renewable energy facility	Land used to generate energy using resources that can be rapidly replaced by an ongoing natural process. Renewable energy resources include the sun, wind, the ocean, water flows, organic matter and the earth's heat. It includes any building or other structure or thing used in or in connection with the generation of energy by a renewable resource. It does not include a renewable energy facility principally used to supply energy for an existing use of the land.	**Wind energy facility** **Solar energy facility**	**Energy generation facility**
Research and development centre	Land used to develop or test electronic technology, biotechnology, or any other scientific discipline. It may include administration, promotion, conference, display, laboratory, assembly, and manufacturing areas.		**Industry**
Research centre	Land used only for scientific research.		
Reservoir	A natural or artificial lake used as a source of water supply that is owned or managed by a public authority.		**Utility installation**
Residential aged care facility	Land used to provide accommodation and personal or nursing care for the aged. It may include recreational, health or laundry facilities and services for residents of the facility.		**Accommodation**
Residential building	Land used to accommodate persons, but does not include camping and caravan park, corrective institution, dwelling, group accommodation, host farm, residential village, retirement village or small second dwelling.	**Community care accommodation** **Residential hotel** **Rooming house** **Rural worker accommodation**	**Accommodation**
Residential hotel	Land used to provide accommodation in serviced rooms for persons away from their normal place of residence. If it has at least 20 bedrooms, it may include the sale of liquor for consumption on, or off, the premises, function or conference	**Motel**	**Residential building**

Land use term	Definition	Includes	Included in
	rooms, entertainment, dancing, amusement machines, and gambling.		
Residential village	Land, in one ownership, containing a number of dwellings, used to provide permanent accommodation and which includes communal, recreation, or medical facilities for residents of the village.		**Accommodation**
Restaurant	Land used to prepare and sell food and drink, for consumption on the premises. It may include: a) entertainment and dancing; and b) the supply of liquor other than in association with the serving of meals, provided that tables and chairs are set out for at least 75% of patrons present on the premises at any one time. It does not include the sale of packaged liquor.		**Food and drink premises**
Restricted place of assembly	Land used by members of a club or group, or by members' guests, for religious, spiritual or cultural activities, entertainment, or meetings. It may include food and drink for consumption on the premises, and gaming.		**Place of assembly**
Restricted recreation facility	Land used by members of a club or group for leisure, recreation, or sport, such as a bowling or tennis club, gymnasium and fitness centre. It may include food and drink for consumption on the premises, and gaming. It may also include use by members' guests, or by the public on payment of a fee.		**Minor sports and recreation facility**
Restricted retail premises	Land used to sell or hire: a) automotive parts and accessories; b) camping, outdoor and recreation goods c) electric light fittings; d) animal supplies including equestrian and pet goods; e) floor and window coverings;	**Equestrian supplies** **Party supplies**	**Shop**

Land use term	Definition	Includes	Included in
	f) furniture, bedding, furnishings, fabric and manchester and homewares; g) household appliances, household electrical goods and home entertainment goods; h) party supplies; i) swimming pools; j) office equipment and supplies; k) baby and children's goods, children's play equipment and accessories; l) sporting, cycling, leisure, fitness goods and accessories; or m) goods and accessories which: ▪ Require a large area for handling, display and storage of goods; or ▪ Require direct vehicle access to the building by customers for the purpose of loading or unloading goods into or from their vehicles after purchase or hire. It does not include the sale of food, clothing and footwear unless ancillary to the primary use.		
Retail premises	Land used to: a) sell goods by retail, or by retail and wholesale; b) sell services; or c) hire goods.	**Food and drink premises** **Gambling premises** **Landscape gardening supplies** **Manufacturing sales** **Market** **Motor vehicle, boat, or caravan sales** **Postal agency** **Primary produce sales** **Shop** **Trade supplies**	

Land use term	Definition	Includes	Included in
Retirement village	Land used to provide permanent accommodation for retired people or the aged and may include communal recreational or medical facilities for residents of the village.		**Accommodation**
Rice growing			**Crop raising**
Road freight terminal			**Transport terminal**
Rooming house	Land used for a rooming house as defined in the *Residential Tenancies Act 1997*.		**Residential building**
Rural industry	Land used to: a) handle, treat, process, or pack agricultural produce; b) service or repair plant, or equipment, used in agriculture; or c) manufacture mud bricks.	**Abattoir** **Sawmill**	**Industry**
Rural store	Land used to store unprocessed agricultural produce, or products used in agriculture.		**Store**
Rural worker accommodation	Land used to accommodate a person engaged in agricultural production, away from their normal place of residence.		**Residential building**
Saleyard	Land used to hold, sell, and buy farm animals.		
Sawmill	Land used to handle, cut, and process timber from logs.		**Rural industry**
Secondary school			**Education centre**
Service industry	Land used to launder, repair, service or wash articles, machinery, or vehicles.	**Car wash** **Dry cleaner** **Motor repairs**	**Industry**
Service station	Land used to sell motor vehicle fuel from bowsers or charge electric vehicles. It may include the: a) selling of motor vehicle lubricants, accessories or parts; b) selling of food, drinks and other convenience goods; c) hiring of trailers;		

Land use term	Definition	Includes	Included in
	d) servicing or washing of motor vehicles; and e) installing of motor vehicle accessories or parts.		
Sex services premises	Land used to sell services involving the use or display of the body of the person providing the service for the sexual arousal or sexual gratification of another person while they are present on the land. It does not include: ▪ Live entertainment performed for an audience, by a person performing an act of an explicit sexual nature, such as lap dancing, nude dancing and striptease. ▪ Sexual activities engaged in by two or more people required to pay an admission fee or charge to enter the premises on the same terms and who do not receive any form of payment or reward, whether directly or indirectly, for engaging in the sexual activities.		**Shop**
Shipping container storage	Land used to store shipping containers. It may include the cleaning, repair, servicing, painting or fumigation of the shipping containers.		**Store**
Shop	Land used to sell goods or services, or to hire goods. It includes: ▪ the selling of bread, pastries, cakes or other products baked on the premises; ▪ demonstrations of products including music performances in shops selling recorded music. It does not include: ▪ food and drink premises; ▪ gambling premises; ▪ landscape gardening supplies; ▪ manufacturing sales; ▪ market;	**Adult sex product shop** **Beauty salon** **Bottle shop** **Convenience shop** **Dry cleaning agent** **Department store** **Hairdresser** **Laundromat** **Restricted retail premises** **Sex services premises**	**Retail premises**

Land use term	Definition	Includes	Included in
	▪ motor vehicle, boat, or caravan sales; ▪ postal agency; ▪ primary produce sales; or ▪ trade supplies.	**Supermarket**	
Sign			
Slipway			**Boat launching facility**
Small second dwelling	A building with a gross floor area of 60 square metres or less, on the same lot as an existing dwelling and used as a self-contained residence, which must include: a) a kitchen sink; b) food preparation facilities; c) a bath or shower; and d) a toilet and wash basin.		**Accommodation**
Solar energy facility	Land used to generate electricity from solar energy using ground-mounted photovoltaic and thermal technology, where the primary role is to export power to the electricity network. It does not include the generation of electricity principally used for an existing use of land.		**Renewable energy facility**
Solid fuel depot	Land used to sell solid fuel, such as briquettes, coal, and fire wood.		**Fuel depot**
Stone exploration	Land used to search for stone, including: a) conducting geological, geophysical, and geochemical surveys; b) costeaning and bulk sampling; c) drilling; and d) taking samples for chemical, physical, or other testing.		**Earth and energy resources industry**
Store	Land used to store goods, machinery, or vehicles.	**Boat and caravan storage** **Freezing and cool storage**	**Warehouse**

Land use term	Definition	Includes	Included in
		Rural store **Shipping container storage** **Vehicle store**	
Supermarket			**Shop**
Take away food premises	Land used to prepare and sell food and drink for immediate consumption off the premises. It may include up to 10 seats available for consumption on the premises.		**Food and drink premises**
Telecommunications facility	Land used to accommodate any part of the infrastructure of a Telecommunications network. It includes any telecommunications line, equipment, apparatus, telecommunications tower, mast, antenna, tunnel, duct, hole, pit, pole, or other structure or thing used, or for use in or in connection with a Telecommunications network.		**Utility installation**
Tertiary institution			**Education centre**
Timber production	Land used to propagate, cultivate, manage and harvest timber.		**Crop raising**
Timber yard	Land used to sell sawn, dressed, and treated timber, wood fibre boards, and the like. It includes cutting the timber and boards to order, and selling hardware, paints, tools, and materials used in conjunction with the use and treatment of timber.		**Trade supplies**
Trade supplies	Land used to sell by both retail and wholesale, or to hire, materials, tools, equipment, machinery or other goods for use in: a) automotive repairs and servicing; b) building; c) commerce; d) industry; e) landscape gardening; f) the medical profession; g) primary production; or	**Timber yard**	**Retail premises**

Land use term	Definition	Includes	Included in
	h) local government, government departments or public institutions.		
Tramway	Land used to provide a system of transport in vehicles connected to a network of tracks, and includes tram stops and shelters, shunting areas and associated passenger facilities.		
Transfer station	Land used to collect, consolidate, temporarily store, sort or recover refuse, used or surplus materials before transfer for disposal, recycling or use elsewhere.	**Automated collection point** **Container deposit scheme centre**	**Industry**
Transport terminal	Land used to assemble and distribute goods or passengers. It includes facilities to park and manoeuvre vehicles. It does not include a Tramway.	**Airport** **Bus terminal** **Heliport** **Railway station** **Road freight terminal** **Wharf**	
Travel agency			**Office**
Utility installation	Land used: a) for telecommunications; b) to transmit or distribute gas or oil; c) to transmit, distribute or store power; d) to collect, treat, transmit, store, or distribute water; or e) to collect, treat, or dispose of storm or flood water, sewage, or sullage. It includes any associated flow measurement device or a structure to gauge waterway flow.	**Data centre** **Minor utility installation** **Reservoir** **Telecommunications facility**	
Vehicle store	Land used to park or store vehicles in connection with a goods or passenger transport business.		**Store**
Veterinary centre	Land used to: a) diagnose animal diseases or disorders; b) surgically or medically treat animals; or c) prevent animal diseases or disorders.		

Land use term	Definition	Includes	Included in
	It may include keeping the animals on the premises for treatment.		
Warehouse	Land used to store or display goods. It may include the storage and distribution of goods for wholesale and the storage and distribution of goods for online retail. It does not include premises allowing in-person retail or display of goods for retail, or allowing persons to collect goods that have been purchased online.	**Commercial display area** **Fuel depot** **Mail centre** **Milk depot** **Store**	
Waste-to-energy facility	Land used for the combustion, treatment or bio-reaction of waste to produce energy for use off site. It includes the activities to collect, temporarily store, process, or transfer waste materials for energy production.		**Energy generation facility**
Water retarding basin	Land used to store storm or flood water on a temporary basis.		**Minor utility installation**
Wharf	Land used to provide facilities for ships, such as bulk and container ships, passenger ships, and defence force marine craft.		**Transport terminal**
Wind energy facility	Land used to generate electricity by wind force. It includes land used for: a) any turbine, building or other structure or thing used in or in connection with the generation of electricity by wind force b) an anemometer. It does not include turbines principally used to supply electricity for domestic or rural use of the land.		**Renewable energy facility**
Winery	Land used to display, and sell by retail, vineyard products, in association with the growing of grape vines and the manufacture of the vineyard products. It may include the preparation and sale of food and drink for consumption on the premises.		
Zoo			**Outdoor recreation facility**

73.04 NESTING DIAGRAMS

08/08/2019
VC159

The information in the table to Clause 73.03 is set out in the following diagrams as a means of indicating the nesting of land use terms.


The table to Clause 73.03 prevails if there is any inconsistency between the table and the diagrams or list.

Land use terms that are not nested are listed at Clause 73.04-17.

Land use terms in bold font are defined in Clause 73.03.


73.04-1 Accommodation group

14/12/2023
VC253




73.04-2 Agriculture group

08/08/2019
VC159




73.04-3 Agriculture group (sub-group of Animal production)

24/01/2020
VC160




73.04-4 Education centre group

24/01/2020
VC160




73.04-5 Industry group

26/09/2023
VC246




73.04-6 Leisure and recreation group

16/08/2019
VC163




73.04-7 Earth and energy resources group

24/01/2020
VC160




73.04-8 Office group

28/10/2022
VC224




73.04-9 Place of assembly group

16/08/2019
VC163




73.04-10 Recreational boat facility group

24/01/2020
VC160




73.04-11 Retail premises group

16/08/2019
VC163




73.04-12 Retail premises group (sub-group of Shop)

01/12/2023
VC217




73.04-13 Transport terminal group

24/01/2020
VC160




73.04-14 Utility installation group

08/08/2019
VC159




73.04-15 Warehouse group

24/01/2020
VC160



73.04-16 Energy Group

24/01/2020
VC160



73.04-17 Land use terms that are not nested

01/12/2023
VC217

Art and craft centre

Car park

Cemetery

Crematorium

Display home centre

Emergency services facility

Freeway service centre

Funeral parlour

Helicopter landing site

Home based business

Hospital

Interpretation centre

Natural systems

Research centre

Saleyard

Service station

Sign

Tramway

Veterinary centre

Winery

74 STRATEGIC IMPLEMENTATION

31/07/2018
VC148

74.01 APPLICATION OF ZONES, OVERLAYS AND PROVISIONS

31/07/2018
VC148

The schedule to this clause must include a general explanation of the relationship between the Municipal Planning Strategy, the objectives and strategies in Clauses 10 to 19 and the controls on the use and development of land in this planning scheme.

A planning authority must take into account the schedule to this clause when it prepares an amendment to this planning scheme.

A responsible authority must not take into account the schedule to this clause when it makes a decision under this planning scheme.

27/06/2024
C225brim

SCHEDULE TO CLAUSE 74.01 APPLICATION OF ZONES, OVERLAYS AND PROVISIONS

1.0 Application of zones, overlays and provisions

27/06/2024
C225brim

This planning scheme applies the following zones, overlays and provisions to implement the Municipal Planning Strategy and the objectives and strategies in Clauses 11 to 19:

- Green Wedge Zone to existing agricultural and rural residential land within the Brimbank portion of the Sunbury Green Wedge.
- Public Conservation and Resource Zone to areas of environmental and habitat significance in public ownership.
- Rural Conservation Zone to sensitive escarpments, ridgelines and riparian areas along Maribyrnong River and Kororoit Creek within the Green Wedge.
- Public Park and Recreation Zone to public open space and recreation areas in public ownership.
- Neighbourhood Residential Zone to land designated for residential development of up to two storeys.
- General Residential Zone to land designated for residential development of up to three storeys.
- Residential Growth Zone to land designated for increased residential densities.
- Commercial 2 Zone to land within Employment Areas.
- Industrial 1 Zone to land designated for general industrial uses, including manufacturing and logistics industries.
- Industrial 2 Zone to land designated for industrial uses with potential for adverse amenity impacts.
- Industrial 3 Zone to land designated for industrial uses that have low amenity impacts on nearby residential communities and sensitive uses and to areas that require a buffer between industrial and sensitive uses.
- Road Zone Category 1 to arterial roads managed by VicRoads.
- Public Use Zone to publically owned community facilities.
- Environmental Audit Overlay to areas of potentially contaminated land.
- Environmental Significance Overlay to the areas adjacent to the Kororoit Creek, Maribyrnong River, areas of significant native vegetation, habitat corridors and environmental significance.
- Heritage Overlay to protect places of heritage significance.

74.02 FURTHER STRATEGIC WORK

31/07/2018
VC148

The schedule to this clause may specify the planning authority's approach to further strategic work.

A planning authority may take into account the schedule to this clause when it prepares an amendment to this planning scheme.

The responsible authority must not take into account the schedule to this clause when it makes a decision under this planning scheme.

27/06/2024
C225brim

SCHEDULE TO CLAUSE 74.02 FURTHER STRATEGIC WORK

1.0
27/06/2024
C225brim

Further strategic work

Settlement

- Review the Sunshine Town Centre Structure Plan in line with recommendations in the *Brimbank Response Strategy, Western Rail Plan, including Melbourne Airport Rail Link and Sunshine Super Hub* (Brimbank City Council, 2019).
- Prepare a Structure Plan for the Deer Park Major Activity Centre, Deer Park Railway Station and surrounding industrial and residential uses, including a review of the boundary of the activity centre.

Built Environment and Heritage

- Prepare a neighbourhood character study to identify areas with neighbourhood character.

Housing

- Review the *Brimbank Housing Strategy, Home and Housed* (Brimbank City Council, 2014).

Economic Development

- Develop industrial design guidelines for the municipality including industrial estates where there are no existing design provisions.

Transport

- Prepare an integrated transport strategy for the municipality.

Infrastructure

- Prepare and implement development contributions plans for community and development infrastructure in accordance with Council adopted strategic plans and works programs.