

BOURKE & NICHOLSON STREET CABLE TRAMWAY.


Drain.	Dimension.	Fall.	Length.	Area Drained.	Rainfall per hour which could be carried.	Municipality.	Cost.	Remarks.
Terminal Pit	9in. pipe		Yards. 20			Melbourne	£ 50	Drainage Tramway only
King Street	Culvert 3ft. 9in. x 15in.	$\frac{1}{140}$	60	30 acres	$\frac{3}{4}$ in.	do.	115	To provide for Drainage intercepted by Tramway construction, in lieu of culvert 3ft. 9in. x 12 in.
William Street	12in. pipe	$\frac{1}{140}$	55	4 acres	1 in.	do.	90	Lowered and extended
Queen Street	12in. pipe	$\frac{1}{140}$	50	4 acres	1 in.	do.	43	Existing pipe lowered and extended
Spring Street Curve	9in. pipe		10			do.	30	Drainage of Tramway only—to be constructed
Victoria Parade	18in. pipe	$\frac{1}{117}$	77	10 acres	1 in.	Fitzroy and Melbourne	150	
Drain down centre of Tramway near Reilly Street	9in. pipe	$\frac{1}{204}$	154			do.	225	Drainage of Tramway only
Connections with Sewer	9in. pipe					do.	30	Do. do.
Sewer at Reilly Street	3ft. 6in. barrel sewer	$\frac{1}{350}$	40	120 acres	$\frac{1}{2}$ in.	do.	300	To provide for Drainage intercepted by Tramway construction, in lieu of existing culvert 6ft. x 1ft. 6in.
Crown Pulleys						do.	20	Drainage of Tramway only
Terminal Pit, Nicholson Street			236			Fitzroy	300	Do. do.
Angle Sheave Pit	9in. pipe		120			do.	200	Do. do.

SUMMARY OF EXPENDITURE.

City of Melbourne	£691
City of Fitzroy	862
				<u>£1553</u>

KEW HORSE TRAMWAY.

Drains.	Dimensions.	Fall.	Length.	Area Drained.	Rainfall per hour which could be carried.	Municipality.	Cost.	Remarks.
Barker's Road and Buleen Road	2 Culverts, each 3ft. x 15in.	$\frac{1}{68}$	Yards. 23	100 acres	$\frac{1}{2}$ in.	Kew and Hawthorn	£ 195	To provide for drainage inter- cepted by Tramway construc- tion, in lieu of open channel



NOTE,

CABLE WAYS, THUS

" " HORSE

g. H. Fischer. Dat 10.10.88.

